



DbVisualizer 11.0

Users Guide



Table of Contents

1	DbVisualizer 11.0	16
2	Getting Started	16
2.1	Downloading	16
2.2	Installing	16
2.2.1	Installing with a Setup Installer	16
2.2.2	Installation from an archive file	16
2.2.3	Silent Install	17
2.3	Starting DbVisualizer	17
2.4	Evaluating the Pro Edition	18
2.5	Installing a Pro Edition License	18
2.5.1	Installing a License Key String	18
2.5.2	Installing a License Key File	18
2.5.3	Uninstalling the license key	19
2.5.4	DbVisualizer Pro, license file location	19
2.6	Creating a Connection - basics	19
2.6.1	Using the Connection Wizard	19
2.6.2	Setting Up a Connection Manually	24
2.7	Creating a Table - basics	25
2.8	Viewing a Table - basics	26
2.9	Editing a Table - basics	27
2.10	Executing SQL - basics	28
2.11	Checking for Updates	29
2.12	Printing	31
2.12.1	Printer Setup	32
2.12.2	Printing a Grid, a Chart and Plain Text	32
2.12.3	Printing a Graph	32
2.12.4	Print Preview	32
3	Getting the Most Out of the GUI	35
3.1	Main Window Layout	35
3.2	Tab Types	36
3.2.1	Navigation Tabs	37



3.2.2	Object View Tabs	39
3.2.3	SQL Commander Tabs	40
3.3	Opening a Tab	40
3.3.1	Database tree objects	40
3.3.2	Scripts and Monitors	40
3.4	Pinning a Tab.....	41
3.5	Closing a Tab	41
3.6	Listing Open Tabs.....	41
3.7	Maximizing and Minimizing a Tab	41
3.8	Floating a Tab.....	42
3.9	Rearranging Tabs	42
3.10	Changing the Tab Label	44
3.11	Selecting a Node for a Tab.....	45
3.12	Preserving Tabs Between Sessions.....	45
3.13	Using Tab Colors and Borders	45
3.14	Changing the GUI Appearance	46
3.15	Changing Keyboard Shortcuts	46
3.16	Internationalization and Localization (i18N and L10N)	50
3.16.1	Fonts and Character Sets.....	50
4	Managing Database Objects	51
4.1	Opening a Database Object	51
4.2	Perform Actions on Multiple Database Objects.....	51
4.3	Filtering Database Objects	53
4.3.1	Object Filtering.....	55
4.3.2	Object Type Visibility	57
4.3.3	Temporarily Disable Filtering	58
4.3.4	Filter Sets.....	59
4.3.5	Show Only Default Database/Schema filter	60
5	Working with Tables	60
5.1	Creating a Table	60
5.1.1	Opening the Create Table Dialog	60
5.1.2	Columns Tab	61
5.1.3	Primary Key Tab	63



5.1.4	Foreign Keys Tab	63
5.1.5	Unique Constraints Tab	64
5.1.6	Check Constraints Tab	65
5.1.7	Indexes Tab	66
5.1.8	SQL Preview.....	66
5.1.9	Execute	66
5.2	Altering a Table	67
5.2.1	Opening the Alter Table Dialog	67
5.2.2	Columns Tab	68
5.2.3	Primary Key Tab	69
5.2.4	Foreign Keys Tab	70
5.2.5	Unique Constraints Tab	71
5.2.6	Check Constraints Tab	71
5.2.7	Indexes Tab	72
5.2.8	SQL Preview.....	73
5.2.9	Execute	73
5.3	Creating a Trigger.....	73
5.3.1	Opening the Create Trigger Dialog.....	73
5.3.2	Trigger Editor	74
5.4	Creating an Index	75
5.5	Viewing Table Data	76
5.5.1	Opening the Data tab.....	76
5.5.2	Formatting.....	77
5.5.3	Sorting	77
5.5.4	Where Filter	78
5.5.5	Column Filter	79
5.5.6	Quick Filter	79
5.5.7	Max Rows/Max Chars	80
5.5.8	Max Rows at First Display	81
5.5.9	Column Header Tooltips.....	81
5.5.10	Highlight Primary Key Columns	82
5.5.11	Auto Resize Columns	82
5.5.12	Show Only Some Columns	82
5.5.13	Right-Click Menu Operations.....	83
5.5.14	Creating Monitors.....	86



5.5.15	Aggregation Data for Selection	86
5.6	Editing Table Data.....	87
5.6.1	Opening the Data tab.....	88
5.6.2	Editing Data in the Grid.....	89
5.6.3	Copy/Paste	89
5.6.4	Updates and Deletes Must Match Only One Table Row	91
5.6.5	Key Column(s) Chooser	91
5.6.6	Editing Multiple Rows	92
5.6.7	Data Type checking.....	92
5.6.8	New Line and Carriage Return.....	93
5.6.9	Using the Cell Editor/Viewer.....	93
5.6.10	Using the Form Editor/Viewer	96
5.6.11	Preview Changes.....	97
5.6.12	Editing Binary/BLOB and CLOB Data	98
5.7	Working with Binary and BLOB Data.....	99
5.8	Working with Large Text/CLOB Data.....	99
5.9	Using Max Rows and Max Chars for a Table.....	99
5.10	Changing the Data Display Format	100
5.10.1	Date, Time and Timestamp formats	100
5.10.2	Number formats.....	101
5.11	Exporting a Table	101
5.11.1	Output Format	102
5.11.2	Output Destination	103
5.11.3	Options	103
5.11.4	Using Variables in Fields	104
5.11.5	Exporting Binary/BLOB and CLOB Data.....	104
5.11.6	Saving And Loading Settings.....	104
5.11.7	Other Ways to Export Table Data	105
5.12	Importing Table Data	105
5.12.1	Input File Format and Other Options.....	105
5.12.2	Data Formats and Data Type Per Column	107
5.12.3	Matching Columns and Data Types for an Existing Table	108
5.12.4	Adjusting Table Declaration for a New Table	110
5.12.5	Importing Binary/BLOB and CLOB Data (CSV and SQL Only)	111
5.12.6	Running the import	112



5.12.7	Saving And Loading Settings	112
5.12.8	Other Ways to Import Table Data	112
5.12.9	Known limitations	112
5.13	Comparing Tables	112
5.14	Viewing Table Relationships.....	113
5.15	Navigating Table Relationships.....	115
5.15.1	Opening the Navigator.....	115
5.15.2	Navigating Relationships.....	116
5.15.3	Adding Context Information to the Graph	119
5.15.4	Arranging the Graph.....	120
5.15.5	Exporting and Printing the Graph	121
5.15.6	Opening the Navigator from the Data tab	121
5.16	Viewing the Table DDL	121
5.17	Filtering Tables in the Tree	122
5.18	Showing Row Count in the Tree	122
5.19	Using Permissions for Table Data Editing.....	122
5.20	Scripting a Table	122
5.21	Managing Table and Column Comments	123
6	Working with Views	123
6.1	Creating a View.....	123
6.2	Altering a View.....	123
6.3	Editing a View	123
6.4	Exporting a View.....	124
6.5	Viewing the View DDL.....	124
6.6	Filtering Views in the Tree	124
6.7	Scripting a View.....	124
7	Working with Procedures, Functions and Other Code Objects	124
7.1	Creating a Function.....	125
7.2	Creating a Procedure	126
7.3	Creating Other Code Objects.....	127
7.4	Editing a Code Object	127
7.4.1	Disable Error Markers in the SQL Editor.....	128



7.5	Executing a Code Object.....	129
7.5.1	Executing in the Code Editor	130
7.5.2	Executing in the SQL Commander	130
7.5.3	Using the Script Object Dialog.....	131
7.6	Exporting a Code Object	132
7.7	Scripting a Code Object	132
8	Working with Schemas	133
8.1	Creating a Schema	133
8.2	Comparing Schemas.....	133
8.3	Viewing Entity Relationships.....	133
8.4	Exporting a Schema	135
8.4.1	Output Format	135
8.4.2	Output Destination	136
8.4.3	Object Types.....	136
8.4.4	Options	136
8.4.5	Using Variables in Fields	137
8.4.6	Saving And Loading Settings.....	137
8.5	Filtering Schemas in the Tree.....	138
9	Working with SQL.....	138
9.1	Selecting Database Connection, Catalog and Schema.....	138
9.1.1	Configuring the Initial Values	139
9.2	Editing SQL Scripts.....	139
9.2.1	Font Settings	140
9.2.2	Editor Styles	140
9.2.3	Comments	141
9.2.4	Charsets and Fonts	142
9.2.5	Loading and Saving Scripts	142
9.2.6	Stale Files Warning.....	143
9.2.7	Drag and Drop a File.....	144
9.2.8	Drag and Drop Database Objects	144
9.2.9	Loading and Saving Bookmarks and Monitors.....	145
9.2.10	Navigating Between History Entries	145
9.2.11	Navigating to Script location.....	145
9.2.12	Confirming Overwriting Unsaved Changes.....	146



9.2.13	SQL Formatting	146
9.2.14	Settings.....	146
9.2.15	Auto Completion	150
9.2.16	Recording and Playing Edit Macros.....	152
9.2.17	Folding Selected Text	153
9.2.18	Selecting a Rectangular Area.....	153
9.2.19	Tab Key Treatment.....	154
9.2.20	Key Bindings.....	154
9.3	Morph Selection	154
9.3.1	Introduction	155
9.3.2	Basic Examples.....	155
9.3.3	Use Cases.....	184
9.4	Using Editor Templates	188
9.4.1	Using a Template	188
9.4.2	Creating a new Template.....	188
9.4.3	Editing or Deleting a Template.....	189
9.4.4	Changing the Expand Keybinding	189
9.5	Executing SQL Statements	189
9.5.1	Execute a Script with Multiple Statements.....	189
9.5.2	Execute Only the Current Statement	190
9.5.3	Execute Buffer	190
9.5.4	Control Execution after a Warning or an Error	190
9.6	Re-Executing SQL Statements.....	190
9.6.1	Using Previous and Next in the SQL Commander	190
9.6.2	Using the SQL History Window.....	190
9.6.3	Using Quick Load	191
9.7	Executing Complex Statements	192
9.7.1	Using Execute Buffer	192
9.7.2	Using an SQL Block	192
9.7.3	Using the @delimiter command	193
9.8	Executing an External Script.....	193
9.9	Locating SQL Errors	194
9.9.1	Disable Error Markers in the SQL Editor.....	194
9.10	Analyzing (explain) Query Performance	195
9.11	Auto Commit, Commit and Rollback	197



9.12	Managing Frequently Used SQL	198
9.12.1	Creating, Editing and Organizing Bookmarks	199
9.12.2	Executing Bookmarks	200
9.12.3	Adding a Bookmark as a Favorite.....	200
9.12.4	Sharing Bookmarks.....	201
9.12.5	Using Quick Load	201
9.13	Creating Queries Graphically.....	201
9.13.1	Creating a Query	202
9.13.2	Testing the Query.....	210
9.13.3	Loading a Query From the Editor	211
9.13.4	Properties for the Query Builder	211
9.13.5	Current Limitations.....	211
9.14	Formatting SQL	212
9.14.1	Settings.....	212
9.15	Using Max Rows and Max Chars for Queries	216
9.16	Getting the DDL for an Object.....	217
9.17	Using the Log Tab.....	217
9.17.1	Preprocessing Script.....	218
9.17.2	Executing.....	218
9.17.3	Auto resize row heights.....	218
9.17.4	Navigating to next/previous failed log entry	218
9.17.5	Highlight statement or error in the SQL editor.....	219
9.17.6	Saving all Log entries to text file.....	219
9.17.7	Copy Log Entries to clipboard	219
9.17.8	Copy executed SQLs to the SQL Commander	219
9.17.9	Filter and search.....	219
9.18	Writing to the Log Tab.....	220
9.19	Using the DBMS Output Tab	220
9.20	Comparing SQL Scripts.....	221
9.21	Using Permissions in the SQL Commander	222
9.22	Sending Comments to the Database with Statements.....	222
9.23	Using Client-Side Commands.....	223
9.23.1	Introduction	223
9.23.2	Commands reference	223



9.23.3	@export - Export query result	224
9.23.4	@mail - Send emails and attach files	229
9.23.5	@import - Importing data.....	235
9.24	Parameterized SQL - Variables and Parameter Markers	248
9.24.1	Using DbVisualizer Variables	249
9.24.2	Using Parameter Markers	255
10	Working with Result Sets	259
10.1	Viewing a Result Set.....	259
10.1.1	Viewing as a Grid	259
10.1.2	Viewing as Text.....	259
10.1.3	Merge Result Sets.....	260
10.1.4	Viewing as a Graph.....	260
10.2	Editing a Result Set	260
10.3	Exporting a Result Set.....	261
10.4	Comparing Result Sets.....	261
10.5	Pinning Result Sets	261
10.6	Show Result Sets in a Separate Window.....	261
11	Working with Charts.....	261
11.1	Charting a Result Set.....	263
11.1.1	Selecting the Category.....	265
11.1.2	Selecting the Series.....	266
11.1.3	Chart Type	266
11.2	Chart Configuration	267
11.2.1	Appearance Preferences.....	268
11.2.2	Series Preferences.....	270
11.3	Zooming	270
11.4	Export	270
12	Exporting a Grid.....	271
12.1	Settings.....	271
12.2	Data page.....	273
12.2.1	Generating Test Data	274
12.3	Preview	275
12.4	Output Destination	275



12.5	Settings Menu.....	276
13	Opening a Grid as Spreadsheet.....	276
13.1	Output.....	277
14	Comparing Data	278
14.1	Selecting the Objects to Compare	278
14.2	Comparing Text Data	279
14.3	Comparing Grids	280
14.4	Comparing Cell Values.....	282
15	Monitoring Data Changes	282
15.1	Creating a Monitored Query	282
15.1.1	Monitor table row count	284
15.1.2	Monitor table row count difference	285
15.2	Running a Monitored Query	286
16	Accessing Frequently Used Objects	287
16.1	Keeping Tabs Open Between Sessions	287
16.2	Using Favorites.....	287
16.3	Using Scripts.....	290
17	Delimited Identifiers and Qualifiers	290
18	Handling Transactions.....	290
18.1	Changing the Auto Commit Setting	290
18.1.1	Changing Auto-Commit for a Database Type	290
18.1.2	Changing Auto-Commit for a Connection.....	290
18.1.3	Changing Auto-Commit for an SQL Commander tab.....	290
18.1.4	Changing Auto-Commit for a Statement Block	291
18.2	Setting Transaction Isolation	291
19	Database Connection Options	291
19.1	Setting Up a Connection Manually.....	291
19.1.1	Setting Up a Connection Manually.....	292
19.2	Configuring Connection Properties	293
19.2.1	Tool Properties.....	293
19.2.2	Connection Properties.....	294
19.3	Copying an Existing Connection.....	297



19.4	Edit Multiple Database Connections.....	298
19.4.1	Changing the database driver	298
19.5	Removing a Connection.....	299
19.6	Organizing Connections in Folders	299
19.7	Rearranging Connections and Folders.....	299
19.8	Setting Common Authentication Options	299
19.8.1	Authentication settings in Connection Properties	300
19.8.2	SSH Settings in Tool Properties	300
19.9	Setting a Master Password	302
19.9.1	Specifying a Master Password	302
19.9.2	Changing a Master Password	303
19.9.3	Resetting the Master Password	303
19.9.4	Connecting with a Master Password specified	304
19.9.5	Manually Requesting the Master Password for New Connections	304
19.9.6	Showing the Encrypted Password in Cleartext	304
19.9.7	Declaring a Master Password Rule	304
19.10	Using Connection Keep-Alive	304
19.11	Security.....	305
19.11.1	Using an SSH Tunnel.....	305
19.11.2	Using SSL.....	307
19.12	Using Oracle TNS Names	309
19.13	Changing an Oracle Password.....	310
19.14	Using SQL Server Single-Sign-On or Windows Authentication.....	310
19.15	Using Variables in Connection Fields.....	310
19.16	Automatically Connecting at Startup	311
19.17	Executing SQL at Connect and Disconnect.....	312
19.18	Using a Single Shared Physical Connection	312
19.18.1	Selecting the Single Shared Physical Connection Mode.....	312
19.18.2	Data Manipulation with a Single Shared Physical Connection.....	312
19.18.3	Transaction Handling with a Single Shared Physical Connection	312
19.19	JDBC-ODBC Bridge Driver Alternatives.....	313
19.19.1	The UCanAccess Driver for MS Access.....	313
19.19.2	Easysoft JDBC-ODBC Bridge Driver	314



20	Finding Database Objects and Data	314
20.1	Finding and Replacing Text in the Editor	314
20.1.1	Regular Expression Example:	314
20.2	Finding Data in a Grid.....	315
20.3	Locating an Object in an SQL Statement	315
20.4	Locating an Object in the Databases tab	315
20.5	Searching a Connection.....	315
20.6	Synchronizing object tab selection and selection in the tree.....	316
21	Transfer DbVisualizer settings	317
21.1	Transfer DbVisualizer settings to new environment	317
21.2	Transfer the DbVisualizer Pro license to new machine	317
22	Exporting and Importing Settings	317
22.1	Export Settings.....	317
22.2	Import Settings	319
23	Command Line Interface	321
23.1	Command Line Options	321
23.2	Examples	323
23.2.1	Executing single statements.....	323
23.2.2	Executing scripts	324
23.2.3	Controlling the output	325
23.2.4	Using variables - prompting for values	326
23.2.5	Combining OS scripts, the command line interface and DbVisualizer variables.....	327
23.3	Setting up the connection properties on the command line	329
23.4	Exit codes from dbviscmd	329
23.5	Generating a Command From SQL Commander.....	329
24	Database Profiles	331
24.1	Understanding Database Profiles	331
24.1.1	Affected DbVisualizer features	332
24.1.2	How a Database Profile is loaded.....	334
24.2	Creating a Database Profile	334
24.3	Extending a Database Profile	334
24.3.1	Extending Commands.....	335



24.3.2	Extending Database Objects Tree	335
24.3.3	Extending Actions	340
24.3.4	Extending Object Views	340
24.3.5	Remove an Element	340
24.3.6	Complete sample Database Profile.....	341
24.4	Top level XML Elements	344
24.4.1	XML template	344
24.4.2	XML element - DatabaseProfile	345
24.4.3	XML element - InitCommands	346
24.4.4	XML element - Commands.....	348
24.4.5	XML element - ObjectsTreeDef	354
24.4.6	XML element - ObjectsViewDef.....	361
24.4.7	XML element - ObjectsActionDef	383
24.5	Icons.....	399
24.5.1	Introduction	399
24.5.2	icons.prefs file	399
24.5.3	Icons Search Path.....	400
24.6	Conditional Processing.....	400
24.6.1	Introduction	400
24.6.2	Conditional processing when database connection is established	401
24.6.3	Conditional processing during command execution	402
24.6.4	drop-on-condition attribute.....	403
24.7	Database Profile Utilities	403
24.7.1	Analyze Database Profile	403
24.7.2	Show All Type and Icon Attributes	403
24.7.3	Show Available Icons	404
24.7.4	Export Merged Profile	405
24.7.5	Configure Search Path	405
24.7.6	Reload Database Profiles List.....	405
24.8	Database Profile changes in 11.0	406
24.8.1	Common attribute changes.....	406
24.8.2	New attributes for the ProcessDataSet sub element for Command	406
24.8.3	New attributes for the ObjectView element	406
24.8.4	New "chart" viewer for DataView elements.....	406
24.9	Database Profile changes in 9.5	406



24.9.1	New/changed attributes for Command	406
24.9.2	Action element improvements.....	407
24.9.3	Changes for DataNode and GroupNode	408
24.9.4	New utility class	408
24.9.5	Changed icons definition.....	409
25	Troubleshooting.....	409
25.1	Debugging DbVisualizer.....	409
25.2	Fixing Connection Issues	410
25.3	Handling Dropped Connections.....	410
25.4	Handling Memory Constraints.....	411
25.5	Reporting Issues.....	412
25.5.1	Contacting support.....	412
25.5.2	Encountering Errors.....	413
25.6	Using special characters in passwords	414
26	Reference Material	414
26.1	GUI Command Line Arguments.....	414
26.2	Installation Structure.....	415
26.3	Installing a JDBC Driver	415
26.3.1	What is a JDBC Driver?	416
26.3.2	Get the JDBC driver file(s).....	416
26.3.3	Driver Manager	416
26.4	Setting Up a JNDI Connection	421
26.5	Special Properties	422



1 DbVisualizer 11.0

2 Getting Started

DbVisualizer is a feature rich, intuitive multi-database tool for developers and database administrators, providing a single powerful interface across a wide variety of operating systems. With its easy-to-use and clean interface, DbVisualizer has proven to be one of the most cost effective database tools available, yet to mention that it runs on all major operating systems and supports all major RDBMS that are available. Users only need to learn and master one application. DbVisualizer integrates transparently with the operating system being used.

The screenshots throughout the users guide are produced on Windows 7 using the Windows Look and Feel, but DbVisualizer lets you choose among other Look and Feels as well.

In addition to this Users Guide, the following online resources may be useful:

1. The home of [DbVisualizer](#),
2. The [Support Portal](#) which hosts solution articles (knowledge base) and support ticketing
3. The [Databases and JDBC Drivers](#) online page. This page gives information about supported databases and JDBC drivers,
4. The [DbVisualizer forums](#).

2.1 Downloading

DbVisualizer installers are available on the DbVis Software web site at <https://www.dbvis.com/download/>.

Download the installer for your operating system that fits your needs:

- **Without Java VM** if you already have Java installed,
- **With Java VM** if you do not have Java installed, or if you want to use the recommended Java version for DbVisualizer and another Java version for other applications,
- An Installer unless you must use an archive format for some reason.

2.2 Installing

There are two ways to install DbVisualizer: using an Installer or extracting files from an archive file.

- [Installing with a Setup Installer](#)
- [Installation from an archive file](#)
 - [Installation Notes for ZIP archives \(Windows\)](#)
 - [Installation Notes for TAR archives \(Unix\)](#)
 - [Installation Notes for RPM archives \(Linux\)](#)
 - [Installation Notes for DEB archives \(Linux\)](#)
- [Silent Install](#)

2.2.1 Installing with a Setup Installer

To install DbVisualizer, just execute the Installer you have downloaded and follow the instructions in the screens. The setup installer optionally creates a desktop shortcut used to launch DbVisualizer which is not the case for the other installers below.

2.2.2 Installation from an archive file

Installation Notes for ZIP archives (Windows)

All files are contained in an enclosing folder named **DbVisualizer**.

Unpack the distribution file with the built-in zip archive extraction utility in Windows or with the **windows** utility.

The ZIP archive installer will not add any entries to the Start menu, add desktop launchers or even register the software in the Windows registry.

Start DbVisualizer by clicking the *dbvis.exe* file in the installation directory for DbVisualizer.

To uninstall DbVisualizer installed via a ZIP archive, simply delete the complete DbVisualizer directory.



Installation Notes for TAR archives (Unix)

All files are contained in an enclosing folder named **DbVisualizer**.
Unpack the distribution file with:

```
gunzip dbvis_unix_11_0.tar.gz
tar xf dbvis_unix_11_0.tar
```

Start DbVisualizer by executing the shell script in the installation directory, e.g. *DbVisualizer/dbvis.sh*.

To uninstall DbVisualizer installed via a TAR archive, simply delete the complete DbVisualizer directory.

Installation Notes for RPM archives (Linux)

Install the rpm with *rpm -i <download_filename>* or your favorite rpm tool.

Start DbVisualizer by executing the shell script in the installation directory, e.g. *DbVisualizer/dbvis*.

To uninstall DbVisualizer installed via an RPM archive, use the rpm utilities.

Installation Notes for DEB archives (Linux)

Install the package with *sudo dpkg -i <download_filename>.deb* or your favorite Debian package manager tool.

Start DbVisualizer by executing the shell script in the installation directory, e.g. *DbVisualizer/dbvis*.

To uninstall DbVisualizer installed via an DEB archive, use *dpkg --remove*.

2.2.3 Silent Install

In order to start a silent installation, the installer has to be invoked with the **-q** argument. The installer will perform the installation as if the user had accepted all default settings.

There is no user interaction on the terminal. The installer will install the application to the default installation directory, unless you pass the **-dir** parameter to the installer. The parameter after **-dir** must be the desired installation directory. Example:

```
dbvis_windows-x64_11_0_jre.exe -q -dir "d:\myapps\DbVisualizer"
```

The output of the installer is not printed to the command line for silent installation. If you pass the **-console** parameter after the **-q** parameter, a console will be allocated that displays the output to the user. This is useful for debugging purposes.

If the installation was successful, the exit code of the installer will be 0, if no suitable JRE could be found it will be 83, for other types of failure it will be 1.

For more options check the [command line options](#) for the installer.

See the following for examples on respective operating system.

Windows

```
dbvis_windows-x64_11_0_jre.exe -q -console
echo %errorlevel%
```

macOS

```
DbVisualizer Installer.app/Contents/MacOS/JavaApplicationStub -q -console
echo $?
```

Linux

```
dbvis_linux_11_0.sh -q -console
echo $?
```

The **-console** argument may be used for debugging purposes. The **echo** command verifies the exit code from the installer which may be useful if automating the installation.

2.3 Starting DbVisualizer

How to start DbVisualizer depends on the operating system you are using.




- **Windows**
In the **Start** menu, select the **DbVisualizer** menu item.
- **Linux/Unix**
Open a shell and change directory to the DbVisualizer installation directory. Execute the *dbvis* program. If DbVisualizer was installed using the setup installer an optional desktop icon can be used to launch the app.
- **macOS**
Double click on the **DbVisualizer** application or the **DbVisualizer.app** application bundle.

You can also start DbVisualizer with the bundled script files, please see the [GUI Command Line Arguments](#) page for details. For tasks that do not require a GUI, such as tasks scheduled via the operating system's scheduling tool, you can also use the [pure command line interface](#).

2.4 Evaluating the Pro Edition

The DbVisualizer Pro edition offers far more features than the Free edition. If you are using the Free edition, it is easy to activate a Pro edition evaluation to see if suits your needs:

1. Open **Help->Evaluate Pro Edition**



2. Enter your email address and click **Evaluate**,
3. Click **Restart** when prompted after the activation of the evaluation.

i If you start DbVisualizer with one of the bundled scripts rather than with the launcher, you need to manually restart DbVisualizer after the activation.

2.5 Installing a Pro Edition License

To enable the Pro edition features, you need to install the License Key String or License Key File that you received after purchasing the license.

- [Installing a License Key String](#)
- [Installing a License Key File](#)
- [Uninstalling the license key](#)
- [DbVisualizer Pro, license file location](#)

2.5.1 Installing a License Key String

1. Select and copy the License Key String included in the email,
2. Start DbVisualizer and select the **Help->License Key** main menu choice,
3. Select License Key String as the **License Type**,
4. Paste the key string into the text area,
5. Click **Install License**,
6. Restart DbVisualizer when prompted to do so.

The DbVisualizer main window should now say **DbVisualizer Pro** in the window title. You're ready to go.

2.5.2 Installing a License Key File

1. Save the *dbvis.license* file attached to the email to disk,



2. Start DbVisualizer and select the **Help->License Key** main menu choice,
3. Select License Key File as the **License Type**,
4. In the **License Key File** field, enter the path to the newly saved *dbvis.license* file or click the button to the right of the field to open a file browser to locate the file,
5. Click **Install License**,
6. Restart DbVisualizer when prompted to do so.



An option to saving the *dbvis.license* file to disk is to drag it from your mail application (or elsewhere) into the **License Key File** field in the **Help->License Key** window.

The DbVisualizer main window should now say DbVisualizer Pro in the window title. You're ready to go.

2.5.3 Uninstalling the license key

If you ever need to uninstall the license key, you can do so by removing the license file. Its path is listed in [DbVisualizer Pro, license file location](#).

2.5.4 DbVisualizer Pro, license file location

The license key file for DbVisualizer Pro is located in the following paths depending on used operating system:

Operating System	Filename
Windows	<code>C:\Users\<user>\.dbvis\dbvis.license</code>
UNIX/Linux	<code>/home/<user>/.dbvis/dbvis.license</code>
macOS	<code>/Users/<user>/.dbvis/dbvis.license</code>

2.6 Creating a Connection - basics

To access a database with DbVisualizer, you must first create and setup a Database Connection. The easiest way to set up a connection is to use the Connection Wizard, but you can also do it manually.


- [Using the Connection Wizard](#)
- [Setting Up a Connection Manually](#)

2.6.1 Using the Connection Wizard

1. Launch the wizard from **Database->Create Database Connection** and click **Use Wizard** when prompted,




2. Enter a name for the connection on the first Wizard page and click **Next**,





3. Select an installed JDBC driver (marked with a green checkmark) on the second wizard page (see [Installing a JDBC Driver](#) for how to install a JDBC driver manually),





4. Enter information about the database server on the third wizard page (see below for details),

CRM Ahoa
(Oracle Thin)

Connection

Notes

Database

Settings Format Server Info

Connection Type Service

Database Server localhost

Database Port 1521

Service ORCL

Authentication

Database Userid

Database Password

Options

Auto Commit

Save Database Password Save Between Sessions


Permission Mode Development

SYS Role

Ping Server

< Back Finish Cancel

5. Verify that a network connection can be established to the specified address and port by clicking the **Ping Server** button,
6. If Ping Server shows that the server can be reached, click the **Finish** button to create the connection.
7. An Object View tab for the new connection is opened automatically. If the connection to the database can be established, the Connection Message area in the tab shows the database and driver versions, otherwise it shows a message about what is wrong.

 See [Fixing Connection Issues](#) for some tips if you have problems connecting to the database.

The information about the database server that needs to be entered depends on the which JDBC driver you use. For most drivers, you need to specify:

Field	Description
Database Server	The IP address or DNS name for the server where the database runs.
Database Port	The TCP/IP port used by the database.
Database Userid	The database user account name. Enter (null) to not send an account name.
Database Password	The database user account password. Enter (null) to not send a password.



For some database such as Oracle, you may use a [TNS name](#) instead of specifying the server and port. Other drivers may add more fields that are driver specific.

You may also optionally specify [SSH tunneling information](#) and Options, such as:

Option	Description
Auto Commit	Check if you want to enable auto commit in the SQL Commander by default for the connection.
Save Database Password	Check if you want the password to be saved (encrypted) during the session, between sessions, or cleared when you disconnect.
Permission Mode	One of Development , Test or Production to select which set of Permissions to use.


Additional options are available for some JDBC drivers, such as [Authentication Domain](#) for the SQL Server jTDS driver.

See the [Configuring Connection Properties](#) page for related topics.




2.6.2 Setting Up a Connection Manually

1. Create a new connection from **Database->Create Database Connection** and click **No Wizard** when prompted. An **Object View** tab for the new connection is opened,



2. Enter a name for the connection in the **Name** field, and optionally enter a description of the connection in the **Notes** field,
3. Leave the **Database Type** as **Auto Detect**,
4. Select an installed **JDBC driver** (marked with a green checkmark) from the Driver (JDBC) list (see [Installing a JDBC Driver](#) for how to install a JDBC driver manually),
5. Enter information about the database server in the remaining fields (see below for details),
6. Verify that a network connection can be established to the specified address and port by clicking the **Ping Server** button,
7. If Ping Server shows that the server can be reached, click **Connect** to actually connect to the database server.

 See [Fixing Connection Issues](#) for some tips if you have problems connecting to the database.

Alternatively, you can set the **Settings Format** to **Database URL** (this is the only choice for some custom JDBC drivers). This replaces the fields for information about the database server with a single **Database URL** field, where you can enter the JDBC URL.



The information about the database server that needs to be entered depends on the which JDBC driver you use. For most drivers, you need to specify:

Field	Description
Database Server	The IP address or DNS name for the server where the database runs.
Database Port	The TCP/IP port used by the database.
Database Userid	The database user account name. Enter (null) to not send an account name.
Database Password	The database user account password. Enter (null) to not send a password.

For some database such as Oracle, you may use a [TNS name](#) instead of specifying the server and port. Other drivers may add more fields that are driver specific.

You may also optionally specify [SSH tunneling information](#) and Options, such as:

Option	Description
Auto Commit	Check if you want to enable auto commit in the SQL Commander by default for the connection.
Save Database Password	Check if you want the password to be saved (encrypted) during the session, between sessions, or cleared when you disconnect.
Permission Mode	One of Development , Test or Production to select which set of Permissions to use.

Additional options are available for some JDBC drivers, such as [Authentication Domain](#) for the SQL Server jTDS driver.

See the [Configuring Connection Properties](#) page for related topics.

2.7 Creating a Table - basics



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

To create a new table:

1. Expand nodes in the **Databases** tab tree under the connection node until you reach the **Tables** node,



2. Select the **Tables** node and launch the **Create Table** dialog from the right-click menu:

Create Table

Create Table in Database Connection: HR Test Data

Database:

Schema: HR

Table: EMPLOYEES

Columns Primary Key Foreign Keys Unique Constraints Check Constraints

Name	Data Type	Size	Scale	Nullable	Default
EMPLOYEE_ID	INTEGER			<input type="checkbox"/>	
DEPARTMENT_ID	INTEGER			<input checked="" type="checkbox"/>	
NAME	VARCHAR2	30		<input checked="" type="checkbox"/>	
EMAIL	VARCHAR2	30		<input checked="" type="checkbox"/>	
ROOM	VARCHAR2	30		<input checked="" type="checkbox"/>	
SALARY	NUMBER	7	2	<input checked="" type="checkbox"/>	
PHOTO	BLOB			<input checked="" type="checkbox"/>	

Show SQL

Execute Cancel

SQL Preview

```
1 CREATE TABLE
2   "HR".EMPLOYEES
3   (
4     EMPLOYEE_ID INTEGER NOT NULL,
5     DEPARTMENT_ID INTEGER,
6     NAME VARCHAR2(30),
7     EMAIL VARCHAR2(30),
8     ROOM VARCHAR2(30),
9     SALARY NUMBER(7,2),
10    PHOTO BLOB
11  )
```

3. Add columns and constraints in the different tabs,
4. Click the **Execute** button to create the table.

You can learn more about the Create Table dialog in the [Creating a Table](#) page.

2.8 Viewing a Table - basics

To view details about a database table:

1. Expand nodes in the **Databases** tab tree under the connection node until you find the table,



2. Double-click on the table node to open its **Object View** tab.

Name	Value
OWNER	HR
TABLE_NAME	EMPLOYEES
TABLESPACE_NAME	USERS
CLUSTER_NAME	(null)
IOT_NAME	(null)
STATUS	VALID
PCT_FREE	10
PCT_USED	(null)
INI_TRANS	1
MAX_TRANS	255
INITIAL_EXTENT	65536
NEXT_EXTENT	(null)
MIN_EXTENTS	1
MAX_EXTENTS	2147483645
PCT_INCREASE	(null)
FREELISTS	(null)
FREELIST_GROUPS	(null)

The Object View has a number of sub tabs. Exactly which sub tabs are available depends on the database type, but these are common for all types:

Subtab	Description
Info	Brief information about the table.
Columns	Information about all table columns, e.g. data types and sizes.
Data	Then table data. Here you can view and edit the data.
Row Count	The number of rows in the table.
Primary Key	Information about the table's primary key columns, if any.
Indexes	Information about the table's indexes, if any.
Grants	Information about granted privileges for the table.
DDL	Shows the CREATE statement for the table.
References	Shows declared primary/foreign key relationships to other tables. Please read more in Viewing Table Relationships .
Navigator	Navigate through the declared relationships. Please read more in Navigating Table Relationships .

2.9 Editing a Table - basics



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

To edit table data:

1. Expand nodes in the **Databases** tab tree under the connection node until you find the table, Double-click on the table node to open its **Object View** tab,



Open the **Data** sub tab

* EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALA
1	198 Donald	OConnell	DOCONNEL	650.507.9833	1999-06-21 00:00:00	SH_CLERK	
2	199 Douglas	Grant	DGRANT	650.507.9844	2000-01-13 00:00:00	SH_CLERK	
3	200 Jennifer	Whalen	JWHALEN	515.123.4444	1987-09-17 00:00:00	AD_ASST	
4	201 Michael	Hartstein	MHARTSTE	515.123.5555	1996-02-17 00:00:00	MK_MAN	
5	202 Pat	Fay	PFAY	603.123.6666	1997-08-17 00:00:00	MK_REP	
6	203 Susan	Mavris	SMAVRIS	515.123.7777	1994-06-07 00:00:00	HR_REP	
7	204 Hermann	Baer	HBAER	515.123.8888	1994-06-07 00:00:00	PR_REP	
8	205 Shelley	Higgins	SHIGGINS	515.123.8080	1994-06-07 00:00:00	AC_MGR	
9	206 William	Gietz	WGIEZT	515.123.8181	1994-06-07 00:00:00	AC_ACCOUNT	
10	100 Steven	King	SKING	515.123.4567	1987-06-17 00:00:00	AD_PRES	
11	101 Neena	Kochhar	NKOCHHAR	515.123.4568	1989-09-21 00:00:00	AD_VP	
12	102 Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13 00:00:00	AD_VP	
13	103 Alexander	Hunold	AHUNOLD	590.423.4567	1990-01-03 00:00:00	IT_PROG	
14	104 Bruce	Ernst	BERNST	590.423.4568	1991-05-21 00:00:00	IT_PROG	
15	105 David	Austin	DAUSTIN	590.423.4569	1997-06-25 00:00:00	IT_PROG	
16	106 Valli	Pataballa	VPATABAL	590.423.4560	1998-02-05 00:00:00	IT_PROG	
17	107 Diana	Lorentz	DLORENTZ	590.423.5567	1999-02-07 00:00:00	IT_PROG	
18	108 Nancy	Greenberg	NGREENBE	515.124.4569	1994-08-17 00:00:00	FI_MGR	
19	109 Daniel	Faviet	DFAVIFT	515.124.4169	1994-08-16 00:00:00	FI_ACCOUNT	

2. Edit column values directly in the grid, add and remove rows by clicking on the buttons in the toolbar,
3. Save the edited data by clicking on the **Save** button in the toolbar.



Note that if the table does not have any declared Primary Key, you will be prompted to select the column(s) that uniquely identify a row.

You can learn more about the editing features in [Editing Table Data](#).

2.10 Executing SQL - basics

To execute SQL statements:

1. Open an SQL Commander window from **SQL Commander->New SQL Commander** or by clicking the **New SQL Commander** button in the main toolbar,



The screenshot shows the DbVisualizer Pro 110 interface. The SQL editor area contains the following SQL statements:

```
1 SELECT * FROM ACTOR;  
2 SELECT CITY_ID, CITY, COUNTRY_ID FROM CITY;  
3  
4 -- SELECT * FROM PAYMENT;  
5
```

The result area displays the execution log and two result sets:

- Log: 3:1 [66] INS
- Result Set 1: ACTOR [200]
- Result Set 2: CITY [600]

* ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33

Annotations in the image point to the SQL editor and the result area.

2. Select the database connection, catalog and schema to use,
3. Enter the SQL statements in the editor area,
4. Execute the statements by clicking the **Execute** button in the toolbar or choosing **SQL Commander->Execute**,
5. The execution log and possible result sets are shown as tabs in the results area below the editor.


You can learn more about editing, saving and executing SQL statements in the [Working with SQL](#) section.

2.11 Checking for Updates

By default, DbVisualizer checks for new versions on a weekly basis. To change the interval or manually check for updates:




1. Open **Help->Check for Updates**,




2. Change the interval to one of **Every Start-Up**, **Daily**, **Weekly**, **Monthly** or **Never**, or click the **Check Now** button to see if there is a new versions available right now.

i If you are interested in getting information about **Beta** versions to help us fine tune upcoming versions, check the corresponding checkbox. By default, Beta versions are not considered when checking for updates (unless you are already running a Beta version).

If a newer version is available, a dialog is displayed from where you can install the new version, read release notes, or in case your license is not valid for the new version, open our purchase page in your web browser.



Upgrading the currently used version is done by clicking the **Upgrade** link in the above dialog and then follow the instructions.



i In some organizations, decisions about software versions and installation is handled as a centralized process and individual users are not allowed to upgrade or install software. The Check for Update feature and auto-update of new versions can be disabled by adding the following row in the *DBVIS-HOME/resources/dbvis-custom.prefs*:

dbvis.url.checkforupdate=

With this setting, the Check for Update will still appears in the **Help** menu but selecting it displays a message saying that the feature is disabled.

2.12 Printing

DbVisualizer supports printing of grids, graphs, charts and plain text, such as the content of an SQL Editor. The print dialog looks somewhat different depending on what is printed. In all cases, you launch the print dialog by clicking on the **Print** button in the toolbar for the object you want to print, or by choosing **Print** from the right-click menu. The right-click menu also contains a **Print Preview** choice, if you want to see what the printout will look like before you actually print.

- [Printer Setup](#)
- [Printing a Grid, a Chart and Plain Text](#)
- [Printing a Graph](#)
- [Print Preview](#)
 - [Grid](#)
 - [Graph](#)



2.12.1 Printer Setup

If you want to set the page orientation (e.g., portrait or landscape) and paper size, you must launch the Printer Setup dialog, using the **File->Printer Setup** main menu option, before you print. Printing varies widely between platforms, so even though the Print dialog (as opposed to the Printer Setup dialog) on some platforms also lets you choose a page orientation and other options, they may be ignored if specified in that dialog. The only supported way to specify the page orientation and other options is via the Printer Setup dialog.

2.12.2 Printing a Grid, a Chart and Plain Text

For a grid, chart and plain text, DbVisualizer launches the platform's native Print dialog, so it looks different on different platforms. The two options available on all platforms are a choice of printer and the page range. On some platforms, the dialog may offer additional options, but they may be ignored by DbVisualizer. Use the Printer Setup dialog to set other options besides which printer to use and the page range, as described above

When you print a grid in DbVisualizer, the grid is printed as it is shown on the screen, i.e., with the table headers, sort and primary key indicator, etc. It is printed as a screenshot that may span several pages, depending on the number of rows and columns that are printed. For a grid, the right-click menu contains a **Print Selection** choice that you can use if you just want to print selected rows and columns.



An alternative to printing a grid as a screenshot is to export the grid to HTML and then use a web browser to print it.

Printing a chart scales the chart to the size of the paper. Plain text is printed as-is and may span multiple pages, both in height and width.

2.12.3 Printing a Graph

Printing a graph adds a custom dialog before the native Print dialog is displayed. You can specify the number of rows (pages) and columns (pages) that the complete image will be split into. You can also select whether the view as it appears on the screen or the complete graph should be printed. If you run a dark theme, you are presented with an option to **Use Light Theme** (good for printing on white paper).


When you click OK, the native Print dialog is displayed, where you can select the printer.

2.12.4 Print Preview

Use the **File->Print Preview** feature to preview what the printout will look like before you actually print it.




Grid






Graph



If you run a dark theme, you may want to **Use Light Theme** theme for printing the graph (good for printing on white paper).



3 Getting the Most Out of the GUI

DbVisualizer has a tab-based user interface that gives you a lot of control over the layout and how to work with your database objects. This section describes how you can open as many tabs as you need, arrange them to focus on what is important to you, and more.

3.1 Main Window Layout

The DbVisualizer GUI main window contains a navigation area to the left and an area for working with database objects and scripts to the right.

At the top of the window, you find the main menus and a toolbar.



ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
6	BETTE	NICHOLSON	2006-02-15 04:34:33
7	GRACE	MOSTEL	2006-02-15 04:34:33
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
9	JOE	SWANK	2006-02-15 04:34:33
10	CHRISTIAN	GABLE	2006-02-15 04:34:33
11	ZERO	CAGE	2006-02-15 04:34:33
12	KARL	BERRY	2006-02-15 04:34:33
13	JIMA	WOOD	2006-02-15 04:34:33

Tooltips are used to provide more details about a component throughout the GUI. They are also used to express status information. An example is the grid column header tooltip that shows information about the column. To see a tooltip, let the mouse hover over an area of the user interface, e.g., a button or grid header. If there is a tooltip for the area, it will pop up in about a second.

ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
6	BETTE	NICHOLSON	2006-02-15 04:34:33
7	GRACE	MOSTEL	2006-02-15 04:34:33
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
9	JOE	SWANK	2006-02-15 04:34:33
10	CHRISTIAN	GABLE	2006-02-15 04:34:33
11	ZERO	CAGE	2006-02-15 04:34:33
12	KARL	BERRY	2006-02-15 04:34:33
13	JIMA	WOOD	2006-02-15 04:34:33

3.2 Tab Types

There are three main types of tabs in DbVisualizer:


- Navigation Tabs
- Object View Tabs




-
- [SQL Commander Tabs](#)

3.2.1 Navigation Tabs

The left part of the DbVisualizer window holds a navigation area with three tabs: **Databases**, **Scripts** and **Favorites**. They all contain an object tree where you can select the objects you want to work with and optionally filter and/or sort the nodes (right-click any node and select **Sort ...**).





The **Databases** tab tree contains your database connections at the top and, when connected, the database objects they contain. If you have many database connections, you can also create folder objects in this tree to organize them.

The **Scripts** tab tree contains Bookmarks and Monitors, see the [Managing Frequently Used SQL](#) and the [Monitoring Data Changes](#) pages for details.

Finally, the **Favorites** tab tree contains objects that you want to have easy access to, either database objects (such as tables, views, or procedures) or scripts. You can read more about Favorites in the [Favorites](#) page.

3.2.2 Object View Tabs

An **Object View** tab shows information about a database object, such as the data and DDL for a table, or the source code for a stored procedure. The different types of information are shown as sub tabs within the Object View tab.

*	film_id	title	release_year	language_id	original_language_id	rental_duration	rental_rate	length
1	1	ACADEMY DINOSAUR	2006-01-01	1	(null)	6	0.99	8
2	2	ACE GOLDFINGER	2006-01-01	1	(null)	3	4.99	4
3	3	ADAPTATION HOLES	2006-01-01	1	(null)	7	2.99	5
4	4	AFFAIR PREJUDICE	2006-01-01	1	(null)	5	2.99	11
5	5	AFRICAN EGG	2006-01-01	1	(null)	6	2.99	13
6	6	AGENT TRUMAN	2006-01-01	1	(null)	3	2.99	16
7	7	AIRPLANE SIERRA	2006-01-01	1	(null)	6	4.99	6
8	8	AIRPORT POLLOCK	2006-01-01	1	(null)	6	4.99	5
9	9	ALABAMA DEVIL	2006-01-01	1	(null)	3	2.99	11
10	10	ALADDIN CALENDAR	2006-01-01	1	(null)	6	4.99	6



3.2.3 SQL Commander Tabs

An SQL Commander tab contains an editor for editing SQL scripts, controls for executing the script and a results area with a **Log** tab and possibly **Result Set** tabs showing results from queries, and a **DMBS Output** tab for databases such as Oracle and DB2 LUW.

The screenshot shows the SQL Commander interface. At the top, there are tabs for 'Test MySQL: actor' and '4: Untitled*'. Below the tabs is a toolbar with various icons for execution and editing. The main area is divided into two panes. The left pane contains the SQL editor with the following text:

```
1 select * from actor;  
2 select * from film;
```

The right pane shows the results of the query, which is a table with the following data:

*	actor_id	first_name	last_name	last_update	photo
1	1	PENELOPE	GUINNESS	2006-02-15 04:34:33	(null)
2	2	NICK	WAHLBERG	2020-02-14 14:52:01	BINARY, 32,952 Bytes
3	3	ED	CHASE	2006-02-15 04:34:33	(null)
4	4	JENNIFER	DAVIS	2006-02-15 04:34:33	(null)

3.3 Opening a Tab

3.3.1 Database tree objects

You can open an object by double-clicking on the object node, or by pressing **Enter** with the node selected, in all navigation tab trees. This opens either an Object View tab or an SQL Commander tab, depending on the object type: database object or script.

By default, a database object is opened in an Object View tab that is "available," meaning it is not pinned, busy running a task, or contains pending edits. The current tab is chosen if it is available, otherwise any other available tab is used. If none of the tabs is available, a new tab is created for the object. You can change this behavior in the **General/Tabs** category in **Tools->Tool Properties**, so that a new tab is always used instead of using an available tab.

If a tab is already open for the object, it is made the active tab. An alternative to double-clicking a database object is to use the **Open in Tab** choice from the node's right-click menu. **Open in Tab** is also available in the **Open Object** drop-down menu button in the **Databases** tab toolbar.

If you want to open a database object in a new tab instead of an available tab, hold down the **Alt** key when you double-click the node, use the **Open in New Tab** choice from the node's right-click menu or from the **Open Object** drop-down menu button in the **Databases** tab toolbar. The drop-down button keeps the last choice as the default, so once you have selected **Open in New Tab** once, you only need to click the button to do the same.

Both **Open in Tab** and **Open in New Tab** can also be used when multiple nodes are selected in the tree to open multiple tabs in one go.

To replace the content in a specific **Object View** tab with information for another object, drag the node for the new object from the object tree and drop it on the **Object View** tab header.

The behaviour when double clicking a Database object can be configured in **Tools->Tool Properties and in General / Database Objects Tree**.

3.3.2 Scripts and Monitors

Scripts (Bookmarks and Monitors) are always opened in a new **SQL Commander** tab unless the script is already opened in a tab. If so, that tab is activated instead. An alternative to double-clicking the node is to use **Open in SQL Commander** in the right-click menu or the corresponding button in the **Scripts** tab toolbar. The right-click menu also holds an **Open in SQL Commander and Execute** choice.

A new, empty SQL Commander tab is created by clicking the **Create SQL Commander** button in the main toolbar or using the corresponding **File** menu item. You can use this kind of **SQL Commander** tab for ad-hoc statement execution or to create a new script.

SQL Commander tabs can also be opened for files in the file system. Click the **Open File** button in the main toolbar or choose **File->Open** to open the file chooser window and select one of more files. Alternatively, you can drag files from your platform's file browser and drop them in the main toolbar area.

In addition see also [Synchronizing object tab selection and selection in the tree](#) which shows how to set up DbVisualizer to automatically select the database tree node when the corresponding object view tab is selected and vice versa.

**Only in DbVisualizer Pro**

Multiple SQL Commander tabs are only available in the DbVisualizer Pro edition.

3.4 Pinning a Tab

To prevent an Object View tab to be reused for another object or to prevent any tab to be removed unless you explicitly asks for it, you can "pin" it. In the right-click menu for a tab you find a **Pin Tab** toggle to accomplish this. A red pin icon is added to the icon when pinned.

You can also click on the icon in the tab header as a shortcut for toggling between the "pinned" and "unpinned" states.

3.5 Closing a Tab

A top level tab and a **Result Set** tab in an **SQL Commander** tab can be closed by clicking the cross to the right of the tab label, or clicking the tab header with the middle mouse button.


If you want to close a number of tabs at the same time, you can use the tab header menu choices:

Close Tab	Close just the current tab.
Close Other Tabs	Close all tabs except the current tab.
Close Closeable Tabs	Close all tabs that are in a state where they can be closed with no action required by the user, e.g. not pinned and no pending edits.
Close All Pinned Tabs	Close all pinned tabs.
Close All Tabs	Close all tabs, regardless of state

You can also **hide Object View** sub tabs that you are not interested in. Use the **Close Tab** right-click menu choice to do so. To see the hidden tabs again, use **Restore Hidden Tabs** in the right-click menu.

3.6 Listing Open Tabs


If you have many tabs opened, there may not be room enough to show them all at the same time. In this case, you can scroll through them using the arrow buttons that appear to the right of the tabs. It is, however, often faster to locate the tab you want to work with by clicking the list icon next to the arrow buttons. This brings up a list of all open tabs so you can select the one you want directly.



3.7 Maximizing and Minimizing a Tab

The three Navigation tabs can be minimized either by double-clicking on the tab header or using **Minimize Tab** in the tab's right-click menu. Clicking on a minimized tab brings it back to its regular place and size again.

All other tabs can be maximized by double-clicking on the tab header or using **Maximize Tab** in the tab's right-click menu. When you maximize a tab, the Navigation tabs are minimized to make as much room as possible available and the tab you maximized fills all available space. Double-clicking on the the tab again restores all tabs back to their original size. The latter can also be accomplished by deselecting the **Maximize Tab** right-click item.



An icon in the main status bar indicates when a tab is maximized. An alternative for restoring the original size of all tabs is to double-click on this icon.

3.8 Floating a Tab

Sometimes it is handy to break up the user interface in multiple freestanding windows. Every tab in DbVisualizer can be placed in a separate window by "floating" the tab. Use the **Floating** menu choice in the tab header right-click menu to float the tab in a separate window. An alternative is to drag the tab outside of the window. To dock the tab with the original location, right-click the tab and deselect **Floating**.

Closing a top level floating window will for **Object View** and **SQL Commander** tabs ask whether to really close the tab as it is then closed permanently and will not be restored in the DbVisualizer window. Closing an Object View sub tab, will hide the tab. To restore it, right-click another sub tab and select **Restore Hidden Tabs**.

3.9 Rearranging Tabs

You can move the tabs around by drag and drop. This allows you to see the content of multiple tabs at the same time

When you drag a tab, an outline of the tab borders shows what will happen when you drop it: place it in above, below or next to another tab, or simply move it to another location among its siblings.



The screenshot shows the DbVisualizer Pro 110 interface. At the top, there's a menu bar (File, Edit, View, Database, SQL Commander, Tools, Window, Help) and a toolbar. Below that, a 'Databases' panel shows 'H2' as the selected database and 'SAKILA' as the schema. A 'Scripts' panel contains a SQL query:

```
1 SELECT * FROM ACTOR;  
2 SELECT CITY_ID, CITY, COUNTRY_ID FROM CITY;  
3  
4 -- SELECT * FROM PAYMENT;  
5
```

Below the query is a 'Favorites' panel with two data tables:

* ACTOR_ID	FIRST_NAME	LAST_NAME
1	PENELOPE	GUINNESS
2	NICK	WAHLBERG
3	ED	CHASE
4	JENNIFER	DAVIS
5	JOHNNY	LOLLOBRIGIDA
6	BETTE	NICHOLSON
7	GRACE	MOSTFI

* CITY_ID	CITY	COUNTRY_ID
1	A Corua (La Corua)	
2	Abha	
3	Abu Dhabi	
4	Acua	
5	Adana	
6	Addis Abeba	
7	Aden	

At the bottom, there are status bars for each table showing execution time and row counts. The right side of the interface has a vertical toolbar with 'SQL Editor' and 'Query Builder' buttons.

The tab header right-click menu also has a couple of choices for arranging all tabs at the same level as either "tiled" (the content of all tabs visible side-by-side) or "collapsed" (only the content of the active tab visible).



The screenshot displays the DbVisualizer Pro 11.0 interface for the 'H2: COUNTRY' table. The main workspace is split into two panes: 'Columns' and 'Data'. The 'Columns' pane shows the table structure with columns: SCHEM, TABLE_NAME, COLUMN_NAME, and DATA_TYPE. The 'Data' pane shows the table data with columns: COUNTRY_ID, COUNTRY, and LAST_UPDATE. Below the workspace is a 'DDL' pane showing the SQL code for creating the COUNTRY table.

```

1 CREATE TABLE
2   COUNTRY
3   (
4     COUNTRY_ID SMALLINT NOT NULL IDENTITY,
5     COUNTRY    VARCHAR(50) NOT NULL,
6     LAST_UPDATE TIMESTAMP DEFAULT CURRENT_TIMESTAMP NOT NULL,
7     PRIMARY KEY (COUNTRY_ID)

```

You can save your rearranged layout of an Object View tab so that it is applied for all objects of the the same type for the same database type. In the sub tab header right-click menu, just select **Save as Default Layout**. To restore the default layout, use **Reset to Factory Layout**.

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

3.10 Changing the Tab Label

The tab labels are set based on a pattern that you can change in **Tools->Tool Properties**, in the General/Tabs category. The pattern can also be changed by selecting the **Modify Tab Labelling** right-click menu for **Object View**, **SQL Commander**, and **Result Set** tabs.

You can also manually change the label for a single **Object View**, **SQL Commander**, and **Result Set** tabs, using the **Rename** menu choice in the tab right-click menu.

You can select one of the predefined patterns or create your own by editing the pattern. The variables available for these patterns are:

Variable	Available For	Description
\${connectionname}	All	Connection name
\${index}	All	A unique index for the tab in the tab group
\${userid}	All	Userid used for the connection
\${filename}	SQL Commander Tabs	Script filename, or "Untitled" if no file is loaded. The nofile option can be used to change "Untitled" to something else, e.g. \${filename nofile=No File} . Set it to blank to only show a label when a file is loaded, i.e. \${filename nofile=}



Variable	Available For	Description
<code>\${longfilename}</code>	SQL Commander Tabs	Absolute path for the script, or "Untitled" if no file is loaded. The nofile option can be used to show something else, see the \${filename} variable for details
<code>\${objectname}</code>	Object View Tabs	Object name
<code>\${objecttype}</code>	Object View Tabs	Object type, e.g. Table, View etc.
<code>\${catalog}</code>	Object View Tabs	The database (if any) for the currently open object
<code>\${schema}</code>	Object View Tabs	The schema (if any) for the currently open object
<code>\${editorindex}</code>	Result Set Tabs	The index for the parent SQL Commander tab
<code>\${rows}</code>	Result Set Tabs	Number of rows in the result set
<code>\${sql}</code>	Result Set Tabs	Part of the SQL statement that produced the result set
<code>\${table}</code>	Result Set Tabs	Name of the table (first if more than one) the result set comes from
<code>\${time}</code>	Result Set Tabs	Time when the result set was produced
<code>\${vendor}</code>	Result Set Tabs	Database vendor name

3.11 Selecting a Node for a Tab

To quickly navigate to and select the node in the **Databases** tab tree that an **Object View** tab belongs to, you can click on the object path in the Object View header area. Alternatively, you can use **Select in Databases Tab** in the tab right-click menu.

Similarly, you can navigate to the object represented by a Favorite object using its **Select Target Object** right-click menu choice. It selects the object in the **Databases** or **Scripts** tab, depending on the Favorite type.

For an **SQL Commander** tab that is associated with a connection, you can use **Select in Databases Tab** in the tab right-click menu to select the connection node.

It is also possible to automatically select the Node whenever its object view tab is clicked. This is done in **Tools->Tool Properties** under the **General / Database Objects Tree** category.

An alternative is by selecting the **Autoscroll FROM Object View tab** in the **Open selected object(s)** drop down in the toolbar of the **Databases** tab tree.

3.12 Preserving Tabs Between Sessions

If you often work with the same objects and a few scripts, you can ensure that the Object View and SQL Commander tabs for these objects remain open between DbVisualizer sessions.

1. Open **Tools->Tool Properties**,
2. Select the **Tabs** category,
3. Enable one or both of **Preserve SQL Commander tabs between Sessions** and **Preserve Object View tabs between Sessions**,
4. Click **Apply** or **OK** to apply the new settings.

This feature is enabled by default for SQL Commander tabs but not for Object View tabs.

The content of the SQL Commander tabs is saved at regular intervals so when you restart DbVisualizer, the content is the same as where you left off.

For Object View tabs, you can also enable **Preserve Object View tabs at Disconnect**. By default, Object View tabs for objects that belong to a connection are closed when it is disconnected.

3.13 Using Tab Colors and Borders



Only in DbVisualizer Pro


This feature is only available in the DbVisualizer Pro edition.



If you like to distinguish tabs and other GUI components for a specific connection from those of others, you can specify a tab background color and/or border to use for a connection. If you set these in the **Tools->Tool Properties** under the **Database / <database type> / Color and Borders** category, they apply to all connections with the corresponding database type. Therefore these properties are typically set in the **Properties** tab for a specific connection instead.

For the border, you can either select one of the predefined styles or specify a small image file to use for the border.

The selected color and border are also shown in the connection tab node in the Databases tab and in the Database Connection list in the SQL Commander.



3.14 Changing the GUI Appearance

To change how the DbVisualizer GUI is displayed:

1. Open **Tools->Tool Properties**,
2. Select the **Appearance** category under the **General** tab.

Under **Appearance** you can select a different Look and Feel and adjust the size and use of icons. You can also enable **Ask at Startup** to be prompted for which Look and Feel to use for each session, which may be useful if you often switch between a dark and a light Look and Feel.

In the subcategories **Fonts**, **Editor Styles** and **Colors** you can adjust the fonts used for different parts of the GUI and the colors used to highlight grid elements. Color choices are saved for the currently used look and feel.

The main **View** menu also contains a number of toggle controls for showing or hiding GUI elements, such as toolbars and status bars.

3.15 Changing Keyboard Shortcuts

You can define key bindings for almost all operations and editor commands in DbVisualizer. Key bindings are defined in **Tools > Tool Properties** under the General / **Key Bindings** category. Key bindings are grouped in **Key Maps**, each with an action list organised in folders; the **Editor Commands** folder lists all actions available in the SQL Commander editor and their current key bindings (in the **Key Bindings** list), the **Main Menu** folder contains



subfolders, each representing a main window menu and other folders group feature specific actions, such as actions to control the references graph, form editor, etc.

DbVisualizer includes a set of predefined key maps targeted for the supported operating systems. These key maps cannot be deleted or modified. To customize key bindings, copy an existing key map and make your changes.

For instance does the **Main Menu** folder contain actions in subfolders, each representing a main window menu, and the **Editor Commands** folder lists all actions available in the SQL editor. For each action the key binding(s) are defined in the **Key Bindings** column.

Key Bindings

Use these settings to define the key bindings in DbVisualizer. You must make a copy of an existing key map to alter key bindings. The **active** indicator highlights the current key map.

Keymaps

Default (active, read-only)	Set Active
Linux-UNIX (read-only)	Make Copy
macOS (read-only)	Remove
SQL Query Analyzer (read-only)	
TOAD (read-only)	

Default (read-only)

Keymap Settings

Search Action Search Key Bindin


Action	Key Bindings
Main Menu	
File	
Open	Ctrl O
Quick File Open	Ctrl+Alt O
Save	Ctrl S
Save As	Ctrl+Shift S
Save All	Ctrl+Alt S
Revert to Saved	
Compare to Saved	
New SQL Commander	Ctrl T
Open in Tab	Ctrl L
Open in New Tab	Ctrl+Alt L
Open in Floating Tab	Ctrl+Shift L
Close Window	Ctrl F4; Ctrl W
New Window	Ctrl+Alt N
Exit	Ctrl Q
Edit	
View	
Database	
SQL Commander	
Tools	

Ctrl+Alt O


Add Key Binding...
Edit...
Remove





All user defined key maps are stored in your `$HOME/.dbvis/config70/keymaps` directory. A key map file contains only the differences between the copied key map and the current. To create a new key map, select the map you want to copy and click the **Make Copy** button. The name of the copied keymap is suffixed with **_copy and is activated automatically**. Set a name on the new key map if you like. The newly created key map now has the exact same key bindings as the parent key map.




To modify the key bindings for an action, select the action from the action list. The current key bindings are listed in the **Key Bindings** list, and you can search for mappings by action or key binding.



The modifier keys **Shift**, **Alt**, **Ctrl** and **Command** can be used to define the key binding. The keystroke dialog controls whether a key binding is already assigned somewhere else. If there is a conflict with another binding, the **Conflicts** area shows the names of the actions that are conflicting.



i Menu items and tooltips show the first defined key binding in the list.





3.16 Internationalization and Localization (i18N and L10N)

DbVisualizer is currently available in US English and supports user data in more or less any language or character encoding; DbVisualizer leverages the character sets supported by the Java VM, the fonts supported by the operating system, and the character encoding capabilities of the database to read, write, and render user data. You can also set your own preferences for date and time formats (see [Changing the Data Display Format](#)).

3.16.1 Fonts and Character Sets


Depending on which platform you run (Windows, Unix/Linux, macOS) and what character set you want to use, you may have to change the font settings.

DbVisualizer offers two settings for fonts:

- **Grids:** controls the font for GUI components where a proportional font is usually preferred (see [Changing the GUI Appearance](#)).
- **Text Editors:** controls the font for editors, log files, and other components where a monospaced font is usually preferred (see [Editing SQL Scripts - Font Settings](#)).

Example:

If you run Microsoft Windows and want to name your database connections using simplified Chinese, you will have to change the default font for **Grids** to one that supports this character set. In this example, we use Microsoft YaHei UI:



4 Managing Database Objects

4.1 Opening a Database Object


To open an **Object View** tab with the details for a database connection or for a specific database object, the simplest way is to double-click the object node in the **Databases** tab. For more information about opening tabs, check the [Opening a Tab](#) section.

4.2 Perform Actions on Multiple Database Objects


The actions menu for a database object in the **Databases** tab consists of actions that are available for the selected object type. Some of the operations are common for any currently selected object while others are only available for the current object. Sometimes it is convenient to run a single action on



multiple nodes at once. To do this, select the nodes (make sure all are of the same object type) and then right-click in the object list. The menu will now highlight those actions that are valid to use.



Choosing for example the **Drop Table** action shows the following window in which the drop can then be performed on multiple tables.



4.3 Filtering Database Objects

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

- [Object Filtering](#)
 - [Inline Objects Filtering](#)
- [Object Type Visibility](#)
- [Temporarily Disable Filtering](#)
- [Filter Sets](#)
 - [Switching Filter Set](#)
- [Show Only Default Database/Schema filter](#)

Managing what database objects are listed in the **Databases** tab is done at two levels:

1. **Objects Filtering**
Defines what individual object nodes are listed for a specific object type. This allows filtering on for example Table objects so that only tables matching a condition are listed.
2. **Object Type Visibility**
Defines what object types such as views, tables, indexes, procedures, etc. are listed. Every database in DbVisualizer supports all sorts of database objects. Having the ability to hide some object types makes it easier to locate the database objects that are of primary interest.

The **Filter Editor** is used to manage both object type visibility and object filters. The Filter Editor is opened from one of:

- **Database** main menu and the **Database Objects Filters->Open Filter Editor**
- Right-click in the **Databases tab** and choose **Database Objects Filters->Open Filter Editor**
- Click the drop-down button on the funnel icon in the **Databases tab** toolbar and choose **Open Filter Editor**.

i Managing filters and opening the filter editor requires that a node is selected in the Databases tab tree and that the related database connection is connected.



Database Objects Filters for Oracle

Filter set: default for Oracle

Show: **Filters** Labels

<input checked="" type="checkbox"/>	Object Type	Filter(s)
<input checked="" type="checkbox"/>	Oracle	
<input checked="" type="checkbox"/>	Schemas	
<input checked="" type="checkbox"/>	Schema	<input checked="" type="checkbox"/> Label beginWith HR; Name [TABLE_SCHEM] equal \${#db.loginSchema}
<input checked="" type="checkbox"/>	Tables	
<input checked="" type="checkbox"/>	Table	<input checked="" type="checkbox"/> Label in [CONTACTS;COUNTRIES;CUSTOMERS;EMPLOYEES;INVENTORIES;LOCATIO
<input checked="" type="checkbox"/>	GlobalTempTables	
<input checked="" type="checkbox"/>	Views	
<input checked="" type="checkbox"/>	Synonyms	
<input checked="" type="checkbox"/>	Indexes	
<input checked="" type="checkbox"/>	Sequences	
<input checked="" type="checkbox"/>	MaterializedViews	
<input checked="" type="checkbox"/>	Functions	
<input checked="" type="checkbox"/>	Procedures	
<input checked="" type="checkbox"/>	Packages	
<input checked="" type="checkbox"/>	PackageBodies	
<input checked="" type="checkbox"/>	JavaSources	
<input checked="" type="checkbox"/>	JavaClasses	
<input checked="" type="checkbox"/>	Triggers	
<input checked="" type="checkbox"/>	ObjectTypes	
<input checked="" type="checkbox"/>	ObjectTypeBodies	
<input checked="" type="checkbox"/>	RecycleBin	
<input checked="" type="checkbox"/>	Jobs	
<input checked="" type="checkbox"/>	Scheduler	
<input checked="" type="checkbox"/>	DatabaseLinks	
<input checked="" type="checkbox"/>	InvalidObjects	

ANY ALL

<input type="checkbox"/>	Field	Condition	Value
<input checked="" type="checkbox"/>	Label	is in	CONTACTS;COUNTRIES;CUSTOMERS;EMPLOYEES;INVENTORIES;LOCATIONS;ORDERS;ORDER_ITEMS;PROD

OK

The upper list shows all available object types for the actual database connection. The leading **check mark** controls whether the object type should be visible in the Databases tab. Read more in the [Object Type Visibility](#) section. The **Filter(s)** column shows any filters defined for each object type. A **green check mark symbol** indicate that at least one filter is active while a **yellow cone symbol** indicate that all filters for the object type are deactivated. Selecting an object type enables the objects filtering area in the lower part of the window. Here individual filters are defined for an object type.




4.3.1 Object Filtering

Object filtering can be made on any database object (**Table, Function, Procedure, User**) except for grouping objects such as **Tables, Functions, Procedures, Users**. Grouping objects in DbVisualizer are often labeled with the related object type name in plural.

i Object Filters for Database and Schema objects also apply to the corresponding drop-down lists in SQL Commander tabs, but only after a reconnect.

To setup a filter, select the object type in the objects list and in the filter area, click the button with a plus sign to insert a new row.



A filter entry consists of a field (e.g **Label**), a condition and a value to match against. Click the **condition** field to select the condition to use. In the **Value** field, enter the value that should be matched. For multi value conditions, such as **is in** and **isn't in**, the list of values are separated with a semicolon or edited in separate window that is opened by pressing the right-most icon in the input field.


Each individual filter can be deactivated using the **check mark**. Uncheck it and the corresponding filter will not be used unless reactivated. The currently defined filters are listed in the upper object type list for each object type. The leading symbol shows either a green check mark which indicates that some of its filters are active or a yellow cone symbol that shows that no filter is active.

You can define more than one filter. Just click the green plus or yellow star (to duplicate an existing row) buttons. If you have more than one active filter, you must also select if the filter should match **Any** or **All** filter entries.


Inline Objects Filtering

The filter area can also be displayed just below the objects tree in the **Databases** tab. This is convenient as you can then quickly manage and verify the effect of certain filters. To toggle the display of the filtering area, either click the left part of the funnel icon in the **Databases** tab toolbar or click the right menu arrow and select **Database Objects Filter->Show/Hide Filter Area**.

i Managing filters and opening the filter editor requires that a node is selected in the Databases tab tree and that the related database connection is connected.



In this example, the filter area is displayed with the filters for the **Tables** object type listed. When filters have been modified, you need to manually apply the filters using one of the **reload buttons** in the filter area toolbar or in the Databases tab toolbar. If a filter results in all object nodes being filtered, "**all filtered**" is displayed next to the parent object node in the tree. Since the filtered object type is now invisible as a result of the current filter, you need to disable the filter to refine it. Do this by selecting the parent node with the "**all filtered**" label and then click the "**Disable Filters**" link just below the objects tree:





Clicking "Disable Filters" deactivates all filters for the object type and you are now able to modify the filter to get the matches you want.

4.3.2 Object Type Visibility

Object type visibility is the functionality used to define what object types should be visible in the **Databases** tab. For some databases, the tree of object types can be really long and many objects are rarely used or of minor interest. By hiding object types, the tree is compressed to only show what you are really interested in. To control the visibility of object types, open the **Filter Editor**.

Database Objects Filters for Oracle

Filter set: default for Oracle

Show: Filters Labels

Object Type	Filter(s)
<input checked="" type="checkbox"/> Oracle	
<input checked="" type="checkbox"/> Schemas	
<input checked="" type="checkbox"/> Schema	<input checked="" type="checkbox"/> Label beginWith HR; Name [TABLE_SCHEM] equal \${#db.loginSchem}
<input checked="" type="checkbox"/> Tables	
<input type="checkbox"/> GlobalTempTables	
<input checked="" type="checkbox"/> Views	
<input type="checkbox"/> Synonyms	
<input type="checkbox"/> Indexes	
<input type="checkbox"/> Sequences	
<input type="checkbox"/> MaterializedViews	
<input checked="" type="checkbox"/> Functions	
<input checked="" type="checkbox"/> Procedures	
<input type="checkbox"/> Packages	
<input type="checkbox"/> PackageBodies	
<input type="checkbox"/> JavaSources	
<input type="checkbox"/> JavaClasses	
<input checked="" type="checkbox"/> Triggers	
<input type="checkbox"/> ObjectTypes	
<input type="checkbox"/> ObjectTypeBodies	
<input type="checkbox"/> RecycleBin	
<input type="checkbox"/> Jobs	
<input type="checkbox"/> Scheduler	
<input type="checkbox"/> DatabaseLinks	
<input type="checkbox"/> InvalidObjects	
<input type="checkbox"/> Properties	
<input type="checkbox"/> DBA	

ANY ALL

Field	Condition	Value
Select an object to setup filters		

OK




The previous image shows the object types available under a **Schema** in Oracle. As you can see, there are plenty of them. (Their sub object types are collapsed in the example for better illustration). The following example shows the database tree in the Databases tab before and after the visibility has been set based on the previous screenshot.



4.3.3 Temporarily Disable Filtering

While browsing the objects in the Databases tab, it may be convenient to quickly toggle between the standard non filtered view and the filtered view of objects and types. This is easily accomplished with the **Disable Filtering** action in the funnel drop-down menu. While filtering is disabled, the funnel symbol in the toolbar shows a red indicator and text in the inline filtering area shows the current status.



While filtering is disabled it is not possible to manage filters at all and the related actions are disabled.

i Disabling filters is applied per database connection. This means that if you disable the current filter set on a MySQL connection it won't affect any filters defined for other database connections.

4.3.4 Filter Sets

When you apply an object filter or hide an object type, that configuration is saved in a **Filter Set** that is saved between sessions. For every database connection, there is always a **default filter set**. If you are happy with the basic filtering capability you can stop reading here. If you however are interested in having multiple filter sets that can optionally be shared between multiple database connections and easily be switched between, keep on reading.


Filter sets are managed in the filter editor. Here you can create and delete filter sets and merge from another. Filter sets are either associated with a specific database connection, its name is then **default for <database connection name>** or a custom filter set that can be enabled for many connections, named as you like. A custom filter set is always associated with the database type currently being used for your database connection. The latter means that you are able to share filter sets that are all associated with the same database type. If you create a filter set for MySQL then this will never show up if you are working with an Oracle database.

The Filter Set drop-down in the filter editor shows the currently used filter set, and when clicked, the available filter sets that you may switch to.

The merge functionality (the blue merge arrow button) can merge not only from custom filter sets but also from the default filter sets associated with other database connections with the same database type.

Switching Filter Set

In the filter editor, you switch filter set by selecting one from the Filter Set drop-down. In the Databases tab, there is the funnel symbol which when clicked is used to toggle the display of the inline filter area. Clicking on the funnel drop-down symbol opens a menu:



At the top of the menu, the default filter set for the database connection is displayed first with any custom filter sets below it. An entry that is check marked indicates that it is active.

4.3.5 Show Only Default Database/Schema filter

There is a special filter used to filter any database and schema objects to show only the default for the session. It is listed as Show Only Default Database/Schema in the filter menu. When selected, a special filter is applied on the corresponding Database and/or Schema object type and the effect is what its name implies.

5 Working with Tables

DbVisualizer provides many ways to work with tables.

5.1 Creating a Table



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).


The Create Table dialog helps you create a table without writing SQL.

- [Opening the Create Table Dialog](#)
- [Columns Tab](#)
- [Primary Key Tab](#)
- [Foreign Keys Tab](#)
- [Unique Constraints Tab](#)
- [Check Constraints Tab](#)
- [Indexes Tab](#)
- [SQL Preview](#)
- [Execute](#)

5.1.1 Opening the Create Table Dialog

To create a new table:

1. Expand nodes in the tree under the connection node in the **Databases** tab tree until you reach the **Tables** node,
2. Select the **Tables** node and open the **Create Table** dialog from the right-click menu.



The **Create Table** dialog is organized in three areas from the top:

- **General Table Info**
Specifies the owning database connection, database and/or schema. These are picked up from the selection in the tree when the dialog is opened. Table name is set to a default name that you should change to the real table name.
- **Table Details**
A number of tabs where you specify information about the columns and, optionally, various constraints. The **Columns**, **Primary Key** and **Foreign Key** tabs are available for all databases. The remaining tabs are database-specific and depends on the features supported by the database engine.
- **SQL Preview**
The SQL previewer shows the SQL statement for creating the table based on your input.

5.1.2 Columns Tab

The **Columns** tab lists all table columns along with their attributes. The actual columns of the Columns tab is dependant on database. Additional columns may be shown for other databases. An example is Oracle and MariaDB which supports invisible columns and thus a column for setting this is shown.



Name	Data Type	Size	Scale	Nullable	Default
CUSTOMER_ID	SMALLINT			<input type="checkbox"/>	
STORE_ID	TINYINT			<input type="checkbox"/>	
FIRST_NAME	VARCHAR	45		<input type="checkbox"/>	
LAST_NAME	VARCHAR	45		<input type="checkbox"/>	
EMAIL	VARCHAR	70		<input checked="" type="checkbox"/>	NULL
ADDRESS_ID	SMALLINT			<input type="checkbox"/>	
ACTIVE	BOOLEAN			<input type="checkbox"/>	TRUE
CREATE_DATE	TIMESTAMP			<input type="checkbox"/>	
LAST_UPDATE	TIMESTAMP			<input checked="" type="checkbox"/>	CURRENT_TIMESTAMP

To add a column:

1. Click the **Add** button,
2. Enter the name of the column in the first field and select a data type from a drop down list in the second field, or start typing the data type name to find it and select it with the **Enter** key. The list contains the names of all data types the database supports,
3. For some data types, such as character types, you may also specify a size, i.e., the maximal length of the value. For others, like the decimal types, you can may specify both a size and a scale (the maximal number of decimals),
4. In the last two fields, specify if the table is nullable and a default value to use for rows inserted into the table without specifying a value for the column.

Below the column list, you may find additional fields depending on the features supported by the database you are working with, and the data type for the current column. The **Collation** field is shown for character columns if the database supports the declaration of a collation for textual data.

Name	Data Type	Size	Scale	Nullable	Default
customer_id	SMALLINT UNSIGNED		5	<input type="checkbox"/>	
store_id	TINYINT UNSIGNED		3	<input type="checkbox"/>	
first_name	VARCHAR		45	<input type="checkbox"/>	
last_name	VARCHAR		45	<input type="checkbox"/>	
email	VARCHAR		50	<input checked="" type="checkbox"/>	
address_id	SMALLINT UNSIGNED		5	<input type="checkbox"/>	
active	TINYINT		1	<input type="checkbox"/>	1
create_date	DATE TIME			<input type="checkbox"/>	
last_update	TIMESTAMP			<input type="checkbox"/>	CURRENT_TIMESTAMP

Collation:

The **Auto Increment** field, and possibly **Start With** and **Increment By** fields, are shown for numeric fields if the database supports automatically inserting the next available sequence number in a numeric column.



Name	Data Type	Size	Scale	Nullable	Default
CUSTOMER_ID	SMALLINT			<input type="checkbox"/>	
STORE_ID	TINYINT			<input type="checkbox"/>	
FIRST_NAME	VARCHAR	45		<input type="checkbox"/>	
LAST_NAME	VARCHAR	45		<input type="checkbox"/>	
EMAIL	VARCHAR	70		<input checked="" type="checkbox"/>	NULL
ADDRESS_ID	SMALLINT			<input type="checkbox"/>	
ACTIVE	BOOLEAN			<input type="checkbox"/>	TRUE
CREATE_DATE	TIMESTAMP			<input type="checkbox"/>	
LAST_UPDATE	TIMESTAMP			<input checked="" type="checkbox"/>	CURRENT_TIMESTAMP

Auto Increment: Start With: Increment By:

The **Create/Alter Table** dialog uses database metadata to try to enable only the fields that apply to the selected data type, but please note that it is not always possible. For instance, there is no metadata available to tell if a data type requires, or allows, a size. If you don't enter a required attribute or enter an attribute that is unsupported for a data type, you will get an error message when you click **Execute** to create/alter the table.

To remove a column:

1. Select a cell in the column row,
2. Click the **Remove** button.

To move a column to another location:

1. Select a cell in the column row,
2. Click the **Up** or **Down** buttons.

5.1.3 Primary Key Tab

The **Primary Key** tab contains information about an optional primary key for the table. A primary key is a column, or a combination of columns, that uniquely identifies a row in a table.

Column	Include
CUSTOMER_ID	<input checked="" type="checkbox"/>
STORE_ID	<input type="checkbox"/>
FIRST_NAME	<input type="checkbox"/>
LAST_NAME	<input type="checkbox"/>
EMAIL	<input type="checkbox"/>
ADDRESS_ID	<input type="checkbox"/>
ACTIVE	<input type="checkbox"/>

To declare a Primary Key:

1. Optionally enter a constraint name for the primary key constraint in the **Constraint Name** field,
2. Select the column(s) to be part of the primary key by clicking the checkboxes in the **Include** field in the columns list.

5.1.4 Foreign Keys Tab

In the **Foreign Keys** tab, you can declare one or more foreign keys for the table. A foreign key is a column, or a combination of columns, that refer to the primary key of another table. Foreign keys are used by the database to enforce integrity, i.e., that there is a row in the referenced table with a primary key



that matches the foreign key value when a new row is inserted or updated, and you can optionally declare rules for what to do when a referenced primary key is removed or updated in the referenced table.

The screenshot shows the 'Foreign Keys' tab in a database management tool. It features a 'Constraints' table with columns for 'Constraint Name', 'Columns', 'On Delete Action', and 'On Update Action'. Below this is a 'Referenced Table' section with dropdowns for 'Database' (SAKILA) and 'Table' (STORE). At the bottom is a 'Constraint Columns' table with columns for 'Column', 'Include' (checkbox), and 'Referenced Column' (pull-down menu).

Constraint Name	Columns	On Delete Action	On Update Action
FK_CUSTOMER_ADDRESS_ID	ADDRESS_ID	RESTRICT	CASCADE
FK_CUSTOMER_STORE_ID	STORE_ID	RESTRICT	CASCADE

Referenced Table

Database: SAKILA, Table: STORE

Column	Include	Referenced Column
CUSTOMER_ID	<input type="checkbox"/>	
STORE_ID	<input checked="" type="checkbox"/>	STORE_ID
FIRST_NAME	<input type="checkbox"/>	
LAST_NAME	<input type="checkbox"/>	
EMAIL	<input type="checkbox"/>	

The tab has the following sections:

- A list of foreign keys,
- Controls for selecting the table the currently selected foreign key refers to, including the database (catalog) and/or schema for the table,
- A list of all columns for the table being created/alterd.

To declare a new foreign key constraint:

1. Click the **Add** button next to the list of foreign keys,
2. Optionally enter a name for the foreign key in the first field in the list,
3. Select **On Delete** and **On Update** actions from the pull-down menus. The pull-down lists include all actions that the database support, typically CASCADE, RESTRICT, NO ACTION and SET NULL. The **Columns** field is read-only and gets its value automatically when you select which columns to include in the key later,
4. Use the **Referenced Table** controls to select the table that the foreign key refers to,
5. Check the **Include** checkbox for all columns in the column list that should be part of the foreign key and then select the corresponding column in the referenced table from the pull-down menu in the **Referenced Column** field.

You can change the column order for the key with the **Up** and **Down** buttons.

To remove an existing foreign key:

1. Select the foreign key in the list in the top section,
2. Click the **Remove** button.

5.1.5 Unique Constraints Tab

The **Unique Constraints** tab is only available for databases that support this constraint type. A unique constraint declares that the columns in the constraint must have unique values in the table.



The screenshot shows the 'Unique Constraints' tab. At the top, there are tabs for 'Columns', 'Primary Key', 'Foreign Keys', 'Unique Constraints', and 'Check Constraints'. The 'Unique Constraints' tab is active. Below the tabs, there are two main sections:

Constraints

Constraint Name	Columns
CUSTOMER_jx1	STORE_ID

Constraint Columns

Column	Include
CUSTOMER_ID	<input type="checkbox"/>
STORE_ID	<input checked="" type="checkbox"/>
FIRST_NAME	<input type="checkbox"/>
LAST_NAME	<input type="checkbox"/>
EMAIL	<input type="checkbox"/>
ADDRESS_ID	<input type="checkbox"/>
ACTIVE	<input type="checkbox"/>
CREATE_DATE	<input type="checkbox"/>
LAST_UPDATE	<input type="checkbox"/>

The top portion of the tab holds a list of all unique constraints, and the lower portion holds a list of all table columns.

To create a constraint:

1. Click the **Add** button,
2. Optionally enter a constraint name in the **Constraint Name** field. The **Columns** field in the constraints list is read-only, filled automatically as you include columns in the constraint,
3. Select the columns to be part of the constraint by clicking the checkboxes in the Include field in the columns list.

You can change the column order for the constraint with the **Up** and **Down** buttons.

To remove an existing constraint:

1. Select the constraint in the list in the top section,
2. Click the **Remove** button.

5.1.6 Check Constraints Tab

The **Check Constraints** tab is only available for databases that support this constraint type. A check constraint declares that a column value fulfills a certain condition when a row is inserted or updated. Some databases use check constraints to enforce nullability rules, so when you alter a table, you may see auto-generated check constraints for columns that you marked as not allowing null values in the **Columns** tab.

The screenshot shows the 'Check Constraints' tab. At the top, there are tabs for 'Columns', 'Primary Key', 'Foreign Keys', 'Unique Constraints', and 'Check Constraints'. The 'Check Constraints' tab is active. Below the tabs, there is a table with two columns: 'Constraint Name' and 'Condition'.

Constraint Name	Condition
CUSTOMER_ck1	EMAIL like '%@%'



To create a check constraint:

1. Click the **Add** button,
2. Optionally enter a constraint name in the **Constraint Name** field.
3. Enter the condition for the column in the **Condition** field. You can use the same type of conditions as you use in a SELECT WHERE clause.

To remove an existing constraint:

1. Select the constraint in the list,
2. Click the **Remove** button.

5.1.7 Indexes Tab

The **Indexes** tab is only used for the MySQL database, as a replacement for the **Unique Constraints** tab. The reason is that for MySQL, the CREATE TABLE statement can be used to declare both unique and non-unique indexes. MySQL also does not make a clear distinction between a unique constraint (a rule, most often enforced and implemented as an index by the database) and a unique index (primarily a database structure for speeding up queries, with the side-effect of ensuring unique column values), as most other databases do.

Constraint Name	Columns	Unique	Fulltext
idx_fk_store_id	store_id	<input type="checkbox"/>	<input type="checkbox"/>
idx_fk_address_id	address_id	<input type="checkbox"/>	<input type="checkbox"/>
idx_last_name	last_name	<input type="checkbox"/>	<input type="checkbox"/>

Column	Include
customer_id	<input type="checkbox"/>
store_id	<input checked="" type="checkbox"/>
first_name	<input type="checkbox"/>
last_name	<input type="checkbox"/>
email	<input type="checkbox"/>
address_id	<input type="checkbox"/>

The top portion of the tab holds a list of all indexes, and the lower portion holds a list of all table columns.

To create an index:

1. Click the **Add** button,
2. Optionally enter a name in the **Constraint Name** field. The **Columns** field in the constraints list is read-only, filled automatically as you include columns in the constraint,
3. If you want the index columns to have unique values for all rows in the table, click the checkbox in the **Unique** field,
4. Select the columns to be part of the index by clicking the checkboxes in the **Include** field in the columns list.

You can change the column order for the index with the **Up** and **Down** buttons.

To remove an existing index:

1. Select the index in the list in the top section,
2. Click the **Remove** button.

5.1.8 SQL Preview

The **SQL Preview** area is updated automatically to match the edits made in the assistant. To show the SQL Preview area check the **Show SQL** checkbox. The preview is read only, but you can copy the SQL to the SQL Commander and flip between formatted and unformatted views using the corresponding choices in the preview area right-click menu.

5.1.9 Execute

When you are satisfied with the table declaration, click the **Execute** button to create it.



5.2 Altering a Table



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

The Alter Table dialog helps you alter a table without writing SQL.

- [Opening the Alter Table Dialog](#)
- [Columns Tab](#)
- [Primary Key Tab](#)
- [Foreign Keys Tab](#)
- [Unique Constraints Tab](#)
- [Check Constraints Tab](#)
- [Indexes Tab](#)
- [SQL Preview](#)
- [Execute](#)

5.2.1 Opening the Alter Table Dialog

To alter an existing table:

1. Locate the table node in the **Databases** tab tree,
2. Select the table node and open the **Alter Table** dialog from the right-click menu.

Alter Table - H2/Schemas/SAKILA/Tables/CUSTOMER

Alter Table in Database Connection: H2

Database:

Schema: SAKILA

Table: CUSTOMER

Columns Primary Key Foreign Keys Unique Constraints Check Constraints

Name	Data Type	Size	Scale	Nullable	Default
CUSTOMER_ID	SMALLINT			<input type="checkbox"/>	
STORE_ID	TINYINT			<input type="checkbox"/>	
FIRST_NAME	VARCHAR	45		<input type="checkbox"/>	
LAST_NAME	VARCHAR	45		<input type="checkbox"/>	
EMAIL	VARCHAR	70		<input checked="" type="checkbox"/>	NULL
ADDRESS_ID	SMALLINT			<input type="checkbox"/>	
ACTIVE	BOOLEAN			<input type="checkbox"/>	TRUE
CREATE_DATE	TIMESTAMP			<input type="checkbox"/>	
LAST_UPDATE	TIMESTAMP			<input checked="" type="checkbox"/>	CURRENT_TIMESTAMP

Show SQL

Execute Cancel

SQL Preview

```
1 ALTER TABLE
2 "SAKILA"."CUSTOMER" ALTER COLUMN "EMAIL" VARCHAR(70) DEFAULT NULL
```

The **Alter Table** dialog is organized in three areas from the top:

- **General Table Info**
Specifies the owning database connection, database and/or schema, and table name. These are picked up from the selection in the tree when the assistant is started.



- **Table Details**
A number of tabs where you specify information about the columns and, optionally, various constraints. The **Columns**, **Primary Key** and **Foreign Key** tabs are available for all databases. The remaining tabs are database-specific and depends on the features supported by the database engine.
- **SQL Preview**
The SQL previewer shows the SQL statements for altering the table based on your input.

i The controls, such as the fields, pull-down menus and buttons, in the assistant are only enabled if the ALTER TABLE statement for the database holding the table provides a way to alter the corresponding table attribute. For instance, for a database that only allows the size of a VARCHAR column to be altered, the **Size** field in the **Columns** tab is disabled for all columns with other data types. If you find that you can not make the change you want, it is because the ALTER TABLE statement does not allow that change to be made.

5.2.2 Columns Tab

The **Columns** tab lists all table columns along with their attributes. The actual columns of the Columns tab is dependant on database. Additional columns may be shown for other databases. An example is Oracle and MariaDB which supports invisible columns and thus a column for setting this is shown.

Name	Data Type	Size	Scale	Nullable	Default
CUSTOMER_ID	SMALLINT			<input type="checkbox"/>	
STORE_ID	TINYINT			<input type="checkbox"/>	
FIRST_NAME	VARCHAR	45		<input type="checkbox"/>	
LAST_NAME	VARCHAR	45		<input type="checkbox"/>	
EMAIL	VARCHAR	70		<input checked="" type="checkbox"/>	NULL
ADDRESS_ID	SMALLINT			<input type="checkbox"/>	
ACTIVE	BOOLEAN			<input type="checkbox"/>	TRUE
CREATE_DATE	TIMESTAMP			<input type="checkbox"/>	
LAST_UPDATE	TIMESTAMP			<input checked="" type="checkbox"/>	CURRENT_TIMESTAMP

To add a column:

1. Click the **Add** button,
2. Enter the name of the column in the first field and select a data type from a drop down list in the second field, or start typing the data type name to find it and select it with the **Enter** key. The list contains the names of all data types the database supports,
3. For some data types, such as character types, you may also specify a size, i.e., the maximal length of the value. For others, like the decimal types, you can may specify both a size and a scale (the maximal number of decimals),
4. In the last two fields, specify if the table is nullable and a default value to use for rows inserted into the table without specifying a value for the column.

Below the column list, you may find additional fields depending on the features supported by the database you are working with, and the data type for the current column. The **Collation** field is shown for character columns if the database supports the declaration of a collation for textual data.



Name	Data Type	Size	Scale	Nullable	Default
customer_id	SMALLINT UNSIGNED		5	<input type="checkbox"/>	
store_id	TINYINT UNSIGNED		3	<input type="checkbox"/>	
first_name	VARCHAR	45		<input type="checkbox"/>	
last_name	VARCHAR	45		<input type="checkbox"/>	
email	VARCHAR	50		<input checked="" type="checkbox"/>	
address_id	SMALLINT UNSIGNED		5	<input type="checkbox"/>	
active	TINYINT		1	<input type="checkbox"/>	1
create_date	DATETIME			<input type="checkbox"/>	
last_update	TIMESTAMP			<input type="checkbox"/>	CURRENT_TIMESTAMP

Collation:

The **Auto Increment** field, and possibly **Start With** and **Increment By** fields, are shown for numeric fields if the database supports automatically inserting the next available sequence number in a numeric column.

Name	Data Type	Size	Scale	Nullable	Default
CUSTOMER_ID	SMALLINT			<input type="checkbox"/>	
STORE_ID	TINYINT			<input type="checkbox"/>	
FIRST_NAME	VARCHAR	45		<input type="checkbox"/>	
LAST_NAME	VARCHAR	45		<input type="checkbox"/>	
EMAIL	VARCHAR	70		<input checked="" type="checkbox"/>	NULL
ADDRESS_ID	SMALLINT			<input type="checkbox"/>	
ACTIVE	BOOLEAN			<input type="checkbox"/>	TRUE
CREATE_DATE	TIMESTAMP			<input type="checkbox"/>	
LAST_UPDATE	TIMESTAMP			<input checked="" type="checkbox"/>	CURRENT_TIMESTAMP

Auto Increment: Start With: Increment By:

The **Create/Alter Table** dialog uses database metadata to try to enable only the fields that apply to the selected data type, but please note that it is not always possible. For instance, there is no metadata available to tell if a data type requires, or allows, a size. If you don't enter a required attribute or enter an attribute that is unsupported for a data type, you will get an error message when you click **Execute** to create/alter the table.

To remove a column:

1. Select a cell in the column row,
2. Click the **Remove** button.

To move a column to another location:

1. Select a cell in the column row,
2. Click the **Up** or **Down** buttons.

5.2.3 Primary Key Tab

The **Primary Key** tab contains information about an optional primary key for the table. A primary key is a column, or a combination of columns, that uniquely identifies a row in a table.



Column	Include
CUSTOMER_ID	<input checked="" type="checkbox"/>
STORE_ID	<input type="checkbox"/>
FIRST_NAME	<input type="checkbox"/>
LAST_NAME	<input type="checkbox"/>
EMAIL	<input type="checkbox"/>
ADDRESS_ID	<input type="checkbox"/>
ACTIVE	<input type="checkbox"/>

To declare a Primary Key:

1. Optionally enter a constraint name for the primary key constraint in the **Constraint Name** field,
2. Select the column(s) to be part of the primary key by clicking the checkboxes in the **Include** field in the columns list.

5.2.4 Foreign Keys Tab

In the **Foreign Keys** tab, you can declare one or more foreign keys for the table. A foreign key is a column, or a combination of columns, that refer to the primary key of another table. Foreign keys are used by the database to enforce integrity, i.e., that there is a row in the referenced table with a primary key that matches the foreign key value when a new row is inserted or updated, and you can optionally declare rules for what to do when a referenced primary key is removed or updated in the referenced table.

Constraint Name	Columns	On Delete Action	On Update Action
FK_CUSTOMER_ADDRESS_ID	ADDRESS_ID	RESTRICT	CASCADE
FK_CUSTOMER_STORE_ID	STORE_ID	RESTRICT	CASCADE

Referenced Table

Database: SAKILA Schema: SAKILA Table: STORE

Column	Include	Referenced Column
CUSTOMER_ID	<input type="checkbox"/>	
STORE_ID	<input checked="" type="checkbox"/>	STORE_ID
FIRST_NAME	<input type="checkbox"/>	
LAST_NAME	<input type="checkbox"/>	
EMAIL	<input type="checkbox"/>	

The tab has the following sections:

- A list of foreign keys,
- Controls for selecting the table the currently selected foreign key refers to, including the database (catalog) and/or schema for the table,
- A list of all columns for the table being created/alterred.

To declare a new foreign key constraint:

1. Click the **Add** button next to the list of foreign keys,
2. Optionally enter a name for the foreign key in the first field in the list,
3. Select **On Delete** and **On Update** actions from the pull-down menus. The pull-down lists include all actions that the database support, typically CASCADE, RESTRICT, NO ACTION and SET NULL. The **Columns** field is read-only and gets its value automatically when you select which columns to include in the key later,
4. Use the **Referenced Table** controls to select the table that the foreign key refers to,
5. Check the **Include** checkbox for all columns in the column list that should be part of the foreign key and then select the corresponding column in the referenced table from the pull-down menu in the **Referenced Column** field.



You can change the column order for the key with the **Up** and **Down** buttons.

To remove an existing foreign key:

1. Select the foreign key in the list in the top section,
2. Click the **Remove** button.

5.2.5 Unique Constraints Tab

The **Unique Constraints** tab is only available for databases that support this constraint type. A unique constraint declares that the columns in the constraint must have unique values in the table.

The screenshot shows the 'Unique Constraints' tab in a database management tool. The top section, titled 'Constraints', contains a table with two columns: 'Constraint Name' and 'Columns'. A single constraint named 'CUSTOMER_ix1' is listed with the column 'STORE_ID'. The bottom section, titled 'Constraint Columns', contains a table with two columns: 'Column' and 'Include'. The 'Include' column has checkboxes for each of the following columns: CUSTOMER_ID, STORE_ID, FIRST_NAME, LAST_NAME, EMAIL, ADDRESS_ID, ACTIVE, CREATE_DATE, and LAST_UPDATE. The 'STORE_ID' row is highlighted in blue, and its checkbox is checked.

Constraint Name	Columns
CUSTOMER_ix1	STORE_ID

Column	Include
CUSTOMER_ID	<input type="checkbox"/>
STORE_ID	<input checked="" type="checkbox"/>
FIRST_NAME	<input type="checkbox"/>
LAST_NAME	<input type="checkbox"/>
EMAIL	<input type="checkbox"/>
ADDRESS_ID	<input type="checkbox"/>
ACTIVE	<input type="checkbox"/>
CREATE_DATE	<input type="checkbox"/>
LAST_UPDATE	<input type="checkbox"/>

The top portion of the tab holds a list of all unique constraints, and the lower portion holds a list of all table columns.

To create a constraint:

1. Click the **Add** button,
2. Optionally enter a constraint name in the **Constraint Name** field. The **Columns** field in the constraints list is read-only, filled automatically as you include columns in the constraint,
3. Select the columns to be part of the constraint by clicking the checkboxes in the Include field in the columns list.

You can change the column order for the constraint with the **Up** and **Down** buttons.

To remove an existing constraint:

1. Select the constraint in the list in the top section,
2. Click the **Remove** button.

5.2.6 Check Constraints Tab

The **Check Constraints** tab is only available for databases that support this constraint type. A check constraint declares that a column value fulfills a certain condition when a row is inserted or updated. Some databases use check constraints to enforce nullability rules, so when you alter a table, you may see auto-generated check constraints for columns that you marked as not allowing null values in the **Columns** tab.



Constraint Name	Condition
CUSTOMER_ck1	EMAIL like '%@%'

To create a check constraint:

1. Click the **Add** button,
2. Optionally enter a constraint name in the **Constraint Name** field.
3. Enter the condition for the column in the **Condition** field. You can use the same type of conditions as you use in a SELECT WHERE clause.

To remove an existing constraint:

1. Select the constraint in the list,
2. Click the **Remove** button.

5.2.7 Indexes Tab

The **Indexes** tab is only used for the MySQL database, as a replacement for the **Unique Constraints** tab. The reason is that for MySQL, the CREATE TABLE statement can be used to declare both unique and non-unique indexes. MySQL also does not make a clear distinction between a unique constraint (a rule, most often enforced and implemented as an index by the database) and a unique index (primarily a database structure for speeding up queries, with the side-effect of ensuring unique column values), as most other databases do.

Constraint Name	Columns	Unique	Fulltext
idx_fk_store_id	store_id	<input type="checkbox"/>	<input type="checkbox"/>
idx_fk_address_id	address_id	<input type="checkbox"/>	<input type="checkbox"/>
idx_last_name	last_name	<input type="checkbox"/>	<input type="checkbox"/>

Column	Include
customer_id	<input type="checkbox"/>
store_id	<input checked="" type="checkbox"/>
first_name	<input type="checkbox"/>
last_name	<input type="checkbox"/>
email	<input type="checkbox"/>
address_id	<input type="checkbox"/>

The top portion of the tab holds a list of all indexes, and the lower portion holds a list of all table columns.

To create an index:

1. Click the **Add** button,
2. Optionally enter a name in the **Constraint Name** field. The **Columns** field in the constraints list is read-only, filled automatically as you include columns in the constraint,



3. If you want the index columns to have unique values for all rows in the table, click the checkbox in the **Unique** field,
4. Select the columns to be part of the index by clicking the checkboxes in the **Include** field in the columns list.

You can change the column order for the index with the **Up** and **Down** buttons.

To remove an existing index:

1. Select the index in the list in the top section,
2. Click the **Remove** button.

5.2.8 SQL Preview

The **SQL Preview** area is updated automatically to match the edits made in the assistant. To show the SQL Preview area check the **Show SQL** checkbox. The preview is read only, but you can copy the SQL to the SQL Commander and flip between formatted and unformatted views using the corresponding choices in the preview area right-click menu.

5.2.9 Execute

When you are satisfied with the alterations, click the **Execute** button to create it.

5.3 Creating a Trigger



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

The Create Trigger dialog helps you create a trigger for a table.

- [Opening the Create Trigger Dialog](#)
- [Trigger Editor](#)

5.3.1 Opening the Create Trigger Dialog

To create a trigger for a table:

1. Locate the table in the **Databases** tab tree,



2. Select the table node and open the **Create Trigger** dialog from the right-click menu,

Create Trigger in Database Connection: H2

Schema: SAKILA

Trigger Name: MyTrigger

Trigger BEFORE: BEFORE AFTER INSTEAD OF

Trigger Type: INSERT UPDATE DELETE SELECT ROLLBACK

Table: COUNTRY

For each Row:

Source

```
1
2 Insert your own trigger code here
3
4
```

Show SQL Execute Cancel

SQL Preview

```
1 @delimiter %%;
2 CREATE TRIGGER
3 "SAKILA".MyTrigger AFTER
4 INSERT
5 ON
6 "SAKILA"."COUNTRY" FOR EACH ROW
7 --
8 -- Insert your own trigger code here
9 --
10;
```

3. Enter the required info in the fields, e.g. trigger name. The fields are database dependent so the figure is just an example,
4. The **Source** area contains stub code that you can later edit in the [Trigger Editor](#). For most databases you can leave it as is, but for some databases, you must adjust the stub code to match your database objects.
5. Click the **Execute** button to create the trigger

5.3.2 Trigger Editor

To edit the trigger code:

1. Expand the **Trigger** node for the table in the Databases tab tree,
2. Double-click the trigger node to open its **Object View** tab,
3. Open the **Trigger Editor** tab and [edit the code](#) in the editor,
4. Click the **Save** toolbar button to save (and for some databases, compile) the trigger.

If the database reports any errors, the location of the errors are highlighted with curly red underlines in the editor for most databases. Hovering the mouse over such an underline shows the error message.

The **Log** tab in the results area also lists all errors. Clicking on the icon next to an error message selects the corresponding line and positions the caret at the error location, if the database reports error locations.



5.4 Creating an Index



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

The Create Index dialog helps you create an index for a table without writing SQL.

To create an index for a table:

1. Locate the table in the **Databases** tab tree,
2. Select the table node and open the **Create Index** dialog from the right-click menu,

Create Index - H2/Schemas/SAKILA/Tables/CUSTOMER

Create Index in Database Connection: H2

Schema: SAKILA

Table: CUSTOMER

Index Name: MyIndex

Type: Non-unique Unique Primary Key

Columns

Column Name	Sort Order
FIRST_NAME	<input checked="" type="radio"/> ASC <input type="radio"/> DESC <input type="radio"/> Default

Show SQL

Execute Cancel

SQL Preview

```
1 CREATE UNIQUE INDEX
2   MyIndex
3 ON
4   "SAKILA"."CUSTOMER"
5   (
6     "FIRST_NAME" ASC
7   )
```

3. Enter the required info in the fields, e.g. index name. The fields are database dependent so for some databases there are additional fields compared to the figure,
4. Click the **Add** button in the **Columns** area to add an index column,
5. Select the column to index from the **Column Name** drop down list,
6. Select the sort order for the index column from the **Sort Order** radio buttons,
7. Click the **Execute** button to create the index.

To remove an index column:

1. Select the column row,
2. Click the **Remove** button.

To move an index column

1. Select the column row,
2. Click the **Up** and **Down** button to move it.



5.5 Viewing Table Data

i Some of the features and screenshots in this section are for the DbVisualizer Pro edition.

A table's data can be viewed in various ways in the **Data** tab in its **Object View** tab.

- [Opening the Data tab](#)
- [Formatting](#)
- [Sorting](#)
- [Where Filter](#)
- [Column Filter](#)
- [Quick Filter](#)
- [Max Rows/Max Chars](#)
- [Max Rows at First Display](#)
- [Column Header Tooltips](#)
- [Highlight Primary Key Columns](#)
- [Auto Resize Columns](#)
- [Show Only Some Columns](#)
- [Right-Click Menu Operations](#)
- [Creating Monitors](#)
- [Aggregation Data for Selection](#)

i Check [Editing Table Data](#) for information about the table data editor in DbVisualizer.

5.5.1 Opening the Data tab

To open the Data tab for a table:

1. Locate the table in the **Databases** tab tree,
2. Double-click the table node to open its **Object View** tab,
3. Open the **Data** sub tab.



	COUNTRY_ID	COUNTRY_NAME	REGION_ID
1	AR	Argentina	2
2	AU	Australia	3
3	BE	Belgium	1
4	BR	Brazil	2
5	CA	Canada	2
6	CH	Switzerland	1
7	CN	China	3
8	DE	Germany	1
9	DK	Denmark	1
10	EG	Egypt	4
11	FR	France	1
12	HK	HongKong	3
13	IL	Israel	4
14	IN	India	3
15	IT	Italy	1
16	JP	Japan	3
17	KW	Kuwait	4
18	MX	Mexico	2
19	NG	Nigeria	4

Each column width is automatically resized to match the column width, including the column header, by default. You can disable this behavior in the the Tool Properties dialog, in the **Grid** category under the General tab.

If **Auto Resize Column Widths** is enabled, the **Max Column Width** setting can be used to limit the column width so that an extremely wide column does not take up all space.

In the same Tool Properties category, you can also disable **Show Grid Row Header**, i.e. the row number shown to the left of the data rows, for read-only grids such as the Data tab in the DbVisualizer Free edition and result sets from joined tables.

The column headers corresponds to the column names by default, but you can specify in the Tool Properties dialog, in the Grid category under the General tab, that you like to use the column alias instead. This is mostly useful for grids representing SQL Commander result sets, but may also be useful in the Data tab grid for some databases.

The **Data** tab contains a number of features for locating and focusing on just the data of interest as described in the following sections.

5.5.2 Formatting

Note that when a cell is selected any format pattern used, to display the cell value is visible at bottom of the grid. By clicking the blue link the [Data Formats](#) section of **Tool Properties** will be opened.

5.5.3 Sorting

You can sort the data grid based on the values in one or more columns:


1. Click on a column header to sort the grid in ascending order on the values in that column, indicated by an up-arrow in the column header.
2. Click the same column header again to sort in descending order, indicated by a down-arrow in the column header.
3. Click a third time to show the data in the order it was received from the database. This removes the sort indicator.



To sort on more than one column, Ctrl-click (keep the Ctrl key pressed when clicking) on additional columns. The grid is then sorted on the values in the first column you clicked on (indicated with a 1 next to the arrow), and then all rows with the same value in the first column are sorted on the values in the second sort column (indicated with a 2 next to the arrow), and so on.

5.5.4 Where Filter

You can use the filter capability in the **Data** tab to limit the number of rows shown in the grid, using the same syntax as for an SQL WHERE clause. The Filter menu button in the grid toolbar contains all operations related to using a filter.




The top entries in the menu are previously used filters for the table, if any. The checkbox is selected for the filter that is currently in use. The filters are saved between DbVisualizer sessions, and you can toggle between them by selecting them from the menu. The maximum number of filters to save is specified in the Tool Properties dialog, in the **Table Data** category under the General tab.

You use the **Use No Filter** choice to disable all filters for the table, and the **Clear Filter List** to permanently remove all filters for the table.

To create a new filter:

1. Select **Open Filter Editor** to launch the **Filter & Sort Configuration** dialog,



2. Select a column name, an operation and the value for the condition using the controls in the **Filter** area,
3. Add the condition to the filter by clicking the **AND** or **OR** button, and create additional conditions in the same way if needed,
4. Click the **Use Filter** button to apply the filter, save it and close the dialog, or close the dialog without applying and saving the filter by clicking the **Close** button.

You can use **Ctrl-Enter** while editing the value field to reload the grid with that single condition applied, or in the editor to reload the grid based on all filter conditions created so far.

The **Sort** area is similar to the **Filter** area. You can select column names and sort order from the two lists, and click the **Add** button to add the sort criteria for the single column to the complete criteria.

If you often need to tweak the filter conditions and want a more compact user interface, you can use the inline filter view. Use the **Show/Hide Filter Area** choice in the **Filter** menu to toggle the visibility of the inline filter.



	COUNTRY_ID	COUNTRY_NAME	REGION_ID
1	AU	Australia	3
2	CN	China	3
3	EG	Egypt	4

5.5.5 Column Filter

Only in DbVisualizer Pro
This feature is only available in the DbVisualizer Pro edition.

The **Column Filter** acts on the data that is already loaded in the grid, as opposed to a **Where Filter** which is used to limit the number of rows fetched from the database. With a **Column Filter**, you can easily list only those rows having a column value matching the **Column Filter**. By customizing the filter it is possible to add more complex filters such as only listing rows where the column value does not contain a certain value or substring.

A **Column Filter is added** by clicking the right part of the column header. A column having a Column Filter is indicated by the presence of a filter icon in the column header.

It is possible to add **Column Filters** to multiple columns. For cases where you don't care which column has a specific value we recommend the [Quick Filter](#)

5.5.6 Quick Filter

Only in DbVisualizer Pro
This feature is only available in the DbVisualizer Pro edition.

The **Quick Filter** acts on the data that is already loaded in the grid, as opposed to a **Where Filter** which is used to limit the number of rows fetched from the database. With a **Quick Filter**, you can easily list only those rows in the grid that match the entered search string.

	COUNTRY_ID	COUNTRY_NAME	REGION_ID
1	AU	Australia	3
2	CN	China	3
3	IL	Israel	4
4	IN	India	3
5	JP	Japan	3
6	KW	Kuwait	4
7	NG	Nigeria	4
8	SG	Singapore	3
9	ZM	Zambia	4
10	ZW	Zimbabwe	4

- All
- COUNTRY_ID
- COUNTRY_NAME
- REGION_ID
- More...
- Case sensitive
- Case insensitive
- Use wild cards
- Use regular expression
- Match from start
- Match exactly
- Match anywhere



Use the Quick Filter pull-down menu (click on the down arrow next to the magnifying glass) to choose if the filter should match cells in all columns or just one selected column, case or case insensitive matching, and where in the cell the value must match.

For the **Use wild cards** option the following characters have special meaning:

- ? - The question mark indicates there is zero or one of the preceding element. For example, colour?r matches both "color" and "colour".
- * - The asterisk indicates there are zero or more of the preceding element. For example, ab*c matches "ac", "abc", "abbc", "abbbc", and so on.
- + - The plus sign indicates that there is one or more of the preceding element. For example, ab+c matches "abc", "abbc", "abbbc", and so on, but not "ac".

5.5.7 Max Rows/Max Chars

DbVisualizer limits the number of rows shown in the Data tab to 1000 rows, by default. This is done to conserve memory. If this limit prevents you from seeing the data of interest, you should first consider:

1. Using a [Where Filter](#) to only retrieve the rows of interest instead of all rows in the table,
2. [Exporting the table](#) to a file

If you really need to look at more than 1000 rows, you can change the value in the **Max Rows** field in the grid status bar. Use a value of 0 or -1 to get all rows, or a specific number (e.g. 5000) to set a new limit.

Character data columns may contain very large values that use up lots of memory. If you are only interested in seeing a few characters, you can set the **Max Chars** field in the grid status bar to the number of characters you want to see.

You can define how to deal with columns that have more characters than the specified maximum in the Tool Properties dialog, in the Grid category under the General tab. You have two choices: **Truncate Values** or **Truncate Values Visually**.

- **Truncate Values** truncates the original value for the grid cell to be less than the setting of Max Chars.



This affects any subsequent edits and SQL operations that use the value since it's truncated. This setting is only useful to save memory when viewing very large text columns.

- **Truncate Values Visually** truncates the visible value only and leave the original value intact. This is the preferred setting since it will not harm the original value. The disadvantage is that more memory is needed when dealing with large text columns.

When the grid data is limited due to either the **Max Rows** or **Max Chars** value, you get an indication about this in the rows/columns field in the grid status bar and in the corresponding limit field. The color is also changed for the affected controls.



Table: EMPLOYEES
Ora12C_HR/Schemas/HR/Tables/EMPLOYEES

Info Columns Data Row Count Primary Key Row Id References Navigator Grants Columns Comment Indexes Constraints

EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALARY	COMMISSION_PCT	MANAGER_ID	DEPARTMENT
100	Steven	King	SKING	515.123.45	2003-06-17 00:00:00	AD_PRES	24000	(null)	(null)	
101	Neena	Kochhar	NKOCHHAR	515.123.45	2005-09-21 00:00:00	AD_VP	17000	(null)	100	
102	Lex	De Haan	LDEHAAN	515.123.45	2001-01-13 00:00:00	AD_VP	17000	(null)	100	
103	Alexander	Hunold	AHUNOLD	590.423.45	2006-01-03 00:00:00	IT_PROG	9000	(null)	102	
104	Bruce	Ernst	BERNST	590.423.45	2007-05-21 00:00:00	IT_PROG	6000	(null)	103	
105	David	Austin	DAUSTIN	590.423.45	2005-06-25 00:00:00	IT_PROG	4800	(null)	103	
106	Valli	Pataballa	VPATABAL	590.423.45	2006-02-05 00:00:00	IT_PROG	4800	(null)	103	
107	Diana	Lorentz	DLORENTZ	590.423.55	2007-02-07 00:00:00	IT_PROG	4200	(null)	103	
108	Nancy	Greenberg	NGREENBE	515.124.45	2002-08-17 00:00:00	FI_MGR	12008	(null)	101	
109	Daniel	Faviet	DFAVIET	515.124.41	2002-08-16 00:00:00	FI_ACCOUNT	9000	(null)	108	
110	John	Chen	JCHEN	515.124.42	2005-09-28 00:00:00	FI_ACCOUNT	8200	(null)	108	
111	Ismael	Sciarra	ISCIARRA	515.124.43	2005-09-30 00:00:00	FI_ACCOUNT	7700	(null)	108	
112	Jose Manue	Urman	JMURMAN	515.124.44	2006-03-07 00:00:00	FI_ACCOUNT	7800	(null)	108	
113	Luis	Popp	LPOPP	515.124.45	2007-12-07 00:00:00	FI_ACCOUNT	6900	(null)	108	
114	Den	Raphaely	DRAPHEAL	515.127.45	2002-12-07 00:00:00	PU_MAN	11000	(null)	100	
115	Alexander	Khoo	AKHOO	515.127.45	2003-05-18 00:00:00	PU_CLERK	3100	(null)	114	
116	Shelli	Baida	SBAIDA	515.127.45	2005-12-24 00:00:00	PU_CLERK	2900	(null)	114	
117	Sigal	Tobias	STOBIAS	515.127.45	2005-07-24 00:00:00	PU_CLERK	2800	(null)	114	
118	Guy	Himuro	GHIMURO	515.127.45	2006-11-15 00:00:00	PU_CLERK	2600	(null)	114	
119	Karen	Colmenares	KCOLMENA	515.127.45	2007-08-10 00:00:00	PU_CLERK	2500	(null)	114	
120	Matthew	Weiss	MWEISS	650.123.12	2004-07-18 00:00:00	ST_MAN	8000	(null)	100	
121	Adam	Fripp	AFRIPP	650.123.22	2005-04-10 00:00:00	ST_MAN	8200	(null)	100	
122	Payam	Kaufling	PKAUFLIN	650.123.32	2003-05-01 00:00:00	ST_MAN	7900	(null)	100	
123	Shanta	Vollman	SVOLLMAN	650.123.42	2005-10-10 00:00:00	ST_MAN	6500	(null)	100	
124	Kevin	Mourgos	KMOURGOS	650.123.52	2007-11-16 00:00:00	ST_MAN	5800	(null)	100	
125	Julia	Nayer	JNAYER	650.124.12	2005-07-16 00:00:00	ST_CLERK	3200	(null)	120	
126	Irene	Mikkilineni	IMIKKILI	650.124.12	2006-09-28 00:00:00	ST_CLERK	2700	(null)	120	
127	James	Landry	JLANDRY	650.124.13	2007-01-14 00:00:00	ST_CLERK	2400	(null)	120	
128	Steven	Markle	SMARKLE	650.124.14	2008-03-08 00:00:00	ST_CLERK	2200	(null)	120	
129	Laura	Bissot	LBISSOT	650.124.52	2005-08-20 00:00:00	ST_CLERK	3300	(null)	121	
130	Mozhe	Atkinson	MATKINSO	650.124.62	2005-10-30 00:00:00	ST_CLERK	2800	(null)	121	
131	James	Marlow	JAMRLOW	650.124.72	2005-02-16 00:00:00	ST_CLERK	2500	(null)	121	
132	TJ	Olson	TJOLSON	650.124.82	2007-04-10 00:00:00	ST_CLERK	2100	(null)	121	
133	Jason	Mallin	JMALLIN	650.127.19	2004-06-14 00:00:00	ST_CLERK	3300	(null)	122	
134	Michael	Rogers	MROGERS	650.127.18	2006-08-26 00:00:00	ST_CLERK	2900	(null)	122	
135	Ki	Gee	KGEE	650.127.17	2007-12-12 00:00:00	ST_CLERK	2400	(null)	122	
136	Hazel	Philtanker	HPHILTAN	650.127.16	2008-02-06 00:00:00	ST_CLERK	2200	(null)	122	
137	Renske	Ladwig	RLADWIG	650.121.12	2003-07-14 00:00:00	ST_CLERK	3600	(null)	123	
138	Stephen	Stiles	SSTILES	650.121.20	2005-10-26 00:00:00	ST_CLERK	3200	(null)	123	
139	John	Seo	JSEO	650.121.20	2006-02-12 00:00:00	ST_CLERK	2700	(null)		
140	Jehua	Patel	JPATFI	650.121.18	2006-04-06 00:00:00	ST_CLERK	2500	(null)		

Max Rows: 100 Max Chars: 10 Pattern: n/a 0.000/0.032 sec 100/11 1-41

Text data truncated by Max Chars

Along with the highlighted field, a warning pops up close to the field. You can disable this behavior in the **Tool Properties** dialog, in the **General / Grid** category.

5.5.8 Max Rows at First Display

By default, opening the Data tab for a table loads all rows, unless there is a Max Rows limit. If you have very large tables and don't want to risk memory issues if you accidentally open the Data tab and have no Max Rows limit, you can specify a **Max Rows at First Display** limit. You do this in the Tool Properties dialog, in the **Table Data** category under the General tab.

The default is -1, which means no limit. If you set it to a positive number, only the specified number of rows are loaded when the Data tab is first opened for a table. To load more rows, click the **Reload** button in the Data tab toolbar.

5.5.9 Column Header Tooltips

The column header tooltip shows data type information about the column. To see the tooltip, let the mouse hover over the column header. The tooltip pops up in about a second.




```
FIRST_NAME VARCHAR2 (20)
Allow NULL
JDBC: VARCHAR (type: 12), Java: String
Column#: 2
```

5.5.10 Highlight Primary Key Columns

By default, a Primary Key column is shown with an icon in the column header. You can disable this in the Tool Properties dialog, in the **Table Data** category under the General tab.

5.5.11 Auto Resize Columns

The column header right-click menu contains a number of options for automatic resizing of column widths.



5.5.12 Show Only Some Columns

The **Grid Column Chooser** dialog controls which columns you want to appear in a grid. Open the dialog by the right-click menu on the column header or the button above the vertical scrollbar in the grid. See screenshot below.



Grid Column Chooser with **default layout**. Icon in grid top right corner indicates standard layout.

Grid Column Chooser with **custom layout**. Icon in grid top right corner indicates the layout is changed.

The **Grid Column Chooser** dialog shows all columns that are available in the grid. The checkmark in front of a column name indicates that the column is visible in the grid, while an unchecked box indicates that it is excluded from the grid. Click the checkmark to change the visibility of a column. You can change the visibility for all columns at once using the two visibility buttons in the dialog.

The order of the columns can also be adjusted in this dialog. Just select a row and use the **Up** and **Down** buttons to move it up (left in grid) or down (right in grid).

If you want to revert your changes, you can click on the **Default Layout** button to reset the grid, i.e., making all column visible and put them in their default locations.



Modifications of column visibility, size and order are saved between invocations of DbVisualizer for the **Log** tab and all grids in the various **Object View** tabs except for the **Data** tab.

If you modify the column visibility in the **Data** tab, the changes persists throughout the session. For instance, if you remove the **Name** column in the **Data** tab for the table EMPLOYEE, the **Name** column remains excluded when you reload the table or come back to the **Data** tab for that table later in the same session. You must manually make it visible again to bring it back. The changes are, however, reset when you restart the application.

If you modify the column visibility in the **Log** tab in the SQL Commander, the changes will affect the Log tab immediately and other SQL Commander Log tabs the next time they are opened or refreshed by running a query. Any custom column setups are saved individually for the Log tab in SQL Commander, Actions, Export (all but export grid), Import, and Procedure Editor.

5.5.13 Right-Click Menu Operations

The right-click menu for the grid contains a lot of operations for working with the data without changing it. In addition to the common select, copy, and print operations, some operations that may require a bit of an explanation are described below. Examples are based on the following simple grid that contains 9 cells on 3 rows with 3 columns, where the first two rows are selected:

*	col1	col2	col3
1	1	A	c3
2	2	B	c3
3	3	C	c3



Operation	Description
Copy Selection	Copy all selected cells onto the system clipboard. <u>Example:</u> 1 A c3 2 B c3
Copy Selection with Column Header	Copy all selected cells including column header onto the system clipboard. <u>Example:</u> col1 col2 col3 1 A c3 2 B c3
Copy Selection as Formatted Text	Copy all selected cells including column header in fixed width columns onto the system clipboard. <u>Example:</u> col1 col2 col3 ---- ---- ---- 1 A c3 2 B c3
Copy Selection as Comma List	Copy all selected cells onto the system clipboard, formatted as Comma Separated Values (CSV), one row for each column. <u>Example:</u> 1, 2 A, B c3, c3
Copy Selection as IN Clause	Copy all selected cells onto the system clipboard, formatted as an IN clause. <u>Example:</u> (col1 IN (1, 2)) and (col2 IN ('A', 'B')) and (col3 IN ('c3'))
Copy Selection as IN Clause with AND (ALL)	Copy all selected cells onto the system clipboard, formatted as a clause to select rows where ALL selected values match. <u>Example:</u> (col1 = 1 and col2 = 'A' and col3 = 'c3') or (col1 = 2 and col2 = 'B' and col3 = 'c3') This is different from Copy Selection as IN Clause with OR(ANY) since the clause matches all column values on each row; it will <i>not</i> select a row with column values 1, B, c3.
Copy Selection as IN Clause with OR (ANY)	Copy all selected cells onto the system clipboard, formatted as a clause to select rows where ANY of the selected values match. <u>Example:</u> (col1 IN (1, 2)) and (col2 IN ('A', 'B')) and (col3 = 'c3') This is similar to Copy Selection as IN Clause , but is slightly more efficient in some situations; in this example, col3 is matched using equals (=) rather than IN since the selected rows have the same value in this column. This is different from Copy Selection as IN Clause with AND (ALL) since the clause matches any column value on each row; it <i>will</i> select a row with column values 1, B, c3.



Operation	Description									
Copy Selection as HTML Table	Copy all selected cells onto the system clipboard, formatted as HTML code. Paste this into an HTML capable editor to get a nicely formatted table. Example: col1 col2 col3 1 A c3 2 B c3									
Copy Selection as JIRA Table	Copy all selected cells onto the system clipboard, formatted as markup code suitable for JIRA and similar tools. Paste this into a suitable editor to get a nicely formatted table. Example: <table border="1"> <thead> <tr> <th>col1</th> <th>col2</th> <th>col3</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>A</td> <td>c3</td> </tr> <tr> <td>2</td> <td>B</td> <td>c3</td> </tr> </tbody> </table>	col1	col2	col3	1	A	c3	2	B	c3
col1	col2	col3								
1	A	c3								
2	B	c3								
Save Selected Cell	Save the value of the selected cell to a file, selected with a file chooser dialog									
Compare	Compare the data in this grid to the data in other open grids.									
Compare Selected Cells	Compare the data in the two cells as text									
Browse Row in Window	Display all data for the selected row in a separate window. Note: for a read/write grid, this entry is named Edit Row in Window .									
Browse Cell in Window	Display the cell value in a separate window. This is especially useful for BLOB/CLOB data. Note: for a read/write grid, this entry is named Edit Cell in Window .									
Show in Navigator	Open the Navigator tab with the current selections and sorting.									
Describe Data	Show detailed information about the columns in the grid.									
Aggregation Data for Selection	Displays aggregation data for the current selection. Read more in Aggregation Data for Selection below.									
Generate Filter & Sort	The operations in this submenu helps you create common Where Filters .									
Create Row Count Data Monitor	Creates a monitor for tracking the row count in the table over time.									
Create Row Count Diff Data Monitor	Creates a monitor for tracking the number of added or removed rows in the table over time.									

There are also a set of operations for generating SQL statements based on the current selection. Choosing any of these creates the appropriate SQL and then switches the view to a new **SQL Commander** tab. You must use these operations to edit table data in the DbVisualizer Free edition. With the DbVisualizer Pro edition, you can instead use [inline and form based editing](#).

Operation	SQL Example
Script: SELECT ALL	select * from HR.COUNTRIES
Script: SELECT ALL WHERE	select * from HR.COUNTRIES where COUNTRY_NAME = 'Brazil'
Script: SELECT ALL WITH FILTER	select * from HR.COUNTRIES where REGION_ID = 1 // If this is the filter, see above



Operation	SQL Example
Script: INSERT INTO TABLE	<pre>insert into HR.COUNTRIES (COUNTRY_ID, COUNTRY_NAME, REGION_ID) values ('', '',)</pre>
Script: INSERT COPY INTO TABLE	<pre>insert into HR.COUNTRIES (COUNTRY_ID, COUNTRY_NAME, REGION_ID) values ('BR', 'Brazil', 2)</pre>
Script: UPDATE WHERE	<pre>update HR.COUNTRIES set COUNTRY_ID = 'BR', COUNTRY_NAME = 'Brazil', REGION_ID = 2 where COUNTRY_NAME = 'Brazil'</pre>
Script: DELETE WHERE	<pre>delete from HR.COUNTRIES where COUNTRY_NAME = 'Brazil'</pre>

You can generate SQL with either static values as they appear in the grid, or with [DbVisualizer variables](#). A variable is essentially a placeholder for a value in an SQL statement. When the statement is executed, DbVisualizer locates all variables and presents them in a dialog where you can enter or modify values for the variables. DbVisualizer replaces the variable placeholders with the new values before executing the statement.

Variables are used in the generated SQL statements by default. You can disable the **Include Variables in SQL** setting in the Tool Properties dialog, in the **Table Data** category under the General tab, to use literal values instead.

Here is an example of the SQL generated for **Script: SELECT ALL WHERE** with the **Include Variables in SQL** setting enabled, assuming the table is named HR.COUNTRIES and has a column named COUNTRY_NAME with the value 'Brazil' on the selected row:

```
select *
from HR.COUNTRIES
where COUNTRY_NAME = ${COUNTRY_NAME (where)||Brazil||String|where nullable ds=40 dt=VARCHAR }$
```

And here is the same example with the **Include Variables in SQL** setting disabled:

```
select *
from HR.COUNTRIES
where COUNTRY_NAME = 'Brazil'
```

5.5.14 Creating Monitors

A monitor in DbVisualizer is an SQL query executed at a specified frequency so you can track changes in data over time. The result can be viewed either as a grid or a graph. The right-click menu for the grid in the Data tab contains operations for creating two common types of monitors for the table: a **Row Count Data** monitor or a **Row Count Diff Data** monitor. The first tracks the number of rows in the table over time and the second tracks the number of added or removed rows over time. Please read more about monitors in [Monitoring Data Changes](#).

5.5.15 Aggregation Data for Selection



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **Aggregation Data for Selection** feature presents aggregation data organized per data type on the current selection in a grid. It provides information about cells holding numbers, text, date/time information and more. The following is an example of what it shows:



Aggregation Data for Selection

Selected Cells Count		153
Rows		17
Columns		9
Nulls		100
Text Count		51
Shortest		4
Avg Length		6
Longest		9
Total Length		218
Nulls		17
Number Count		51
Min		100
Avg		108
Median		108
Max		116
Sum		1,836
Std Deviation		5.05
Nulls		34
Timestamp Count		17
First	1987-06-17 00:00:00	
Avg	2001-12-09 11:00:00	
Median	2001-12-09 11:00:00	
Last	2016-06-03 00:00:00	
Nulls		15
Binary/BLOB Count		17
Nulls		17
CLOB Count		17
Nulls		17

Handle Numbers in Text Types as Numbers Max Scale

Auto Update

With **Auto Update** checked, the data is updated automatically when you change the selection in the grid. For very large selections, you may prefer to disable this feature and instead click **Update** when you want to refresh the data. Click a link (blue underlined text) in the aggregation table to locate and highlight the actual value in the source data grid. The **Handle Number Values in Text Types as Numbers** setting simply treats all valid numbers in text data types as numbers and include them in the **Number Count** summary.

5.6 Editing Table Data

Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).



With the DbVisualizer Pro edition, you can edit table data in the **Data** tab grid; just click a cell value and edit. Edits are saved in a single database transaction which ensures that all or no changes are committed. The editing feature supports saving binary and large text data and it even presents common data formats in their respective viewers, such as image viewer, PDF, XML, HEX, etc.

- [Opening the Data tab](#)
- [Editing Data in the Grid](#)
- [Copy/Paste](#)
- [Updates and Deletes Must Match Only One Table Row](#)
- [Key Column\(s\) Chooser](#)
- [Editing Multiple Rows](#)
- [Data Type checking](#)
- [New Line and Carriage Return](#)
- [Using the Cell Editor/Viewer](#)
- [Using the Form Editor/Viewer](#)
- [Preview Changes](#)
- [Editing Binary/BLOB and CLOB Data](#)

5.6.1 Opening the Data tab

To open the **Data** tab for a table:

1. Locate the table in the **Databases** tab tree,
2. Double-click the table node to open its **Object View** tab,
3. Open the **Data** sub tab.

* COUNTRY_ID	COUNTRY	LAST_UPDATE
1	1 Afghanistan	2006-02-15 04:44:00
2	2 Algeria	2006-02-15 04:44:00
3	3 American Samoa	2006-02-15 04:44:00
4	4 Angola	2006-02-15 04:44:00
5	5 Anguilla	2006-02-15 04:44:00
6	6 Argentina	2006-02-15 04:44:00
7	7 Armenia	2006-02-15 04:44:00
8	8 Australia	2006-02-15 04:44:00
9	9 Austria	2006-02-15 04:44:00
10	10 Azerbaijan	2006-02-15 04:44:00
11	11 Bahrain	2006-02-15 04:44:00
12	12 Bangladesh	2006-02-15 04:44:00
13	13 Belarus	2006-02-15 04:44:00
14	14 Belgium	2006-02-15 04:44:00

Max Rows: -1 Max Chars: -1 Format: <Select a Cell> 0.032/0.000 sec 109/3 1-14

Each column width is automatically resized to match the column width, including the column header, by default. You can disable this behavior in the the Tool Properties dialog, in the **Grid** category under the General tab.

If **Auto Resize Column Widths** is enabled, the **Max Column Width** setting can be used to limit the column width so that an extremely wide column does not take up all space.



5.6.2 Editing Data in the Grid

To edit a column value:

1. Select the column cell,
2. Type the new value, or double click to edit the current value,
3. Click the **Save** toolbar button to update the database.

You can also use the **Set Selected Cells** drop down menu to set a number of column values to things like null or the current date or time.

To add a new row:

1. Select the row above where you want to insert the new row,
2. Click the **Add Row** toolbar button,
3. Enter values for the columns,
4. Click the **Save** toolbar button to update the database.

To duplicate a row:

1. Select the row you want to duplicate,
2. Click the **Duplicate Row** toolbar button,
3. Edit at least the key column(s) value(s),
4. Click the **Save** toolbar button to update the database.

To delete one or more rows:

1. Select the rows to delete,
2. Click the **Delete Rows** toolbar button,
3. Click the **Save** toolbar button to update the database.

If you change your mind, you easily can undo edits:

1. Select the cell(s) you want to revert,
2. Click the **Undo** toolbar button.

Reverting all cells in a row that are marked as **Insert** or **Duplicate** removes the complete row from the grid while a **Delete** marked row is cleared from its delete state. Undoing updated cells simply reverts the changes to the original values.

5.6.3 Copy/Paste

You can copy selected cell values with the **Copy Selection** right-click menu choice or the corresponding key binding (**Ctrl-C** or **Command-C** by default). The data on the clipboard may then be pasted either into DbVisualizer or any external application. The column and newline delimiter used for copy and paste operations in the grid editor are defined by the **Copy Grid Cells in CSV Format** settings in the **Grid** category in the Tool Properties dialog, under the General tab. The default settings are sufficient for most uses.

The grid editor supports pasting data from the major spreadsheet applications, such as Excel and OpenOffice. The grid editor supports pasting single data as well as block of data. Copy/paste of binary data is transparent between grids or in the same grid. Binary files may also be copied in an external application and pasted in a cell in DbVisualizer (target cell must be a binary type).

Copy from spreadsheet					Paste into DbVisualizer grid				
A single cell is copied					Paste into selected target cell				
	A	B	C	D		EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE
1	200	Jennifer	Whalen	515.123.4444	7	100	Steven	King	515.123.
2	201	Michael	Hartstein	515.123.5555	8	101	Neena	Kochhar	515.123.
3	203	Susan	Mavris	515.123.7777	9	102	Lex	Susan	515.123.
4	204	Hermann	Baer	515.123.8888	10	108	Nancy	Greenberg	515.124.
5	205	Shelley	Higgins	515.123.8080	11	109	Daniel	Faviet	515.124.
6	206	William	Gietz	515.123.8181	12	110	John	Chen	515.124.
7	100	Steven	King	515.123.4567	13	111	Ismael	Sciarra	515.124.
8	101	Neena	Kochhar	515.123.4568	14	112	Jose Manuel	Urman	515.124.
9	102	Lex	De Haan	515.123.4569	15	113	Luis	Popp	515.124.
					16	114	Den	Raphaely	515.127.



Copy from spreadsheet					Paste into DbVisualizer grid																																																																																																									
A single cell is copied					Paste and fill the single column target selection																																																																																																									
<table border="1"><thead><tr><th></th><th>A</th><th>B</th><th>C</th><th>D</th></tr></thead><tbody><tr><td>1</td><td>200</td><td>Jennifer</td><td>Whalen</td><td>515.123.4444</td></tr><tr><td>2</td><td>201</td><td>Michael</td><td>Hartstein</td><td>515.123.5555</td></tr><tr><td>3</td><td>203</td><td>Susan</td><td>Mavris</td><td>515.123.7777</td></tr><tr><td>4</td><td>204</td><td>Hermann</td><td>Baer</td><td>515.123.8888</td></tr><tr><td>5</td><td>205</td><td>Shelley</td><td>Higgins</td><td>515.123.8080</td></tr><tr><td>6</td><td>206</td><td>William</td><td>Gietz</td><td>515.123.8181</td></tr><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.4567</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.4568</td></tr><tr><td>9</td><td>102</td><td>Lex</td><td>De Haan</td><td>515.123.4569</td></tr></tbody></table>		A	B	C	D	1	200	Jennifer	Whalen	515.123.4444	2	201	Michael	Hartstein	515.123.5555	3	203	Susan	Mavris	515.123.7777	4	204	Hermann	Baer	515.123.8888	5	205	Shelley	Higgins	515.123.8080	6	206	William	Gietz	515.123.8181	7	100	Steven	King	515.123.4567	8	101	Neena	Kochhar	515.123.4568	9	102	Lex	De Haan	515.123.4569					<table border="1"><thead><tr><th></th><th>EMPLOYEE_ID</th><th>FIRST_NAME</th><th>LAST_NAME</th><th>PHONE</th></tr></thead><tbody><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.</td></tr><tr><td>9</td><td>102</td><td>Susan</td><td>De Haan</td><td>515.123.</td></tr><tr><td>10</td><td>108</td><td>Susan</td><td>Greenberg</td><td>515.124.</td></tr><tr><td>11</td><td>109</td><td>Susan</td><td>Faviet</td><td>515.124.</td></tr><tr><td>12</td><td>110</td><td>Susan</td><td>Chen</td><td>515.124.</td></tr><tr><td>13</td><td>111</td><td>Ismael</td><td>Sciarra</td><td>515.124.</td></tr><tr><td>14</td><td>112</td><td>Jose Manuel</td><td>Urman</td><td>515.124.</td></tr><tr><td>15</td><td>113</td><td>Luis</td><td>Popp</td><td>515.124.</td></tr><tr><td>16</td><td>114</td><td>Den</td><td>Raphaely</td><td>515.127.</td></tr></tbody></table>		EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE	7	100	Steven	King	515.123.	8	101	Neena	Kochhar	515.123.	9	102	Susan	De Haan	515.123.	10	108	Susan	Greenberg	515.124.	11	109	Susan	Faviet	515.124.	12	110	Susan	Chen	515.124.	13	111	Ismael	Sciarra	515.124.	14	112	Jose Manuel	Urman	515.124.	15	113	Luis	Popp	515.124.	16	114	Den	Raphaely	515.127.
	A	B	C	D																																																																																																										
1	200	Jennifer	Whalen	515.123.4444																																																																																																										
2	201	Michael	Hartstein	515.123.5555																																																																																																										
3	203	Susan	Mavris	515.123.7777																																																																																																										
4	204	Hermann	Baer	515.123.8888																																																																																																										
5	205	Shelley	Higgins	515.123.8080																																																																																																										
6	206	William	Gietz	515.123.8181																																																																																																										
7	100	Steven	King	515.123.4567																																																																																																										
8	101	Neena	Kochhar	515.123.4568																																																																																																										
9	102	Lex	De Haan	515.123.4569																																																																																																										
	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE																																																																																																										
7	100	Steven	King	515.123.																																																																																																										
8	101	Neena	Kochhar	515.123.																																																																																																										
9	102	Susan	De Haan	515.123.																																																																																																										
10	108	Susan	Greenberg	515.124.																																																																																																										
11	109	Susan	Faviet	515.124.																																																																																																										
12	110	Susan	Chen	515.124.																																																																																																										
13	111	Ismael	Sciarra	515.124.																																																																																																										
14	112	Jose Manuel	Urman	515.124.																																																																																																										
15	113	Luis	Popp	515.124.																																																																																																										
16	114	Den	Raphaely	515.127.																																																																																																										
Multiple cells in a single row is copied					Paste and fill the target selection																																																																																																									
<table border="1"><thead><tr><th></th><th>A</th><th>B</th><th>C</th><th>D</th></tr></thead><tbody><tr><td>1</td><td>200</td><td>Jennifer</td><td>Whalen</td><td>515.123.4444</td></tr><tr><td>2</td><td>201</td><td>Michael</td><td>Hartstein</td><td>515.123.5555</td></tr><tr><td>3</td><td>203</td><td>Susan</td><td>Mavris</td><td>515.123.7777</td></tr><tr><td>4</td><td>204</td><td>Hermann</td><td>Baer</td><td>515.123.8888</td></tr><tr><td>5</td><td>205</td><td>Shelley</td><td>Higgins</td><td>515.123.8080</td></tr><tr><td>6</td><td>206</td><td>William</td><td>Gietz</td><td>515.123.8181</td></tr><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.4567</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.4568</td></tr><tr><td>9</td><td>102</td><td>Lex</td><td>De Haan</td><td>515.123.4569</td></tr></tbody></table>		A	B	C	D	1	200	Jennifer	Whalen	515.123.4444	2	201	Michael	Hartstein	515.123.5555	3	203	Susan	Mavris	515.123.7777	4	204	Hermann	Baer	515.123.8888	5	205	Shelley	Higgins	515.123.8080	6	206	William	Gietz	515.123.8181	7	100	Steven	King	515.123.4567	8	101	Neena	Kochhar	515.123.4568	9	102	Lex	De Haan	515.123.4569					<table border="1"><thead><tr><th></th><th>EMPLOYEE_ID</th><th>FIRST_NAME</th><th>LAST_NAME</th><th>PHONE</th></tr></thead><tbody><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.</td></tr><tr><td>9</td><td>102</td><td>Susan</td><td>Mavris</td><td>515.123.</td></tr><tr><td>10</td><td>108</td><td>Susan</td><td>Mavris</td><td>515.124.</td></tr><tr><td>11</td><td>109</td><td>Susan</td><td>Mavris</td><td>515.124.</td></tr><tr><td>12</td><td>110</td><td>Susan</td><td>Mavris</td><td>515.124.</td></tr><tr><td>13</td><td>111</td><td>Ismael</td><td>Sciarra</td><td>515.124.</td></tr><tr><td>14</td><td>112</td><td>Jose Manuel</td><td>Urman</td><td>515.124.</td></tr><tr><td>15</td><td>113</td><td>Luis</td><td>Popp</td><td>515.124.</td></tr><tr><td>16</td><td>114</td><td>Den</td><td>Raphaely</td><td>515.127.</td></tr></tbody></table>		EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE	7	100	Steven	King	515.123.	8	101	Neena	Kochhar	515.123.	9	102	Susan	Mavris	515.123.	10	108	Susan	Mavris	515.124.	11	109	Susan	Mavris	515.124.	12	110	Susan	Mavris	515.124.	13	111	Ismael	Sciarra	515.124.	14	112	Jose Manuel	Urman	515.124.	15	113	Luis	Popp	515.124.	16	114	Den	Raphaely	515.127.
	A	B	C	D																																																																																																										
1	200	Jennifer	Whalen	515.123.4444																																																																																																										
2	201	Michael	Hartstein	515.123.5555																																																																																																										
3	203	Susan	Mavris	515.123.7777																																																																																																										
4	204	Hermann	Baer	515.123.8888																																																																																																										
5	205	Shelley	Higgins	515.123.8080																																																																																																										
6	206	William	Gietz	515.123.8181																																																																																																										
7	100	Steven	King	515.123.4567																																																																																																										
8	101	Neena	Kochhar	515.123.4568																																																																																																										
9	102	Lex	De Haan	515.123.4569																																																																																																										
	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE																																																																																																										
7	100	Steven	King	515.123.																																																																																																										
8	101	Neena	Kochhar	515.123.																																																																																																										
9	102	Susan	Mavris	515.123.																																																																																																										
10	108	Susan	Mavris	515.124.																																																																																																										
11	109	Susan	Mavris	515.124.																																																																																																										
12	110	Susan	Mavris	515.124.																																																																																																										
13	111	Ismael	Sciarra	515.124.																																																																																																										
14	112	Jose Manuel	Urman	515.124.																																																																																																										
15	113	Luis	Popp	515.124.																																																																																																										
16	114	Den	Raphaely	515.127.																																																																																																										
A block of cells is copied					The block is pasted into the selected region																																																																																																									
<table border="1"><thead><tr><th></th><th>A</th><th>B</th><th>C</th><th>D</th></tr></thead><tbody><tr><td>1</td><td>200</td><td>Jennifer</td><td>Whalen</td><td>515.123.4444</td></tr><tr><td>2</td><td>201</td><td>Michael</td><td>Hartstein</td><td>515.123.5555</td></tr><tr><td>3</td><td>203</td><td>Susan</td><td>Mavris</td><td>515.123.7777</td></tr><tr><td>4</td><td>204</td><td>Hermann</td><td>Baer</td><td>515.123.8888</td></tr><tr><td>5</td><td>205</td><td>Shelley</td><td>Higgins</td><td>515.123.8080</td></tr><tr><td>6</td><td>206</td><td>William</td><td>Gietz</td><td>515.123.8181</td></tr><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.4567</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.4568</td></tr><tr><td>9</td><td>102</td><td>Lex</td><td>De Haan</td><td>515.123.4569</td></tr></tbody></table>		A	B	C	D	1	200	Jennifer	Whalen	515.123.4444	2	201	Michael	Hartstein	515.123.5555	3	203	Susan	Mavris	515.123.7777	4	204	Hermann	Baer	515.123.8888	5	205	Shelley	Higgins	515.123.8080	6	206	William	Gietz	515.123.8181	7	100	Steven	King	515.123.4567	8	101	Neena	Kochhar	515.123.4568	9	102	Lex	De Haan	515.123.4569					<table border="1"><thead><tr><th></th><th>EMPLOYEE_ID</th><th>FIRST_NAME</th><th>LAST_NAME</th><th>PHONE</th></tr></thead><tbody><tr><td>7</td><td>100</td><td>Steven</td><td>King</td><td>515.123.</td></tr><tr><td>8</td><td>101</td><td>Neena</td><td>Kochhar</td><td>515.123.</td></tr><tr><td>9</td><td>102</td><td>Susan</td><td>Mavris</td><td>515.123.</td></tr><tr><td>10</td><td>108</td><td>Hermann</td><td>Baer</td><td>515.124.</td></tr><tr><td>11</td><td>109</td><td>Shelley</td><td>Higgins</td><td>515.124.</td></tr><tr><td>12</td><td>110</td><td>William</td><td>Gietz</td><td>515.124.</td></tr><tr><td>13</td><td>111</td><td>Ismael</td><td>Sciarra</td><td>515.124.</td></tr><tr><td>14</td><td>112</td><td>Jose Manuel</td><td>Urman</td><td>515.124.</td></tr><tr><td>15</td><td>113</td><td>Luis</td><td>Popp</td><td>515.124.</td></tr><tr><td>16</td><td>114</td><td>Den</td><td>Raphaely</td><td>515.127.</td></tr></tbody></table>		EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE	7	100	Steven	King	515.123.	8	101	Neena	Kochhar	515.123.	9	102	Susan	Mavris	515.123.	10	108	Hermann	Baer	515.124.	11	109	Shelley	Higgins	515.124.	12	110	William	Gietz	515.124.	13	111	Ismael	Sciarra	515.124.	14	112	Jose Manuel	Urman	515.124.	15	113	Luis	Popp	515.124.	16	114	Den	Raphaely	515.127.
	A	B	C	D																																																																																																										
1	200	Jennifer	Whalen	515.123.4444																																																																																																										
2	201	Michael	Hartstein	515.123.5555																																																																																																										
3	203	Susan	Mavris	515.123.7777																																																																																																										
4	204	Hermann	Baer	515.123.8888																																																																																																										
5	205	Shelley	Higgins	515.123.8080																																																																																																										
6	206	William	Gietz	515.123.8181																																																																																																										
7	100	Steven	King	515.123.4567																																																																																																										
8	101	Neena	Kochhar	515.123.4568																																																																																																										
9	102	Lex	De Haan	515.123.4569																																																																																																										
	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE																																																																																																										
7	100	Steven	King	515.123.																																																																																																										
8	101	Neena	Kochhar	515.123.																																																																																																										
9	102	Susan	Mavris	515.123.																																																																																																										
10	108	Hermann	Baer	515.124.																																																																																																										
11	109	Shelley	Higgins	515.124.																																																																																																										
12	110	William	Gietz	515.124.																																																																																																										
13	111	Ismael	Sciarra	515.124.																																																																																																										
14	112	Jose Manuel	Urman	515.124.																																																																																																										
15	113	Luis	Popp	515.124.																																																																																																										
16	114	Den	Raphaely	515.127.																																																																																																										



Copy from spreadsheet

A block of cells is copied

	A	B	C	D
1	200	Jennifer	Whalen	515.123.4444
2	201	Michael	Hartstein	515.123.5555
3	203	Susan	Mavris	515.123.7777
4	204	Hermann	Baer	515.123.8888
5	205	Shelley	Higgins	515.123.8080
6	206	William	Gietz	515.123.8181
7	100	Steven	King	515.123.4567
8	101	Neena	Kochhar	515.123.4568
9	102	Lex	De Haan	515.123.4569

Paste into DbVisualizer grid

The block is pasted into a non equal number of target cells

	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	PHONE_NUMBER	EMAIL
7	100	Steven	King	515.123.4567	SKING
8	101	Neena	Kochhar	515.123.4568	NKOCHH...
9	102	Lex	De Haan	515.123.4569	LDEHAAN
10	108	Nancy	Greenberg	515.124.4569	NGREENBE
11	109	Daniel	Faviet	515.124.4169	DFAVIET
12	110	John	Chen	515.124.4269	JCHEN

Notification Alert

You have requested to paste 4 rows into the selection of 2 target rows.
Do you want to **Add Rows** in the grid so that all rows in the clipboard are pasted?

5.6.4 Updates and Deletes Must Match Only One Table Row

When you update or delete rows, DbVisualizer ensures that only one row in the table will be affected. This is to prevent changes in one row to silently affect data in other rows. DbVisualizer uses the following strategies to determine the uniqueness of the edited row:

1. Primary Key,
2. Unique Index,
3. Manually Selected Columns.

The Primary Key concept is widely used in databases to uniquely identify the key columns in tables. If the table has a primary key, DbVisualizer uses it. There are situations when primary keys are not supported by a database or when primary keys are supported but not used. If no primary key is defined, DbVisualizer checks if there is a unique index. If there are several unique indexes, DbVisualizer picks one of them. If there is no primary key or any unique indexes defined for the table, you need to manually choose what columns to use. The **Key Column Chooser** is automatically displayed if the key columns can't be determined automatically.

5.6.5 Key Column(s) Chooser

Normally database tables have a primary key or at least one unique index. If this is the case, editing is no problem. If there is no way to uniquely identify rows in the table, you need to manually define what columns DbVisualizer should use. While saving the changes, DbVisualizer checks that there is a way to identify unique rows in the table. If it cannot be accomplished, the following window is displayed.



	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER
1	100	Steven	King	SKING	515.123.4567
2	101	Neena	Kochhar	NKOCHHAR	515.123.4568
3	102	Lex	De Haan	LDEHAAN	515.123.4569
4	103	Alex	Hunold	AHUNOLD	590.423.4567
5	104	Bruce	Ernst	BERNST	590.423.4568
6	105	David	Austin	DAUSTIN	590.423.4569
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24	123	Shanta	Vollman	SVOLLMAN	590.123.4567
25	124	Kevin	Mourgos	KMOURGOS	650.123.5234

Key Column(s) Chooser

Select the column(s) that will be used to form the **where** clause for **update** and **delete** edits. This is used by DbVisualizer to ensure that only one row in the target database table will be affected by each edited row. (If there is a primary key or unique index for the table then the Key Column is automatically set).

Key Column	Column Name	Data Type
<input checked="" type="checkbox"/>	EMPLOYEE_ID	NUMBER
<input type="checkbox"/>	FIRST_NAME	VARCHAR2
<input type="checkbox"/>	LAST_NAME	VARCHAR2
<input type="checkbox"/>	EMAIL	VARCHAR2
<input type="checkbox"/>	PHONE_NUMBER	VARCHAR2
<input type="checkbox"/>	HIRE_DATE	DATE
<input type="checkbox"/>	JOB_ID	VARCHAR2
<input type="checkbox"/>	SALARY	NUMBER

Select All Deselect All Close

The key column chooser can also be manually opened via the **Edit Table Data->Key Column Chooser** right-click menu choice.

If the database request to save the edits cannot uniquely identify the single row that should be changed, an error dialog is displayed and the editing state is kept for that row in the grid editor.

5.6.6 Editing Multiple Rows

The grid editor supports editing multiple rows and saving all changes in one database transaction. Edited rows are indicated with an icon in the row header:


- Cell(s) in the row has been edited
- Row is new
- Row is duplicated from another row
- Row is marked for deletion (edit is not allowed)

5.6.7 Data Type checking

When leaving an edited cell, the new value is validated with the data type for the column. If there is an error, the following dialog is displayed.




	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE
1	100	Steven	King	SKING	515.123.4567	1987-06-17 00:00:00
2	101	Neena	Kochhar	NKOCHHAR	515.123.4568	1989-09-21 00:00:00
3	102	Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13 00:00:00
4	103	Alex	Hunold	AHUNOLD	590.423.4567	June 6 2016
5	104	Bruce	Ernst	BERNST	590.423.4568	1991-05-21 00:00:00
6	105	David				00:00:00
7	106	Valli				00:00:00
8	107	Diana				00:00:00
9	108	Nancy				00:00:00
10	109	Daniel				00:00:00
11	110	John				00:00:00
12	111	Ismail				00:00:00
13	112	Jose				00:00:00
14	113	Luis				00:00:00
15	114	Den	Raphaely	DRAPHEAL	515.127.4561	1994-12-07 00:00:00



5.6.8 New Line and Carriage Return

If a cell in the grid editor or form editor contains new line, carriage return or tab characters, these are not visually represented in the grid. Instead a warning will be displayed whenever you try to edit such value:

	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE
1	100	Steven	King	SKING	515.123.4567	1987-06-17
2	101	Neena	Kochhar	NKOCHHAR	515.123.4568	1989-09-21
3	102	Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13
4	103	Alex	Hunold the gr...	AHUNOLD	590.423.4567	1990-01-03
5	104	Bruce	Ernst	BERNST	590.423.4568	1991-05-21
6						5-25
7						2-05
8						2-07
9						3-17
10						3-16
11						9-28
12						9-30
13						3-07
14						2-07
15	114	Den	Raphaely	DRAPHEAL	515.127.4561	1994-12-07




You may choose to edit the value in the [Cell Editor](#), which we recommend, as the control characters will then be preserved. Alternatively, you can edit the value in the grid anyway but you then risk losing the control characters.


5.6.9 Using the Cell Editor/Viewer

The **Cell Editor/Viewer** is available in the right-click menu (**Edit Cell in Window** or **View Cell in Window** if the data is read-only) and on the toolbar for all grids in DbVisualizer. It presents the data for a single cell (column in a row) in a window. If the data is of a recognized type, it is presented by a corresponding editor that allows you to view, edit and/or format the content, and also to save or load the data to/from a file.


The **Text Editor** can be used for viewing and editing textual data, including JSON and XML. It does not offer any syntax coloring or validation; it is a plain text editor.




The **Hex Viewer** shows the content in hexadecimal format.



The **JSON Formatter** can transform the JSON structure to a human readable multi-line format (sometimes called "pretty printed") or to a compact single line format where insignificant whitespace is trimmed. The formatting will fail if the text does not comply with JSON syntax.



The **XML Viewer** is shown if the cell value is recognized as well-formed XML, or if you manually select to open the XML Viewer (which, for obvious reasons, may fail). The viewer presents data in a structured way but does not allow editing; you need to switch to the **Text Editor** to edit.




The **Image Viewer** displays full size images for [binary data](#) that conforms to a supported image format:

- GIF (Graphics Interchange Format)
- JPG/JPEG (Joint Photographic Experts Group)
- PNG (Portable Networks Graphics)



- TIFF (Tagged Image File Format)
- BMP (Bitmap Image File)
- PDF (Portable Document Format)



Opening the Cell Viewer for binary data will automatically render the content if a supported image type or if a PDF document.

5.6.10 Using the Form Editor/Viewer

The **Row Viewer** is available in the right-click menu (**Browse/Edit Row in Window**) for all grids in DbVisualizer. It is used to either browse or edit information and to present binary data in viewers.

The **Row Editor** adds editing capability to the form viewer. This editor is useful when inserting new rows and when it is important to get a more balanced and transposed overview of all the data.

The form editor transpose or "rotate" the data in one row and presents it as a vertical form with the column name as a label. All edits made in the form editor are reflected in the grid with the edited state icon being updated along with new values. Saving edits in the database is always done with the Save button in the grid editor toolbar, just as for data edited directly in the grid.

Open the form editor via the **Edit Row in Window** right-click menu choice, via the corresponding button in the toolbar or by double-clicking the row number header.


	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	PHOTO
1	100	Steven	King	SKING	515.123.4567	(null)
2	101	Neena	Kochhar	NKOCHHAR	515.123.4568	(null)
3	102	Lex	De Haan	LDEHAAN	515.123.4569	(null)
4	103	Alexander	Hunold	AHUNOLD	590.423.4567	BINARY, 8,327 Bytes
5	104	Bruce	Ernst	BERNST	590.423.4568	(null)
6	105	David	Austin	DAUSTIN	590.423.4569	(null)

The same row looks like this in the row form window:



Row Form (Editable)

Key Name Value

	EMPLOYEE_ID	103
	FIRST_NAME	Alexander
	LAST_NAME	Hunold
	EMAIL	AHUNOLD
	PHONE_NUMBER	590.423.4567
	HIRE_DATE	1990-01-03 00:00:00
	JOB_ID	IT_PROG
	SALARY	9000
	COMMISSION_PCT	(null)
	MANAGER_ID	102
	DEPARTMENT_ID	60
	PHOTO	 BINARY, 8,327 Bytes, image/jpeg
	RESUME	(null)

Close

The **Key** field contains an icon for primary key columns and the **Name** field corresponds to the column name in the grid. None of **Key** or the **Name** fields can be edited. You can edit the values in the form in the same way as you edit values in the grid editor.

The form viewer presents images as thumbnails. The size of these is controlled by the **Image Thumbnail Size** setting in the Tool Properties dialog, in the **General / Form Viewer** category under the **General** tab. To see the original size of an image, open the cell in the cell viewer either by selecting **Edit in Cell Window** in the grid right-click menu, the toolbar button or by double-clicking on the image.

If you want numbers to be right-aligned in the viewer/editor, enable **Right Aligned Numbers** in the **Tool Properties** dialog, in the **Form Viewer** category under the **General** tab.

5.6.11 Preview Changes

You may preview the SQL statements that will be executed when choosing to **Save** the edits via the **Edit Table Data->SQL Preview** right-click menu choice.



	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID
1	100	Steven	King	SKING	515.123.4567	1987-06-17 00:00:00	AD_PRES
2	101	Neena	Kochhar	NKOCHHAR	515.123.4568	1989-09-21 00:00:00	AD_VP
3	102	Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13 00:00:00	AD_VP
4	103	Alex	Hunold	AHUNOLD	590.423.4567	1990-01-03 00:00:00	IT_PROG
5	104	Bro	Ernst	BERNST	590.423.4568	1991-05-21 00:00:00	IT_PROG
6	105	David	Austin	DAUSTIN	590.423.4569	1997-06-25 00:00:00	IT_PROG
7	105	David	Austin	DAUSTIN	590.423.4569	1997-06-25 00:00:00	IT_PROG
8	106	Valli	Pataballa	VPATABAL	590.423.4560	1998-02-05 00:00:00	IT_PROG
9	107	Diana	Lorentz	DLORENTZ	590.423.5567	1999-02-07 00:00:00	IT_PROG
10	108	Nancy	Greenberg	NGREENBE	515.124.4569	1994-08-17 00:00:00	FI_MGR
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							
27	125	Julia	Nayer	JNAYER	650.124.1214	1997-07-16 00:00:00	ST_CLERK

SQL Preview


This is a preview of the SQL that will be executed when the table data edit(s) are saved.

```

1 UPDATE "HR"."EMPLOYEES" SET "FIRST_NAME" = 'Alex' WHERE "EMPLOYEE_ID" = 103;
2 UPDATE "HR"."EMPLOYEES" SET "FIRST_NAME" = 'Bro' WHERE "EMPLOYEE_ID" = 104;
3 INSERT INTO "HR"."EMPLOYEES" ("EMPLOYEE_ID", "FIRST_NAME", "LAST_NAME", "EMAIL", "PH
4 DELETE FROM "HR"."EMPLOYEES" WHERE "EMPLOYEE_ID" = 106;
5 DELETE FROM "HR"."EMPLOYEES" WHERE "EMPLOYEE_ID" = 107

```

Close

 The listed SQL statements may not be 100% identical to what is sent to the database, as the save process uses variable binding to pass values to the database.

5.6.12 Editing Binary/BLOB and CLOB Data

Due to the nature of binary/BLOB and CLOB data, cells of these types can only be fully modified and viewed in the [Cell Editor](#) (there is partial support in the [Form Editor](#) to view image data and to load from file).

In the grid, Binary/BLOB and CLOB data is by default presented by an icon and the size of the value. You can select another presentation format in the **Tools Properties** dialog, in the **General/Data Formats** category under the General tab. Selecting **By Value** results in performance penalties and the memory consumption increases dramatically.

In the same Tool Properties category, you can also specify how to handle **Copy/Paste and Drag and Drop** when pasting binary data in a target component that doesn't support binary data.

Editing binary data can be done by importing from a file or via the text editor in the [Cell Editor](#). You can also copy the file in the operating system's file browser and paste it into a BLOB/CLOB cell.

Binary data in DbVisualizer is the generic term for several common binary database types:

- LONGVARBINARY
- BINARY
- VARBINARY
- BLOB



5.7 Working with Binary and BLOB Data

DbVisualizer provides special support for working with Binary/BLOB data in a number of areas, such as:

- [Viewing and Editing Binary/BLOB data](#),
- [Exporting Binary/BLOB data](#),
- [Importing Binary/BLOB data](#)

5.8 Working with Large Text/CLOB Data

DbVisualizer provides special support for working with Large Text/CLOB data in a number of areas, such as:

- [Viewing and Editing Large Text/CLOB data](#),
- [Exporting Large Text/CLOB data](#),
- [Importing Large Text/CLOB data](#)

5.9 Using Max Rows and Max Chars for a Table

DbVisualizer limits the number of rows shown in the Data tab to 1000 rows, by default. This is done to conserve memory. If this limit prevents you from seeing the data of interest, you should first consider:

1. Using a [Where Filter](#) to only retrieve the rows of interest instead of all rows in the table,
2. [Exporting the table](#) to a file

If you really need to look at more than 1000 rows, you can change the value in the **Max Rows** field in the grid status bar. Use a value of 0 or -1 to get all rows, or a specific number (e.g. 5000) to set a new limit.

Character data columns may contain very large values that use up lots of memory. If you are only interested in seeing a few characters, you can set the **Max Chars** field in the grid status bar to the number of characters you want to see.

You can define how to deal with columns that have more characters than the specified maximum in the Tool Properties dialog, in the Grid category under the General tab. You have two choices: **Truncate Values** or **Truncate Values Visually**.

- **Truncate Values** truncates the original value for the grid cell to be less than the setting of Max Chars.



This affects any subsequent edits and SQL operations that use the value since it's truncated. This setting is only useful to save memory when viewing very large text columns.

- **Truncate Values Visually** truncates the visible value only and leave the original value intact. This is the preferred setting since it will not harm the original value. The disadvantage is that more memory is needed when dealing with large text columns.

When the grid data is limited due to either the **Max Rows** or **Max Chars** value, you get an indication about this in the rows/columns field in the grid status bar and in the corresponding limit field. The color is also changed for the affected controls.



EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALARY	COMMISSION_PCT	MANAGER_ID	DEPARTMENT
100	Steven	King	SKING	515.123.45	2003-06-17 00:00:00	AD_PRES	24000	(null)	(null)	
101	Neena	Kochhar	NKOCHHAR	515.123.45	2005-09-21 00:00:00	AD_VP	17000	(null)	100	
102	Lex	De Haan	LDEHAAN	515.123.45	2001-01-13 00:00:00	AD_VP	17000	(null)	100	
103	Alexander	Hunold	AHUNOLD	590.423.45	2006-01-03 00:00:00	IT_PROG	9000	(null)	102	
104	Bruce	Ernst	BERNST	590.423.45	2007-05-21 00:00:00	IT_PROG	6000	(null)	103	
105	David	Austin	DAUSTIN	590.423.45	2005-06-25 00:00:00	IT_PROG	4800	(null)	103	
106	Valli	Pataballa	VPATABAL	590.423.45	2006-02-05 00:00:00	IT_PROG	4800	(null)	103	
107	Diana	Lorentz	DLORENTZ	590.423.55	2007-02-07 00:00:00	IT_PROG	4200	(null)	103	
108	Nancy	Greenberg	NGREENBE	515.124.45	2002-08-17 00:00:00	FI_MGR	12008	(null)	101	
109	Daniel	Faviet	DFAVIET	515.124.41	2002-08-16 00:00:00	FI_ACCOUNT	9000	(null)	108	
110	John	Chen	JCHEN	515.124.42	2005-09-28 00:00:00	FI_ACCOUNT	8200	(null)	108	
111	Ismael	Sciarra	ISCIARRA	515.124.43	2005-09-30 00:00:00	FI_ACCOUNT	7700	(null)	108	
112	Jose Manue	Urman	JMURMAN	515.124.44	2006-03-07 00:00:00	FI_ACCOUNT	7800	(null)	108	
113	Luis	Popp	LPOPP	515.124.45	2007-12-07 00:00:00	FI_ACCOUNT	6900	(null)	108	
114	Den	Raphaely	DRAPHEAL	515.127.45	2002-12-07 00:00:00	PU_MAN	11000	(null)	100	
115	Alexander	Khoo	AKHOO	515.127.45	2003-05-18 00:00:00	PU_CLERK	3100	(null)	114	
116	Shelli	Baida	SBIDA	515.127.45	2005-12-24 00:00:00	PU_CLERK	2900	(null)	114	
117	Sigal	Tobias	STOBIAS	515.127.45	2005-07-24 00:00:00	PU_CLERK	2800	(null)	114	
118	Guy	Himuro	GHIMURO	515.127.45	2006-11-15 00:00:00	PU_CLERK	2600	(null)	114	
119	Karen	Colmenares	KCOLMENA	515.127.45	2007-08-10 00:00:00	PU_CLERK	2500	(null)	114	
120	Matthew	Weiss	MWEISS	650.123.12	2004-07-18 00:00:00	ST_MAN	8000	(null)	100	
121	Adam	Fripp	AFRIPP	650.123.22	2005-04-10 00:00:00	ST_MAN	8200	(null)	100	
122	Payam	Kaufling	PKAUFLIN	650.123.32	2003-05-01 00:00:00	ST_MAN	7900	(null)	100	
123	Shanta	Vollman	SVOLLMAN	650.123.42	2005-10-10 00:00:00	ST_MAN	6500	(null)	100	
124	Kevin	Mourgos	KMOURGOS	650.123.52	2007-11-16 00:00:00	ST_MAN	5800	(null)	100	
125	Julia	Nayer	JNAYER	650.124.12	2005-07-16 00:00:00	ST_CLERK	3200	(null)	120	
126	Irene	Mikkilineni	IMIKKILI	650.124.12	2006-09-28 00:00:00	ST_CLERK	2700	(null)	120	
127	James	Landry	JLANDRY	650.124.13	2007-01-14 00:00:00	ST_CLERK	2400	(null)	120	
128	Steven	Markle	SMARKLE	650.124.14	2008-03-08 00:00:00	ST_CLERK	2200	(null)	120	
129	Laura	Bissot	LBISSOT	650.124.52	2005-08-20 00:00:00	ST_CLERK	3300	(null)	121	
130	Mozhe	Atkinson	MATKINSO	650.124.62	2005-10-30 00:00:00	ST_CLERK	2800	(null)	121	
131	James	Marlow	JAMRLOW	650.124.72	2005-02-16 00:00:00	ST_CLERK	2500	(null)	121	
132	TJ	Olson	TJOLSON	650.124.82	2007-04-10 00:00:00	ST_CLERK	2100	(null)	121	
133	Jason	Mallin	JMALLIN	650.127.19	2004-06-14 00:00:00	ST_CLERK	3300	(null)	122	
134	Michael	Rogers	MROGERS	650.127.18	2006-08-26 00:00:00	ST_CLERK	2900	(null)	122	
135	Ki	Gee	KGEE	650.127.17	2007-12-12 00:00:00	ST_CLERK	2400	(null)	122	
136	Hazel	Philtanker	HPHILTAN	650.127.16	2008-02-06 00:00:00	ST_CLERK	2200	(null)	122	
137	Renske	Ladwig	RLADWIG	650.121.12	2003-07-14 00:00:00	ST_CLERK	3600	(null)	123	
138	Stephen	Stiles	SSTILES	650.121.20	2005-10-26 00:00:00	ST_CLERK	3200	(null)	123	
139	John	Seo	JSEO	650.121.20	2006-02-12 00:00:00	ST_CLERK	2700	(null)	123	
140	Neena	Patel	NPATL	650.121.18	2006-04-06 00:00:00	ST_CLERK	2500	(null)	123	

Along with the highlighted field, a warning pops up close to the field. You can disable this behavior in the **Tool Properties** dialog, in the **General / Grid** category.

5.10 Changing the Data Display Format

Some data, like numeric and date/time data, can be displayed in many different ways.

To define how to display and enter data in grids and forms in DbVisualizer:

1. Open **Tools->Tool Properties**,
2. Select the **General / Data Formats** node under the **General** tab,
3. Select or enter your preferred format for the different data types.

5.10.1 Date, Time and Timestamp formats

The lists for date, time and timestamp format contain collections of standard formats. If these formats are not suitable, you can enter your own format in the appropriate field. The tokens used to define the format are listed in the right-click menu when the field has focus.



G - Era Designator
y - Year
M - Month in year
w - Week in year
W - Week in month
D - Day in year
d - Day in month
F - Day of week in month
E - Day in week
a - AM/PM marker
H - Hour in day (0-23)
k - Hour in day (1-24)
K - Hour in AM/PM (0-11)
h - Hour in AM/PM (1-12)
m - Minute in hour
s - Second in minute
S - Millisecond
z - Time zone
Z - Time zone

The complete documentation for these tokens is available at the following web page: [SimpleDateFormat](#).

5.10.2 Number formats

The lists for number and decimal number contain collections of standard formats. If these formats are not suitable, you can enter your own format in the appropriate field. The tokens used to define the format are listed in the right-click menu when the field has focus, and complete documentation for these tokens is available at the following web page: [DecimalFormat](#).

The **Unformatted** format for numbers and decimal number allows no grouping character. For Unformatted and decimal numbers a dot (".") is used as the decimal number separator.

5.11 Exporting a Table



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

You can export an individual table using the Export Table assistant.

- [Output Format](#)
- [Output Destination](#)
- [Options](#)
- [Using Variables in Fields](#)
- [Exporting Binary/BLOB and CLOB Data](#)
- [Saving And Loading Settings](#)
- [Other Ways to Export Table Data](#)

To export a table:

1. Select a table node in the **Databases** tab tree,
2. Open the **Export Table** dialog from the right-click menu,



3. Select an **Output Format**, **Output Destination**, and **Options**,
4. Click **Export**.

Below is how the Export Table window look. There may be different options based on what database type the table is exported from.

Export Table - SAKILA sample/Schemas/SAKILA/Tables/FILM

Settings | **Export**

Output Format

CSV HTML SQL XML Excel JSON Encoding: UTF-8

Output Destination

File C:\Users\mike

SQL Commander New Editor At Caret First Last Replace All

Clipboard

Options

Common Options

Max Rows: -1

Common SQL Options

Generate CREATE	<input type="checkbox"/>
Generate DROP	<input type="checkbox"/>
Use Qualifier	<input type="checkbox"/>
Qualifier	SAKILA
Delimiters	None
Statement Separator	;
Group By	Object
Add Before	
Add After	
Split Larger Than Size	-1
Generate Multi-Row INSERT statements	<input type="checkbox"/>
Rows per Multi-Row INSERT statement	10

Table SQL Options

Generate INSERT	<input checked="" type="checkbox"/>
Include Auto-Generated values	<input checked="" type="checkbox"/>
Generate CREATE INDEX	<input type="checkbox"/>

Data Format Settings...

Settings | Export | Close

5.11.1 Output Format

You can export tables in one of these formats: **CSV**, **HTML**, **SQL**, **XML**, **Excel**, or **JSON**.

For the **SQL** and **XML** formats, you can choose to export the DDL and the table data; the other formats only export table data.

You can control whether to [use delimited identifiers and/or qualified names](#) by default in the DDL and INSERT statements generated for the SQL format, and you can override the defaults in the Export dialog for a single export operation.



5.11.2 Output Destination

The destination can be one of:

- a file,
- an open or new SQL Commander tab, with options for where in an open SQL Commander to insert the result,
- to the system clipboard.

5.11.3 Options

The **Options** section contains options common to all Output Formats at the top, followed by options for the selected format.

Example of the options for SQL:

Options	
Common Options	
Max Rows	11
Total Rows in Grid	11
Common SQL Options	
Use Qualifier	<input checked="" type="checkbox"/>
Qualifier	
Table Name	
Delimiters	""
Statement Separator	;
Include Basic DDL	<input type="checkbox"/>
Include Original SQL	Don't Include
Row Comment Identifier	--
Add Before	
Add After	
Generate Multi-Row INSERT statements	<input type="checkbox"/>
Rows per Multi-Row INSERT statement	10

Example of the options for Excel:

Options	
Common Options	
Max Rows	11
Total Rows in Grid	11
Common XLS Options	
File Format	XLSX
Title	
Description	
Sheet Name	
Include Column Names	<input checked="" type="checkbox"/>
Use any Label (Alias)	<input checked="" type="checkbox"/>
Export Number as Text	<input type="checkbox"/>
Export Date/Time as Text	<input checked="" type="checkbox"/>
Include Original SQL	None
Auto Resize Columns	<input type="checkbox"/>

For the **SQL** and **XML** formats, you can choose to export the DDL, the DDL for indexes for a table and the table data: as INSERT statements for the SQL statement or in one of three XML formats.

For the **Excel** format, you can choose to export table data as either in the **XLSX** (default) or the legacy **XLS** format.



Most formats also let you specify other options, such as delimiters, title and descriptions. Just select an Output Format to see which options are available. All options are described in the context of the `@export` command, as the Export dialog is just a GUI for the command.

You can adjust the **Data Formats** specifically for the exported table data. By default, the formats defined in **Tool Properties** are used, but sometimes you need to export dates and numbers in a different format because you intend to import the data into a different type of database.

i If you are exporting table data in the **SQL** format from one database type (e.g. Oracle) to import it in a database of a different type (e.g. PostgreSQL) by executing the generated script, you need to be aware of differences in the literal formats for Date, Time and Timestamp data. If you connect to the other database using a JDBC client like DbVisualizer, you can select the **JDBC escape** format for these data format. This generates literals that the JDBC driver converts into a format the target database can interpret.

In the **Data Format Settings** dialog you can also specify how to quote text data and how to handle quotes within the text value.

5.11.4 Using Variables in Fields

You can use some of the [pre-defined DbVisualizer variables](#) (`${dbvis-date}`, `${dbvis-time}`, `${dbvis-timestamp}`, `${dbvis-connection}`, `${dbvis-database-type}` and `${dbvis-object}`) in all fields that hold free text (e.g. title and description fields) and as part of the file name field.

5.11.5 Exporting Binary/BLOB and CLOB Data

You can use the export assistant to export Binary/BLOB and CLOB data. You enable this by choosing **File** as the data format for **Binary/BLOB** and/or **CLOB** data. Optionally, you can specify the directory or filename pattern for the data files. If you do not specify a directory or filename pattern, the operating system's default directory for temporary files (e.g. `C:\TEMP` or `/tmp`) is used.

Binary/BLOB:	File	C:\Users\hans	▼	📁
CLOB:	File	C:\Users\hans\exp\\${dbvis-date}\\${COUNTRY_NAME}.txt	▼	📁

A pattern is a path with fixed and variable parts, where the variable parts are expressed as DbVisualizer variables, e.g. `C:\Users\hans\exp\${dbvis-date}\${COUNTRY_NAME}.txt`. You can select variables to insert at the current caret position in the path field from the dropdown. The variables that can be used are the predefined DbVisualizer variables plus variables for each column in the table, e.g. `${COUNTRY_NAME}` in the example above. Another special variable that can be helpful here is `${dbvis-column-name}`. If a table has multiple BLOB or CLOB columns, you can use it in the pattern to export the columns to separate files, e.g. `C:\Users\hans\exp\${dbvis-column-name}.txt`. All variables that can be used are listed in the menu that is displayed when you click the blue arrow to the right of the field. You can select a variable from the menu to insert it in the pattern field at the caret position.

The data for each individual value of this type is then exported to a separate file and a DbVisualizer variable referencing the file is inserted in the main export file.

5.11.6 Saving And Loading Settings

If you often use the same settings, you can save them as the default settings for this assistant. If you use a number of common settings, you can save them to individual files that you can load as needed. Use the **Settings** drop-down button menu to accomplish this:

- **Save as Default Settings**
Saves all format settings as default. These are then loaded automatically when open an Export Schema dialog
- **Use Default Settings**
Use this choice to initialize the settings with default values
- **Remove Default Settings**
Removes the saved defaults and restores the regular defaults
- **Load...**
Use this choice to open the file chooser dialog, in which you can select a settings file
- **Save As...**
Use this choice to save the settings to a file
- **Copy Settings to Clipboard**
Copies the settings to the system clipboard
- **Copy Settings to Clipboard**
Use this choice to copy all settings to the system clipboard. These can then be pasted into the SQL Commander to define the settings for the `@export` editor commands.



5.11.7 Other Ways to Export Table Data

- Export all or selected tables with the [Export Schema](#) assistant,
- Export a subset of the table data with the [@export](#) command.

5.12 Importing Table Data



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

You can import data using the Import Table Data wizard.

- [Input File Format and Other Options](#)
 - [CSV format page](#)
 - [Excel format page](#)
- [Data Formats and Data Type Per Column](#)
- [Matching Columns and Data Types for an Existing Table](#)
- [Adjusting Table Declaration for a New Table](#)
- [Importing Binary/BLOB and CLOB Data \(CSV and SQL Only\)](#)
- [Running the import](#)
- [Saving And Loading Settings](#)
- [Other Ways to Import Table Data](#)
- [Known limitations](#)

You can import data from a file into an existing table or to a new table. The import source can be either a CSV file or an Excel file (.xls or .xlsx). The steps are almost identical:

1. Select the table node for the table you want to import to, or the **Tables** node if you are importing to a new table, in the **Databases** tab tree,
2. Open the **Import Table Data** wizard from the right-click menu,
3. Specify the input file on the first wizard page (CSV or Excel file),
4. [Excel only]: If the input file is an Excel file, you are asked to choose the Excel sheet to import on the next page.
5. Specify file format and other options,
6. Specify data formats and the data type per column,
7. Adjust details about the destination table,
8. Click **Import** on the last page.



Instead of choosing Import Table Data from the right-click menu, you can **drag and drop a file** from the operating system's file manager on the Tables node or a table node.

How many INSERT statements to execute during the import process before committing the changes can be specified in the **Properties** tab for the connection, in the **Transaction** category.

5.12.1 Input File Format and Other Options

On the File Format page, you specify what and how the data in the source file should be imported. This includes specifying what row to start the import from and if empty rows should be skipped.

Currently DbVisualizer supports import of CSV files and the Excel file formats ".xls" and ".xlsx".



CSV format page

Import Table Data - Oracle/Schemas/HR/Tables/[New Table] ✕

Delimiters

Column Delimiter: Auto Detect String

Options

Row of Header:

Start Row of Data:

Skip Empty Row(s):

Skip Rows Starting With:

Values Quoted Between: Detect Data Type for Quoted Values

Data

Grid | File

*	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	
4	102	Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13 00:00:00	A
5	103	Alexander	Hunold	AHUNOLD	590.423.4567	1990-01-03 00:00:00	Π
6	104	Bruce	Ernst	BERNST	590.423.4568	1991-05-21 00:00:00	Π
7	105	David	Austin	DAUSTIN	590.423.4569	1997-06-25 00:00:00	Π
8	106	Valli	Pataballa	VPATABAL	590.423.4560	1998-02-05 00:00:00	Π
9	107	Diana	Lorentz	DLORENTZ	590.423.5567	1999-02-07 00:00:00	Π
10	108	Nancy	Greenberg	NGREENBE	515.124.4569	1994-08-17 00:00:00	F
11	109	Daniel	Faviet	DFAVIET	515.124.4169	1994-08-16 00:00:00	F
12	110	John	Chen	JCHEN	515.124.4269	1997-09-28 00:00:00	F

Preview Rows: Fit Column Widths

Settings < Back Next > Cancel

In the **Delimiters** section, define the character that separates the columns in the file. If you enable **Auto Detect**, DbVisualizer tries to auto detect which delimiter is used. Examples of auto detected delimiters are:

- comma ","
- tab "TAB"
- semicolon ";"
- percent "%"
- pipe "|"
- Using Unicode Code Points such as \u2656.

i You can specify any character sequence as a delimiter, but it must not contain more than four characters.

You can use the **Options** area to further specify how to read the input file, for instance if certain rows should be skipped and how text data is quoted.

The **Data** section at the bottom of the page shows a preview of the parsed data in the **Grid** tab and the original source file in the **File** tab. If a row in the Grid tab is red, it indicates that the row will be ignored during the import process. This happens if any of the **Options** settings result in rows not being qualified.



If the checkbox **Detect Data Type for Quoted Values** is checked the data type is also detected for that value. E.g a value "1" will be detected as a Number and not a String.

Excel format page

The Excel format page is very much like the CSV format page.

As Excel is from start organized in columns and rows the **Column delimiter** setting is not applicable to Excel files. The **Skip Rows Starting With** and the **Text Quoted Between** options are also not supported for Excel.

As shown in the snapshot below there is no **File** tab for Excel files.

The **Grid** tab shows a preview of the data, just as in the CSV case.

The screenshot shows the 'Import Table Data' dialog box for Oracle/Schema/HR/Tables/[New Table]. The 'Options' section includes 'Row of Header' (1), 'Start Row of Data' (2), and 'Skip Empty Row(s)' (checked). The 'Data' section has a 'Grid' tab selected, displaying a table with columns: EMPLOYEE..., FIRST_NAME, LAST_NAME, EMAIL, PHONE_N..., HIRE_DATE, JOB_ID, and SALARY. The table contains 9 rows of data. Below the grid, 'Preview Rows' is set to 20, and there is a 'Fit Column Widths' checkbox. At the bottom, there are 'Settings', '< Back', 'Next >', and 'Cancel' buttons.

*	EMPLOYEE...	FIRST_NAME	LAST_NAME	EMAIL	PHONE_N...	HIRE_DATE	JOB_ID	SALARY
2	167.0	Amit	Banda	ABANDA	011.44.134...	2000-04-21 ...	SA_REP	6200.0
3	185.0	Alexis	Bull	ABULL	650.509.2876	1997-02-20 ...	SH_CLERK	4100.0
4	187.0	Anthony	Cabrio	ACABRIO	650.509.4876	1999-02-07 ...	SH_CLERK	3000.0
5	147.0	Alberto	Errazuriz	AERRAZUR	011.44.134...	1997-03-10 ...	SA_MAN	12000.0
6	121.0	Adam	Fripp	AFRIPP	650.123.2234	1997-04-10 ...	ST_MAN	8200.0
7	103.0	Alexander	Hunold	AHUNOLD	590.423.4567	1990-01-03 ...	IT_PROG	9000.0
8	175.0	Alyssa	Hutton	AHUTTON	011.44.164...	1997-03-19 ...	SA_REP	8800.0
9	115.0	Alexander	Khoo	AKHOO	515.127.4562	1995-05-18 ...	PU_CLERK	3100.0

5.12.2 Data Formats and Data Type Per Column

The Data Formats page is used to define formats for some data types. The first row in the preview grid contains a data type drop-down lists. DbVisualizer tries to determine the data type for each column by looking at the value for the number of rows specified as **Preview Rows**. If this data type is incorrect for a column, use the drop-down lists to select the appropriate type.



Import Table Data - Oracle/Schemas/HR/Tables/[New Table]

Data Formats

Date: 2020-02-28

Time: 11:15:00

Timestamp: 2020-02-28 11:15:00

Number Separators: Grouping Decimal

Boolean Text Value: True False

Null Value Text

Data

Grid

EMPLOYEE...	FIRST_NAME	LAST_NAME	EMAIL	PHONE_N...	HIRE_DATE	JOB_ID	SALARY
\$ Decima...	\$ String	\$ String	\$ String	\$ String	\$ Timest...	\$ String	\$ Decima...
167.0	Amit	Banda	ABANDA	011.44.134...	2000-04-21 ...	SA_REP	6200.0
185.0	Alexis	Bull	ABULL	650.509.2876	1997-02-20 ...	SH_CLERK	4100.0
187.0	Anthony	Cabrio	ACABRIO	650.509.4876	1999-02-07 ...	SH_CLERK	3000.0
147.0	Alberto	Errazuriz	AERRAZUR	011.44.134...	1997-03-10 ...	SA_MAN	12000.0
121.0	Adam	Fripp	AFRIPP	650.123.2234	1997-04-10 ...	ST_MAN	8200.0
103.0	Alexander	Hunold	AHUNOLD	590.423.4567	1990-01-03 ...	IT_PROG	9000.0
175.0	Alyssa	Hutton	AHUTTON	011.44.164...	1997-03-19 ...	SA_REP	8800.0
115.0	Alexander	Khoo	AKHOO	515.127.4562	1995-05-18 ...	PU_CLERK	3100.0
158.0	Allan	McEwen	AMCEWEN	011.44.134...	1996-08-01 ...	SA_REP	9000.0

Preview Rows: Fit Column Widths

Settings

i If you need to change the data type for a number of columns, e.g. set them all to String, you can Copy/Paste the data type. First change it for one of the columns using the drop-down, select and copy that new data type value and then select the data type for all other columns and use paste to change them all at once. If you make a mistake, you can change the **Preview Rows** value to let DbVisualizer determine the types again.

If you import to an existing table, there is yet another way to adjust the data types for the file columns, described in the next section.

5.12.3 Matching Columns and Data Types for an Existing Table

When you are importing to an existing table, the Import Destination page provides two options: **Grid** and **Current Database Table**. You can use the **Grid** choice to import the data into a grid that is presented in its own window in DbVisualizer if you just want to just process the data in some way without saving it in the database.

When the **Current Database Table** choice is selected, the page shows information about the table into which the data will be imported in the **Map Table Columns with File Columns** grid shows the columns in the selected database table and the columns in the source file.



Import Table Data - Oracle/Schemas/HR/Tables/EMPLOYEES

Import Into
 Grid Current Database Table New Database Table

Database Table
Database Connection: Oracle
Database:
Schema: HR
Table: EMPLOYEES

Map Table Columns with File Columns

Key	Table Column Name	Table Data Type	File Column Name	File Data Type
	EMPLOYEE_ID	NUMBER		
	FIRST_NAME	VARCHAR2		
	LAST_NAME	VARCHAR2		
	EMAIL	VARCHAR2	4 EMAIL	String
	PHONE_NUMBER	VARCHAR2	5 PHONE_NUMBER	String
	HIRE_DATE	DATE	6 HIRE_DATE	Times
	JOB_ID	VARCHAR2	7 JOB_ID	String
	SALARY	NUMBER	8 SALARY	Decim
	COMMISSION_PCT	NUMBER	9 COMMISSION_PCT	Decim

Map Columns

- Map by Column Name
- Map by Column Index
- Map File Data Type = Table Data Type
- Clear Mappings

Empty Table First TRUNCATE DELETE Use Delimited Identifiers

Settings < Back Next > Cancel

DbVisualizer automatically associates the columns in the source file with the columns in the target table in the order they appear. If the columns appear in a different order in the file than in the table, but they are named the same, you can use the auto-mapping menu in the upper right corner of the **Map Table Columns with File Columns** grid to automatically map the columns by name. **Map by Column Name** and **Map by Column Index** do exactly what it sounds like. **Map File Data Type = Table Data Type** sets the **File Data Type** for each column to the type of the corresponding table column.

If the column names are different between the file and the table and also appear in different order, you can manually map them using the drop-down lists in the File Column Name field. Choose the empty choice in the columns drop-down to ignore the column during import.



Import Table Data - Oracle/Schemas/HR/Tables/EMPLOYEES

Import Into
 Grid Current Database Table New Database Table

Database Table
Database Connection: Oracle
Database:
Schema: HR
Table: EMPLOYEES

Map Table Columns with File Columns

Key	Table Column Name	Table Data Type	File Column Index	File Column Name	File Data Type
	EMPLOYEE_ID	NUMBER	1	EMPLOYEE_ID	Decimal
	FIRST_NAME	VARCHAR2	2	FIRST_NAME	String
	LAST_NAME	VARCHAR2	3	LAST_NAME	String
	EMAIL	VARCHAR2	4		String
	PHONE_NUMBER	VARCHAR2	5	EMPLOYEE_ID	String
	HIRE_DATE	DATE	6	FIRST_NAME	Times
	JOB_ID	VARCHAR2	7	LAST_NAME	String
	SALARY	NUMBER	8	EMAIL	Decimal
	COMMISSION_PCT	NUMBER	9	PHONE_NUMBER	Decimal

Empty Table First TRUNCATE DELETE Use Delimited Identifiers

Settings < Back Cancel

i You can use copy/paste of the values in the **File Column Name** and **File Data Type** fields to quickly fill the selection of cells instead of manually selecting the correct data in the drop-downs.

There are two checkboxes at the bottom of the page:

- **Use Delimited Identifiers:** check this if you want the SQL statements for importing the table to use delimited identifiers; in other words, if you want to use table and column names with special characters, mixed case, or anything else that requires delimited (quoted) identifiers.
- **Empty Table First:** check this if you want to clear/empty the table before import. Choose between **Truncate** or **Delete**. Truncate is faster as it usually will clear the data without occupying the rollback management in the database.

5.12.4 Adjusting Table Declaration for a New Table

When you are importing to a new table, the Import Destination page provides two options: **Grid** and **New Database Table**. You can use the Grid choice to import the data into a grid that is presented in its own window in DbVisualizer if you just want to just process the data in some way without saving it in the database.

When the New Database Table choice is selected, you are presented with a field for the table name and a number of tabs for column and constraint declarations. The Columns tab is filled out based on the source data and the data types from the Data Formats page.



Import Table Data - Oracle/Schemas/HR/Tables/[New Table]

Import Into
 Grid Current Database Table New Database Table

New Table Details

Database Connection: Oracle

Database:

Schema: HR

Table: newTable

Columns Primary Key Foreign Keys Unique Constraints Check Constraints Organize On

Name	Data Type	Size	Scale	Nullable	Default	Invisible
EMPLOYEE_ID	NUMBER			<input checked="" type="checkbox"/>		<input type="checkbox"/>
FIRST_NAME	VARCHAR2	10		<input type="checkbox"/>		<input type="checkbox"/>
LAST_NAME	VARCHAR2	10		<input type="checkbox"/>		<input type="checkbox"/>
EMAIL	VARCHAR2	10		<input type="checkbox"/>		<input type="checkbox"/>
PHONE_NUMBER	VARCHAR2	20		<input type="checkbox"/>		<input type="checkbox"/>
HIRE_DATE	TIMESTAMP			<input type="checkbox"/>		<input type="checkbox"/>
JOB_ID	VARCHAR2	10		<input type="checkbox"/>		<input type="checkbox"/>
SALARY	NUMBER			<input checked="" type="checkbox"/>		<input type="checkbox"/>
COMMISSION_PCT	NUMBER			<input checked="" type="checkbox"/>		<input type="checkbox"/>
MANAGER_ID	NUMBER			<input checked="" type="checkbox"/>		<input type="checkbox"/>
DEPARTMENT_ID	NUMBER			<input checked="" type="checkbox"/>		<input type="checkbox"/>

Drop Existing Table, if any Use Delimited Identifiers

Settings > < Back Next > Cancel

Note that it is not always possible to find a database specific type for the data format specified on the Data Format page. You must then pick the correct type from the **Data Type** drop-down menu. The size for string column types may also need to be adjusted. By default, the size is set to the maximum number of characters found for the column in the number of rows specified as **Preview Rows**, adjusted up to the next power of ten. You can ignore certain columns by removing them in the **Columns** tab. **Keys** and other constraints can be created using the other tabs.

You can go back to the Data Format page and increase the **Preview Rows** value if you believe that it will help DbVisualizer to pick better defaults. If you do so, you need to click the **Reload** button when you come back to this page to rescan the source data and get new default values.

If you make a mistake, or if the import fails, so you have to go back and make adjustments before you import again, make sure you enable **Drop Existing Table, if any**. It is disabled by default to prevent you from accidentally dropping an existing table when you intend to import to a new table, but if the import fails, the new table may already have been created so it needs to be dropped before a new table with your adjusted input can be created.

There is also a **Use Delimited Identifiers** checkbox. Check this box if you want the SQL statements for importing the table to use delimited identifiers; in other words, if you want to use table and column names with special characters, mixed case, or anything else that requires delimited (quoted) identifiers.

5.12.5 Importing Binary/BLOB and CLOB Data (CSV and SQL Only)

If you have exported data to a CSV file using DbVisualizer, use the Import Table Data feature to import it. On the Data Format page, ensure that the format for the source file column is set to **BLOB** or **CLOB**.



ID	PHOTO
1	<code>\$(data1-1) C:\Users\ulf\Documents\tmp\blobs\dbvis-3503876270486780709.bin BinaryData noshow vl=file}\$(</code>

If you have exported Binary/BLOB and CLOB data as an SQL script, you just run the script in the SQL Commander to import it. When the SQL Commander encounters a variable that refers to a file, it reads the file and inserts the content as the column value.

5.12.6 Running the import

The last wizard page contains some basic settings for the import.

- **Import All rows/Import** Used to limit the number of rows to import
- **Keep Window After import** If checked the Import window will remain open after import. If the import fails the window will always remain open.
- **Stop On Error** If checked the import will stop if an error occurs.
- **Batch Import:** If checked the import will be performed using batch import. Using batch import may improve performance of the import considerably making the import faster. Note that different databases/drivers may have different level of support for batch import. The number of rows to include in each batch can be controlled by the **Commit Batch Size (rows)** setting in in the **Properties** tab for the connection, in the **Transaction** category.

5.12.7 Saving And Loading Settings

If you often use the same settings, you can save them as the default settings for this assistant. If you use a number of common settings, you can save them to individual files that you can load as needed. Use the **Settings** drop-down button menu to accomplish this:

- **Save as Default Settings**
Saves all format settings as default. These are then loaded automatically when open an Export Schema dialog
- **Use Default Settings**
Use this choice to initialize the settings with default values
- **Remove Default Settings**
Removes the saved defaults and restores the regular defaults
- **Load...**
Use this choice to open the file chooser dialog, in which you can select a settings file
- **Save As...**
Use this choice to save the settings to a file
- **Copy Settings to Clipboard**
Copies the settings to the system clipboard

5.12.8 Other Ways to Import Table Data

If you have a script containing INSERT statements for all data, you can execute it in the [SQL Commander](#).

5.12.9 Known limitations

- Excel files cannot contain CLOB/BLOB type of data (e.g. images etc). Cells with this kind of data are imported as empty.
- There is a size limitation when importing Excel files with the `.xls` filename extension. The size limitation is roughly 20 megabytes, depending on your configuration and how much memory is used for other things. [Increasing DbVisualizer max memory](#) may allow you to import larger files.

5.13 Comparing Tables



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.



You can compare different aspects of a table to other tables and/or result set grids.

For instance, to compare the DDL for a table to the DDL for another table:

1. Open the **DDL** tab for the table,
2. Open the **DDL** tab for the other table,
3. Select **Compare** from the right-click menu in one of the **DDL** tabs to [compare their text content](#).

To compare the table data to the data of another table or a result set:

1. Open the **Data** tab for the table,
2. Open the **Data** tab for another table or execute an SQL query to open a result set tab,
3. Select **Compare** from the right-click menu in one of the tabs to [compare their grid content](#).

You can do the same for all the other Object View sub tabs containing a grid, such as the **Primary Key** or **Columns** tab.

5.14 Viewing Table Relationships

Use the References graph to see how a table is related to other tables through Foreign Keys. This is done by selecting the **References** sub tab of the Database object view, as further described below

You can view relations to/from one or more tables in different graph layouts: **Hierarchical**, **Organic**, **Orthogonal**, or **Circular**.

Layout settings can be changed in the **Graph Control** area, which is shown or hidden with the settings toggle button in the toolbar. For instance, you can select how much information to include for each table in the graph: just the **Table Name**, the **Primary Key** column(s) or all **Columns**, which links to include, and whether or not to highlight links for selected tables. Settings vary slightly depending on whether you are viewing relations for a single table or multiple tables, and some settings (e.g. **Links to Columns**) are only available in **Hierarchical** layout.

If you choose the **Hierarchical** layout and select **Links to Columns** and **Highlight Links**, the graph will for all selected table nodes color code links and columns to indicate usage:

- foreign key columns and outbound links are green
- primary key columns and inbound links are red
- bidirectional columns (used for both inbound and outbound links) and bidirectional links (where both source and target tables are selected) are orange

The graph can be **Exported** to a file in **JPG**, **GIF**, **PNG**, **SVG**, **PDF** or **EMF**. It can also be saved as a **GML** (Graph Modeling Language) file that you can then open in the **yEd** tool from yWorks for further manipulation. The **GML** format is saved using **Save As** in the right-click menu. You can also control whether the table names should be [qualified with the schema/catalog](#) in the graph.

When opened on a single table, the graph will only show links to/from this table. You can choose which links to show: **Inbound**, **Outbound**, **All**, or **None**.

You can also [view entity relationships](#) to get an overview of multiple tables.


1. Locate the desired table in the **Databases** tab tree
2. Open the table's **Object View** tab (right-click -> **Open in Tab**)
3. Select the **References** sub tab



The screenshot shows the DbVisualizer interface with the following components:

- Database:** Sakila H2 (dbvis/test)
- Schema:** SAKILA
- Table:** FILM
- Table Structure:**
 - LANGUAGE:** LANGUAGE_ID (TINYINT, PK), NAME (CHAR(20)), LAST_UPDATE (TIMESTAMP)
 - FILM:** FILM_ID (SMALLINT, PK), TITLE (VARCHAR(128)), DESCRIPTION (CLOB), RELEASE_YEAR (SMALLINT), LANGUAGE_ID (TINYINT, FK), ORIGINAL_LANGUAGE_ID (TINYINT, FK), RENTAL_DURATION (TINYINT), RENTAL_RATE (DECIMAL(4,2)), LENGTH (SMALLINT), REPLACEMENT_COST (DECIMAL(5,2)), RATING (ENUM), SPECIAL_FEATURES (VARCHAR(256)), LAST_UPDATE (TIMESTAMP)
 - INVENTORY:** INVENTORY_ID (INTEGER, PK), FILM_ID (SMALLINT, FK), STORE_ID (TINYINT, FK), LAST_UPDATE (TIMESTAMP)
 - FILM_ACTOR:** ACTOR_ID (SMALLINT, FK), FILM_ID (SMALLINT, FK), LAST_UPDATE (TIMESTAMP)
 - FILM_CATEGORY:** FILM_ID (SMALLINT, FK), CATEGORY_ID (TINYINT, FK), LAST_UPDATE (TIMESTAMP)
- Relationships:** Arrows indicate foreign key relationships from FILM to LANGUAGE, INVENTORY, FILM_ACTOR, and FILM_CATEGORY.
- UI Elements:** A toolbar with icons for Count, Primary Key, Indexes, Grants, Row Id, DDL, References, and Navigator. A status bar at the bottom right shows "77% Tables: 5 References: 5".

By selecting one or more tables, links and columns are highlighted using colors to indicate usage.



Check [Viewing Entity Relationships](#) section for information about the references graph showing all tables in a schema.

5.15 Navigating Table Relationships

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

A powerful way to study database data is to navigate between the tables in a schema by following table relationships declared by Primary and Foreign Keys. DbVisualizer includes a **Navigator** feature for this purpose, visualizing the relationships graphically while making the data for each navigation case easily accessible in a data grid.

- [Opening the Navigator](#)
- [Navigating Relationships](#)
- [Adding Context Information to the Graph](#)
- [Arranging the Graph](#)
- [Exporting and Printing the Graph](#)
- [Opening the Navigator from the Data tab](#)

5.15.1 Opening the Navigator

To launch the **Navigator**:

1. Locate the table you want to start the navigation from in the **Databases** tab tree,
2. Double-click the table node to open its **Object View** tab,
3. Select the **Navigator** sub tab.



Table: DEPARTMENTS
Ora12C_HR/Schemas/HR/Tables/DEPARTMENTS

Info Columns Data Row Count Primary Key Row Id References Navigator Grants Columns Comment Ir

DEPARTMENTS

DEPARTMENT_ID
DEPARTMENT_NAME Human Resources

EMPLOYEES
DEPARTMENT_ID 40

DEPARTMENT_ID
DEPARTMENT_NAME IT

EMPLOYEES
DEPARTMENT_ID 60

Powered by yFiles

Related Table

* DEPARTMENT_ID	DEPARTMENT_NAME	MANAGER_ID	LOCATION_ID
1	10 Administration	200	1700
2	20 Marketing	201	1800
3	30 Purchasing	114	1700
4	40 Human Resources	203	2400
5	50 Shipping	121	1500
6	60 IT	103	1400
7	70 Public Relations	204	2700
8	80 Sales	145	2500
9	90 Executive	100	1700
10	100 Finance	108	1700
11	110 Accounting	205	1700
12	120 Treasury	(null)	1700
13	130 Corporate Tax	(null)	1700

Max Rows: 1000 Max Chars: -1 Pattern: n/a 124.663/0.000 sec 27/4 1-13

The **Navigator** tab has two parts: a graphical view and a data grid. Initially, the graphical view shows just the selected start table, and the data grid shows the data for the start table.

The data grid is of the same type as you encounter in other parts of DbVisualizer, such as in the **Data** tab, but extended with a **Related Table** list and a **Tag** button.

5.15.2 Navigating Relationships

Data navigation in DbVisualizer means following table relationships declared by Primary and Foreign Keys, using a unique key value. In the example schema shown in the screen shots in this section, there is a table named DEPARTMENTS with a primary key named DEPARTMENT_ID. Another table named EMPLOYEES has a foreign key constraint, declaring that values in its DEPARTMENT_ID column refer to primary key values in the column with the same name in the DEPARTMENTS table.



	DEPARTMENT_ID	DEPARTMENT_NAME	MANAGER_ID	LOCATION_ID
1	10	Administration	200	
2	20	Marketing	201	
3	30	Purchasing	114	1700
4	40	Human Resources	203	2400
5	50	Shipping	121	1500
6	60	IT	103	1400
7	70	Public Relations	204	2700
8	80	Sales	145	2500
9	90	Executive	100	1700
10	100	Finance	108	1700
11	110	Accounting	205	1700
12	120	Treasury	(null)	1700
13	130	Corporate Tax	(null)	1700

Max Rows: 1000 Max Chars: -1 Pattern: ... 124.663/0.000 sec 27/4 1-13

If you use DEPARTMENTS as your start table, you can easily navigate to the EMPLOYEES table for different DEPARTMENT_ID values. In the data grid, select one or more columns in the row that holds the DEPARTMENT_ID you want to use for navigation. In the figure above, the DEPARTMENT_NAME column in the row for DEPARTMENT_ID = 60 is selected.

Next, bring up the **Related Table** list. It lists all tables the DEPARTMENTS table is related to through Primary and Foreign Keys, with the key columns within parenthesis. A forward arrow (->) between the table names means that the DEPARTMENTS table has a foreign key relation to the named table. A backward arrow (<-) means that the named table has a foreign key relation to the DEPARTMENTS table.



Table: DEPARTMENTS
Ora12C_HR/Schemas/HR/Tables/DEPARTMENTS

Info Columns Data Row Count Primary Key Row Id References Navigator Grants

DEPARTMENTS → DEPARTMENT_ID DEPARTMENT_NAME IT → EMPLOYEES DEPARTMENT_ID 60

Powered by yFiles

EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALARY	COMMISSION
103	Alexander	Hunold	AHUNOLD	590.423.4567	2006-01-03 00:00:00	IT_PROG	9000	
104	Bruce	Ernst	BERNST	590.423.4568	2007-05-21 00:00:00	IT_PROG	6000	
105	David	Austin	DAUSTIN	590.423.4569	2005-06-25 00:00:00	IT_PROG	4800	
106	Valli	Pataballa	VPATABAL	590.423.4560	2006-02-05 00:00:00	IT_PROG	4800	
107	Diana	Lorentz	DLORENTZ	590.423.5567	2007-02-07 00:00:00	IT_PROG	4200	

Max Rows: 1000 Max Chars: -1 Pattern: n/a 0.000/0.000 sec 5/11 1-5

When you select "DEPARTMENTS (DEPARTMENT_ID) <- EMPLOYEES (DEPARTMENT_ID)" in the **Related Table** list, a node is added to the graph for the EMPLOYEES table, with an arrow from the DEPARTMENTS table node to show the navigation direction. We call this a navigation case.

The EMPLOYEES node contains the key columns (just one in this example) and their values.

The arrow between the nodes is labeled with the key column name. In addition, the arrow label also shows the name and value of the column that you selected in the DEPARTMENTS table when you created this navigation case, i.e., the DEPARTMENT_NAME column. If you select multiple columns when you create a navigation case, all non-key column names and values are included in the arrow label. This can make it easier to see at a glance what a navigation case represents.

The grid is also updated when you create a navigation case, to show all rows in the table you navigated to that has a key value corresponding to the selected key value in the table you navigated from. In this case, it shows all rows in the EMPLOYEES table with DEPARTMENT_ID equal to 60.

i You can edit the grid values, but be aware that if you change the value of a key in the grid for a navigation case, the row will disappear from the grid since the grid only shows rows with keys matching the navigation case key value.

You can continue to create more navigation cases from any node in the graph. For instance, if the schema contains a table with job history information for employees, you can navigate to the history for an employee from the EMPLOYEES node. Or, you can select the DEPARTMENTS node in the graph to navigate to the EMPLOYEES table for a different department. Just click on the DEPARTMENTS node, select another row in the data grid and then the same **Related Table** list entry.



Table: DEPARTMENTS
Ora12C_HR/Schemas/HR/Tables/DEPARTMENTS

Info Columns Data Row Count Primary Key Row Id References Navigator Grants Column

DEPARTMENTS

DEPARTMENT_ID
DEPARTMENT_NAME Human Resources

EMPLOYEES
DEPARTMENT_ID 40

DEPARTMENT_ID
DEPARTMENT_NAME IT

EMPLOYEES
DEPARTMENT_ID 80

Powered by yFiles

* EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALARY	COMMISSION_P
1	203 Susan	Mavris	SMAVRIS	515.123.7777	2002-06-07 00:00:00	HR_REP	6500	

Max Rows: 1000 Max Chars: -1 Pattern: n/a 0.000/0.000 sec 1/11 1-1

i If you want to create multiple navigation cases from one table to another using the same relationship, you can select columns in multiple rows in the first table. When you make a selection in the **Related Table** list, one navigation case per row is created.

Every time you select a node in the graph, the data grid is updated to show the corresponding data. The grid settings for one node are independent of the settings for another node. For instance, if you define a filter for one node, the filter is only associated with the grid for that node.

5.15.3 Adding Context Information to the Graph

The navigation node always shows the key columns and their values, but sometimes you may want to add other columns to the node to better describe what it represents. This is called tagging the node. There are two ways to do so: drag and drop cells from the grid to any node, or use the **Tag** button in the grid toolbar to tag the currently selected node with the currently selected cells in the grid.


To drag and drop cells to a node, select one or more cells in the grid. With the left mouse button pressed and the mouse positioned over one of the selected cells, drag the cells over a node in the graph and release the mouse button. The cells are added to the node.



The screenshot shows the DbVisualizer interface. At the top, the title bar reads "Table: DEPARTMENTS" and the breadcrumb is "Ora12C_HR/Schemas/HR/Tables/DEPARTMENTS". The toolbar includes buttons for Info, Columns, Data, Row Count, Primary Key, Row Id, References, Navigator, Grants, Columns Comment, Indexes, and Constrain. Below the toolbar is a graph view showing a relationship between the DEPARTMENTS table and two instances of the EMPLOYEES table. The first instance is for DEPARTMENT_ID 40 (Human Resources) with employees Susan and Mavis. The second instance is for DEPARTMENT_ID 60 (IT). Below the graph is a table view for the EMPLOYEES table with the following data:

EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID	SALARY	COMMISSION_PCT	MANAGER_ID	DEPARTMENT_ID
203	Susan	Mavis	SMAVRIS	515.123.7777	2002-06-07 00:00:00	HR_REP	6500	(null)	101	

At the bottom of the table view, there are controls for Max Rows (1000), Max Chars (-1), Pattern (n/a), and performance metrics (0.000/0.000 sec, 1/11, 1-1).

Alternatively, you can select the cells in the grid and click on the Tag button () to add the cell values to the currently selected node.


5.15.4 Arranging the Graph

As you add navigation cases, you may find that you need to move nodes around, remove selected nodes, zoom and move around in the graph, etc.

You can rearrange the layout of the graph by selecting a node and, with the left mouse button pressed, drag it around. The arrow and its label move with the node.

The toolbar for the graph offers a number of tools to help you with other tasks

The **Overview** control is useful for large graphs that do not fit into the display area.



The gray area in the **Overview** control indicates the portion of the graph that is currently shown in the display area. You can drag the gray area around to study other portions of the graph.

To get a larger graph display area, you can put the **Overview** control in a separate window. Just uncheck the **Docked** checkbox.

5.15.5 Exporting and Printing the Graph

You can also export the graph to an image file or print it. Use the corresponding toolbar buttons to do this

When you print the graph, you are prompted for information about what to print (the Graph or the View, i.e., just the portion visible in the display area) and how many rows and columns to split the printing over (one page is used for each row/column).

5.15.6 Opening the Navigator from the Data tab

Sometimes, you may realize that you want to analyze the relationships for a table when you are working with it in the **Data** tab. If you have configured the **Data** tab to show only filtered data, sorted in a specific way, etc. opening the **Navigator** tab and making all the same configurations there may be a bit of a hassle. A more convenient way is to just pick **Show in Navigator** in the right-click menu in the **Data** tab. It opens the table in the **Navigator** tab with all the same configurations as you made in the **Data** tab.

5.16 Viewing the Table DDL



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

To see the DDL (CREATE statement) for a table:

1. Locate the table node in the **Databases** tab tree,
2. Double-click the table node to open its **Object View** tab,
3. Select the **DDL** sub tab.

The DDL shown is based on metadata retrieved from the database, and will not include some database-specific information, such as storage clauses. For some databases, there is an additional sub tab named **Native DDL** (or similar) that shows the DDL as generated by the database itself, including all clauses.



5.17 Filtering Tables in the Tree

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

If you have many tables in the tree, it may be hard to find the ones of most interest. You can then define a filter so that only a few tables are shown, as described in [Filtering Database Objects](#).

5.18 Showing Row Count in the Tree

You can use the **Database->Show/Hide Table Row Count** menu choice to see the number of rows within parenthesis next to the table name in the Database tab tree.

i Enabling this property results in a performance degradation.

5.19 Using Permissions for Table Data Editing

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **Permission** functionality is a security mechanism, where you can specify that certain database operations must be confirmed. You configure permissions in the Tool Properties dialog, in the **Permissions** category of the General tab, per *connection mode* (Development, Test and Production).

You specify which connection mode to use for a connection in the **Properties** tab of the Object View tab for the connection. By default a connection mode is specified to be Development.

i The permission feature is part of DbVisualizer and does not replace the authorization system in the actual database.

For table grid edits, you can pick the permission type from a drop-down list for each operation:

Permission Type	Description
Confirm	A confirmation window is displayed, and you can accept the operation or cancel it
No Confirm	The SQL operation is performed without any confirmation

Table Data Editor Permissions

Define here if insert, update and delete must be confirmed in the table data editor.

	Development	Test	Production
INSERT:	No Confirm	No Confirm	Confirm
UPDATE:	No Confirm	Confirm	Confirm
DELETE:	No Confirm	Confirm	Confirm

5.20 Scripting a Table

To open the Script Table dialog, where you can insert generated text for a table in an SQL Commander editor:

1. Select one or more table nodes in the Databases tab tree,
2. Choose **Script Table** from the right-click menu.



You can also launch the dialog by dragging and dropping one or more nodes of the same type in an SQL Commander editor.

- i** If you just want to insert the object names in the editor, hold down the **Ctrl** key (or the **Alt** key on macOS) while dragging and dropping. This behavior can be reversed in **Tool Properties**, in the **SQL Commander** category, so that dropping without pressing a key inserts the names and pressing the key launches the dialog.

The Script dialog provides a choice of which type of statement to generate, options for formatting, use of delimited identifiers, qualified names and statement delimiters. You can also pick an open SQL Commander or a new as the destination, and where in the SQL Commander editor to insert the text.

5.21 Managing Table and Column Comments

- i** This feature is only available for some databases. Please execute the corresponding SQL in the [SQL Commander](#) if it is not available for your database.

Many databases support adding comments for various database objects, such as tables and columns. How this is done is database-dependent, but for some of the databases with specific support in DbVisualizer, you can enter and edit comments using an action in the right-click menu for the object node selected in the **Databases** tab. For instance, for an Oracle database, you can manage table comments like this:

1. Select the table node in the tree,
2. Choose **Comment Table** in the right-click menu,
3. Add or edit the comment.

For Oracle, you can manage comments for other database object types, such as columns and views, in the same way. An Oracle **Tables** node also has a **Table Comments** tab in its Object Views tab, listing then comments for all tables in a schema.

6 Working with Views

DbVisualizer provides many ways to work with views.

6.1 Creating a View

There is no GUI dialog for creating a view, but you can:

1. Use the [Query Builder](#) to create the SELECT statement graphically,
2. Load the generated SELECT statement into the SQL Editor by clicking the corresponding button in the toolbar,
3. Add `CREATE VIEW name AS` before the SELECT statement,
4. Execute the CREATE VIEW statement.

6.2 Altering a View

Views can typically not be altered; they must be dropped and recreated. You can:

1. Select the view in the **Databases** tree,
2. Double-click the view node to open its **Object View** tab,
3. Open the **DDL** sub tab,
4. Select **Copy to New Editor** from the **DDL** tab's right-click menu, which opens an **SQL Commander** tab with the DDL,
5. Remove the CREATE VIEW part in the **SQL Commander** editor so you are left with just the SELECT statement,
6. Load the SELECT statement into the **Query Builder** and alter it graphically,
7. Launch the **Drop View** assistant from the view node's right-click menu, and click **Execute** to drop it,
8. [Create the new view](#) from the altered SELECT statement.

6.3 Editing a View

You can edit view data the same as you [edit table data](#).



6.4 Exporting a View

You can export a view the same way as you [export a table](#).

6.5 Viewing the View DDL



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

To see the DDL (CREATE statement) for a view:

1. Locate the view node in the **Databases** tab tree,
2. Double-click the view node to open its **Object View** tab,
3. Select the **DDL** sub tab.

6.6 Filtering Views in the Tree



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

If you have many views in the tree, it may be hard to find the ones of most interest. You can then define a filter so that only a few views are shown, as described in [Filtering Database Objects](#).

6.7 Scripting a View

To open the Script View dialog, where you can insert generated text for a view in an SQL Commander editor:

1. Select one or more view nodes in the Databases tab tree,
2. Choose **Script View** from the right-click menu.

You can also launch the dialog by dragging and dropping one or more nodes of the same type in an SQL Commander editor.



If you just want to insert the object names in the editor, hold down the **Ctrl** key (or the **Alt** key on macOS) while dragging and dropping. This behavior can be reversed in **Tool Properties**, in the **SQL Commander** category, so that dropping without pressing a key inserts the names and pressing the key launches the dialog.

The Script dialog provides a choice of which type of statement to generate, options for formatting, use of delimited identifiers, qualified names and statement delimiters. You can also pick an open SQL Commander or a new as the destination, and where in the SQL Commander editor to insert the text.

7 Working with Procedures, Functions and Other Code Objects

Many databases offer the capability to store custom code in the database, primarily as functions and procedures, where a function has a return value but a procedure does not (a procedure may instead have output parameters). In addition, some databases offer a package concept, which means that a collection of functions and/or procedures are grouped together in one unit. A package is the interface describing the functions and procedures, while the package body contains the implementation. Many databases also support triggers: code that is executed when triggered by an event such as deleting a row in a table.

You can use DbVisualizer actions to create and drop procedural object of these types, and use the code editor to browse, edit and compile these object types. Procedures and functions can also be executed in the SQL Commander, with return values and parameters bound to DbVisualizer variables.




7.1 Creating a Function

Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

To create a new function:

1. Expand nodes in the tree under the connection node in the **Databases** tab tree until you reach the **Functions** node,
2. Select the **Functions** node and open the **Create Function** dialog from the right-click menu.



Create Function

Create Function in Database Connection: Ora12C_HR

Function Owner: HR

Function Name: myfunction

Return Data Type: VARCHAR2

Parameters

Name	Direction	Type	Default
p1	IN	VARCHAR2	
p1	IN OUT	VARCHAR2	

Show SQL

Execute Cancel

SQL Preview

```
1 @delimiter %%;
2 CREATE
3 FUNCTION "HR".myfunction (p1 IN VARCHAR2,
4                           p1 IN OUT VARCHAR2)
5   RETURN VARCHAR2 AS
6   BEGIN
7     DBMS_OUTPUT.PUT_LINE('Sample output');
8     RETURN NULL;
9   END;
10  %%%
11 @delimiter ;
12 %%%
13
```

The details of the dialog depends on the database, but typically you need to:

1. Enter an object name,
2. Click the **Add** button in the **Parameters** area to add parameters,
3. Enter a name and data type for each parameter. For some databases you can also enter a direction (typically IN, OUT, or INOUT) and a default value.

You can use the other buttons to the right of the parameter list to remove and move a parameter.

The dialog uses this information together with a simple sample body to compose a CREATE statement. For most databases, you can not enter the real code in the dialog. The real code is often complex and large, so DbVisualizer provides a more powerful editing environment than would fit in a dialog via the [Code Editor](#). What you create with the dialog should be seen as a template that you then complete and work with in the Code Editor.



For some databases the sample code is editable because there is no way to write a generic sample that compiles. You must then modify the template to something that is syntactically correct, but we still recommend that you finish the real code in the Code Editor instead.

Click **Execute** in the dialog to create the new function.

7.2 Creating a Procedure

i Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

To create a new procedure:

1. Expand nodes in the tree under the connection node in the **Databases** tab tree until you reach the **Procedures** node,
2. Select the **Procedures** node and open the **Create Procedure** dialog from the right-click menu.

Create Procedure

Create Procedure in Database Connection: CRM Ahoa

Procedure Owner: HR

Procedure Name: UPDATE_HISTORY

Parameters

Name	Direction	Type	Default
order_id_start	IN	NUMBER	-1
order_id_end	IN	NUMBER	-1
status	IN	VARCHAR2	'CLOSED'

Show SQL

Execute Cancel

SQL Preview

```
1 @delimiter %%%;  
2 CREATE PROCEDURE "HR".UPDATE_HISTORY  
3 (order_id_start IN NUMBER default -1, order_id_end IN NUMBER default -1  
4 AS  
5 BEGIN  
6   DBMS_OUTPUT.PUT_LINE('Sample output');  
7 END;%%  
8 @delimiter ;%%  
9
```

The details of the dialog depends on the database, but typically you need to:

1. Enter an object name,
2. Click the **Add** button in the **Parameters** area to add parameters,
3. Enter a name and data type for each parameter. For some databases you can also enter a direction (typically IN, OUT, or INOUT) and a default value.

You can use the other buttons to the right of the parameter list to remove and move a parameter.



The dialog uses this information together with a simple sample body to compose a CREATE statement. For most databases, you can not enter the real code in the dialog. The real code is often complex and large, so DbVisualizer provides a more powerful editing environment than would fit in a dialog via the [Code Editor](#). What you create with the dialog should be seen as a template that you then complete and work with in the Code Editor.

For some databases the sample code is editable because there is no way to write a generic sample that compiles. You must then modify the template to something that is syntactically correct, but we still recommend that you finish the real code in the Code Editor instead.

Click **Execute** in the dialog to create the new procedure.

7.3 Creating Other Code Objects



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

Some databases support other code object types in addition to function, stored procedure and trigger, e.g. Package in Oracle and Module in Mimer.

To create a new database-specific code object:

1. Expand nodes in the tree under the connection node in the **Databases** tab tree until you reach the group node for the code type, e.g. **Packages**,
2. Select the group node and open the **Create** dialog from the right-click menu.

The details of the dialog depends on the database, but typically you need to:

1. Enter an object name,
2. Click the **Add** button in the **Parameters** area to add parameters,
3. Enter a name and data type for each parameter. For some databases you can also enter a direction (typically IN, OUT, or INOUT) and a default value.

You can use the other buttons to the right of the parameter list to remove and move a parameter.

The dialog uses this information together with a simple sample body to compose a CREATE statement. For most databases, you can not enter the real code in the dialog. The real code is often complex and large, so DbVisualizer provides a more powerful editing environment than would fit in a dialog via the [Code Editor](#). What you create with the dialog should be seen as a template that you then complete and work with in the Code Editor.

For some databases the sample code is editable because there is no way to write a generic sample that compiles. You must then modify the template to something that is syntactically correct, but we still recommend that you finish the real code in the Code Editor instead.

Click **Execute** in the dialog to create the new code object.

7.4 Editing a Code Object



Only in DbVisualizer Pro

This feature is only available in the Pro edition. In the Free edition, please execute the corresponding SQL in the [SQL Commander](#).

To edit the code for an object, such as a function, stored procedure or database-dependent code object:

1. Expand nodes in the tree under the connection node in the **Databases** tab tree until you reach the node for the object you want to edit,
2. Double-click the node to open an **Object View** tab for it, and select the editor sub tab (e.g., the **Procedure Editor** tab).

The editor has a toolbar with various actions to save/compile the procedure, save and load the source to/from file and perform common editing operations. The **Status** indicator shows whether the procedure is valid or invalid based on last compilation (not available for all databases).

Edit the source code and save/compile the procedure when you are happy with the code, using the **Save** toolbar button.



```
1 CREATE OR REPLACE PROCEDURE "HR"."UPDATE_STATUS" (
2     order_id_start IN NUMBER DEFAULT -1,
3     order_id_end IN NUMBER DEFAULT -1,
4     status IN VARCHAR2 DEFAULT 'CLOSED')
5 AS
6 BEGIN
7     update oders
8     set current_status = status
9     where id >= order_id_start and id <= order_id_end;
10 END;
```

Time	Status	Message
15:06:07	✓ SUCCESS	Source code was compiled/saved
15:06:07	✗ FAILED	PL/SQL: ORA-00942: table or view does not exist
15:06:07	✗ FAILED	PL/SQL: SQL Statement ignored

If errors occur, the corresponding text is underlined with a red wavy line. Hovering the mouse over the error indication shows the corresponding error message. The right margin contains markers for each error as well, and clicking on a marker scrolls the editor to the corresponding error. Alternatively, you can click the **FAILED** link in the Log tab grid to move the caret to the error location.

If you prefer to navigate between errors using the keyboard, you can use the defined key bindings for the **Insertion Point to Next Marker** and **Insertion Point to Previous Marker** actions in the Tool Properties dialog, in the **Key Bindings** category, in the Editor Commands group. Alternative is to use the **Goto Next Failed** and **Goto Previous Failed** in the right click menu of Log tab grid, and then click the link for the FAILED entries.



Error location information is not available for some databases. In that case the complete statement is underlined in the editor.

7.4.1 Disable Error Markers in the SQL Editor

From DbVisualizer 10.0.5 it is possible to disable error markers in the **SQL Commander->SQL Commander Options** menus. With **Show Error Position Markers** turned on it shows markers only for databases that specifically report positions of errors in a statement. With **Show Error Statement Markers** turned on the complete statement is highlighted if it fails during execution, but only if either the **Show Error Position Markers** is turned off or if the driver/database doesn't report positions of errors.


If you're looking to minimize the amount of error markers when executing scripts, turn off **Show Error Statement Markers** and keep the **Show Error Position Markers** checked (turned on). DbVisualizer will then report errors reported by the JDBC driver only.

To set default values for these settings visit **Tools->Tool Properties** and the **General / SQL Commander** category.



In addition to the **Status** indicator in the editor, the object icon in the tree shows a little red cross for invalid procedures, for databases that provide this information. You can see this for the **UPDATE_STATUS** procedure node in the screenshot above.

The figure below shows the result after correcting the errors and recompiling the procedure:



The status indicator now shows that the procedure is **VALID**.

7.5 Executing a Code Object

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.


You can execute a code object, such as a function or stored procedure, either in the [Code Editor](#) or in the [SQL Commander](#).

- [Executing in the Code Editor](#)
- [Executing in the SQL Commander](#)
- [Using the Script Object Dialog](#)



7.5.1 Executing in the Code Editor

In the Code Editor, click the **Execute** button. DbVisualizer then generates a script for executing the code object, using variables for all parameters, and executes it.



Because the script contains variables, the **Variable Prompt** dialog pops up. Enter values for all parameters and click **Continue** to execute the procedure. The result is shown in the results area below the editor.

In the example shown in the figure, all parameters are input parameters but DbVisualizer also support execution of procedures with output parameters and functions returning a value. In this case, the generated script includes @echo statements to write the result in the **Log** tab. Please see below for more details.

7.5.2 Executing in the SQL Commander

The scripts generated and executed by the Code Editor can also be included in a script and executed in an SQL Commander. Here's an example of a script calling a function and writing the result in the **SQL Commander Log** tab:

```
@call ${STATUS}|| (null)||String|noshow dir=out}$ = "HR"."GET_STATUS"(1002);
@echo STATUS: ${STATUS}$;
```

In this example, the result value from the GET_STATUS function is assigned to a variable named STATUS. Note that it has an option `dir=out`. This is a requirement for a variable that is assigned a value at runtime, whether it is used for a return value from a function call or for an output parameter in a



procedure call. It also has the `noshow` option, to avoid getting prompted for a value for the variable. The value of the `STATUS` variable is then written to the log using the `@echo` command.

You can also use the output from one function or procedure as input to another, or even as a value in a `SELECT` or other SQL statement:

```
@call ${STATUS}|| (null)||String|noshow dir=out}$ = "HR"."GET_STATUS"(1002);  
@call "HR"."UPDATE_STATUS"(1000, 2000, ${STATUS}||String|noshow dir=in}$);
```

Note that `dir=in` is specified for the `STATUS` variable when it is used in the `UPDATE_STATUS` procedure call. When you use a variable first for output and then as input with another `@call` command, you must change the direction option like this.

More formally, the `@call` command has this syntax when calling a function:

```
@call <OutVariable> = <FunctionName>(<ParamList>)
```

where the `<FunctionName>` may need to be fully qualified with a schema (and/or catalog/database) and the `<ParamList>` is a comma separated list of literal values or variables. Here's an example:

```
@call ${return_value}|| (null)||String|dir=out noshow}$ = get_some_value();
```

For a procedure, use this syntax:

```
@call <ProcedureName>(<ParamList>)
```

where the `<ProcedureName>` may need to be fully qualified with a schema (and/or catalog/database) and the `<ParamList>` is a comma separated list of literal values or variables. Here's an example:

```
@call my_process('literal input',  
                ${var_in}|| (null)||String|dir=in}$,  
                ${var_out}|| (null)||String|dir=out noshow}$,  
                ${var_inout}|| 'in_value' ||String|dir=inout}$);
```


As shown in these examples, you must use the `dir` option to specify how the variable is to be used (in, out or inout) and you may use the `noshow` option to prevent being prompted for a value for an output variable.

You can use the [@echo command](#) to write the value assigned to an output variable to the log.

7.5.3 Using the Script Object Dialog

Instead of writing a `@call` script by hand in an SQL Commander, you can use the Script Object (e.g. **Script Procedure** or **Script Function**) right-click menu choices for the object node in the tree.

This opens the Script Object dialog where you select that you want to generate a CALL script and can adjust settings for using delimiters and qualifiers, as well as the destination for the generated script. This is how the Script Dialog will look like when opened for a Procedure.



7.6 Exporting a Code Object

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

To export a code object:

1. Select the object node in the **Databases** tab tree,
2. Open the Export Object dialog (e.g. **Export Procedure** or **Export Function**) from the right-click menu,
3. Select an **Output Format**, **Output Destination**, and **Options**,
4. Click **Export**.

For these object types, you can select either the **SQL** (CREATE statement) or **XML** Output Format and which delimiters to use in the Options area.


You can control whether to [use delimited identifiers and/or qualified names](#) in the DDL and INSERT statements generated for the SQL format.

7.7 Scripting a Code Object

To open the Script Function/Procedure dialog, where you can insert generated text for a code object in an SQL Commander editor:

1. Select one or more code object nodes in the Databases tab tree,
2. Choose **Script Function/Procedure** from the right-click menu.

You can also launch the dialog by dragging and dropping one or more nodes of the same type in an SQL Commander editor.

 If you just want to insert the object names in the editor, hold down the **Ctrl** key (or the **Alt** key on macOS) while dragging and dropping. This behavior can be reversed in **Tool Properties**, in the **SQL Commander** category, so that dropping without pressing a key inserts the names and pressing the key launches the dialog.



The Script dialog provides a choice of which type of statement to generate, options for formatting, use of delimited identifiers, qualified names and statement delimiters. You can also pick an open SQL Commander or a new as the destination, and where in the SQL Commander editor to insert the text.

8 Working with Schemas

DbVisualizer provides many ways to work with schemas.

8.1 Creating a Schema

To create a new schema:

1. Locate the **Schemas** node in the Databases tab tree,
2. Open the **Create Schema** dialog from the right-click menu,
3. Enter all required information (database dependent),
4. Click **Execute** to create the schema.

i This feature is only available for some databases. Please execute the corresponding SQL in the [SQL Commander](#) if it is not available for your database.

8.2 Comparing Schemas

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

While DbVisualizer does not provide a way to fully show the differences between two schemas in terms of objects and data, you can compare different aspects of a schema to another schema one by one.

For instance, to compare the list of tables in one schema with the list of tables in another schema:

1. Expand the schema node for the first schema and select its **Tables** node and open it in a new Object View tab, select the **Tables** tab,
2. Do the same for the second schema,
3. Select "**Compare...**" from the right-click menu in one of the Tables grids to [compare their grid content](#), or **select** Tools->Compare.

You can do the same for all the other schema object types, such as views and stored procedures. You can also dig deeper and compare the individual objects, such as [comparing individual tables](#).

8.3 Viewing Entity Relationships

Use the References graph to see how tables are related to other tables through Foreign Keys.

You can view relations to/from one or more tables in different graph layouts: **Hierarchical**, **Organic**, **Orthogonal**, or **Circular**.

Layout settings can be changed in the **Graph Control** area, which is shown or hidden with the settings toggle button in the toolbar. For instance, you can select how much information to include for each table in the graph: just the **Table Name**, the **Primary Key** column(s) or all **Columns**, which links to include, and whether or not to highlight links for selected tables. Settings vary slightly depending on whether you are viewing relations for a single table or multiple tables, and some settings (e.g. **Links to Columns**) are only available in **Hierarchical** layout.

If you choose the **Hierarchical** layout and select **Links to Columns** and **Highlight Links**, the graph will for all selected table nodes color code links and columns to indicate usage:

- foreign key columns and outbound links are green
- primary key columns and inbound links are red
- bidirectional columns (used for both inbound and outbound links) and bidirectional links (where both source and target tables are selected) are orange


The graph can be **Exported** to a file in **JPG**, **GIF**, **PNG**, **SVG**, **PDF** or **EMF**. It can also be saved as a **GML** (Graph Modeling Language) file that you can then open in the **yEd** tool from yWorks for further manipulation. The **GML** format is saved using **Save As** in the right-click menu. You can also control whether the table names should be [qualified with the schema/catalog](#) in the graph.




When opened on multiple tables, the graph shows all links between the tables; you cannot choose to show inbound or outbound relations since all links are both outbound (from one table) and inbound (to some other table). You can however exclude unreferenced tables and/or manually select which tables to include on the graph.

To zoom in on a specific table, you can also [view table relationships](#) for a specific table.

1. Locate the **Tables** node in the **Databases** tab tree
2. Open the **Object View** tab (right-click -> **Open in Tab**)
3. Select the **References** sub tab



Removing details and turning on highlighting to focus on certain aspects of the schema can be quite useful, especially if you choose to export the graph to discuss it with someone else.



Check [Viewing Table Relationships](#) section for information about the references graph showing references for specific a table.

8.4 Exporting a Schema



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

You can export all or selected objects in a schema using the Export Schema assistant.

- [Output Format](#)
- [Output Destination](#)
- [Object Types](#)
- [Options](#)
- [Using Variables in Fields](#)
- [Saving And Loading Settings](#)

To export a schema:

1. Select the schema node in the **Databases** tab tree,
2. Launch the **Export Schema** assistant from the right-click menu,
3. Select an **Output Format**, **Output Destination**, **Objects** to export and **Options**,
4. Click **Export**.

8.4.1 Output Format

You can export objects in one of these formats: **CSV**, **HTML**, **SQL**, **XML**, **XLS** (Excel), or **JSON**.

The **CSV**, **HTML**, **XLS** and **JSON** formats are specifically for table data and are not supported for any other type of objects.

The **SQL** and **XML** formats can be used for all objects to export the DDL, and for tables you can also choose to include the table data in these formats.



You can control whether to [use delimited identifiers and/or qualified names](#) in the DDL and INSERT statements generated for the SQL format, using the controls in the Options area.

8.4.2 Output Destination

The destination can be one of:

- a file,
- an open or new SQL Commander tab, with options for where in an open SQL Commander to insert the result,
- to the system clipboard.

8.4.3 Object Types

In the **Object Types** area you select what to export. You can check the checkbox for an object type to export all objects of that type, or expand a type node and select individual objects. To select all objects, just check the checkbox for the schema itself at the top of the tree.

8.4.4 Options

The **Options** section contains options common to all Output Formats at the top, followed by options for the selected format.

Example of the options for SQL:

Options	
[-] Common Options	
Max Rows	11
Total Rows in Grid	11
[-] Common SQL Options	
Use Qualifier	<input checked="" type="checkbox"/>
Qualifier	
Table Name	
Delimiters	**
Statement Separator	;
Include Basic DDL	<input type="checkbox"/>
Include Original SQL	Don't Include
Row Comment Identifier	--
Add Before	
Add After	
Generate Multi-Row INSERT statements	<input type="checkbox"/>
Rows per Multi-Row INSERT statement	10

Example of the options for Excel:



Options

Common Options	
Max Rows	11
Total Rows in Grid	11

Common XLS Options	
File Format	XLSX
Title	
Description	
Sheet Name	
Include Column Names	<input checked="" type="checkbox"/>
Use any Label (Alias)	<input checked="" type="checkbox"/>
Export Number as Text	<input type="checkbox"/>
Export Date/Time as Text	<input checked="" type="checkbox"/>
Include Original SQL	None
Auto Resize Columns	<input type="checkbox"/>

For the **SQL** and **XML** formats, you can choose to export the DDL, the DDL for indexes for a table and the table data: as INSERT statements for the SQL statement or in one of three XML formats.

For the **Excel** format, you can choose to export table data as either in the **XLSX** (default) or the legacy **XLS** format.

Most formats also let you specify other options, such as delimiters, title and descriptions. Just select an Output Format to see which options are available. All options are described in the context of the [@export command](#), as the Export dialog is just a GUI for the command.

You can adjust the **Data Formats** specifically for the exported table data. By default, the formats defined in **Tool Properties** are used, but sometimes you need to export dates and numbers in a different format because you intend to import the data into a different type of database.



If you are exporting table data in the **SQL** format from one database type (e.g. Oracle) to import it in a database of a different type (e.g. PostgreSQL) by executing the generated script, you need to be aware of differences in the literal formats for Date, Time and Timestamp data. If you connect to the other database using a JDBC client like DbVisualizer, you can select the **JDBC escape** format for these data format. This generates literals that the JDBC driver converts into a format the target database can interpret.

In the **Data Format Settings** dialog you can also specify how to quote text data and how to handle quotes within the text value.

8.4.5 Using Variables in Fields

You can use some of the [pre-defined DbVisualizer variables](#) (`${dbvis-date}`, `${dbvis-time}`, `${dbvis-timestamp}`, `${dbvis-connection}`, `${dbvis-database-type}` and `${dbvis-object}`) in all fields that hold free text (e.g. title and description fields) and as part of the file name field.

Use the `${dbvis-object}` variable as part of the filename if you want to export the DDL and/or data to a separate file for each object. The variable is replaced with the object type and object name, e.g. `${dbvis-object}.sql` becomes `table_COUNTRIES.sql` for a table named COUNTRIES.

8.4.6 Saving And Loading Settings

If you often use the same settings, you can save them as the default settings for this assistant. If you use a number of common settings, you can save them to individual files that you can load as needed. Use the **Settings** drop-down button menu to accomplish this:

- **Save as Default Settings**
Saves all format settings as default. These are then loaded automatically when open an Export Schema dialog
- **Use Default Settings**
Use this choice to initialize the settings with default values
- **Remove Default Settings**
Removes the saved defaults and restores the regular defaults
- **Load...**
Use this choice to open the file chooser dialog, in which you can select a settings file
- **Save As...**
Use this choice to save the settings to a file
- **Copy Settings to Clipboard**
Copies the settings to the system clipboard



- **Copy Settings to Clipboard**

Use this choice to copy all settings to the system clipboard. These can then be pasted into the SQL Commander to define the settings for the @export editor commands.

8.5 Filtering Schemas in the Tree

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.


If you have many schema in the tree, it may be hard to find the ones of most interest. You can then define a filter so that only a few schemas are shown, as described in [Filtering Database Objects](#).

9 Working with SQL

With DbVisualizer, you can use a powerful SQL editor or a graphical Query Builder to create and edit your scripts, save them as Bookmarks for easy access, and execute all or just a few of the statements, and lots more.

9.1 Selecting Database Connection, Catalog and Schema

You use the **Database Connection** and **Database** (or Catalog) lists above the editor to specify which connection and database to use when executing the SQL in the SQL Commander. The list of connections shows all connections as they are ordered in the Databases tab tree, except that all currently active connections are listed first.



The screenshot shows the Prod database being selected, when hovering a name its full path including any folders are listed in a tooltip.

If you check the **Sticky** box above the Database Connection, the current connection selection will not change automatically when passing SQL statements from other parts of DbVisualizer, for instance, when opening a [Bookmark](#). Consider a Bookmark defined for database connection Prod. If the Sticky checkbox is not checked (i.e., disabled), the database connection is automatically changed to Prod when you open the Bookmark in the SQL Editor. However, if the Sticky checkbox is checked (i.e., enabled), the current database connection setting is unchanged. You can specify if you want to have Sticky enabled by default in the Tool Properties dialog, in the **SQL Commander** category under the General tab.

The **Database** list (or Catalog) defines which catalog in the connection is the target for the execution. Since not all databases use catalogs, this list may be disabled.

For most databases, the schema selected in the **Schema** list is used **only** to limit the tables the Auto Completion feature shows in the completion pop-up; it does *not* define a default schema for tables referenced in the SQL, because most databases do not allow the default schema to be changed during a session.

For the databases that do allow the default schema to be changed, however, the selected schema is also used as the default schema, i.e., the schema used for unqualified table names in the SQL. Currently, the databases that support setting a default schema are DB2 LUW, DB2 z/OS, DB2 iSeries, H2, JavaDB/Derby, Oracle, NuoDB, PostgreSQL, and Vertica. If the Database Type is set to **Generic** for a connection, DbVisualizer tries to set the default schema (if **Use Schema** is chosen) but it depends on the JDBC driver if this works or not.

If you don't want the selected schema to be used as the default schema for these database, you can disable this behavior in the **Properties** tab for the connection, in the **SQL Commander** category.



9.1.1 Configuring the Initial Values


When a new Database Connection is selected, the initial values for the **Database** and **Schema** lists are by default based on the default values for the connection. You can change this behavior in the **Properties** tab for the connection, in the **SQL Commander** category. The initial value for each list that is applicable for the database type can be set to one of **The Connection Default**, **None** or **The Most Recently Used**.

9.2 Editing SQL Scripts

The SQL Commander contains an SQL editor, used to edit SQL scripts.

- [Font Settings](#)
- [Editor Styles](#)
- [Comments](#)
- [Charsets and Fonts](#)
- [Loading and Saving Scripts](#)
- [Stale Files Warning](#)
- [Drag and Drop a File](#)
- [Drag and Drop Database Objects](#)
- [Loading and Saving Bookmarks and Monitors](#)
- [Navigating Between History Entries](#)
- [Navigating to Script location](#)
- [Confirming Overwriting Unsaved Changes](#)
- [SQL Formatting](#)
- [Settings](#)
- [Auto Completion](#)
- [Recording and Playing Edit Macros](#)
- [Folding Selected Text](#)
- [Selecting a Rectangular Area](#)
- [Tab Key Treatment](#)
- [Key Bindings](#)

The editor area looks like this:



Above the editor is a toolbar with buttons related both to execution of scripts and to editing. The editing related buttons are covered below.

The left margin shows the line numbers.

Below the editor, you see a Status Bar with the following fields, from left to right:




1. The current caret position in the format: <line>:<column> [<position from top>]
The last figure, within square brackets, is the caret position from the top. This can be useful when you get an error message executing a script that contains this information rather than a line/column location.
2. Insert/Overwrite Mode: **INS** if characters you type will be inserted at the caret position or **OVR** if they will overwrite the current text at the caret position. You can toggle this mode using the **Toggle Typing Mode** keyboard shortcut, by default bound to the **Insert** key.
3. Macros: this field is only visible when working with macros, as described in the [Recording and Playing Edit Macros](#) section.
4. File Format: A button that shows the format of the file as detected when the file was loaded (if any). Click the button to select which format to use when saving the file; **Windows**, **Unix/Linux/macOS**, or **Old MacOS**.
5. Auto Commit Status field shows whether or not **Auto Commit** is enabled.
6. Character Set: The character encoding as detected when the file was loaded (if any). Click the button to select which encoding to use when saving the file.
7. The name of the loaded file (if any). You can click on the filename to copy the file path or open the OS file chooser for the directory holding the file. If you just type into the editor without loading a file, the filename "Untitled" is shown instead. An asterisk (*) after the filename indicates that there are unsaved edits.

The SQL Editor is like any editor you're used to when it comes to typing, scrolling etc. But it also offers additional features to help you specifically with editing SQL scripts. These are described in the following sections.

You can change how to display in the **Tools->Tool Properties** dialog, in the **General / Appearance** category. This is explained in more detailed below.

9.2.1 Font Settings

In the **Appearance/Fonts** category, you can select the font for **Text Editors** to control the font in the SQL Editor (**Monospaced Fonts** are usually a good choice for code editors).



9.2.2 Editor Styles

An SQL script consists of keywords, operators, object identifiers, quoted text, etc. It may also contain comments. To make it easier to see at a glance what is what, the SQL Editor displays words using different font styles depending on their classification. For instance, keywords are displayed with a bold blue font, while quoted text is displayed with a regular type red font.

In the **Appearance/Editor Styles** category you can select colors for the different kinds of words, as well as the editor selection background color, the current line highlight color and the editor background color, and more.

The **SQL Editor Column Guide** is an optional visual guide that appears as a thin vertical line at specified column (this works best if you use monospaced fonts).



The screenshot shows the 'Tool Properties' dialog box with the 'General' tab selected. The left sidebar contains a tree view of settings categories, with 'Editor Styles' highlighted. The main area is divided into three sections:

- SQL Editor Colors:** Settings used to control the generic colors for the SQL editor. Note that these are defined for the current look and feel. It includes color pickers for Background (255, 255, 255), Selection Background (207, 234, 254), Current Line Highlight (255, 255, 215), Caret Color (0, 0, 0), and Special Character Color (197, 197, 197).
- SQL Editor Styles:** These settings control the syntax highlighting in the SQL editor per token type. Note that these are defined for the current look and feel. It includes a list of styles (Normal, Line Comment, Block Comment, Quoted Literal, Bracketed Literal, Label, Standard Keyword, Non-Standard Keyword, Client-Side Command, Operator) and corresponding font settings (Bold, Italic), background, foreground, effect, effect color, and stripe color.
- SQL Editor Column Guide:** Setting used to control the vertical column guide line for the SQL editor. It includes a checkbox for 'Show Guide at Column' and a numeric input set to 80.

Buttons for 'Defaults', 'OK', 'Apply', and 'Cancel' are located at the bottom of the dialog.

9.2.3 Comments

The editor uses the Tool Properties settings from the **SQL Commander/Comments** category under the General tab to detect comments.



Comment Delimiters

Specify the comment identifiers that might appear in an SQL statement. If **Strip Comments when Executing** is enabled in the **Processing Controls** drop-down menu in the **SQL Commander** toolbar, comments are removed from the SQL statement before execution.

Single Line Identifier 1:

Single Line Identifier 2:

Block Comment Begin Identifier: End:

Preview

```
select id, name, adr as 'Address' from Emp; -- This is a single line 1 comment
select Size, Age from Type; // This is a single line 2 comment

/*
(This is a block comment)
create table Car (Type varchar2(20), Color varchar2(10));*/

create index CarInd (Type /*desc*/)
```

9.2.4 Charsets and Fonts

You can also change the SQL Editor font family, which is useful and necessary in order to display characters for languages like Chinese, Japanese, etc., in **Tool Properties** in the **Appearance/Fonts** category to set the font for the SQL Editor (see [Internationalization and Localization \(i18N and L10N\)](#) for more information).

```
1 -- 插入产品
2 INSERT INTO PRODUCTS (ID, NAME, TYPE) VALUES ('1', '沃尔沃', '汽车');
3 INSERT INTO PRODUCTS (ID, NAME, TYPE) VALUES ('2', '特斯拉', '汽车');
4 INSERT INTO PRODUCTS (ID, NAME, TYPE) VALUES ('3', '欧宝', '汽车');
5
```

9.2.5 Loading and Saving Scripts

The SQL editor supports loading statements from a file and saving the content of the editor to a file. Use the standard file operations, **Open**, **Save** and **Save As** in the **File** main menu or the main toolbar to accomplish this. Loading a file loads it into a new **SQL Commander** tab or activates the tab that already holds it.

The name of the loaded file is listed in the status bar of the editor, with the full file path shown in the window title. The editor tracks any modifications and indicates changes with an asterisk (*) after the filename. When you close the SQL Commander tab or exit DbVisualizer, you are asked what to do if there are any pending edits that need to be saved.

The **File->Open Recent** submenu lists the recently loaded files. How many recent files to keep track of can be specified in the Tool Properties dialog, in the **SQL Commander** category under then General tab.

You can also use the **Quick File Open** feature to open recent files as well as Bookmarks and History entries. By default, it is bound to the **Ctrl+Alt+O** key combination, and is also available via a main toolbar button as well as in the main **File->Quick File Open** menu.



Search: Recent Files Bookmarks History Monitors

Enter search text: 25 matches

Recent Files

- report.sql (C:\Users\ulf\.dbvis\Bookmarks\Oracle)
- insertEx.sql (C:\Users\ulf\Documents\db\scripts\div)
- createEx.sql (C:\Users\ulf\Documents\db\scripts\div)

Bookmarks


- report.sql (C:\Users\ulf\.dbvis\Bookmarks\Oracle)

History

- INSERT INTO BLOBTAB (ID, PHOTO) VALUES (0, ''); (2016-06-07 09:30:52, HR Production)
- SELECT EMP.FIRST_NAME, EMP.LAST_NAME, EMP.EMAIL, D (2016-06-07 08:28:31, HR Production)
- SELECT EMP.FIRST_NAME, EMP.LAST_NAME, EMP.EMAIL, D (2016-06-07 08:27:39, HR Production)
- SELECT EMP.FIRST_NAME, EMP.LAST_NAME, EMP.EMAIL, D (2016-06-07 08:27:09, HR Production)
- SELECT EMP.FIRST_NAME, EMP.LAST_NAME, EMP.EMAIL, D (2016-06-07 08:26:30, HR Production)

9.2.6 Stale Files Warning


SQL Commander monitors open files to detect external changes, for example if an open file is modified by an external editor, reloaded from a network connection or repository, etc. If a file is externally modified, you will see a warning ribbon at the top of the editor area, presenting options to handle the situation:

 The file was externally modified at **2020-02-13 15:17:41** (editor content is stale).

Ignore Save As... Compare to Saved... Revert to Saved

```
1 SELECT
2   EMP.FIRST_NAME,
3   EMP.LAST_NAME,
4   EMP.EMAIL,
5   DEPARTMENT_NAME,
6   CASE
7     WHEN EMP.SALARY>100000
8     THEN 'HIGH'
9     WHEN EMP.SALARY BETWEEN 50000 AND 100000
10    THEN 'MEDIUM'
11    ELSE 'LOW'
12  END AS SALARY_LEVEL
```

You can turn off this control in **Tool Properties/SQL Commander**:




9.2.7 Drag and Drop a File

You can also select a file in the platform's file browser and drop it somewhere in the DbVisualizer window. If you drop it in an editor, the file content is inserted at the caret position in the editor. If you instead drop it in the toolbar area, the file is opened in a new **SQL Commander** tab.

9.2.8 Drag and Drop Database Objects

If you want to include an object shown in the database objects tree, you can select the node and drop it in the editor where you want it inserted. The **Script Object** dialog is shown where you can select exactly what you want to insert in the editor.



First of all, you can select to insert an SQL statement based on the dropped object, e.g. a SELECT statement or a CREATE statement. You can also choose to just insert the object name. The choices available depends on the type of object you drop.

In the **Options** area, you can opt to format the SQL before it is inserted and use qualifiers and quoted identifiers, and even change which statement delimiter to use.

The **Output Destination** is set to the SQL Commander tab you dropped the object on by default, but you can change your mind and pick another destination. If you stick with an **SQL Commander** as the destination, you can tell where in the editor to insert the text.

You can also open this dialog from the **Databases** tab, from the object's right-click menu.




i If you just want to insert the object names in the editor, hold down the **Ctrl** key (or the **Alt** key on macOS) while dragging and dropping. This behavior can be reversed in **Tool Properties**, in the **SQL Commander** category, so that dropping without pressing a key inserts the names and pressing the key launches the dialog.

9.2.9 Loading and Saving Bookmarks and Monitors

Bookmarks and Monitors are also files, but with special meaning. See the [Managing Frequently Used SQL](#) for how to create and edit them in the SQL Editor.


9.2.10 Navigating Between History Entries

When you execute a script, DbVisualizer saves it as a history entry, see the [Re-Executing SQL Statements](#) section for details. You can use the **Previous** and **Next** buttons in the editor toolbar to navigate between (load) these entries.



9.2.11 Navigating to Script location

By selecting the script filename in the right bottom corner it is possible to select the file in the **Scripts** tab.





9.2.12 Confirming Overwriting Unsaved Changes

By default, you have to confirm overwriting unsaved changes in an editor, e.g. when navigating between history entries, and when closing an SQL Commander tab with unsaved edits. You can disable these confirmation popups in the Tool Properties dialog, under the **SQL Commander** category under the General tab.

9.2.13 SQL Formatting



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **SQL Commander** main menu on the (or right-click in the editor) and its **Format SQL** sub menu contains operations for formatting SQL statements.

```

/*-- CASE example*/
SELECT
FIRST_NAME,
LAST_NAME,
SALARY,
CASE
WHEN SALARY > 10000
THEN 'High'
WHEN SALARY BETWEEN 5000 AND 999
THEN 'Midlevel'
ELSE 'Low'
END AS "Income Level",
CASE DEPARTMENT_ID
WHEN 40
THEN 'Administration'
WHEN 20
THEN 'Sales Related'

```

- **Format Buffer** and **Format Current** formats the complete editor content or the current SQL (at cursor position) respectively.
- **Copy Formatted** and **Paste Formatted** are powerful tools for copying SQL statements between programs written in languages like Java, C#, PHP, VB, etc. and the SQL Editor. Both operations display a dialog where you can adjust some of the formatting options, most importantly the **Target SQL** option and the **SQL is Between** option. **Target SQL** can be set to a number of common programming language formats.
- **Unformat Buffer** and **Unformat Current** produces compact statements by removing unnecessary whitespace.

Example:

To copy an SQL statement and paste it as Java code for adding it to a Java StringBuffer:

1. Select the statement. Example:
SELECT * FROM SAKILA.STAFF)
2. Choose **SQL->Format SQL->Copy Formatted**,
3. Set **Target SQL** to Java StringBuffer,
4. Click **Format** to place the formatted statement on the system clipboard,
5. Paste it into your Java code. Example:
StringBuffer sql = new StringBuffer();
sql.append("SELECT ");
sql.append(" * ");
sql.append("FROM ");
sql.append(" SAKILA.STAFF");

To copy a statement wrapped in code from a program:

1. Select the code containing an SQL statement in your program,
2. Copy it to the system clipboard,
3. Choose **SQL->Format SQL->Paste Formatted**,
4. Check **SQL is Between** and enter the character enclosing the SQL statement in the code,
5. Click **Format** to extract the SQL statement and paste the formatted SQL in the editor.

9.2.14 Settings

All formatting is done according to the settings defined in the **Tool Properties** dialog, in the **SQL Editor/SQL Formatting** category under the General tab.

There are many things you can configure; use the default example or your own SQL to check the effect of the settings. After making some changes, press **Apply** and format again to see the result.

**Example:**

```
-- Basic SELECT example, with Sub-SELECT and JOIN
SELECT e.LAST_NAME AS "Last Name", e.FIRST_NAME AS "First Name", d.DEPARTMENT_NAME AS "Department", e.SALARY AS
"Salary", e.SALARY + e.SALARY * e.COMMISSION_PCT, e.COMMISSION_PCT * 100 || '%', ROUND(e.SALARY / ( SELECT MAX(SALAR
Y) FROM HR.EMPLOYEES), 2) * 100 AS "Percentage of Max" FROM HR.EMPLOYEES e INNER JOIN HR.DEPARTMENTS d ON
( e.DEPARTMENT_ID = d.DEPARTMENT_ID) WHERE d.DEPARTMENT_ID IN (10, 20, 90, 210) AND e.SALARY > 3000;
-- CASE example
SELECT FIRST_NAME, LAST_NAME, SALARY, CASE WHEN SALARY > 10000 THEN 'High' WHEN SALARY BETWEEN 5000 AND 999 THEN
'Midlevel' ELSE 'Low' END AS "Income Level", CASE DEPARTMENT_ID WHEN 40 THEN 'Administration' WHEN 20 THEN 'Sales
Related' ELSE 'Other' END AS "Special Departments" FROM EMPLOYEES;
-- JOIN example, with GROUP BY, HAVING and ORDER BY
SELECT COUNT(d.DEPARTMENT_NAME) AS "Departments per Location", c.COUNTRY_NAME, l.STATE_PROVINCE FROM DEPARTMENTS d
INNER JOIN LOCATIONS l ON d.LOCATION_ID = l.LOCATION_ID INNER JOIN COUNTRIES c USING (COUNTRY_ID) GROUP BY
c.COUNTRY_NAME, l.STATE_PROVINCE HAVING COUNT(d.DEPARTMENT_NAME) > 1 ORDER BY 2, 3, 1;
-- UPDATE example
UPDATE EMPLOYEES SET COMMISSION_PCT = 10 WHERE COMMISSION_PCT = 0 AND SALARY < 5000;
-- INSERT example
INSERT INTO EMPLOYEES ( FIRST_NAME, LAST_NAME ) VALUES ( 'Roger', 'Bjarevall' );
-- DELETE example
DELETE FROM EMPLOYEES WHERE HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');
-- CREATE TABLE example
CREATE TABLE DEPARTMENTS ( DEPARTMENT_ID NUMBER(4) NOT NULL, DEPARTMENT_NAME VARCHAR2(30) NOT NULL, MANAGER_ID
NUMBER(6), LOCATION_ID NUMBER(4), CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID), CONSTRAINT DEPT_LOC_FK FOREIGN
KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"), CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES
"EMPLOYEES" ("EMPLOYEE_ID"), CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL) );
```

**Formatted with default settings:**

```
-- Basic SELECT example, with Sub-SELECT and JOIN
SELECT
  e.LAST_NAME           AS "Last Name",
  e.FIRST_NAME          AS "First Name",
  d.DEPARTMENT_NAME     AS "Department",
  e.SALARY              AS "Salary",
  e.SALARY + e.SALARY * e.COMMISSION_PCT,
  e.COMMISSION_PCT * 100 || '%',
  ROUND(e.SALARY /
    ( SELECT
      MAX(SALARY)
    FROM
      HR.EMPLOYEES), 2) * 100 AS "Percentage of Max"
FROM
  HR.EMPLOYEES e
INNER JOIN
  HR.DEPARTMENTS d
ON
  (
    e.DEPARTMENT_ID = d.DEPARTMENT_ID)
WHERE
  d.DEPARTMENT_ID IN (10,
                     20,
                     90,
                     210)
AND e.SALARY > 3000;

-- CASE example
SELECT
  FIRST_NAME,
  LAST_NAME,
  SALARY,
  CASE
    WHEN SALARY > 10000
    THEN 'High'
    WHEN SALARY BETWEEN 5000 AND 999
    THEN 'Midlevel'
    ELSE 'Low'
  END AS "Income Level",
  CASE DEPARTMENT_ID
    WHEN 40
    THEN 'Administration'
    WHEN 20
    THEN 'Sales Related'
    ELSE 'Other'
  END AS "Special Departments"
FROM
  EMPLOYEES;

-- JOIN example, with GROUP BY, HAVING and ORDER BY
SELECT
  COUNT(d.DEPARTMENT_NAME) AS "Departments per Location",
  c.COUNTRY_NAME,
  l.STATE_PROVINCE
FROM
  DEPARTMENTS d
INNER JOIN
  LOCATIONS l
ON
  d.LOCATION_ID = l.LOCATION_ID
INNER JOIN
  COUNTRIES c
USING
  (COUNTRY_ID)
GROUP BY
```



```
c.COUNTRY_NAME,  
l.STATE_PROVINCE  
HAVING  
COUNT(d.DEPARTMENT_NAME) > 1  
ORDER BY  
2,  
3,  
1;  
  
-- UPDATE example  
UPDATE  
EMPLOYEES  
SET  
COMMISSION_PCT = 10  
WHERE  
COMMISSION_PCT = 0  
AND SALARY < 5000;  
  
-- INSERT example  
INSERT INTO  
EMPLOYEES  
(  
    FIRST_NAME,  
    LAST_NAME  
)  
VALUES  
(  
    'Roger',  
    'Bjarevall'  
);  
  
-- DELETE example  
DELETE  
FROM  
EMPLOYEES  
WHERE  
HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');  
  
-- CREATE TABLE example  
CREATE TABLE  
DEPARTMENTS  
(  
    DEPARTMENT_ID NUMBER(4) NOT NULL,  
    DEPARTMENT_NAME VARCHAR2(30) NOT NULL,  
    MANAGER_ID NUMBER(6),  
    LOCATION_ID NUMBER(4),  
    CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID),  
    CONSTRAINT DEPT_LOC_FK FOREIGN KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"),  
    CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES "EMPLOYEES" ("EMPLOYEE_ID"),  
    CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL)  
);
```

**Unformatted to compact form:**

```
/*-- Basic SELECT example, with Sub-SELECT and JOIN*/ SELECT e.LAST_NAME AS "Last Name", e.FIRST_NAME AS "First Name", d.DEPARTMENT_NAME AS "Department", e.SALARY AS "Salary", e.SALARY + e.SALARY * e.COMMISSION_PCT, e.COMMISSION_PCT * 100 || '%' , ROUND(e.SALARY / ( SELECT MAX(SALARY) FROM HR.EMPLOYEES), 2) * 100 AS "Percentage of Max" FROM HR.EMPLOYEES e INNER JOIN HR.DEPARTMENTS d ON ( e.DEPARTMENT_ID = d.DEPARTMENT_ID) WHERE d.DEPARTMENT_ID IN (10, 20, 90, 210) AND e.SALARY > 3000;
/*-- CASE example*/ SELECT FIRST_NAME, LAST_NAME, SALARY, CASE WHEN SALARY > 10000 THEN 'High' WHEN SALARY BETWEEN 5000 AND 999 THEN 'Midlevel' ELSE 'Low' END AS "Income Level", CASE DEPARTMENT_ID WHEN 40 THEN 'Administration' WHEN 20 THEN 'Sales Related' ELSE 'Other' END AS "Special Departments" FROM EMPLOYEES;
/*-- JOIN example, with GROUP BY, HAVING and ORDER BY*/ SELECT COUNT(d.DEPARTMENT_NAME) AS "Departments per Location", c.COUNTRY_NAME, l.STATE_PROVINCE FROM DEPARTMENTS d INNER JOIN LOCATIONS l ON d.LOCATION_ID = l.LOCATION_ID INNER JOIN COUNTRIES c USING (COUNTRY_ID) GROUP BY c.COUNTRY_NAME, l.STATE_PROVINCE HAVING COUNT(d.DEPARTMENT_NAME) > 1 ORDER BY 2, 3, 1;
/*-- UPDATE example*/ UPDATE EMPLOYEES SET COMMISSION_PCT = 10 WHERE COMMISSION_PCT = 0 AND SALARY < 5000;
/*-- INSERT example*/ INSERT INTO EMPLOYEES ( FIRST_NAME, LAST_NAME ) VALUES ( 'Roger', 'Bjarevall' );
/*-- DELETE example*/ DELETE FROM EMPLOYEES WHERE HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');
/*-- CREATE TABLE example*/ CREATE TABLE DEPARTMENTS ( DEPARTMENT_ID NUMBER(4) NOT NULL, DEPARTMENT_NAME VARCHAR2(30) NOT NULL, MANAGER_ID NUMBER(6), LOCATION_ID NUMBER(4), CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID), CONSTRAINT DEPT_LOC_FK FOREIGN KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"), CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES "EMPLOYEES" ("EMPLOYEE_ID"), CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL) );
```


9.2.15 Auto Completion

**Only in DbVisualizer Pro**

This feature is only available in the DbVisualizer Pro edition.


Auto completion is a convenient feature used to assist you when editing SQL statements and DbVisualizer commands. By default, you activate auto completion with the key binding **Ctrl-SPACE**, but you can also configure it to activate as you type (in the Tool Properties dialog, in the **SQL Editor/Auto Completion** category under the General tab).

With the caret in any place in a statement where you can type something other than a table name or a column name, and at least one character just before the caret, activating auto completion displays a list of keywords that starts with the letters you have typed so far. As you continue to type, the list narrows.




The list of keywords is database specific, selected based on the database type for the connection currently selected in the **Database Connection** list above the editor.

With the caret placed where a table or view name may be typed in a supported SQL statement type, the auto completion list shows a list of tables and views from the currently selected database connection, assuming you are actually connected to the database. The following figure shows the completion pop up with table names.




A completion pop-up showing column names is shown when the caret is placed where a column name may be typed.




DbVisualizer provides auto completion for table and columns names for the following DML commands:

- SELECT
- INSERT
- UPDATE
- DELETE

Auto completion for DbVisualizer commands is very similar. Activating it after a partial command name lists all matching commands. If you activate it after a complete command name, you get a list of all valid parameters for the command. After a parameter name, you can select from a list of valid values.



For the @export set command, the parameter list is adapted for the specified output format after you have entered the Format parameter setting, for instance only showing parameters that are valid for the CSV format.



To display the completion pop-up, use the key binding **Ctrl-SPACE** (by default). You select an entry in the pop-up menu with a mouse double-click, the **ENTER** key, or the **TAB** key. To cancel the pop-up, press the **ESC** key.



If there are several SQL statements in the editor, make sure to separate them using the statement delimiter character (the default is ";").

In order for the column name completion pop-up to appear, you must first make sure there are table names in the statement.

All table names that have been listed in the completion pop-up are cached by DbVisualizer to make sure subsequent displays of the pop-up is performed quickly without asking the database. The cache is cleared only when doing a **Refresh** in the database objects tree or reconnecting the database connection.

The **Database** and **Schema** lists above the editor are used to limit the list of tables in the auto complete pop-up to those in the selected database and/or schema. To include all tables, select the blank entries in these lists. The default selections for the lists can be set as connection properties, in the **SQL Commander** category.

It is possible to fine-tune how auto completion works in the connection properties.

- Enable or disable the use of identifier qualifiers (i.e. qualifying table names with the schema name) in the **[Database Type]/Qualifiers** category,
- Enable or disable the use of delimited identifiers (e.g. quotes around a table name) in the **[Database Type]/Delimited Identifiers** category.

Sorting, when to show the popup, upper/lower case transformation, etc. can be configured in the **Tool Properties** dialog, in the **SQL Editor/Auto Completion** category under the **General** tab.

9.2.16 Recording and Playing Edit Macros

If you repeatedly need to run a sequence of edit operation, you can record them as a macro and play it as many times as needed during an editing session. The editor status bar indicates when a recording is in progress and when a macro is available to play.

As an example, suppose you have some plain text that you need to convert into INSERT statements:

```
12345 123456
89012 890123
45678 456789
```

Place the caret at the beginning of the first line and start the macro recording, using the right-click menu or the corresponding key binding, and then type text and use key bindings to perform the following operations:

1. Type `insert into mytable values('`
2. **Insertion Point to Next Word**
3. Type `,`
4. **Insertion Point to Next Word**
5. Type `'`
6. **Insertion Point to Next Word**
7. Type `');`
8. **Insertion Point Down**
9. **Insertion Point to Beginning of Line**

Then stop the recording. You now have a macro for converting a single line to an INSERT statement. To convert the remaining lines, just use Play Macro for each line. The result will look like this:

```
insert into mytable values('12345', '123456');
insert into mytable values('89012', '890123');
insert into mytable values('45678', '456789');
```




i The Find operation, by default mapped to the **Find** key and **Ctrl-F** key stroke, can not be recorded. You must instead use **Find Selection**, **Find with Dialog**, **Find Next** and **Find Previous**. Mouse gestures are also not recorded, only key strokes and menu selections.

9.2.17 Folding Selected Text

If you work with a large script, it can sometimes be helpful to hide parts of it. You can do so using the Code Folding feature.

Select the text you want to hide and then choose **Folding Operations->Toggle Fold Selection** in the right-click menu. The selected text is then replaced (visually only) with a folding marker.

Here's an unfolded script:

```
1 SELECT
2     EMP.FIRST_NAME,
3     EMP.LAST_NAME,
4     EMP.EMAIL,
5     DEP.DEPARTMENT_NAME,
6     CASE
7         WHEN SALARY > 100000
8         THEN 'HIGH'
9         WHEN SALARY BETWEEN 50000 AND 99000
10        THEN 'MEDIUM'
11        ELSE 'LOW'
12    END AS SALARY_LEVEL
13 FROM
14     EMPLOYEES EMP
15 INNER JOIN
16     DEPARTMENTS DEP
17 ON
18     (
19         EMP.DEPARTMENT_ID = DEP.DEPARTMENT_ID);
20
```

14:18 [276] INS Auto Commit: ON Cp1252 report.sql*

And here is the same script with the CASE expression folded:

```
1 SELECT
2     EMP.FIRST_NAME,
3     EMP.LAST_NAME,
4     EMP.EMAIL,
5     DEP.DEPARTMENT_NAME,
6     ...
13 FROM
14     EMPLOYEES EMP
15 INNER JOIN
16     DEPARTMENTS DEP
17 ON
18     (
19         EMP.DEPARTMENT_ID = DEP.DEPARTMENT_ID);
20
```

6:5 [91] INS Auto Commit: ON Cp1252 report.sql*

You can fold more than one part of a script using the same procedure.

To unfold just one part, select the folding marker (be careful to select all of it) and then choose **Toggle Fold Selection** from the menu again. To unfold all folded parts, use **Expand All Foldings**.

9.2.18 Selecting a Rectangular Area

In some cases, it is handy to be able to select a rectangular area in the middle of a script. Say, for instance, that you need to copy just the first part of a few lines and paste it at the beginning of some other lines.



To do this in the SQL editor, click the mouse where you want to start the selection and then press the **Alt** key (by default) while you extend the selection by dragging the mouse. If you prefer to use the **Ctrl** key as the modifier, you can change the default in Tool Properties in the SQL Commander category under the General tab.

```
1 SELECT
2   EMP . FIRST_NAME ,
3   EMP . LAST_NAME ,
4   EMP . EMAIL ,
5   DEP . DEPARTMENT_NAME ,
6   ...
13 FROM
14 EMPLOYEES EMP
```

4:8 [54] INS Auto Commit: ON Cp1252 report.sql*

9.2.19 Tab Key Treatment

Pressing the TAB key in the editor inserts eight (8) space characters by default. If you instead want a TAB character to be inserted, or want to insert another number of space characters, you can specify this in the **Tool Properties** dialog, in the **General / SQL Commander** category under the General tab.

9.2.20 Key Bindings

The editor shortcuts, or key bindings, can be redefined in the **Tool Properties** dialog, in the **Key Bindings** category under the **General** tab (see [Changing Keyboard Shortcuts](#)). Expand the **Editor Commands** node to manage all editor actions and the **Main Menu/Edit** node to manage the key bindings for the edit operations in the right-click editor menu and the main window **Edit** menu.

9.3 Morph Selection



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

- [Introduction](#)
- [Basic Examples](#)
 - [Detect Input Delimiter](#)
 - [Detect Numbers](#)
 - [Input Prefix and Suffix](#)
 - [Limit Preview](#)
 - [Missing Input Prefix](#)
 - [Missing Input Suffix](#)
 - [New Line as Input Delimiter](#)
 - [No Delimiters](#)
 - [Output Prefix](#)
 - [Output Prefix and Suffix](#)
 - [Output Prefix and Suffix with Text Quoting](#)
 - [Preserve Output New Line](#)
 - [Quote Output Text Tokens](#)
 - [Repeated Delimiters](#)
 - [Sort Ascending](#)
 - [Sort Descending](#)
 - [Sort Multiline Output](#)
 - [Transform Delimiter](#)
 - [Transform Delimiters on Multi Line Tokens](#)
 - [Trim Input Empty Tokens](#)
 - [Trim Input Empty Tokens with Include Input New Line as Delimiter](#)
 - [Trim Input Whitespace](#)
 - [Trim Input Whitespace and Empty Tokens](#)
 - [Trim Input Whitespace and Empty Tokens with Input New Line as Delimiter](#)
 - [Trim Input Whitespace and Empty Tokens with Input New Line as Delimiter Preserved in Output](#)
 - [Trim Input Whitespace with Prefix and Suffix](#)
 - [Wrap Output Lines](#)
 - [Wrap Output Lines with Continuation Symbol](#)



- Use Cases
 - Morph IN Clause Data to CSV Format
 - Morph Table Data into CSV Format
 - Morph Table Data to IN Clause Format

9.3.1 Introduction

The **Morph Selection with Dialog** in the SQL editor allows you to convert a selection of text into a delimited list with the appropriate options. Simply select text in the editor and choose **Edit->Morph Selection with Dialog (or from the editor right-click menu)**. This will prompt you for different options about the **Input Format**, and the **Output Format**, with the **Output Preview** overwriting the input text with the result. This lets you paste text from a Grid, Excel or some other application into the editor and then convert it into a delimited list suitable for completing a query or other documentation.

Input Format

Delimiter: UNIX/Linux/macOS - LF ▾

Include New Line Detect Delimiter

Trim Prefix: None ▾ Trim Suffix: None ▾

Trim Whitespace Trim Empty Tokens

Detect Numbers

Grouping: , ▾ Decimal: . ▾

Output Format

Delimiter: , ▾

Preserve New Line

Prefix: Suffix:

Quote Text Value: " ▾

Sort: None ASC DESC

Wrap Lines

Length: 80 ▾ Continuation: None ▾

Output Preview

Preview Token Count: 100 ▾

"GUINNESS", "WAHLBERG", "CHASE", "DAVIS", "LULLOBRIGIDA", "NICHOLSON", "MOSTEL", "JOHAN...

Input/Output settings are disabled unless the corresponding delimiter is specified.
The preview is automatically updated to reflect current settings (if both input and output delimiters are specified).

Restore Defaults Morph to Clipboard Morph to Editor Cancel

9.3.2 Basic Examples

Some basic examples of how various settings affect the transformations.



Detect Input Delimiter

Detect the input delimiter by counting occurrences of the default delimiters (the predefined delimiters shown in dropdown). In this case, comma (,) is the most frequent of the predefined separators (single quote (') is not a predefined delimiter).

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	ON		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
'A', 'B': 'C', 'D'
```

Result

```
'A'; 'B': 'C'; 'D'
```



Detect Numbers

Detect numbers and quote text tokens; recognized numbers (strings that match the specified number format) are not quoted.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	ON		Continuation	(N/A)
Grouping	,		preview setting	value
Decimal	.		Preview Token Count	OFF

Input

```
1,000.00:two thousand:3000,00:4000
```

Result

```
1000.0;"two thousand";"3000,00";4000
```



Input Prefix and Suffix

Trim prefix and suffix in input tokens. Text inside prefix/suffix are treated as one token.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	(Suffix	None
Trim Suffix)		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

A: (B:C)

Result

A;B:C



Limit Preview

If the input is large, it may be useful to limit preview to speed up things while sorting out options. The limit is applied to number of input tokens as determined by the current settings.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	2

Input

Token1: Token2: Token3

Result

Token1;Token2



Missing Input Prefix

Ignore trimming of input prefix and suffix unless both are defined (here we only defined the prefix).

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	'		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
A: 'B:C
```

Result

```
A; 'B;C
```




Missing Input Suffix

Ignore trimming of input prefix and suffix unless both are define (here we only defined the suffix).

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	'		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
A: 'B:C
```

Result

```
A; 'B;C
```



New Line as Input Delimiter

Transform delimiter and quote text spanning multiple lines.

Since we recognize New Line as a delimiter, **Token2** and **Token3** are interpreted as separate tokens.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
Token1: Token2  
Token3: Token4
```

Result

```
"Token1"; "Token2"; "Token3"; "Token4"
```



No Delimiters

No transformation occurs unless both input and output delimiters are defined.

Settings

input setting	value		output setting	value
Delimiter	None		Delimiter	None
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00::' one thousand '
```

Result

```
1,000.00::' one thousand '
```



Output Prefix

We can add a single prefix or suffix to output tokens (we can define one without the other).

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	+
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

A : B : C

Result

+A ; +B ; +C



Output Prefix and Suffix

We can add prefix and/or suffix to output tokens.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	[
Trim Prefix	None		Suffix]
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00::' one thousand '
```

Result

```
[1,000.00];[];[' one thousand ']
```



Output Prefix and Suffix with Text Quoting

We can both quote text and add a prefix and/or suffix to output tokens.

Prefix/suffix are added to all tokens outside the quoting symbols.

Since we detect numbers, the recognized number token is unformatted and not quoted.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	[
Trim Prefix	None		Suffix]
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	ON		Continuation	(N/A)
Grouping	,		preview setting	value
Decimal	.		Preview Token Count	OFF

Input

```
1,000.00:one thousand:1 000,00
```

Result

```
[1000.0];["one thousand"];["1 000,00"]
```



Preserve Output New Line

Transform delimiter and quote multiline text.

Since we recognize and preserve New Line, we maintain a multiline output with quoted tokens.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	ON
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
Token1:Token2  
Token3:Token4
```

Result

```
"Token1";"Token2"  
"Token3";"Token4"
```



Quote Output Text Tokens

Quote text tokens. Since we do not detect numbers, or strip input prefix/suffix, all tokens are quoted and prefix/suffix preserved.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00::' one thousand '
```

Result

```
"1,000.00";";'" one thousand '"
```




Repeated Delimiters

We use **Space** (" ") as a delimiter on an input with several repeated spaces and trim single quote (') suffix but do NOT trim whitespace. Spaces outside the prefix/suffix are treated as a single delimiter, spaces inside the prefix/suffix remain.

Settings

input setting	value		output setting	value
Delimiter	Space		Delimiter	:
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	'		Suffix	None
Trim Suffix	'		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00 ' one thousand ' 1k
```

Result

```
1,000.00: one thousand :1k
```



Sort Ascending

Sort tokens in ascending order on a single line.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	ASC
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

A : C : B

Result

A ; B ; C



Sort Descending

Sort tokens in descending order on a single line.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	DESC
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

A : C : B

Result

C ; B ; A



Sort Multiline Output

This is an unsupported setup: sorting is done on tokens, not lines. Sorting tokens in a multiline text would be very confusing.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	ON
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	DESC
Trim Empty Tokens	OFF		Wrap Lines	8
Detect Numbers	OFF		Continuation	\
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
Token1: Token2  
Token3: Token4
```

Result

```
"Token1"\  
;"Token2\  
"  
"Token3"\  
;"Token4\  
"
```



Transform Delimiter

Basic transformation of delimiters using default settings.
The defined input delimiters are replaced with the defined output delimiters.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00::' one thousand '
```

Result

```
1,000.00;;' one thousand '
```



Transform Delimiters on Multi Line Tokens

Transform delimiters and quote text spanning multiple lines.

Since we ignore New Line, the **Token2** and **Token3** are interpreted as one token with two embedded New Line.

The resulting output is three tokens on three lines, where the middle token includes two consecutive New Line (producing an empty line).

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

Token1:Token2

Token3:Token4

Result

"Token1";"Token2

Token3";"Token4"



Trim Input Empty Tokens

Since the input starts with a delimiter, we get an initial empty token that is trimmed.

Since don't trim whitespace or consider New Line as a delimiter, the middle and trailing tokens are not trimmed.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	ON		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B :  
: C : D :
```

Result

```
A ; B ;  
; C ; D ;
```



Trim Input Empty Tokens with Include Input New Line as Delimiter

Trim empty tokens while treating New Line as a delimiter.

Since the input starts with a delimiter, we get an initial empty token that is trimmed.

Since New Line is considered a delimiter, we get an empty middle token that is trimmed.

Since the input ends with a delimiter and a New Line, we get a trailing empty token that is trimmed.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	ON		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B :  
: C : D :
```

Result

```
A ; B ; C ; D
```




Trim Input Whitespace

Trim whitespace outside any prefix/suffix (whitespace inside prefix/suffix is preserved).
Since New Line is considered as whitespace, we get an empty middle token.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B :  
: C : D :
```

Result

```
;A;B;;C;D;
```



Trim Input Whitespace and Empty Tokens

Trim whitespace outside any prefix/suffix (whitespace inside prefix/suffix is preserved).

Since the input starts with a delimiter, we get an initial empty token that is trimmed.

Since New Line is considered as whitespace, we get an empty middle token that is trimmed.

Since the input ends with a delimiter and a New Line, we get a trailing empty token that is trimmed.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	ON		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B :  
: C : D :
```

Result

```
A;B;C;D
```



Trim Input Whitespace and Empty Tokens with Input New Line as Delimiter

Trim whitespace and Empty Tokens while recognizing New Line as an input delimiter.

Since the input starts with a delimiter, we get an initial empty token that is trimmed.

Since New Line is considered as whitespace, we get an empty middle token that is trimmed.

Since the input ends with a delimiter and a New Line, we get a trailing empty token that is trimmed.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	ON		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B  
C : D :
```

Result

```
A;B;C;D
```



Trim Input Whitespace and Empty Tokens with Input New Line as Delimiter Preserved in Output

Trim whitespace and Empty Tokens while recognizing New Line as a delimiter and preserving it in the Output.

Since the input starts with whitespace and a delimiter, we get an initial empty token that is trimmed.

Since New Line is considered as whitespace, we get an empty middle token that is trimmed.

Since the input ends with a delimiter and a New Line that is trimmed, we get a trailing empty token that is trimmed.

Since we preserve New Line in Output, we get the first two tokens (A and B) on the first line and the last two tokens (C and D) on the second line.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	ON
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	ON		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
: A : B
```

```
C : D :
```

Result

```
A;B
```

```
C;D
```



Trim Input Whitespace with Prefix and Suffix

Whitespace is trimmed before trimming prefix/suffix - whitespace inside prefix/suffix is preserved.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	(Suffix	None
Trim Suffix)		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
1,000.00: ( 1k ) : one thousand
```

Result

```
1,000.00; 1k ;one thousand
```



Wrap Output Lines

Wrap lines at specified length, including any prefix, suffix or quoting symbols. Wrapping does not observe any tokens or words, it breaks here at specified length.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	8
Detect Numbers	OFF		Continuation	None
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
Token1:Token2:Token3
```

Result

```
"Token1"  
;"Token2"  
;"Token3"
```



Wrap Output Lines with Continuation Symbol

Wrap a multiline output text with a symbol terminating each line that continues on the next line. Regular line breaks (not resulting from wrapping) are not terminated with the wrapping symbol.

Settings

input setting	value		output setting	value
Delimiter	:		Delimiter	;
Include New Line	ON		Preserve New Line	ON
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	OFF		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	8
Detect Numbers	OFF		Continuation	\
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
Token1: Token2  
Token3: Token4
```

Result

```
"Token1"\  
;"Token2\  
"  
"Token3"\  
;"Token4\  
"
```



9.3.3 Use Cases

A few "real world" use cases of how to use the Morph function to transform input data into the desired output format.

Morph IN Clause Data to CSV Format

I have an IN clause with text values that I want to use as unquoted data in a CSV file.

I need to trim whitespace and prefix/suffix before transforming the input delimiter to my desired output delimiter.

Settings

input setting	value		output setting	value
Delimiter	,		Delimiter	;
Include New Line	OFF		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	'		Suffix	None
Trim Suffix	'		Quote Text Value	None
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
'BETTE', 'CHRISTIAN', 'GRACE', 'JENNIFER', 'JOE', 'JOHNNY', 'KARL', 'MATTHEW', 'UMA', 'ZERO'
```

Result

```
BETTE;CHRISTIAN;GRACE;JENNIFER;JOE;JOHNNY;KARL;MATTHEW;UMA;ZERO
```




Morph Table Data into CSV Format

I copied a table from a web page into SQL Commander and want to save it as a file that can be used for import. I want the data in CSV format, lines sorted, text values quoted and any empty lines suppressed.

Input is tab separated, not quoted, in random order and a mix of strings and numbers.

Output is not sorted, separated by semi-colon and all text values are quoted.

Note: it is not possible to sort the output lines. The morph operation is about tokens, not lines.

Settings

input setting	value		output setting	value
Delimiter	Space		Delimiter	;
Include New Line	ON		Preserve New Line	ON
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	"
Trim Whitespace	ON		Sort	None
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	ON		Continuation	(N/A)
Grouping	,		preview setting	value
Decimal	.		Preview Token Count	OFF

Input

```
1 PENELOPE GUINNESS
6 BETTE NICHOLSON
3 ED CHASE
7 GRACE MOSTEL
2 NICK WAHLBERG
4 JENNIFER DAVIS
5 JOHNNY LOLLOBRIGIDA
8 MATTHEW JOHANSSON
12 KARL BERRY
9 JOE SWANK
11 ZERO CAGE
10 CHRISTIAN GABLE
13 UMA WOOD
```



Result

```
1; "PENELOPE"; "GUINNESS"  
6; "BETTE"; "NICHOLSON"  
3; "ED"; "CHASE"  
7; "GRACE"; "MOSTEL"  
2; "NICK"; "WAHLBERG"  
4; "JENNIFER"; "DAVIS"  
5; "JOHNNY"; "LOLLOBRIGIDA"  
8; "MATTHEW"; "JOHANSSON"  
12; "KARL"; "BERRY"  
9; "JOE"; "SWANK"  
11; "ZERO"; "CAGE"  
10; "CHRISTIAN"; "GABLE"  
13; "UMA"; "WOOD"
```



Morph Table Data to IN Clause Format

I copied a column from Excel into SQL Commander and want to convert it to a string that I can use as an IN clause in a SQL Query.

I want the data comma separated with a space (,), all values quoted, whitespaces trimmed and any empty lines suppressed. Since there is no predefined delimiter that includes a space after the comma, I type this delimiter directly in the combo box ¹.

Input is tab separated, not quoted, in random order and a mix of strings and numbers.

Output is sorted, separated by semi-colon and all text values are quoted.

¹ it is hard to see the trailing space in the settings below

Settings

input setting	value		output setting	value
Delimiter	UNIX/Linux/macOS - LF		Delimiter	,
Include New Line	ON		Preserve New Line	OFF
Detect Delimiter	OFF		Prefix	None
Trim Prefix	None		Suffix	None
Trim Suffix	None		Quote Text Value	'
Trim Whitespace	ON		Sort	ASC
Trim Empty Tokens	OFF		Wrap Lines	OFF
Detect Numbers	OFF		Continuation	(N/A)
Grouping	(N/A)		preview setting	value
Decimal	(N/A)		Preview Token Count	OFF

Input

```
JENNIFER
    JOHNNY
BETTE
    GRACE
MATTHEW
    JOE
CHRISTIAN
ZERO
KARL
UMA
```

Result

```
'BETTE', 'CHRISTIAN', 'GRACE', 'JENNIFER', 'JOE', 'JOHNNY', 'KARL', 'MATTHEW', 'UMA', 'ZERO'
```



9.4 Using Editor Templates

Editor Templates can be used to easily insert text that you often use, such as code snippets, current date and time, or anything you like.

- [Using a Template](#)
- [Creating a new Template](#)
- [Editing or Deleting a Template](#)
- [Changing the Expand Keybinding](#)




Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.


9.4.1 Using a Template

A template is an **Abbreviation** that can easily be replaced by its **Expanded Text**, and it may optionally have a **Description**.

To expand a template, just type a few characters that at least partially match one or more template abbreviation and press the TAB key. This displays a list of matching templates that you can pick from, along with the description or a part of the corresponding expanded text for each.



When you select a template by pressing the TAB or ENTER key, its expanded text replaces the abbreviation you typed in the editor.



You can also enable **Instant Substitution** to immediately expand the text if you have typed enough of the abbreviation to match a single template when you press the TAB key:

1. Open **Tools->Tool Properties**,
2. Select the **General/SQL Commander/Editor Templates** category,
3. Click the **Instant Substitution** checkbox in the toolbar,
4. Click the **Apply** or **OK** button to save the updated setting.

Instead of pressing the TAB key to list matching templates, you can use the **Show Editor Templates** entry in the main Edit menu or the editor right-click menu.

9.4.2 Creating a new Template

DbVisualizer comes with some default templates, but you can create additional templates:



1. Open **Tools->Tool Properties**,
2. Select the **General/SQL Commander/Editor Templates** category,
3. Click the **Insert** button in the toolbar to add a new template, and enter an Abbreviation, Expanded Text, and optionally a Description,
4. Check off the checkbox in the **Format** column if you want the Expanded Text to be formatted by the SQL Formatter when it is inserted in the editor,
5. Click the **Apply** or **OK** button to save the new templates.

If you want to use an existing template as a starting point, you can select it and then click the **Duplicate** button instead of the Insert button. The Edit in Window button opens the selected cell in a separate window where it is easier to work with larger templates.

i Always use a special character, such as dot or hashmark, as the first character in the Abbreviation. The default templates use a dot but you can pick any special character you like. If you use a regular character as the first character, unexpected matches may be found if one abbreviation starts with the same characters as another abbreviation ends with.

9.4.3 Editing or Deleting a Template

You can edit any piece of a template or delete templates you no longer need:

1. Open **Tools->Tool Properties**,
2. Select the **General/SQL Commander/Editor Templates** category,
3. To edit, double-click any cell you want to change and edit its value,
4. To delete a template, select any of its cells and click the Delete button,
5. Click the **Apply** or **OK** button to save the changes.

9.4.4 Changing the Expand Keybinding

The keyboard shortcut used to expand a template, or bring up the list of matching templates if more than one, is the TAB key. You can add other shortcuts or change the default, as described in [Changing Keyboard Shortcuts](#). The shortcut is named **Show Editor Templates** and you find it in the **Main Menu/Edit** category.

9.5 Executing SQL Statements

In the SQL Commander, you can execute one or multiple statements. You can also control if the execution should stop or continue when the execution of a statement results in a warning or error.

- [Execute a Script with Multiple Statements](#)
- [Execute Only the Current Statement](#)
- [Execute Buffer](#)
- [Control Execution after a Warning or an Error](#)

9.5.1 Execute a Script with Multiple Statements

Use the **SQL Commander->Execute** main menu operation to execute the SQL in the SQL Commander editor. The SQL Commander executes the statements one by one and indicates the progress in the log area. The currently selected Database Connection is used for all statements. The SQL Commander does not support executing SQLs for multiple database connections in one batch.

DbVisualizer uses the delimiters specified in the Tool Properties dialog, in the **General / SQL Commander / Statement Delimiters** category under the General tab, to separate one statement from the next. Usually semicolon ";" following the actual statement or "go" which should be the only command on a new line directly after the statement (then with no semicolon after) that should be executed. The "go" command supports setting the number of times the statement should be executed. For example "**go 5**" will then execute the statement 5 times.

The result of the execution is displayed in the results area based on the type of results result(s) that are returned. If there are several results and an error occurred in one of them, the Log tab is automatically displayed to indicate the error.

If you select a statement in the SQL editor and choose **SQL Commander->Execute** main menu option, only the selected statement is executed. This is a useful feature when you have several SQL statements in the SQL editor and you just want to execute one or a few of the statements.

i Comments in the SQL editor are sent to the database when you use **SQL Commander->Execute**, unless you have enabled **Strip Comments when Executing** in the **SQL Commander->SQL Commander Options** menu.



Note the option **Change Default Values** in the **SQL Commander->SQL Commander Options**. This offers a shortcut to navigate to the Connection properties section for the options. Setting the options in the Connection properties will result in that these values will be the default for SQL Commanders opened for this connection.

9.5.2 Execute Only the Current Statement

The **SQL Commander->Execute Current** operation is useful when you have a script with several SQL statements. It lets you execute the statement at the cursor position without first having to select the SQL statement. The default key binding for execute current is **Ctrl-PERIOD** (Ctrl-.).

i **Execute Current** determines the actual statement by parsing the editor buffer using the standard statement delimiters. The current statement is the statement containing the caret or that ends on the line with the caret. This means that the caret may be after the statement delimiter as long as there is no other statement on the same line.

If you are unsure what the boundaries are for the current statement then use **Edit->Select Current Statement**. This will highlight the current statement without executing it.

9.5.3 Execute Buffer

The **SQL Commander->Execute Buffer** sends all of the content in the SQL editor to the database in a single run. This is useful when executing complex SQL statements such as CREATE STORE PROCEDURE (or similar) where statement splitting on semicolon must not be done as with SQL Commander->Execute and SQL Commander->Execute Current.

9.5.4 Control Execution after a Warning or an Error

You can control whether subsequent statements should be executed when a statement results in an error, a warning or returns or affects no rows.

Open **Tools->Tool Properties** and select the **SQL Commander** category under the **General** tab. There you find **Stop on Error**, **Stop on SQL Warning** and **Stop on No Rows** check boxes for enabling these features in all **SQL Commander** tabs.

Alternatively, you can use DbVisualizer client side commands to enable or disable these features in a script.

```
@stop on error;  
@stop on sqlwarning;  
@stop on norows;  
  
@continue on error;  
@continue on sqlwarning;  
@continue on norows;
```

9.6 Re-Executing SQL Statements

As you execute SQL statements in the SQL Commander, DbVisualizer saves them as History entries, along with information about the Connection, Catalog, Schema and the execution result. This makes it easy to locate statements and scripts you have executed in the past.

- [Using Previous and Next in the SQL Commander](#)
- [Using the SQL History Window](#)
 - [Reusing a History Entry](#)
 - [Saving a History Entry as a Bookmark or Other File](#)
- [Using Quick Load](#)

9.6.1 Using Previous and Next in the SQL Commander

If you just want to go back and forth between statements you have executed recently, you can use the **Get Previous from History** and **Get Next from History** toolbar buttons in the SQL Commander.

9.6.2 Using the SQL History Window

To look through all saved statements, you can display the History entries by clicking the **SQL History** toolbar button in the main window or select the corresponding operation from the **Tools** menu.



Time	Script Preview	Size (Bytes)	Database Type	Database Connection	Count	Elapsed	Success	Errors	Rows
2016-06-07 13:42:19	select * from HR.DEPARTMENTS; select EMPLO...	194	Oracle	CRM Ahoa	1	1	3	0	144
2016-06-07 13:41:40	SELECT e.FIRST_NAME, e.LAST_NAME, h.STA...	180	Oracle	CRM Ahoa	1	0.59	1	0	10
2016-06-07 13:41:22	SELECT FIRST_NAME, LAST_NAME, START_DA...	164	Oracle	CRM Ahoa	1	0.02	0	1	0
2016-06-07 13:40:02	@call \${returnValue} (null) String nulla...	254	Oracle	CRM Ahoa	1	0.05	2	0	0
2016-06-07 13:38:09	@export on; @export set Filename="/tmp/cou...	121	Oracle	CRM Ahoa	1	0.08	5	0	25
2016-06-07 13:37:44	@export on; @export set Filename="name.csv...	106	Oracle	CRM Ahoa	1	0.53	4	1	0
2016-05-26 15:34:23	select * from HR.COUNTRIES; select * from HR...	54	Oracle	HR Production	1	0.91	2	0	29
2016-05-18 16:54:56	select * from HR.DEPARTMENTS; select EMPLO...	194	Oracle	CRM Ahoa	2	0.91	3	0	144

```
1 select * from HR.DEPARTMENTS;
2 select EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL from HR.EMPLOYEES;
3 select * from HR.JOB_HISTORY;
4
5 --select * from HR.JOBS;
6 --select * from HR.LOCATIONS;
```

Filename: C:\Users\hans\dbvis\History\20160607-134219501.sql Encoding: Cp1252

The entries are ordered with the most recently executed entries at the top by default, but you can reorder them by clicking on the column headers. The complete content of the selected entry is shown below the list, unless you disable it by clicking the Show Details toolbar button.

The columns show when the entry was executed, a part of the script/statement, the size of the complete statement/script, and then the database type and connection it was executed for, and how long it took to execute. The **Success** and **Errors** columns show how many of the statements in a script were executed successfully or that caused an error. Finally, the **Rows** column show the number of rows retrieved or affected by the script.

You can use the field at the top right corner in the dialog to search for entries matching a criteria. Clicking on the magnifying glass reveals a configuration menu where you can, among other things, specify which columns to search in and if you want to search through the complete script rather than just the part of the script shown in the Script/SQL Statement column.

In the Tool Properties dialog, in the **SQL History** category under the General tab, you can specify that sequential executions of the same SQL statement/script should be collected into a single history entry. When this feature is enabled, the **Count** field number is increased for each execution. In the same Tool Properties category you can also specify rules for when not to create a history entry.

Reusing a History Entry

When you have found the entry you're looking for, you can open it in an SQL Commander by double-clicking it or clicking the corresponding toolbar button.

You can also add the content of an entry to the current content of an SQL Editor. Select the entry in the list, drag it with the mouse key depressed to the position in the editor where you want to add it, and drop it there by releasing the mouse button.


Saving a History Entry as a Bookmark or Other File

If you realise that you need easy access to a History entry in the future, you can save it as a Bookmark or other file. Just select the entry and use the **Save As** operation, or just drag it to the **Bookmarks** tree and drop it.

You can also locate the file holding the history entry in the file system using the **Open Enclosing Directory** right-click menu entry or toolbar button. This opens a file chooser for the directory holding the file.

9.6.3 Using Quick Load

An alternative to locating Bookmarks or Monitors from the Scripts tab and History entries from the History window is to use the **Quick Load** feature, by default bound to the **Ctrl+Alt+O** key combination. It is also available via a main toolbar button as well as in the **File->Quick File Open** menu.



The Quick Load feature locates files with partly matching names from the categories you have selected, as you type. You can use an asterisk ("*") as a wildcard in the search string.

When you see the file you're looking for, just select it and press **Enter** to load it into an SQL Commander editor. If the file is already loaded in an editor, that tab is made visible instead.

The number of matches is shown on the search panel as seen on the figure above. If the number of matches is big and you want to change the size, you can press **Escape** and change the number in the **Max entries** field that is shown. Go then to the **Enter search text** field and press arrow down. The result list shown will be limited to your set number for each category.

9.7 Executing Complex Statements

If you need to execute a complex statement that itself contains other statements in the SQL Commander, such as a CREATE PROCEDURE statement, you need to help DbVisualizer figure out where the complex statement starts and ends. The reason is that DbVisualizer needs to send statements to the database for execution one by one.



We recommend that you use the [Create Procedure](#) dialog and [Procedure Editor](#) to work with procedures and similar objects, so only use the SQL Commander to run statements like this if these features do not work for you for some reason.

- [Using Execute Buffer](#)
- [Using an SQL Block](#)
- [Using the @delimiter command](#)

9.7.1 Using Execute Buffer

The **SQL->Execute Buffer** operation sends the complete editor buffer for execution as one statement. No comments are removed and no parsing of individual statements based on any delimiters is made. You can use this feature if the complex statement is the only statement in the SQL Commander editor.

9.7.2 Using an SQL Block

To tell DbVisualizer that a part of a script should be handled as a single statement, you can insert an SQL block begin identifier just before the block and an end identifier after the block. The delimiter must be the only text on the line. The default value for the **Begin Identifier** is `--/` and for the **End Identifier** it is `/`.

Here is an example of an SQL block for Oracle:



```
--/  
script to disable foreign keys  
  
declare cursor tabs is select table_name, constraint_name  
  from user_constraints where constraint_type = 'R' and owner = user;  
  
begin  
  for j in tabs loop  
    execute immediate ('alter table '||j.table_name||' disable constraint'||j.constraint_name);  
  end loop;  
end;  
/  
/
```

9.7.3 Using the @delimiter command

With the **@delimiter** command you can temporarily change the statement delimiter DbVisualizer uses to separate the statements and send them one by one to the database. Use it before the complex statement, and after the statement if the script contains additional statements. Here's an example:


```
@delimiter ++;  
CREATE OR REPLACE FUNCTION HELLO (p1 IN VARCHAR2) RETURN VARCHAR2  
AS  
BEGIN  
  RETURN 'Hello ' || p1;  
END;  
++  
@delimiter ;++  
@call ${returnValue}|| (null)||String||noshow dir=out}$ = HELLO('World');  
@echo returnValue = ${returnValue}$;
```

The first **@delimiter** command sets the delimiter to ++ so that the default ; delimiter can be used within the function body in the CREATE statement. The ++ delimiter is then used to end the CREATE statement, and another **@delimiter** command sets the delimiter back to ; for the remaining commands in the script.

9.8 Executing an External Script

If you have a very large script to execute, you may not have enough memory available to be allocated for DbVisualizer to load it into an SQL Commander editor.

To save memory, you can use the **@run** command. If you try to load a very large file, DbVisualizer suggests using the **@run** command automatically:



The **@run** command executes a script file by only loading one statement at a time, minimizing the memory requirements. A related command is the **@cd** command for changing the current directory.

- **@run <file> [<variables>]**
Request to execute the file specified as parameter, optionally with a list of variables
- **@cd <directory>**
Change the working directory for the following **@run** command

Here's an example of a script using these commands:




```
@run createDB.sql;    -- Execute the content in the
                    -- createDB.sql file without loading into the SQL editor.
                    -- The location of this file is the same as the working
                    -- directory for DbVisualizer (when not using an absolut path).
@cd /home/mupp;     -- Request to change directory to /home/mupp
@cd myscripts;      -- Request to change directory relative to current, i.e. to /home/mupp/myscripts
@run loadBackup.sql; -- Execute the content in the loadBackup.sql
                    -- file relative to current directory. This file will now be read from the
                    -- /home/mupp/myscripts directory.
```

You can also include [DbVisualizer variables](#) as parameters to the **@run** command, with values to be used for the corresponding variables in the script:

```
@run monthlyReport ${month|2010-05-05|Date|noshow}$ ${dept|HR|String|noshow}$
```

Even though the **@run** command reads one statement at a time from the file, there are other parts of the execution process that require the whole file to be read before the statements can be executed: parsing the script for variables, parameter markers, and restricted commands, as well as counting all statements in order to provide progress information. When you run a script that is large enough (more than 10 MB) for these things to potentially cause memory problems and slow down the processing, DbVisualizer gives you a chance to turn off this preprocessing and progress reporting so that the statements instead can be executed directly as they are read from the file, one at a time.



To ensure that you don't have any problems running scripts this large we strongly recommend that you click **Continue w/o Preprocessing**, thereby disabling all variable, parameter and restricted commands processing. Only click **Continue Normally** if you know for sure that you have enough memory available and have adjusted your installation so that DbVisualizer can use it. With the preprocessing disabled, you should be able to execute scripts of any size (we have tested with scripts as large as 4 GB).

Another alternative for execution of large scripts is to use the DbVisualizer [command line interface](#) instead of the GUI application. This option is the most efficient and fastest.

Running without preprocessing is always more efficient, so if your script does not use any variables or parameter markers and you do not use the Permissions feature, you can disable preprocessing even for scripts smaller than 10 MB by unchecking the **SQL Commander Options->Preprocess Script** checkbox in the SQL Commander menu.

9.9 Locating SQL Errors

If errors occur, the corresponding text is underlined with a red wavy line. Hovering the mouse over the error indication shows the corresponding error message. The right margin contains markers for each error as well, and clicking on a marker scrolls the editor to the corresponding error. Alternatively, you can click the **FAILED** link in the Log tab grid to move the caret to the error location.

If you prefer to navigate between errors using the keyboard, you can use the defined key bindings for the **Insertion Point to Next Marker** and **Insertion Point to Previous Marker** actions in the Tool Properties dialog, in the **Key Bindings** category, in the Editor Commands group. Alternative is to use the **Goto Next Failed** and **Goto Previous Failed** in the right click menu of Log tab grid, and then click the link for the FAILED entries.



Error location information is not available for some databases. In that case the complete statement is underlined in the editor.

9.9.1 Disable Error Markers in the SQL Editor

From DbVisualizer 10.0.5 it is possible to disable error markers in the **SQL Commander->SQL Commander Options** menus. With **Show Error Position Markers** turned on it shows markers only for databases that specifically report positions of errors in a statement. With **Show Error Statement Markers** turned on the complete statement is highlighted if it fails during execution, but only if either the **Show Error Position Markers** is turned off or if the driver/database doesn't report positions of errors.



If you're looking to minimize the amount of error markers when executing scripts, turn off **Show Error Statement Markers** and keep the **Show Error Position Markers** checked (turned on). DbVisualizer will then report errors reported by the JDBC driver only.

To set default values for these settings visit **Tools->Tool Properties** and the **General / SQL Commander** category.

9.10 Analyzing (explain) Query Performance

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

You can analyze how a query is executed by the database, e.g. whether indexes are used or if the database has to do an expensive full scan. To analyze a query:

1. Enter the query in the **SQL Commander** editor,
2. Click **Execute Explain Plan** button in the toolbar,
3. Look at the result in the results area.

Explain Plan is supported for DB2 LUW, Exasol, H2, JavaDB/Derby, MariaDB, Mimer SQL, MySQL, Netezza, NuoDB, Oracle, PostgreSQL, Amazon Redshift, SQLite, Microsoft SQL Server and Vertica. The available presentations options vary per database as shown in this table.

Database	Graph Format	Tree Format	Text Format	Grid Format	Node Cost Coloring (Graph and Tree only)
DB2 LUW	✓	✓			✓
Exasol				✓	
H2			✓		
JavaDB/Derby			✓		
Mimer SQL	✓	✓			✓
MariaDB	✓	✓	✓		✓
MySQL	✓	✓	✓		✓
Netezza			✓		
NuoDB			✓		
Oracle	✓	✓	✓		✓
PostgreSQL	✓	✓	✓		✓
Amazon Redshift			✓		
SQLite			✓		
Microsoft SQL Server	✓	✓			✓



Database	Graph Format	Tree Format	Text Format	Grid Format	Node Cost Coloring (Graph and Tree only)
Vertica			✓		

Explain Plan executes your query and records the plan that the database devises to execute it. By examining this plan, you can find out if the database is picking the right indexes and joining your tables in the most efficient manner. The explain plan feature works much the same as executing SQLs to present result sets; you may highlight statements, run a script or load from file. The explain plan results can easily be compared by pinning the tabs for different runs.

DbVisualizer presents the plan either in a tree style format or in a graph, or in a simple text format. What information is shown depends on the database you use. In the tree view, put the mouse pointer on the column header for a tooltip description what that column represents. The following screenshot shows the SQL in the editor at top and the corresponding explain plan as the result.

```

1 SELECT
2   d.DEPARTMENT_NAME,
3   l.CITY,
4   c.COUNTRY_NAME,
5   r.REGION_NAME
6 FROM
7   HR.DEPARTMENTS d,
8   HR.LOCATIONS l,
9   HR.COUNTRIES c,
10  HR.REGIONS r
11 WHERE
12  d.LOCATION_ID = l.LOCATION_ID
13 AND l.COUNTRY_ID = c.COUNTRY_ID
14 AND c.REGION_ID = r.REGION_ID
15 AND d.MANAGER_ID IN
16   (
17     SELECT
18       EMPLOYEE_ID
19     FROM
20       HR.EMPLOYEES
21     WHERE
22       FIRST_NAME LIKE 'A%')
  
```

5:18 [80] INS Auto Commit: ON Cp1252 Untitled*


Log DBMS Output **EXPLAIN at 17:30:03** ×

Tree View Graph View

Operation	Node Cost	Cost	CPU Cost	I/O Cost	Optimizer	Cardinality	Bytes
SELECT STATEMENT	0.0 %	6	275,474	6	ALL_ROWS	2	14
NESTED LOOPS	0.0 %	6	275,474	6		2	14
NESTED LOOPS	16.7 %	5	258,792	5		2	11
NESTED LOOPS	0.0 %	3	207,423	3		6	28
NESTED LOOPS	0.0 %	2	150,072	2		14	40
HR.COUNTRY_C_ID_PK INDEX (FULL SCAN)	16.7 %	1	12,121	1	ANALYZED	25	35
HR.LOCATIONS TABLE ACCESS (BY INDEX ROWID)	16.7 %	1	8,871	1	ANALYZED	1	1
HR.LOC_COUNTRY_IX INDEX (RANGE SCAN)	0.0 %	0	1,250	0	ANALYZED	2	
HR.DEPARTMENTS TABLE ACCESS (BY INDEX ROWID)	16.7 %	1	9,689	1	ANALYZED	1	1
HR.DEPT_LOCATION_IX INDEX (RANGE SCAN)	0.0 %	0	1,650	0	ANALYZED	4	
HR.EMPLOYEES TABLE ACCESS (BY INDEX ROWID)	16.7 %	1	8,561	1	ANALYZED	1	1

0.016/0.031 sec 14/12 1-11

The Graph View shows the plan as a graph. The graph can be exported to an image file or printed. Use the menubar buttons to export and print.



The databases use different techniques to manage their explain plan support. You can make database-specific configurations in the **Properties** tab for a connection, in the **Explain Plan** category.

9.11 Auto Commit, Commit and Rollback

With Auto Commit enabled, all changes you make to the database data is automatically committed after the successful execution of an SQL statement. Auto Commit is enabled for a connection by default. You can change the default in the **Options** area of the **Object View** tab for the connection. Note that this change can only be done when the connection is disconnected.

You can toggle the Auto Commit setting for an open SQL Commander tab using the **SQL Commander** main menu item of the corresponding button in the SQL Commander toolbar. The setting is also available both on the right-click menu under the **Transaction** menu item.

Alternatively, you can use this command in a script to set it:

```
@set autocommit on/off;
```




If Auto Commit is disabled, it is very important to manually issue the commit or rollback operations when appropriate. Use the **Commit** and **Rollback** buttons in the SQL Commander toolbar or the corresponding operations in the **SQL Commander** main menu to commit and rollback transactions.

Alternatively, you can use the following commands in a script executed in the SQL Commander:

```
@commit;  
@rollback;
```

There is an **Auto-Commit: ON/OFF** indicator in the editor status bar:



The first number represents the number of records updated in the database since the last commit/rollback. The second number shows the number of statements (except SELECTs) that has been executed since last commit/rollback.

Having Auto Commit off for a connection should be handled with great care since transactions may lock parts of the database (this is database dependent). To minimize the risk of forgetting uncommitted transactions, there is an **Ask when Auto Commit is OFF** settings in the connection **Properties** tab, in the **Transactions** category, that can be set to warn you when there are changes that hasn't been committed. You can set it to **Always** or **When Uncommitted Updates**. When set to **When Uncommitted Updates**, you are warned when there is at least one updated record reported by the database. For database that do not accurately report updated records, you can set it to **Always** to be warned if at least one statement (other than SELECT) has been executed since the last commit or rollback.


There is also a **Pending Transactions at Disconnect** setting in the Tool Properties dialog, in the Transaction category under the General tab. It specifies what DbVisualizer should do when you disconnect a connection that has pending changes, and you can set it to **Commit**, **Rollback** or **Ask**.

9.12 Managing Frequently Used SQL

You may have a set of SQL statements that you use over and over to perform frequent tasks. You probably have them saved in script files that you can load into an SQL Commander, but DbVisualizer **Bookmarks** make it even easier to work with them. A Bookmark is a script visible in the Scripts tab in the navigation area.

- [Creating, Editing and Organizing Bookmarks](#)
- [Executing Bookmarks](#)
- [Adding a Bookmark as a Favorite](#)
- [Sharing Bookmarks](#)
- [Using Quick Load](#)


You find your Bookmarks under the Scripts tab in the navigation area to the left in the main DbVisualizer window. The content of a Bookmark is one or more SQL statements. It may also be associated with a Connection, a Catalog and a Schema, to be used when executing the statements. This information is displayed, and can be edited, in the lower part of the Scripts tab, along with information about the file that holds the Bookmark. If you don't want to see these details, you can disable it with the Show Details toggle control in the right-click menu for a node.



9.12.1 Creating, Editing and Organizing Bookmarks

You can create a new Bookmark by selecting the **Bookmarks** node in the tree and clicking the **Create File** toolbar button. This adds a new node in the tree, with the default name selected so that you can replace it with the name you want to use. You can also rename the Bookmark later using the **Rename** right-click menu item.


A Bookmark can also be created from the current content in an SQL Editor. Click the **Save File As** toolbar button to open a file chooser dialog, and click the **Bookmarks** button in the file chooser dialog to go to the Bookmarks root directory. Enter a filename for the Bookmark and click **Save**.



To put some SQL statements in a new empty Bookmark or to edit the contents of an existing Bookmark, you need to open the Bookmark in an SQL Commander. Double-click the Bookmark node in the tree or click the corresponding toolbar button to open a new SQL Commander tab for the Bookmark, or activate the SQL Commander that already holds the Bookmark. When you are done with your edits, use the **Save** toolbar button in the SQL Editor to save them.

You can also add the content of a Bookmark to the current content of an SQL Commander editor. Select the Bookmark node, drag it with the mouse key depressed to the position in the editor where you want to add it, and drop it there by releasing the mouse button.


Folders can be used to organize your Bookmarks. Click the **Create Folder** toolbar button to create a new folder and give it the name you want. You can then drag an existing Bookmark node to the folder, and create new Bookmarks and subfolders in the folder by selecting it and clicking the **Create File** and **Create Folder** buttons.

 The folders and the Bookmarks within a folder are ordered alphabetically and cannot be changed manually.

9.12.2 Executing Bookmarks

With a Bookmark opened in an SQL Commander tab, you can of course execute its statements by clicking the **Execute** toolbar buttons as usual, but you can also open and execute a Bookmark directly by selecting it in the tree and using the **Open in SQL Commander and Execute** operations in the right-click menu.

9.12.3 Adding a Bookmark as a Favorite

 **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

If you are using a Bookmark very often, you may find it more convenient to add it to the [Favorites area](#). You can drag and drop a Bookmark from the Scripts tab to the Favorites area, or via the **Add to Favorites** right-click menu operation.



9.12.4 Sharing Bookmarks


It's easy to share your Bookmarks with someone else because they are stored as regular files. The files are located in a subfolder of the DbVisualizer user preferences folder named *Bookmarks*. The user preferences folder is typically a subfolder named *.dbvis* in your home folder.

The main Bookmark content is stored in a file with exactly the same name as the node in the Scripts tab. The additional data associated with the Bookmark is stored in a file with the same name plus the *.met* extension.

To share some of your Bookmarks with someone, we recommend that you use DbVisualizer to create a separate Bookmarks subfolder for the shared Bookmarks. You can then use any external tool to create a file archive (e.g. a ZIP file) of that subfolder and send it to your friend or colleague. He or she can then extract the files into the local DbVisualizer user preferences *Bookmarks* folder.

9.12.5 Using Quick Load

An alternative to locating Bookmarks or Monitors from the Scripts tab and History entries from the History window is to use the **Quick Load** feature, by default bound to the **Ctrl+Alt+O** key combination. It is also available via a main toolbar button as well as in the **File->Quick File Open** menu.



The Quick Load feature locates files with partly matching names from the categories you have selected, as you type. You can use an asterisk ("*") as a wildcard in the search string.

When you see the file you're looking for, just select it and press **Enter** to load it into an SQL Commander editor. If the file is already loaded in an editor, that tab is made visible instead.

The number of matches is shown on the search panel as seen on the figure above. If the number of matches is big and you want to change the size, you can press **Escape** and change the number in the **Max entries** field that is shown. Go then to the **Enter search text** field and press arrow down. The result list shown will be limited to your set number for each category.

9.13 Creating Queries Graphically

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.


The Query Builder provides an easy way to develop database queries. The Query Builder provides a point and click interface and does not require in-depth knowledge about the SQL syntax.

- [Creating a Query](#)
 - [Adding tables](#)
 - [Joining Tables](#)
 - [Setting Join Properties](#)
 - [Removing Tables and Joins](#)
 - [Specifying Query Details](#)
 - [SQL Preview](#)




- [Testing the Query](#)
- [Loading a Query From the Editor](#)
- [Properties for the Query Builder](#)
 - [Express joins as JOIN clause or WHERE condition](#)
 - [Table and Column Name qualifiers](#)
 - [Delimited Identifiers](#)
- [Current Limitations](#)

The Query Builder is part of the SQL Commander, alongside the SQL Editor. When you are ready to test a query built with the Query Builder, you just load it to the SQL Editor for execution.

 This document talks only about Tables even though the Query Builder supports both table and view objects.

9.13.1 Creating a Query

To create a query, open the query builder using the **SQL Commander->Show Query Builder** menu choice or click the vertical **Query Builder** button in the SQL Commander. Make sure that the controls in the top section of the Query Builder are set correctly.



The screenshot shows the Query Builder interface. At the top, there is a toolbar with icons for running, undo, redo, and adding tables. Below the toolbar are dropdown menus for Database Connection (HR Production), Schema (HR), Max Rows (1000), and Max Chars (-1). The main area is titled "Query Builder" and contains the instruction "Drag tables from the objects tree and drop here" with a target icon. At the bottom, there are tabs for "Columns", "Conditions", "Grouping", and "Sorting". The "Columns" tab is active, showing a table with columns: Column/Expression, Alias, Aggregate, and Group By. There is also a checkbox for "Only include unique records:".

The easiest way to jump between the Query Builder and the SQL Editor is by clicking the vertical control buttons to the right in the SQL Commander. Clicking these buttons changes the display, but does not copy the query from one display to the other. To copy the current query from the Query Builder to the SQL Editor, use the toolbar buttons at the top of the Query Builder:



1. The first button (from left) replaces the content of the SQL Editor with the query SQL and executes it,
2. The second button replaces the content of the SQL Editor with the query SQL, without executing it,
3. The third button adds the query last in the SQL Editor,
4. The fourth button copies the query to the system clipboard,
5. The fifth button opens a dialog that lets you add tables matching a search criteria,




6. The sixth button is a drop-down menu for selecting what to show below the diagram area: query details or the SQL preview.

The first three buttons automatically change the display to the SQL Editor.

You can also load a query from the SQL Editor into the Query Builder, as described in detail [below](#).

Adding tables

To add tables using drag and drop, make sure the database objects tree and the table and/or view objects are visible. Then select and drag nodes from the tree into the diagram area.




To add a table, drag it from the object tree to the diagram area of the Query Builder. When the table is dropped in the diagram area, it is shown as a window with the table name as the window title. You can select multiple tables and/or views and drag and drop them together.

Below the title is a text field where an optional table alias can be entered. If a table alias is specified, it is used in the Query Builder and the generated SQL statement to refer to this table.

Under the table alias field is a list of all table columns. Use the check box in front of each name to select whether the column should be included in the query result set. Columns selected for the query result set also appear in the **Columns** and **Sorting** details tabs.

An alternative to dragging and dropping tables into the Query Builder is to use the Quick Table Add dialog.



It lists tables matching the search criteria as you type it in the search text field. An asterisk ("*") can be used as a wildcard for any characters.

Joining Tables

To join two tables, select the column in the source table window with the mouse, drag it to the target table column, and drop it.




The screenshot shows a query builder interface with two tables: HR.EMPLOYEES and HR.DEPARTMENTS. The HR.EMPLOYEES table has columns: EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL, PHONE_NUMBER, HIRE_DATE, JOB_ID, SALARY, COMMISSION_PCT, MANAGER_ID, and DEPARTMENT_ID. The HR.DEPARTMENTS table has columns: DEPARTMENT_ID, DEPARTMENT_NAME, MANAGER_ID, and LOCATION_ID. A join condition is established between the DEPARTMENT_ID columns of both tables, represented by a link with an equals sign icon. Below the tables is a 'Columns' tab with a table for defining column aliases and aggregates.

Column/Expression	Alias	Aggregate	Group By
			<input type="checkbox"/>

The two columns now represent a join condition, shown in the graph as a link between the columns. If more than one join condition is needed, link additional columns in the two tables by dragging and dropping the columns in the same way as for the first join condition. The default join type is an Inner join and the default condition is "equal to" (=), represented as an icon with overlapping circles with the shared area shaded and an equal sign below them.

Some database schemas declare how tables are related using primary and foreign keys. Other schemas use column names to indicate these relationships. For instance, in the figure above, the EMPLOYEES table has a column named DEPARTMENT_ID, which refers to the column with the same name in the DEPARTMENTS table. The Query Builder can be configured to use both kinds of rules to automatically join the tables you add to the query builder.

The auto-join feature is disabled by default. You can enable it in the tool properties for the database type (**Tools->Tool Properties**, under the **Database** tab) or for a specific connection (the **Properties** tab in the **Object View** tab for the connection).



In the Query Builder category, you can enable the auto-join feature and select whether to use key declarations (FK/PK) or column names to find out how the tables are related.

When you add a new table with auto-join enabled, the Query Builder automatically joins it to the tables already in the builder if table columns match the selected matching rule.

If columns in the table you add are related to other columns in the same table, the Query Builder creates two windows for the table and joins them based on the matching rule. In this case, a table alias is also added for one of the windows so that you can tell the two windows for the same table apart.

Setting Join Properties

A Join Properties dialog can be opened by double-clicking the icon or selecting **Join Properties** from the right-click menu while the mouse pointer is over the join icon. The Join Properties dialog shows the source and target table columns and the conditional operator.

You can change the join type and the conditional operator in the Join Properties dialog. The join type defines how the records from the tables should be combined:

- **Inner**
This is the most common join type as it finds the results in the intersection between the tables.
- **Left**
This join type limits the results to those in the left table leaving 0 matching records in the right table as NULL.
- **Right**
This is the same as left join but reversed
- **Full**
A full join combines the results of both left and right joins.



Join Properties

Operator

Table: EMPLOYEES DEPARTMENTS

Column: DEPARTMENT_ID DEPARTMENT_ID

Join Type

Inner

Left

Right

Full

Apply Cancel


i If you have multiple join conditions (linked columns) between two tables, you can specify different conditional operators for each join condition, but the join type is shared between all join conditions; if you change it for one join condition, it is changed for all the other join conditions linking the two tables. This is not a restriction in the Query Builder but rather how SQL is defined.

Here is the sample SQL generated from the previous join definition:

```
SELECT
*
FROM
HR.EMPLOYEES
INNER JOIN
HR.DEPARTMENTS
ON
(HR.EMPLOYEES.DEPARTMENT_ID = HR.DEPARTMENTS.DEPARTMENT_ID)
```

Removing Tables and Joins

A table window is removed by clicking the close icon in the window header. A join is removed by selecting **Remove Join** in the right-click menu while the mouse pointer is over the join icon.



All tables and joins may be removed via Remove All Joins and Remove All Tables.

Specifying Query Details

The Details tabs below the diagram area are used to define the various parts of the query. The tabs basically represent the following parts of the final SQL:

```
SELECT <Columns>
FROM <Tables>
WHERE <Conditions>
GROUP BY <Columns>
```



HAVING <Grouping>
ORDER BY <Sorting>

(The Tables clause is defined in the diagram, not by a tab).

Use the **Columns** tab to specify characteristics of the columns that are included in the query. The list is initially empty until a column is checked in a table window or a column expression is added manually (see below). Columns will appear in the list in the same order as they are checked but may be moved at any time with the up and down buttons. To include all columns from a table, right-click in the column list in the table window and choose **Select All**.

The screenshot shows the DbVisualizer interface. At the top, there are two table windows: HR.EMPLOYEES and HR.DEPARTMENTS. The HR.EMPLOYEES window has a list of columns with checkboxes: EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL, PHONE_NUMBER, HIRE_DATE, JOB_ID, SALARY, COMMISSION_PCT, MANAGER_ID, and DEPARTMENT_ID. The HR.DEPARTMENTS window has a list of columns with checkboxes: DEPARTMENT_ID, DEPARTMENT_NAME, MANAGER_ID, and LOCATION_ID. Below the table windows is the Columns tab, which has a table with the following columns: Column/Expression, Alias, Aggregate, and Group By. The table contains the following rows:

Column/Expression	Alias	Aggregate	Group By
EMPLOYEES.FIRST_NAME	"First name"		<input type="checkbox"/>
EMPLOYEES.LAST_NAME	"Family name"		<input type="checkbox"/>
EMPLOYEES.EMAIL	"E-Mail"		<input type="checkbox"/>
DEPARTMENTS.DEPARTMENT_NAME	"Department"		<input type="checkbox"/>
			<input type="checkbox"/>

The previous screenshot shows a total of 5 checked columns in the two tables. These are presented in the columns list by their full column identifier, qualified by either the table name or the table alias. To remove a column from the list, uncheck the corresponding column in the table window.

The alias field is used to specify an optional alias identifier for the column. The alias is used as the identifier for the column in the final query and also appears as the column name in the result set produced by the query. Check the documentation for the actual database to see if the alias must be quoted since the Query Builder does not do this for you.

The **Aggregate** and **Group by** fields are used in combination:

- The **Aggregate** field lists the available aggregation functions (AVG, COUNT, MAX, MIN, SUM) that may be used for columns
- The **Group By** field specifies whether the column should be included in the group for which aggregate columns are summarized

The **Group By** field is disabled unless an aggregate function is selected for at least one column, and once you select an aggregate function for one column, you must set **Group By** for at least one of the other columns to form a valid query. If you remove the aggregate function for all columns, **Group By** is automatically reset for all columns. **Group By** and **Aggregate** are also mutually exclusive options for one column, so when you select one of them, the field for the other is disabled for that column.

A custom expression may be added by entering data in the empty row last in the list, e.g., `col1 + col2` or `TO_CHAR(ts_col, 'DD-MON-YYYY HH24:MI:SSxFF')`. Once entered, press enter to insert a new empty row. You can remove a custom expression by selecting it and clicking the Remove button.

You can also launch a multi-line text editor for a custom expression, to make it easier to edit a large expression such as a CASE clause. Just double-click the expression cell, and then click on the editor launch button to the right.



The screenshot shows the DbVisualizer interface. On the left, the 'HR.EMPLOYEES' table is selected, and its columns are listed with checkboxes. The 'EMAIL' column is checked. On the right, the 'HR.DEPARTMENTS' table is also visible. A 'Text Editor' window is open in the center, displaying a SQL CASE statement:

```
CASE
  WHEN SALARY > 100000 THEN 'High'
  WHEN SALARY BETWEEN 50000 AND 99999 THEN 'Medium'
  WHEN SALARY < 50000 THEN 'Low'
END
```

Below the text editor, the 'Columns' tab of the query editor is active. It shows a table with the following columns: 'Column/Expression', 'Alias', 'Aggregate', and 'Group By'. The rows are:

Column/Expression	Alias	Aggregate	Group By
EMPLOYEES.FIRST_NAME	"First name"		<input type="checkbox"/>
EMPLOYEES.LAST_NAME	"Family name"		<input type="checkbox"/>
EMPLOYEES.EMAIL	"E-Mail"		<input type="checkbox"/>
DEPARTMENTS.DEPARTMENT_NAME	"Department"		<input type="checkbox"/>
CASE WHEN SALARY > 100000 THEN ...	"Salary level"		<input checked="" type="checkbox"/>

The **Conditions** tab is used to manage the WHERE clause for the query. A WHERE clause may consist of several conditions connected by AND or OR. The evaluation order for each condition is defined by indentation in the condition list. Each level in the list will be enclosed by brackets in the final SQL.

Here is an example from the **Conditions** tab.



The screenshot shows the Query Builder interface with two table aliases: HR.EMPLOYEES and HR.DEPARTMENTS. The HR.EMPLOYEES table has columns: EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL, PHONE_NUMBER, HIRE_DATE, JOB_ID, SALARY, COMMISSION_PCT, MANAGER_ID, and DEPARTMENT_ID. The HR.DEPARTMENTS table has columns: DEPARTMENT_ID, DEPARTMENT_NAME, MANAGER_ID, and LOCATION_ID. A dashed line connects the DEPARTMENT_ID column in HR.EMPLOYEES to the DEPARTMENT_ID column in HR.DEPARTMENTS. Below the table selection, the 'Conditions' tab is active, showing a list of conditions:

- 1 All of the conditions in this branch must match
 - 1.1 IR.EMPLOYEES.SALARY > 1500
 - 1.2 Any of the conditions in this branch must match
 - 1.2.1 'S.DEPARTMENT_NAME' = Human Resources
 - 1.2.2 'S.DEPARTMENT_NAME' = IT

To create a new WHERE condition, press the indexed button in the list. In the menu that is displayed you may choose to create a new condition on the same level, a compound condition or delete the current condition.

For compound conditions you may choose whether **All** (AND), **Any** (OR), **None** (NOT OR) or **Not All** (NOT AND) conditions must be met for its sub conditions. The SQL for the **Conditions** tab in the figure is:

```
WHERE
  emp.SALARY > 4000
AND
  (
    dept.DEPARTMENT_NAME = 'Human Resources'
  OR dept.DEPARTMENT_NAME = 'IT'
  )
```

Next to the input field for each condition, there is a drop down button. When pressed it shows all columns that are available in the tables currently being in the Query Builder. You can pick columns from the list instead of typing these manually.

The screenshot shows the Query Builder interface with the 'Conditions' tab active. The condition list is the same as in the previous screenshot. A dropdown menu is open for the 'S.DEPARTMENT_NAME' column in condition 1.2.1, showing the following options:

- HR.EMPLOYEES >
- HR.DEPARTMENTS >
- DEPARTMENT_ID
- DEPARTMENT_NAME
- MANAGER_ID
- LOCATION_ID

A condition field may also contain a custom expression, and just as for a custom expression in the columns list, you can launch a multi-line editor for the expression by selecting the field and click the editor launch button.



The **Grouping** tab is used to define the conditions for the HAVING clause that may follow a GROUP BY clause in an SQL query. This tab is only enabled when at least one of the columns in the Columns tab is marked as a Group By column.

The HAVING clause is similar to the WHERE clause, except that the HAVING clause limits what rows are included in the groups defined by the GROUP BY clause, after the WHERE clause has been used to limit the total number of rows to process.

You work with conditions in this tab in the same way as in the **Conditions** tab, with one exception regarding the drop-down button for the fields in a condition. In the **Grouping** tab, the drop-down shows all columns listed in the **Columns** tab, with an aggregate function expression for columns that have an aggregate function defined. This is because (according to the SQL specification) the conditions in a HAVING clause must only refer to columns that are being returned by the query.

Finally, the **Sorting** tab is used to specify how the final result set will be sorted. All columns for the tables in the graph, plus any custom expressions created for the selection list in the **Columns** tab, are listed in the **Sorting** tab.

SQL Preview

Select **SQL Preview** in the drop-down menu in the toolbar to show a preview of the final SQL. This is a read-only view and cannot be modified.

9.13.2 Testing the Query

To test the query, simply press the appropriate toolbar button in the Query Builder to copy the SQL to the SQL Editor. Then execute the SQL as usual in the SQL Editor. Or click the **Execute** button in the Query Builder toolbar to copy and execute the SQL in one step.

The screenshot shows the DbVisualizer Query Builder interface. The top toolbar contains various icons for query building and execution. Below the toolbar, the 'Database Connection' is set to 'HR Production', 'Sticky Database' is unchecked, 'Schema' is 'HR', 'Max Rows' is 1000, and 'Max Chars' is -1. The SQL editor displays the following query:

```
1 SELECT
2   HR.EMPLOYEES.FIRST_NAME      AS "First name",
3   HR.EMPLOYEES.LAST_NAME      AS "Family name",
4   HR.EMPLOYEES.EMAIL          AS "E-Mail",
5   HR.DEPARTMENTS.DEPARTMENT_NAME AS "Department",
6   CASE
7     WHEN SALARY > 100000
8     THEN 'High'
9     WHEN SALARY BETWEEN 50000 AND 99999
10    THEN 'Medium'
11    WHEN SALARY < 50000
12    THEN 'Low'
13  END AS "Salary level",
14  HR.EMPLOYEES.SALARY
15 FROM
16   HR.EMPLOYEES
17 INNER JOIN
18   HR.DEPARTMENTS
```

Below the SQL editor, the status bar shows '15:5 [439] INS', 'Auto Commit: ON', 'Cp1252', and 'Untitled*'. The 'DBMS Output' tab is active, showing a table with 6 columns: 'First name', 'Family name', 'E-Mail', 'Department', 'Salary level', and 'SALARY'. The table contains 5 rows of data:

*	First name	Family name	E-Mail	Department	Salary level	SALARY
1	Susan	Mavris	SMAVRIS	Human Resources	Low	6500
2	Alexander	Hunold	AHUNOLD	IT	Low	9000
3	Bruce	Ernst	BERNST	IT	Low	6000
4	David	Austin	DAUSTIN	IT	Low	4800
5	Valli	Pataballa	VPATABAL	IT	Low	4800

The status bar at the bottom right shows '0.000/0.000 sec', '6/6', and '1-6'.



To further refine the SQL press the Query Builder button and make the necessary changes.

9.13.3 Loading a Query From the Editor

If you have an existing SQL query that you want to modify using the Query Builder, you can load it from the SQL Editor into the Query Builder by clicking the **Load in Query Builder** button in the SQL Editor toolbar.

It's important to be aware that the Query Builder does not support all features of the SQL SELECT statement, such as comments, UNION, and database-specific keywords. If you load a query into the Query Builder that contains unsupported constructs or keywords, they are ignored and a dialog pops up with a warning about this fact. You can then use the SQL Preview tab in the Query Builder to compare the SQL as it is represented in the Query Builder with the original SQL that you loaded to understand what was ignored.

9.13.4 Properties for the Query Builder

In addition to the **Auto Join** setting discussed above, there are a few other properties that control how the Query Builder works and the SQL it generates. You can set these properties for the database type (**Tools->Tool Properties**, under the **Database** tab) or for a specific connection (the **Properties** tab in the **Object View** tab for the connection).

Express joins as JOIN clause or WHERE condition

The **Generate JOIN Clause in SQL Builder** property is available in the **[Database Type]->Query Builder** category. Joins can be expressed either via the standardized SQL JOIN clause or a WHERE clause, using database-specific syntax for the Left and Right join types. The database-specific WHERE clause syntax is somewhat different between the supported databases and the Full outer join type is not supported. The default for this property is to use a JOIN clause.

A simple inner join expressed as a JOIN clause:

```
FROM HR.EMPLOYEES
INNER JOIN HR.DEPARTMENTS
ON (HR.EMPLOYEES.DEPARTMENT_ID = HR.DEPARTMENTS.DEPARTMENT_ID
```

Here is the same join expressed as a WHERE condition:

```
FROM HR.EMPLOYEES, HR.DEPARTMENTS
WHERE HR.EMPLOYEES.DEPARTMENT_ID = HR.DEPARTMENTS.DEPARTMENT_ID
```

The syntax for expressing Inner and Outer joins in WHERE conditions is different between databases. Oracle, for example, uses the "(+)" sequence to the left or right of the conditional operator to express left or right joins. SQL Server and Sybase use "*"=" or "=*" for the same purpose.

DbVisualizer automatically uses the correct join notation when generating joins as WHERE conditions for databases that support left and right joins using WHERE conditions. For databases that do not provide syntax for left and right joins, the join type is ignored and the WHERE condition that is generated produces an inner join result.

Table and Column Name qualifiers

Whether to qualify table names with the schema or database name and whether to qualify column names with the table name are defined in the **[Database Type]->Qualifiers** category.

Delimited Identifiers

Identifiers that contain mixed case characters or include special characters need to be delimited. Define this in the **[Database Type]->Delimited Identifiers** category.

9.13.5 Current Limitations

These are the current limitations in the Query Builder:

- Unions and sub queries are not supported.
- Not all join types are supported when joins are expressed as WHERE clause conditions. The **Inner** join type is supported for all databases, but the **Left** and **Right** types are only supported for databases with proprietary syntax to express these types, e.g., Oracle, SQL Server and Sybase. The **Full** type is not supported for any database. If a join type is not supported, the setting in the **Join Properties** dialog is silently ignored.
- When importing an SQL query from the SQL Editor, comments, unsupported keywords and statement clauses are ignored. A dialog tells you which parts of the query are being ignored when unsupported parts are found in the imported statement.




- There is only limited support for the CASE clause, in that everything between CASE and END is treated as uninterpreted text. This means that, as opposed to plain object references in the select list or conditions, column names and other identifiers within a CASE clause are not affected by changes to the Query Builder property settings, such as Delimited Identifiers and Qualifiers.

9.14 Formatting SQL

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **SQL Commander** main menu on the (or right-click in the editor) and its **Format SQL** sub menu contains operations for formatting SQL statements.



```

/*-- CASE example*/
SELECT
  FIRST_NAME,
  LAST_NAME,
  SALARY,
  CASE
    WHEN SALARY > 10000
    THEN 'High'
    WHEN SALARY BETWEEN 5000 AND 999
    THEN 'Midlevel'
    ELSE 'Low'
  END AS "Income Level",
  CASE DEPARTMENT_ID
    WHEN 40
    THEN 'Administration'
    WHEN 20
    THEN 'Sales Related'
  
```

- **Format Buffer** and **Format Current** formats the complete editor content or the current SQL (at cursor position) respectively.
- **Copy Formatted** and **Paste Formatted** are powerful tools for copying SQL statements between programs written in languages like Java, C#, PHP, VB, etc. and the SQL Editor. Both operations display a dialog where you can adjust some of the formatting options, most importantly the **Target SQL** option and the **SQL is Between** option. **Target SQL** can be set to a number of common programming language formats.
- **Unformat Buffer** and **Unformat Current** produces compact statements by removing unnecessary whitespace.

Example:

To copy an SQL statement and paste it as Java code for adding it to a Java StringBuffer:

1. Select the statement. Example:
SELECT * FROM SAKILA.STAFF)
2. Choose **SQL->Format SQL->Copy Formatted**,
3. Set **Target SQL** to Java StringBuffer,
4. Click **Format** to place the formatted statement on the system clipboard,
5. Paste it into your Java code. Example:
StringBuffer sql = new StringBuffer();
sql.append("SELECT ");
sql.append(" * ");
sql.append("FROM ");
sql.append(" SAKILA.STAFF");

To copy a statement wrapped in code from a program:

1. Select the code containing an SQL statement in your program,
2. Copy it to the system clipboard,
3. Choose **SQL->Format SQL->Paste Formatted**,
4. Check **SQL is Between** and enter the character enclosing the SQL statement in the code,
5. Click **Format** to extract the SQL statement and paste the formatted SQL in the editor.

9.14.1 Settings

All formatting is done according to the settings defined in the **Tool Properties** dialog, in the **SQL Editor/SQL Formatting** category under the General tab.

There are many things you can configure; use the default example or your own SQL to check the effect of the settings. After making some changes, press **Apply** and format again to see the result.

**Example:**

```
-- Basic SELECT example, with Sub-SELECT and JOIN
SELECT e.LAST_NAME AS "Last Name", e.FIRST_NAME AS "First Name", d.DEPARTMENT_NAME AS "Department", e.SALARY AS
"Salary", e.SALARY + e.SALARY * e.COMMISSION_PCT, e.COMMISSION_PCT * 100 || '%', ROUND(e.SALARY / ( SELECT MAX(SALAR
Y) FROM HR.EMPLOYEES), 2) * 100 AS "Percentage of Max" FROM HR.EMPLOYEES e INNER JOIN HR.DEPARTMENTS d ON
( e.DEPARTMENT_ID = d.DEPARTMENT_ID) WHERE d.DEPARTMENT_ID IN (10, 20, 90, 210) AND e.SALARY > 3000;
-- CASE example
SELECT FIRST_NAME, LAST_NAME, SALARY, CASE WHEN SALARY > 10000 THEN 'High' WHEN SALARY BETWEEN 5000 AND 999 THEN
'Midlevel' ELSE 'Low' END AS "Income Level", CASE DEPARTMENT_ID WHEN 40 THEN 'Administration' WHEN 20 THEN 'Sales
Related' ELSE 'Other' END AS "Special Departments" FROM EMPLOYEES;
-- JOIN example, with GROUP BY, HAVING and ORDER BY
SELECT COUNT(d.DEPARTMENT_NAME) AS "Departments per Location", c.COUNTRY_NAME, l.STATE_PROVINCE FROM DEPARTMENTS d
INNER JOIN LOCATIONS l ON d.LOCATION_ID = l.LOCATION_ID INNER JOIN COUNTRIES c USING (COUNTRY_ID) GROUP BY
c.COUNTRY_NAME, l.STATE_PROVINCE HAVING COUNT(d.DEPARTMENT_NAME) > 1 ORDER BY 2, 3, 1;
-- UPDATE example
UPDATE EMPLOYEES SET COMMISSION_PCT = 10 WHERE COMMISSION_PCT = 0 AND SALARY < 5000;
-- INSERT example
INSERT INTO EMPLOYEES ( FIRST_NAME, LAST_NAME ) VALUES ( 'Roger', 'Bjarevall' );
-- DELETE example
DELETE FROM EMPLOYEES WHERE HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');
-- CREATE TABLE example
CREATE TABLE DEPARTMENTS ( DEPARTMENT_ID NUMBER(4) NOT NULL, DEPARTMENT_NAME VARCHAR2(30) NOT NULL, MANAGER_ID
NUMBER(6), LOCATION_ID NUMBER(4), CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID), CONSTRAINT DEPT_LOC_FK FOREIGN
KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"), CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES
"EMPLOYEES" ("EMPLOYEE_ID"), CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL) );
```

**Formatted with default settings:**

```
-- Basic SELECT example, with Sub-SELECT and JOIN
SELECT
  e.LAST_NAME           AS "Last Name",
  e.FIRST_NAME          AS "First Name",
  d.DEPARTMENT_NAME     AS "Department",
  e.SALARY              AS "Salary",
  e.SALARY + e.SALARY * e.COMMISSION_PCT,
  e.COMMISSION_PCT * 100 || '%',
  ROUND(e.SALARY /
    ( SELECT
      MAX(SALARY)
    FROM
      HR.EMPLOYEES), 2) * 100 AS "Percentage of Max"
FROM
  HR.EMPLOYEES e
INNER JOIN
  HR.DEPARTMENTS d
ON
  (
    e.DEPARTMENT_ID = d.DEPARTMENT_ID)
WHERE
  d.DEPARTMENT_ID IN (10,
                     20,
                     90,
                     210)
AND e.SALARY > 3000;

-- CASE example
SELECT
  FIRST_NAME,
  LAST_NAME,
  SALARY,
  CASE
    WHEN SALARY > 10000
    THEN 'High'
    WHEN SALARY BETWEEN 5000 AND 999
    THEN 'Midlevel'
    ELSE 'Low'
  END AS "Income Level",
  CASE DEPARTMENT_ID
    WHEN 40
    THEN 'Administration'
    WHEN 20
    THEN 'Sales Related'
    ELSE 'Other'
  END AS "Special Departments"
FROM
  EMPLOYEES;

-- JOIN example, with GROUP BY, HAVING and ORDER BY
SELECT
  COUNT(d.DEPARTMENT_NAME) AS "Departments per Location",
  c.COUNTRY_NAME,
  l.STATE_PROVINCE
FROM
  DEPARTMENTS d
INNER JOIN
  LOCATIONS l
ON
  d.LOCATION_ID = l.LOCATION_ID
INNER JOIN
  COUNTRIES c
USING
  (COUNTRY_ID)
GROUP BY
```



```
c.COUNTRY_NAME,  
l.STATE_PROVINCE  
HAVING  
COUNT(d.DEPARTMENT_NAME) > 1  
ORDER BY  
2,  
3,  
1;  
  
-- UPDATE example  
UPDATE  
EMPLOYEES  
SET  
COMMISSION_PCT = 10  
WHERE  
COMMISSION_PCT = 0  
AND SALARY < 5000;  
  
-- INSERT example  
INSERT INTO  
EMPLOYEES  
(  
    FIRST_NAME,  
    LAST_NAME  
)  
VALUES  
(  
    'Roger',  
    'Bjarevall'  
);  
  
-- DELETE example  
DELETE  
FROM  
EMPLOYEES  
WHERE  
HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');  
  
-- CREATE TABLE example  
CREATE TABLE  
DEPARTMENTS  
(  
    DEPARTMENT_ID NUMBER(4) NOT NULL,  
    DEPARTMENT_NAME VARCHAR2(30) NOT NULL,  
    MANAGER_ID NUMBER(6),  
    LOCATION_ID NUMBER(4),  
    CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID),  
    CONSTRAINT DEPT_LOC_FK FOREIGN KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"),  
    CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES "EMPLOYEES" ("EMPLOYEE_ID"),  
    CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL)  
);
```

**Unformatted to compact form:**


```
/*-- Basic SELECT example, with Sub-SELECT and JOIN*/ SELECT e.LAST_NAME AS "Last Name", e.FIRST_NAME AS "First Name", d.DEPARTMENT_NAME AS "Department", e.SALARY AS "Salary", e.SALARY + e.SALARY * e.COMMISSION_PCT, e.COMMISSION_PCT * 100 || '%' , ROUND(e.SALARY / ( SELECT MAX(SALARY) FROM HR.EMPLOYEES), 2) * 100 AS "Percentage of Max" FROM HR.EMPLOYEES e INNER JOIN HR.DEPARTMENTS d ON ( e.DEPARTMENT_ID = d.DEPARTMENT_ID) WHERE d.DEPARTMENT_ID IN (10, 20, 90, 210) AND e.SALARY > 3000;
/*-- CASE example*/ SELECT FIRST_NAME, LAST_NAME, SALARY, CASE WHEN SALARY > 10000 THEN 'High' WHEN SALARY BETWEEN 5000 AND 999 THEN 'Midlevel' ELSE 'Low' END AS "Income Level", CASE DEPARTMENT_ID WHEN 40 THEN 'Administration' WHEN 20 THEN 'Sales Related' ELSE 'Other' END AS "Special Departments" FROM EMPLOYEES;
/*-- JOIN example, with GROUP BY, HAVING and ORDER BY*/ SELECT COUNT(d.DEPARTMENT_NAME) AS "Departments per Location", c.COUNTRY_NAME, l.STATE_PROVINCE FROM DEPARTMENTS d INNER JOIN LOCATIONS l ON d.LOCATION_ID = l.LOCATION_ID INNER JOIN COUNTRIES c USING (COUNTRY_ID) GROUP BY c.COUNTRY_NAME, l.STATE_PROVINCE HAVING COUNT(d.DEPARTMENT_NAME) > 1 ORDER BY 2, 3, 1;
/*-- UPDATE example*/ UPDATE EMPLOYEES SET COMMISSION_PCT = 10 WHERE COMMISSION_PCT = 0 AND SALARY < 5000;
/*-- INSERT example*/ INSERT INTO EMPLOYEES ( FIRST_NAME, LAST_NAME ) VALUES ( 'Roger', 'Bjarevall' );
/*-- DELETE example*/ DELETE FROM EMPLOYEES WHERE HIRE_DATE < to_timestamp('1900-01-10', 'RR-MM-DD');
/*-- CREATE TABLE example*/ CREATE TABLE DEPARTMENTS ( DEPARTMENT_ID NUMBER(4) NOT NULL, DEPARTMENT_NAME VARCHAR2(30) NOT NULL, MANAGER_ID NUMBER(6), LOCATION_ID NUMBER(4), CONSTRAINT DEPT_ID_PK PRIMARY KEY (DEPARTMENT_ID), CONSTRAINT DEPT_LOC_FK FOREIGN KEY (LOCATION_ID) REFERENCES "LOCATIONS" ("LOCATION_ID"), CONSTRAINT DEPT_MGR_FK FOREIGN KEY (MANAGER_ID) REFERENCES "EMPLOYEES" ("EMPLOYEE_ID"), CONSTRAINT DEPT_NAME_NN CHECK ("DEPARTMENT_NAME" IS NOT NULL) );
```

9.15 Using Max Rows and Max Chars for Queries

DbVisualizer limits the number of rows shown in the result set tab to 1000 rows, by default. This is done to conserve memory. If this limit prevents you from seeing the data of interest, you should first consider:

1. Using a WHERE clause in the query to only retrieve the rows of interest instead of all rows in the table,
2. [Exporting the table](#) to a file

If you really need to look at more than 1000 rows, you can change the value in the **Max Rows** field in the SQL Commander toolbar. Use a value of 0 or -1 to get all rows, or a specific number (e.g. 5000) to set a new limit.



Character data columns may contain very large values that use up lots of memory. If you are only interested in seeing a few characters, you can set the **Max Chars** field in the SQL Commander toolbar to the number of characters you want to see.

A value of 0 or -1 (default) will include all characters in the character data columns.

You can define how to deal with columns that have more characters than the specified maximum in the Tool Properties dialog, in the Grid category under the General tab. You have two choices: **Truncate Values** or **Truncate Values Visually**.


- **Truncate Values** truncates the original value for the grid cell to be less than the setting of Max Chars.



This affects any subsequent edits and SQL operations that use the value since it's truncated. This setting is only useful to save memory when viewing very large text columns.

- **Truncate Values Visually** truncates the visible value only and leave the original value intact. This is the preferred setting since it will not harm the original value. The disadvantage is that more memory is needed when dealing with large text columns.

When the grid data is limited due to either the **Max Rows** or **Max Chars** value, you get an indication about this in the rows/columns field in the grid status bar and in the corresponding limit field.



Along with the highlighted field, a warning pops up close to the field. You can disable this behavior in the Tool Properties dialog, in the **Grid** category under the General tab.

9.16 Getting the DDL for an Object

You can use the `@ddl` command in a script to get the DDL for a number of different database object types. The command supports this general syntax:

```
@ddl <objType>=<"<objId>" [ drop="true | false" ] [ constrCtrl=<"<constrCtrl>" ]
```

where `<objType>` is one of `table`, `indexesfortable`, `view`, `procedure`, `function`, `package` (Oracle only), `packagebody` (Oracle only), `objecttype` (Oracle only), `objecttypebody` (Oracle only), `sequence` (Oracle only), `synonym` (Oracle only), `module` (Mimer SQL only) or `trigger`, and `<objId>` is the qualified identifier for the object (case sensitive). Here's an example:

```
@ddl table="HR.EMPLOYEES";
```

If `drop` is set to `true`, a DROP statement is included before the CREATE statement.

The `constrCtrl` parameter only applies to tables. It accepts two values: `noconstr` means that no constraints should be included in the statement that can potentially cause creating the table or inserting data into it to fail (FK and CHECK constraints), while `onlyconstr` means that an ALTER statement adding the remaining constraints should be generated instead of a CREATE statement.

9.17 Using the Log Tab

The Log reports progress and results when executing in the **SQL Commander**, **Import**, **Export Schema/Database**, **Procedure Editor**, and when running **Database Object Actions**. The appearance of the Log may differ slightly depending on which of these functions is used. The Log was completely redesigned in 10.0 and now saves unlimited number of log entries to file. Due to memory constraints, the Log grid in the DbVisualizer tool keeps up to 10 000 entries until it starts truncating the oldest entries.

Note that the detail level in a log entry message depends on the driver and database that is being used. Some databases are very good at telling you what went wrong and why, while others provide less detail.

- [Preprocessing Script](#)
- [Executing](#)
 - [Disabled functionality during execution](#)
 - [Progress information](#)
 - [Auto scroll](#)
 - [Auto Clear log](#)
 - [Log truncation](#)
- [Auto resize row heights](#)
- [Navigating to next/previous failed log entry](#)
- [Highlight statement or error in the SQL editor](#)
- [Saving all Log entries to text file](#)
- [Copy Log Entries to clipboard](#)
- [Copy executed SQLs to the SQL Commander](#)
- [Filter and search](#)



9.17.1 Preprocessing Script

The preprocessing step is performed just before a script is executed. It locates any variables, parameters, and restricted commands (defined in the Permissions category in Tools->Tool Properties) in the script. Depending how large the script is, preprocessing may take some time to complete and DbVisualizer may even advise you to run without preprocessing if the script is too large.

Check [Executing an External Script](#) page for more information.

9.17.2 Executing

Disabled functionality during execution


When a script is executed some functions in the Log are disabled:

- Quick Search
- Sorting
- Filtering
- Expand row heights (double-click)
- Hyperlinks to highlight errors and statements
- Save Log to Text File

Progress information

While executing there is progress information in the Log status bar showing overall metrics for the execution. It helps getting a quick overview of number of failed and successful statements, elapsed time, and number of statements executed per time unit.

The progress bar shows how much of the script has been executed. The progress bar switch to an indeterminate mode when **Preprocess Script** is switched off or when running a script using the **@run** client-side command. The reason is that the Log then doesn't count how many statements to execute.



Auto scroll

When new log entries are added the Log grid is automatically scrolled to the bottom. This can be turned off in the toolbar or by right-click in the grid, and select **Auto Scroll**.

Auto Clear log

Having auto clear checked, the log is cleared when execution is started. Disabling auto clear will keep all entries until number of entries exceeds 10 000 when truncation is triggered.

Log truncation

When the number of entries in the grid exceeds 10 000 the log is truncated by removing the oldest entries. When the log is truncated an icon and "Truncated" text is displayed in the grid status bar. If having auto clear log disabled, you will still see the STARTED and FINISHED entries for a previous executions in the grid along with an entry telling how many log entries has been truncated for that execution.

9.17.3 Auto resize row heights

The **Message** and **SQL/Command** columns may include multi-lined content. During execution only a single line of content is displayed in the grid. Once the execution has completed, and there are any FAILED statements these rows automatically expands to show all of its content. In the right-click menu under **Auto Resize Row Heights**, the auto resizing may be configured to also expand SUCCESS entries.

A cell having multi-lined content ends with three dots, "...". To manually expand/collapse a row with more content, double-click the row.

9.17.4 Navigating to next/previous failed log entry

To navigate to next/previous failed statement, use the **Goto Next Failed** and **Goto Previous Failed** actions in the right-click menu. An alternative is to filter out all but FAILED log entries in the grid, see [Filter and search](#) section below for more information.



9.17.5 Highlight statement or error in the SQL editor

If there is an editor associated with the log grid, such as the SQL Commander, the **Command** column for all log entries is represented by a hyperlink. Clicking the link will navigate to, and highlight the corresponding SQL/command in the SQL editor.

The same applies for any FAILED statements whereas the **Status** column is then a hyperlink, when clicked it will show the statement that failed. Depending on if the database reports error positions, clicking the link will set the caret at the position where the error started.

If a single statement produces multiple errors, clicking on the FAILED status link, will then show a menu with all errors. Selecting an error highlights it in the SQL editor.

For **@run** commands, clicking the @run link in the **Command** column shows a menu in which you can select to load the related file in a new SQL Commander tab.

The matching actions are in the right-click menu, **Highlight Statement** and **Highlight Failed Statement**.

9.17.6 Saving all Log entries to text file

All log entries are written to file, even those that has been truncated in the Log grid. The **Save Log to Text File** right-click menu action saves this log to text. Note that the log file is cleared between executions if auto clear log is enabled and when manually clearing the log. It is also removed when closing down the SQL Commander tab.

The internal log file is stored in json format under the \$HOME/.dbvis/sqllogs folder with the .dson extension. A log file may be loaded in the Log grid using **Load Log File** in the right-click menu.

9.17.7 Copy Log Entries to clipboard

The copy log entries to clipboard actions transforms the selected rows to text format and puts these on the system clipboard. This is useful if you want to share all or some log entries with others. The difference with the standard **Copy Selection** is that the latter copies only the selected cells in standard grid copy format typically separated with tabs.


9.17.8 Copy executed SQLs to the SQL Commander

The SQLs displayed in the log may be copied as a script to an existing or a new SQL Commander. Just select the rows you want to copy and then right-click and **Load Selected Commands into Editor**.

9.17.9 Filter and search

The filtering capability is useful to quickly limit what entries are displayed in the grid. A good example is to click the filtering icon in the **Status** column header and then de-select all statuses than **FAILED** (or just double-click FAILED to de-select the others). The result is that only FAILED statements are displayed in the log grid. That type of filtering can be applied to any on the columns (and in fact in most grids in DbVisualizer). The quick search field can be used to further refine to do full text search on all entries in the grid.

There is also a (**Custom...**) option that let you define your own condition to be used in the filter.




Applying a column filter will not have any effect on the **STARTED** or any **@run** log entries as these are grouping (indented) entries in the Log grid.



Configure the Log

The **Time** column in the log shows by default **hour:minute:second** (HH:mm:ss) but can be configured to show date, milliseconds, and more. Change this in **Tools->Tool Properties** and the **General / SQL Commander / SQL Log** category.



9.18 Writing to the Log Tab

You can use the `@echo` client side command to write information to the Log tab.

```
@echo <message>
```

The message may contain [DbVisualizer variables](#), e.g. one of the predefined variables.

```
@echo Today is ${dbvis-date}$ and the time is ${dbvis-time}$
```

Variables can also be used to display values produced by [executing a function or stored procedure](#):

```
@call ${STATUS||(null)||String|noshow dir=out}$ = "HR"."GET_STATUS"(1002);  
@echo STATUS: ${STATUS}$;
```

9.19 Using the DBMS Output Tab

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **DBMS Output** tab is only available for Oracle and DB2 LUW databases. It is used to capture messages produced by stored procedures, packages, and triggers using the `DBMS_OUTPUT` utility. These messages are typically inserted in the code for debugging purposes. For SQL*Plus users, the corresponding feature is enabled via the **set serveroutput on** command. To enable display of DBMS messages in DbVisualizer,



1. Select the **DBMS Output** tab
2. Press the **Enable** button.

Once DBMS output is enabled, the icon in the tab header is changed. Invoking a stored procedure that produces messages in the SQL Commander results in content similar to this in the output tab. (Each block of output is separated with a timestamp).

The screenshot shows the SQL Commander interface. The top panel displays the SQL editor with the command `@call EMP_REPORT();`. The bottom panel shows the DBMS Output tab, which contains the output of the stored procedure. The output is a table with columns `Empno`, `Last Name`, and `Job`. The table contains 14 rows of data.

Empno	Last Name	Job
206	Gietz	Public Acco
205	Higgins	Accounting
200	Whalen	Administrat
100	King	President
101	Kochhar	Administrat
102	De Haan	Administrat
111	Sciarra	Accountant
110	Chen	Accountant
113	Popp	Accountant
112	Urman	Accountant
109	Faviet	Accountant

i If you never use the DBMS Output tab and want to preserve screen real estate, you can select to not show it in the connection properties, in the SQL Commander category.

9.20 Comparing SQL Scripts

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

You can compare a script in one SQL Commander editor to a script in another SQL Commander editor, or to the original file loaded into the editor.

- To compare the script to another script, select **Compare** from the right-click menu in one editor and pick the SQL Commander holding the other script in **Select Object** dialog to [compare their text content](#).
- To compare the script to the original file, select **Compare to Saved** from the right-click menu.



9.21 Using Permissions in the SQL Commander

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

The **Permission** functionality is a security mechanism, where you can specify that certain database operations must be confirmed. You configure permissions in the Tool Properties dialog, in the **Permissions** category of the General tab, per *connection mode* (Development, Test and Production).

You specify which connection mode to use for a connection in the **Properties** tab of the Object View tab for the connection. By default a connection mode is specified to be Development.

i The permission feature is part of DbVisualizer and does not replace the authorization system in the actual database.

For the SQL Commander, you can pick the permission mode type from a drop-down list for each SQL command:

Permission Type	Description
Allow	This permission type means that you can run the SQL statement without any confirmation
Deny	This permission type means that the SQL statement is not executed at all.
Ask	This permission type means that when executing an SQL statement, or a script of statements, the SQL Commander asks you whether the actual SQL command(s) should be executed.

SQL Commander Permissions

Define here whether the SQL Commander should **allow (execute)**, **deny (not execute)** or **ask** before executing the following SQLs organized per permission mode.
(The permission mode for a database connection is set either in the **Tool Properties->Database** tab or in **Connection Properties** for a specific database connection).


	Development	Test	Production
SELECT:	Allow	Allow	Allow
INSERT:	Allow	Allow	Ask
UPDATE:	Allow	Allow	Deny
DELETE:	Allow	Ask	Deny
TRUNCATE:	Allow	Ask	Ask
CREATE:	Allow	Allow	Ask
ALTER:	Allow	Allow	Ask
DROP:	Allow	Ask	Ask
COMMIT/ROLLBACK:	Allow	Allow	Ask
Other:	Allow	Ask	Ask

9.22 Sending Comments to the Database with Statements

Comments in an SQL script, identified by the delimiters defined in Tool Properties dialog in the **SQL Commander/Comments** category under the General tab, are sent to the database by default. In some cases, you may not want to include the comments with the statement, for instance if your database does



not handle them. You can then enable the stripping of comments using the **Strip Comments when Executing** toggle item in the **SQL Commander Options** menu button in the SQL Commander toolbar or in the **SQL Commander->SQL Commander Options** main menu.



9.23 Using Client-Side Commands

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

9.23.1 Introduction

A client-side command is a DbVisualizer specific command prefixed with the at-sign (@). These commands are used in SQL scripts executed either in the SQL Commander in the DbVisualizer UI or in the command-line interface, dbviscmd. Client-side commands are used to control the execution of scripts and run for example export and import functionality without needing to interact with the DbVisualizer UI. The @mail command sends emails with attachment support, useful when using @export and then to mail the result of a query.

9.23.2 Commands reference

You can use these DbVisualizer client-side commands in your SQL scripts. (These commands are processed by DbVisualizer and never sent to the database as-is).

Command	Description
@cd <directory> @run <file> [<variables>]	Use these command to execute an external script .
@export	Use this command to export the result of a query .
@mail	Use this command to send emails and attach files .
@import	Import table data from CSV, Excel, and TEXT (fixed width column) files
@open <file_name>	Use this command to open the specified file in the associated tool. (Not supported in the command-line interface, dbviscmd).
@delimiter <new_delimiter>	Use this command to temporarily change the statement delimiter for a complex statement .
@call <function_or_proc>	Use this command to execute a function or procedure .
@beep	Use this command to emit a beep sound, e.g. to indicate a significant point in a script.
@sleep <milliseconds>	Use this command to halt the processing the specified number of milliseconds.
@echo <text>	Use this command to write to the Log tab .
@window iconify @window restore	Use these commands to lower (iconify) or raise (restore) the DbVisualizer main window.
@desc <table>	Use this command to show column information for a table. The table name may be qualified with a schema and/or database name.
@ddl <params>	Use this command to get the DDL for a database object .



Command	Description
@log <file_name> [spool close]	Use this command to write log messages to a named file. Examples <pre>@log /tmp/myLog.txt; @log /tmp/myLog.txt close; @log /tmp/allLog.txt spool;</pre> <ol style="list-style-type: none">1. Logs subsequent commands to the file /tmp/myLog.txt. If we are already logging to another file as the result of a previous @log command that log is closed2. Stops logging to the file3. Writes all log messages up to this @log command to the named file
@spool log <file_name>	This command is not supported any more. Please use the @log command instead.
@stop on error @stop on sqlwarning @stop on norows @continue on error @continue on sqlwarning @continue on norows	Use these commands to control what to do when a statement results in a warning or an error .
@set autocommit on @set autocommit off	Use these commands to control the Auto Commit state.
@set dryrun [off]	Offers a way to execute a script or part of a script without actually executing the command fully. As an example below no actual sleep will be done nor will the Select be executed. <pre>@set dryrun; @sleep 2000; select * from Actor; @set dryrun off;</pre> <p>The command is primarily used to debug scripts and check that script can actually be run. An exception to this is when used in connection with client-side import commands.</p>
@commit @rollback	Use these commands to explicitly commit or rollback updates.
@set serveroutput on @set serveroutput off	Use these commands to enable or disable output to the DBMS Output tab for Oracle databases.
@set maxrows <number> @set maxchars <number>	Use these commands to adjust the Max Rows and Max Chars limits for specific queries.
@set resultset name <name>	Use this command to name any following result set. When executed with a following SQL statement that produces a result set the tab showing this result set will be named using the <name> supplied as a parameter to the command. Example: <pre>@set resultset name MyEmployees; select * from EMPLOYEE;</pre> <p>DbVisualizer will for the example above show the result of the select in a tab named MyEmployees</p>

9.23.3 @export - Export query result

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

Instead of viewing query results in Result Set grids, you can export the result of one or more queries to a file. For very large results, this may be the preferred choice due to memory constraints.



To export a query result, create a script with

1. an **@export on** command,
2. an **@export set** command,
3. one or more queries,
4. an **@export off** command.

Here is a basic example:

```
@export on;
@export set filename="c:\Backups\Orders.csv";
select * from Orders;
@export off;
```

The **@export set** command takes a parameter name followed by an equal sign and a value. You can use the following parameters, where only filename is required and all names are case-insensitive:

Parameter	Default	Valid Values
AppendFile	false	true, false, clear (i.e. start with a new file for the first result and then append to it)
BinaryFileDir		Path for data files when BinaryFormat is set to File , see Exporting a Table for details. Note! Variables for column names must include the scope option when entered manually into a script, e.g. /Users/hans/exp/{dbvis-date} / {COUNTRIES scope=post} \$
BinaryFormat	Don't Export	Don't Export, Size, Value, Hex, Base64, File
BooleanFalseFormat	false	false, no, 0, off (you can specify custom entries separated by comma)
BooleanTrueFormat	true	true, yes, 1, on (you can specify custom entries separated by comma)
CLOBFileDir		Path for data files when CLOBFormat is set to File , see Exporting a Table for details. Note! Variables for column names must include the scope option when entered manually into a script, e.g. /Users/hans/exp/{dbvis-date} / {COUNTRIES scope=post} \$
CLOBFormat	Don't Export	Don't Export, Size, Value, File
CsvColumnDelimiter	\t (TAB)	The delimiter between columns in a CSV output. In addition to literals it can also be specified using Unicode Code Points as \u2656.
CsvIncludeColumnHeader	true	true, false
CsvIncludeColumnHeaderPerResult	false	true, false
CsvColumnHeaderIsColumnAlias	true	true, false
CsvIncludeSQLCommand	Don't Include	Don't Include, Top, Bottom
CsvSplitFileSize	-1	Split the result over multiple files if it is larger than the specified size, or -1 to never split. The size must be specified as <i>size</i> [g G m M k K]
CsvRemoveNewlines	false	true, false
CsvRowCommentIdentifier		
CsvRowDelimiter	\n	\n (UNIX/Linux/macOS), \r\n (Windows) (you may set this to any literal)
DateFormat	yyyy-MM-dd	See valid formats in Changing the Data Display Format document
DecimalNumberFormat	Unformatted	See valid formats in Changing the Data Display Format document
Destination	File	File, Clipboard, SQL Commander



Parameter	Default	Valid Values						
Encoding	UTF-8	Check supported encodings for all encodings. (Use the encoding in the Canonical Name for java.nio API column).						
ExcelAutoResizeColumns	false	true, false						
ExcelColumnHeaderIsColumnAlias	true	true, false						
ExcelFileFormat		If ExcelFileFormat is not specified, the file extension is used to set this parameter to one of the below <ul style="list-style-type: none"> • xls is for binary (or legacy) Excel max 65 535 rows • xlsx is the current and recommended OOXML format 						
ExcelIncludeColumnHeader	true	true, false						
ExcelIncludeSqlCommand	false	true, false						
ExcelIntroText		Any description						
ExcelSheetName		Used when exporting to excel. Sets the name of exported excel sheet.						
ExcelTextOnly	false	true, false. Convert numeric values to text in the Excel file if true.						
ExcelTextDateTime	true	true, false. Convert date, time and timestamp data to text in the Excel file if true.						
ExcelTitle		Any title						
Filename		The output file name for exported file. This parameter is required if Destination="file". If setting a relative filename the output path depends on the current working folder set by any @cd command.						
Format	Based on file extension, or CSV if none	CSV, HTML, XML, SQL, Excel, JSON. If Format is not specified, the file extension is used to determine the format. If there is no recognized file extension, CSV is used as the default.						
HtmlColumnHeaderIsColumnAlias	true	true, false						
HtmlConvertChars	true	true, false. Set to false if you have HTML code in the exported data, so that e.g. < and > characters are not converted to < and >;						
HtmlFooter	[Generated by: DbVisualizer version]	Any text to use in the document footer. Can be set to blank to remove the footer.						
HtmlIncludeSqlCommand	false	true, false						
HtmlIntroText		Any description						
HtmlPerTableHeader	E.g. <table border="1" data-bbox="501 1541 863 1666"> <tr> <td>Date:</td> <td>2017-05-31 16:48:23</td> </tr> <tr> <td>Columns:</td> <td>4</td> </tr> <tr> <td>Table:</td> <td>COUNTRIES</td> </tr> </table>	Date:	2017-05-31 16:48:23	Columns:	4	Table:	COUNTRIES	HTML code that describes the table. To fit into the rest of the HTML code, it must start with <tr> and end with </tr>. The pre-defined DbVisualizer variables can be used, e.g. \${dbvis-object}\$ to include the table name.
Date:	2017-05-31 16:48:23							
Columns:	4							
Table:	COUNTRIES							
HtmlTitle		Any title						
JSONColumnHeaderIsColumnAlias	true	true, false						
JsonSplitFileSize	-1	Split the result over multiple files if it is larger than the specified size, or -1 to never split. The size must be specified as size [g G m M k K]						
JSONStyle	Array	Array, Rows						
NumberFormat	Unformatted	See valid formats in Changing the Data Display Format document						
QuoteAllValues	false	true, false						
QuoteDuplicateEmbedded	true	true, false (quote char is the same as QuoteTextData)						



Parameter	Default	Valid Values
QuoteTextData	None	None, Single, Double
Settings		The path to an XML file containing all settings
ShowNullAs	(null)	
SqlAfterExportStmts		Any statements to include in the script after the SQL statements for the exported objects, e.g. <code>set foreign_key_checks = 1;</code>
SqlBeforeExportStmts		Any statements to include in the script before the SQL statements for the exported objects, e.g. <code>set foreign_key_checks = 0;</code>
SqlBeginIdentifier		Character to use to begin a quoted identifier. Note! To specify a double-quote, you must duplicate it since double-quote is also used to enclose the parameter value.
SqlBlockBeginDelim		String to use to begin an SQL block when exporting complex DDL statements using the <code>@ddl</code> command.
SqlBlockEndDelim		String to use to end an SQL block
SqlDelimitedIdentifiers	true	true, false
SqlEndIdentifier		Character to use to end a quoted identifier. Note! To specify a double-quote, you must duplicate it since double-quote is also used to enclose the parameter value.
SqlGroupBy	Object	Object, Statement. Set to Object to generate DROP, CREATE, INSERT, and ALTER statements (where applicable) for each exported object in turn. Set to Statement to group all statements of the same type together, e.g. first DROP statements for all exported objects, then CREATE statements for all exported objects, etc.
SqlIncludeAutoGeneratedValues	true	true, false. Set to false to exclude columns declared as AUTO_INCREMENT or IDENTITY in the INSERT statements.
SqlIncludeCreateDDL	false	true, false
SqlIncludeSQLCommand	Don't Include	Don't Include, Top, Bottom
SqlMultiRowInsert	false	true, false. If true Multiple rows are included in each INSERT statement. The number of rows to include in each INSERT statement is limited by the <code>SqlMultiRowInsertLimit</code> parameter.
SqlMultiRowInsertLimit	10	The maximum number of rows to include in a multirow INSERT.
SqlQualifier		Qualifier to use when qualifying table names. If not set, DbVisualizer tries to determine the schema and use it as the qualifier.
SqlQualifyColumnName	false	true, false
SqlQualifyObjectName	true	true, false
SqlRowCommentIdentifier	--	
SqlSeparator	;	Statement separator character.
SqlSplitFileSize	-1	Split the result over multiple files if it is larger than the specified size, or -1 to never split. The size must be specified as <code>size [g G m M k K]</code>
TableName		Can be set if DbVisualizer cannot determine the value for the \$ {dbvis-object}\$ variable
TimeFormat	HH:mm:ss	See valid formats in Changing the Data Display Format document
TimeStampFormat	yyyy-MM-dd HH:mm:ss.SSSSSS	See valid formats in Changing the Data Display Format document
XmlColumnHeaderIsColumnAlias	true	true, false



Parameter	Default	Valid Values
XmlIncludeSqlCommand	false	true, false
XmlIntroText		Any description
XmlStyle	DbVisualizer	DbVisualizer, XmlDataSet, FlatXmlDataSet

Here are a few examples using some of these settings.

Automatic table name to file mapping

This example shows how to make the filename the same as the table name in the select statement. The example also shows several select statements. Each will be exported in the SQL format. Since the filename is defined to be automatically set, this means that there will be one file per result set and each file is named by the name of its table.

```
@export on;
@export set filename="c:\Backups\${dbvis-object}%" format="sql";
select * from Orders;
select * from Products;
select * from Transactions;
@export off;
```



There must be only one table name in a select statement in order to automatically set the filename with the **`\${dbvis-object}%** variable, i.e if the select joins from several tables or pseudo tables are used, you must explicitly name the file.

The **`\${dbvis-object}%** variable is not substituted with a table name if using the `AppendFile="true/clear"` parameter.

Multiple results to a single file

This example shows how all result sets can be exported to a single file. The **AppendFile** parameter supports the following values.

- **true**
The following result sets will all be exported to a single file
- **false**
Turn off the append processing
- **clear**
Same as the true value but this will in addition clear the file before the first result set is exported

```
@export on;
@export set filename="c:\Backups\alltables.sql" appendfile="clear" format="sql";
select * from Orders;
select * from Products;
select * from Transactions;
@export off;
```

Using predefined settings

If you save settings when [exporting a table](#) or a [schema](#), you can use the **Settings** parameter to reference the settings file.

```
@export on;
@export set settings="c:\tmp\htmlsettings.xml" filename="c:\Backups\${dbvis-object}%" ;
select * from Orders;
select * from Products;
select * from Transactions;
@export off;
```

Limit the number of exported rows

You can use the `@set maxrows` command in combination with the `@export` command to override the [Max Rows](#) field value in the SQL Commander tab toolbar.



```
@set maxrows 10;
@export on;
@export set filename="c:\Backups\alltables.sql" format="sql";
select * from Orders;
select * from Products;
select * from Transactions;
@export off;
```

If Max Rows is set to a positive number, you can use the `@set maxrows` command to set it to `-1` to export all rows.

Don't Export

9.23.4 @mail - Send emails and attach files



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

- [Mail with DbVisualizer](#)
- [FileSource parameter - attaching files](#)
- [Body parameter](#)
- [Defining Mail Server Accounts](#)
- [MailTemplate parameter](#)
- [Usage Examples](#)
 - [Sending mail with inline attachment](#)
 - [Exporting to CSV Including csv in Mail body](#)
 - [All parameters on command line](#)
- [Expanding variables in the Body](#)

Mail with DbVisualizer

The `@mail` client side command is used to send emails from scripts executed in the SQL Commander and the command-line interface, `dbviscmd`. It offers full email setup including attaching multiple files and embedding data from files in the body of the email. There is also the capability to group settings for a mail server setup in a **Mail Server Account** enabling a simple reference for a mail server definition in the `@mail` command rather than a lot of parameters.

Here is a basic example with mail server parameters:

```
@mail
To="<recipient>"
Subject="<subject>"
Body="<body>"
MailServerHost="smtp.gmail.com"
MailServerPort="587"
MailServerUser="<user>"
MailServerPassword="<password>";
```

The following are the supported parameters for the `@mail` command:

Parameter	Default	Values
Subject		The subject
To		Defining the recipients of the mail. Multiple email addresses may be specified separated with comma: E.g.: John <john.doe@nowhere.com>, jane.doe@nowhere.com
Cc		Defining Cc recipients of the mail
Bcc		Defining Bcc recipients of the mail
From	Same as MailServerUser	This is by default the same address specified in MailServerUser. The mail server may reject sending from another email address depending how it is configured



ReplyTo	Same as From (if specified) or MailServerUser	An address to which replies should be sent
Body		The mail message body. Read more in Body parameter
FileSource		File attachment parameter Should specify the path to the file being attached. The path can be absolute or relative to the working directory: E.g: FileSource="/tmp/file.txt" Read more in FileSource parameter
FileSource_AttachType	Attach	Specifies how files are attached. Possible values: <ul style="list-style-type: none"> • Attach: Add the file as an attachment • Inline: Add the file as inline. Note that it is not supported to specify inline attachments and message body in the same email. • Embed. Since inline attachment and body text can not be specified at the same time DbVisualizer adds support to include text file content from multiple files in the message body. By setting the AttachType to Embed DbVisualizer will not also attach the file. More about this in the section about specifying message content (Body)
FileSource_ContentType		Optional, determined by the type of file attached.
MailHeaders		For adding mail headers to the mail. E.g: MailHeaders="X-Priority=""1"" The above mail header will result in a mail marked as important. For information about this and other headers please use online resources as the interpretation of mail headers may differ between different mail clients
MailTemplate		Offers the possibility to use a file as a template for the mail. Read more in MailTemplate parameter
The following parameters are used to setup the mail server connection		
MailServerHost		The host name or IP address of the outgoing mail server
MailServerPort		The port number of the outgoing mail server
MailServerUser		The user account for the outgoing mail server
MailServerPassword		The user account password for the outgoing mail server. Note that the password is in plain text. The solution is to setup a mail server account
MailServerSecurity	None	For connecting to the mail server securely. Possible values are: <ul style="list-style-type: none"> • None (secure connection not enabled) • STARTTLS • SSL
MailServerProperties		Comma separated list of properties sent to the mail server. Eg.: MailServerProperties="mail.smtp.starttls.enable=""true"" mail.smtp.auth=""true"" Note the double-quotes of the values. I.e=""true"" is correct. Using ="true" would render an error
MailServerAccount		Refers to the name of a mail server account defined in Tools->Tool Properties->Mail Server Account. By defining a mail server account, MailServerAccount is the only parameter you will need when using @mail. Read more in Defining Mail Server Accounts



FileSource parameter - attaching files

The FileSource parameter should identify the path to an absolute or relative file that will be attached to the email. Files may be attached as a regular attachment, inline (for content and mail clients supporting it), and embedded as plain text (useful for text data).

Example of basic use resulting in the files being attached:

```
FileSource="C:\Data\file1.csv" FileSource_AttachType="Embed"  
FileSource1="C:\Data\file2.xlsx"  
FileSource2="C:\Data\file3.html" FileSource2_AttachType="Attach";
```

Restrictions with AttachType:

- If using AttachType="Inline" there must only be a single file attached. If multiple files, these will be attached
- Having Body specified and AttachType="Inline" is not allowed. The file will then be attached
- AttachType="Inline, Embed" is not valid. File will then be embedded.
- A text file may both be attached and embedded in the body of the email, use AttachType="Attach, Embed"

One more FileSource related parameter is the FileSource_ContentType. Use this to specify a MIME content type representing the file being attached.

For embedded files, check the next chapter for information how to specify where in the body content it should be inserted.

Body parameter

The Body parameter specifies the plain text content of the mail. With variables (place holders) any files with AttachType="Embed" can be specified which when the email is sent is replaced with the file content. In addition there are a collection of variables that can be included in the body related to the script execution. Read more about these in [Expanding variables in the Body](#).

Example:

```
FileSource="C:\Temp\sales.csv"  
FileSource_AttachType="Embed"  
Body="Dear Mgmt,  
  
Please find the requested product information:  
  
{{FileSource}}  
  
/Staff"
```

Sample output:

```
Dear Mgmt,  
  
Please find the requested product information:  
  
id brand length width hp weight  
1 Audi A4 48 76 28 44  
2 Audi A6 96 6 51 86  
  
/Staff
```

Defining Mail Server Accounts

Sending an email in DbVisualizer requires mail server related information that includes userid, password, server name, port, etc. These parameters are prefixed "MailServer" for the @mail command. Instead of specifying these as parameters a **Mail Server Account** can be defined in **Tools->Tool Properties** and under the **Mail Server Accounts** category.



Mail Server Accounts

Here you can set up your Mail Server Accounts. The accounts can be used when using the parameter **MailServerAccount** for the **@mail** Client-Side command.

+ * -

Name	Host Name	User Name
Private @gmail	smtp.gmail.com	kirk55@gmail.com
bigcorp.com	smtp-mail.outlook.com	kirk@bigcorp.com

Name: Private @gmail

Description: Use this to setup a Gmail SMTP server. Note that you may need to set the "Allow less secure apps" for your gmail account, which is done in the gmail web interface.

Host Name: smtp.gmail.com Port: 587

User Name: kirk55@gmail.com Password: ●●●●●●●●

Connection Security: STARTTLS

Advanced Properties: (1)

Name	Value
mail.smtp.auth	
mail.smtp.auth.digest-md5.disable	
mail.smtp.auth.login.disable	
mail.smtp.auth.mechanisms	
mail.smtp.auth.ntlm.disable	
mail.smtp.auth.ntlm.domain	
mail.smtp.auth.ntlm.flags	
mail.smtp.auth.plain.disable	
mail.smtp.auth.xoauth2.disable	
mail.smtp.connectiontimeout	
mail.smtp.dsn.notify	
mail.smtp.dsn.ret	
mail.smtp.ehlo	
mail.smtp.localaddress	
mail.smtp.localhost	
mail.smtp.mailextension	
mail.smtp.noop.strict	
mail.smtp.proxy.host	
mail.smtp.proxy.port	
mail.smtp.quitwait	

connect.
(properties for more information).
defined using the **MailServerProperties** parameter.

OK Apply Cancel

Use the left most button **Add new ...** to add a new account. Note choosing one of the top ones from the menu will create a new account from a named template. The template contains predefined values for well known mail servers. E.g the one named **Gmail** defines a temple for accessing an existing gmail account. Unless google changes connection data for gmail the only change that would be required is changing the **User Name** and **Password**.

The data entered for Mail Server Account are

Name	The name of the account. Example: "My Gmail" Corresponds to the MailServerAccount parameter for the @mail command.
Description	Optional short description of the mail server account



Host Name	The name or IP address of the mail server. Example: smtp.gmail.com Corresponds to the MailServerHost parameter for the @mail command.
Port	The port number of the mail server. Example: 587 Corresponds to the MailServerPort parameter for the @mail command.
User Name	The mail account user name. Example: someuser@gmail.com Corresponds to the MailServerUser parameter for the @mail command.
Password	The mail account password. Example: "password for someuser@gmail.com " Corresponds to the MailServerPassword parameter for the @mail command.
Connection Security	For connecting to the mail server securely. Example: STARTTLS Corresponds to the MailServerSecurity parameter for the @mail command.

Testing a Mail Server Account

By selecting an account in the list and pressing the **mail icon** in the toolbar it is possible to send a test mail.

Generating client side commands @mail

Select an account in the list and press the copy icon in the toolbar. Two menu alternatives exist:

"**Copy to clipboard as @mail command with all parameters**" generates a @mail command with all mail server parameters as defined for the mail server account.

"**Copy to clipboard as @mail command with MailAccountServer parameter**" generates a @mail command with only the **MailAccountServer** parameter.

MailTemplate parameter

The **MailTemplate** parameter is used to specify a template file for the final email and some of the settings such as **To, Subject, Body**, etc.

Note:

The **Body** parameter must be defined as the last parameter in the template. Please see the section about [Specifying Mail Content](#) for a description of how to specify the **Body**.

Any parameters defined for the @mail command line will override the ones in the template. Example:

```
@mail MailTemplate="template.txt"
Subject="A better subject"
MailServerAccount="gmail";
```

And the **template.txt** file:

```
To: jane.doe@somewhere.com
Subject: Hey take care of this!
Body: The report
of the last ...
```

The mail will be sent to "**jane.doe@somewhere.com**" and the subject of the mail will be "Hey take care of this!".

Usage Examples

Sending mail with inline attachment

The following script exports an HTML file, sends an email with that file attached as inline (most email clients will render the HTML in the body of the email). Note that Body parameter is not defined.



```
@export on;
@export set filename="g_actors.html" Format="HTML";
SELECT * FROM ACTOR WHERE last_name LIKE 'G%';
@export off;

@mail Subject="The actors" To="first.last@somewhere.com" MailServerAccount="gmail"
FileSource="g_actors.html" FileSource_AttachType="Inline";
```

Exporting to CSV Including csv in Mail body

Please see [Export and Mail example](#).

All parameters on command line

```
@mail To="someone@somewhere.com"
Subject="The subject"
Body="The body"
MailServerHost="smtp.gmail.com"
MailServerPort="587"
MailServerUser="first.last@gmail.com"
MailServerPassword="password"
MailServerSecurity="STARTTLS";
```

Expanding variables in the Body

The body of the mail can contain references to place holders with values supplied by DbVisualizer during execution of the script in which @mail is executed. The values are inserted using the syntax: **{{place holder}}**

Example:

```
@mail Body="Hi, Number of records exported where {{dbvis-current.rowCount}} ....."
```

The above example shows how we are referring the property `dbvis-current.rowCount`. `dbvis-current` refers to the current total result.

Following is a list of accessible variables.

Variable/property	Description
dbvis-last properties. Properties referring the result of the command executed just before the @mail command	
{{dbvis-last.statusCode}}	The result status code
{{dbvis-last.isError}}	"true" if the last command failed
{{dbvis-last.executionMetrics.elapsed}}	The execution time
{{dbvis-last.executionMetrics.begin}}	Execution start time
dbvis-current properties. These refers the script execution up to but not including the @mail command in which they are used	
{{dbvis-current.executionCount}}	Number of statements/commands executed
{{dbvis-current.schemaChanged}}	"true" if the schema has changed
{{dbvis-current.catalogChanged}}	"true" if the catalog has changed
{{dbvis-current.updateCount}}	The number of updated records
{{dbvis-current.numberOfResultSetsFetched}}	The number of result sets fetched
{{dbvis-current.rowCount}}	The number of records returned
{{dbvis-current.emptyResultSetsCount}}	The number of empty result sets fetched
{{dbvis-current.successCount}}	The number of statements/commands successfully executed
{{dbvis-current.errorCount}}	The number of statements/commands failed
{{dbvis-current.warningCount}}	The number of statements/commands with result warning



Variable/property	Description
{{dbvis-current.stoppedOnErrors}}	"true" if the execution of the script was stopped on errors
{{dbvis-current.stoppedOnSQLWarning}}	"true" if the execution of the script was stopped because of SQL Warnings
{{dbvis-current.stoppedOnNoRows}}	"true" if the execution of the script was stopped because of result returned no rows
{{dbvis-current.executorWasInterrupted}}	"true" if the execution of the script was stopped due to user interrupt
File attachment related variables	
{{FileSource}}	Replaced in runtime with the content of the file FileSource is referring to

The use of variables is illustrated in the following example.

Export and mail Example

```
1 @log "logfile.txt";
2
3 @export on;
4 @export set filename="g_actors.csv" Format="CSV";
5 SELECT * FROM ACTOR WHERE last_name LIKE 'G%';
6 @export off;
7
8 @export on;
9 @export set filename="f_contry.csv" Format="CSV" CsvIncludeColumnHeader="false";
10 SELECT country FROM COUNTRY WHERE country LIKE 'F%';
11 @export off;
12
13 @mail Subject="Last report" To="first.last@somewhere.com" MailServerAccount="gmail"
14 Body="Hi,
15 The total export took: {{dbvis-current.commandElapsedExecTime}} sec and {{dbvis-current.rowCount}}
16 records where exported.
17 Actors with a last name starting with 'G':
18 {{FileSource}}
19
20 Countries starting with 'F':
21 {{FileSource1}}
22
23 The log file is attached.
24 "
25 FileSource="g_actors.csv" FileSource_AttachType="Embed"
26 FileSource1="f_contry.csv" FileSource1_AttachType="Embed"
27 FileSource2="logfile.txt";
```

9.23.5 @import - Importing data



Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

- [Importing data - Example](#)
- [The @import commands](#)
 - [@import on](#)
 - [@import set](#)
 - [@import parse](#)
 - [@import target](#)
 - [@import execute](#)
- [Examples](#)
 - [Selecting data to import and mapping columns](#)
 - [Overriding analysed type information](#)
 - [Importing fixed column width input data \(TxtColumns parameter\)](#)
 - [The TxtColumns parameter](#)



- [Importing Excel data](#)
- [Continuing an export that has failed](#)
- [Testing an import - Dry Run](#)


Instead of using the GUI to import data you can use client-side commands to import data, i.e **@import**. This enables you to use the DbVisualizer command-line interface to automate your imports and utilise other client-side commands such as @export, @mail, among others. Import data using the @import command supports the following formats:

- **Excel**
xlsx or the legacy xls format
- **XML**
The same XML formats that can be exported with DbVisualizer
- **JSON**
The same XML formats that can be exported with DbVisualizer
- **CSV**
Importing CSV files supports a lot of configurations such as multi-symbol column separator, multi-line values, etc.
- **TXT**
[Importing fixed width text files](#)

These are client-side commands for @import are:

@import on	The command starts an import session
@import set	Set parameters for the import
@import parse	Parse and convert the source data to an intermediary format, and analyze the data.
@import target	Identify the target table and what target columns should be used
@import execute	Runs the export

The import process is explained by the following figure.



The **@import parse** step (1) lays the foundation for the database import as it based on the source file format (csv, json, xlsx, etc), parses the data to an intermediary and internal file. This file is then analyzed in order to detect widths, data types and their sizes based on the data, row and cell references back to the source file, and a lot more.

The intermediary format stores the input data as **Records** associated with information from where the data **originates**.

Once the data has been parsed some basic tests are performed to see if the properties of the data is compatible with the **target table** properties. E.g. if the size of the input data will fit the targeted table columns. This done when when the **@import target** command is run (2).

Final step of an import is to **execute** (3-4) the actual operations towards the database to import the data. I.e. **execute** the INSERT statements. Any failures in the import will include specification of where in the source file the invalid data originates.

Following is a complete example where a simple CSV file is imported to a Target table Expenses.

Importing data - Example

The example shows how data about fruits included in a CSV file **fruits.csv** is imported into a database table **fruits**.

The example shows a minimal example where the columns of the CSV file is mapped directly to the table columns.

1	ID, FRUIT, PRICE
2	1, Banana, 1.22
3	2, Apple, 0.35
4	3, Orange, 0.55

The SQL needed to import the file



```

1 @import on;
2 @import set ImportSource="fruits.csv";
3 @import parse;
4 @import target Table="fruits";
5 @import execute;
6 @import off;

```

Running the import script in DbVisualizer

Time	Status	Command	Exec	Fetch	Rows	Message
10:12:18	STARTED					Executing for: 'MySQLServer (mac 2)' [MySQL], I
10:12:18	INFO					Physical database connection acquired for: MySQ
10:12:18	SUCCESS	@import on	0.093			OK
10:12:18	SUCCESS	@import set	0			OK
10:12:18	SUCCESS	@import parse	0.156			Parsed 4 records
10:12:18	SUCCESS	@import target	0.079			OK
10:12:18	SUCCESS	@import execute	0.063			3 OK, Handled 4 records. Inserted: 3 Skipped: 1
10:12:18	SUCCESS	@import off	0			OK
10:12:18	SUCCESS					Import Succeeded...
10:12:18	FINISHED		0.391	0	3	Success: 6

As seen in the screen-shot above 3 records were inserted and and 1 was skipped (the header).

Read further on in the guide for how you can tailor your import using the different parameters of the import commands.

The @import commands

@import on

The **@import on** command initialises the import session. When a client-side command import session is started an **output folder** is created where DbVisualizer generates data representing intermediate results of the import. The output folder is created under a root folder (importresults) in the DbVisualizer preferences directory. The name of the folder is generated to be unique.

These folders are automatically cleaned by DbVisualizer on regular basis.

Note: Normally there is no need to specify any parameters to the **@import on** command. Default values should be sufficient for most uses.

Parameter	Default	Valid Values
ImportResultRoot	PREFSDIR/importresults	The root folder for parsing results and other temporary files produced by the import session. Note: Any results produced in this directory will automatically be removed on regular basis.



Parameter	Default	Valid Values
ImportResultDir	Automatically generated as a sub folder to <i>PR</i> <i>EFSDIR</i> /importresults	The path to put the DbVisualizer import results. If the path is an absolute path the results are stored in this folder. If it's not an absolute path it is assumed that it's path relative to the ImportResultRoot The folder is created when import is started. If the folder already exists, the import fails unless the Clean parameter is also used. If none of the ImportResultRoot/ImportResultDir is specified DbVisualizer will create a new uniquely named directory for every import session.
Clean	false	If true, the ImportResultDir is cleaned before import. If false import fails if directory exists. No need of specifying this parameter if ImportResultDir is not specified.
ContinueImportFile		Specified if you are continuing an import. See chapter about Continuing an Import .

Example 1

```
@import on ImportResultDir=/tmp/myimport Clean="true";
```

Import results are stored in the folder /tmp/myimport. Any existing folder /tmp/myimport will be deleted/cleaned.

Example 2

```
@import on ImportResultDir="newimport";
```

Import results are stored in *PR**EFSDIR*/importresults/newimport. If this directory exists the import will fail.

@import set

The **@import set** command takes a parameter name followed by an equal sign and a value, e.g. parameter="value". You can use the following parameters, where **ImportSource** is the only required parameter. All names are case-insensitive. **Note** that you may use multiple @import set commands but the first one must include the parameter **ImportSource** setting the input data to import.

Parameter	Default	Valid Values
BooleanFalseFormats	false, no, 0, off	Comma separated string of values that should be interpreted as boolean false.
BooleanTrueFormats	true, yes, 1, on	Comma separated string of values that should be interpreted as boolean true
CsvColumnDelimiter		Can be used to override the auto detection by specifying a column delimiter. <code>CsvColumnDelimiter=";"</code> The most common column delimiters are auto detected.
CsvColumnDelimiterType	Auto Detect	Valid values are: String or Auto Detect . If only <code>CsvColumnDelimiter</code> is specified in the command <code>CsvColumnDelimiterType</code> is set to String



Parameter	Default	Valid Values
CsvTextQuotedBetween	None	<p>Having data quoted is needed if the data itself contains the delimiter use to separate columns, special characters such as tabs, multiline separators, etc.</p> <p>The CsvTextQuotedBetween parameter is used to specify the identifier which is used to enclose this type of data. Please note that there may not be multiple text quote identifiers in the same import source.</p> <p>Any character is valid to use. Some additional aliases can be used to make the values more clear.</p> <ul style="list-style-type: none"> • Single Equal to specifying the value as "'" • Double Equal to specifying the value as """". Note that a " character need to be escaped with an additional " • None Equal to specifying the value as "" (The default) <p>Example 1: For the following CsvTextQuotedBetween="Single" is used:</p> <pre>1 'Apple' 'Round fruit'</pre> <p>Example 2: For the following CsvTextQuotedBetween="Double" is used:</p> <pre>2 "Lemon" "Yellow fruit"</pre> <p>Example 3: For the following CsvTextQuotedBetween=" " is used:</p> <pre>3 Lemon Yellow fruit </pre> <p>If you have quoted data in your import source and do not specify CsvTextQuotedBetween, the data will be detected as text data.</p>
DateFormat	yyyy-MM-dd	See valid formats in Changing the Data Display Format document.
DecimalSeparator	.	The decimal separator to use when parsing decimal numbers
Encoding	As set in Tool Properties	The file encoding to use when parsing the file to import
ErrorIncludeStackTrace	false	true/false If true the Java stack trace of any exception will be included in error messages.
ExcelCellPolicyError	SKIP	Defines what to do for a formula cell where the cached value indicates an error. Possible values: EMPTY: Set the cell to blank SKIP_ROW: Skip the complete row ERROR: Produce an error for the cell/row TO_STRING: Include the error as data.
ExcelSheetId	0	An id specifying the sheet id of a workbook when importing from xls/xlsx files. First sheet has id = 0 Either this parameter or ExcelSheetName parameter can be used. Not both.
ExcelSheetName		A name specifying the sheet name of a workbook when importing from xls/xlsx files.
FailOnConvertFailure	false	If true, the Import will fail if data conversion fails.
FailOnNoColumnsFoundFailure	false	If true, the Import will fail if we found no columns during continue import
FailOnParseFailure	false	If true, the Import will fail if we got a failure during parsing of the source data.



Parameter	Default	Valid Values
HeaderStartRow	0	The row index of the row where the Header starts. If set to a number x the StartRowOfData parameter is automatically set to x +1 . The default value 0 indicates that the source data has no header information.
ImportSource		A path to the file to import. Must be included in the first @import set command. The path is an absolute path or a relative path to the script location. If a @cd command has been run before the @import set command a relative path is relative to the @cd directory
MaxRows	-1	The Maximum row to parse/import
ShowNullAs		The value that should be considered as NULL. E.g. (null)
SkipEmptyRows	true	true/false
SkipHeader	true	true/false If set to false the header is also imported.
SkipRowsStartingWith		String
StartRowOfData	1	The row index of the row where data starts. See also HeaderStartRow.
ThousandSeparator	,	The thousand separator to use
TxtColumns		Used when fixed columns text files are imported. Example 0, 4 . For detailed syntax of the TxtTrim parameter please see the example Importing fixed column width input data
TxtTrim	true	If true, the column data retrieved when importing fixed column text files is trimmed.
TimeFormat	HH:mm:ss	See valid formats in Changing the Data Display Format document.
TimeStampFormat	yyyy-MM-dd HH:mm:ss.SSSSS	See valid formats in Changing the Data Display Format document.

Example 1

```
@import set StartRowOfData="5" SkipRowsStartingWith="//";
```

We are starting to import data from row 5 of the source data file and skipping rows starting with "//".

Example 2

```
@import set HeaderStatRow="1";
```

The input data has header information at row 1. We are starting to import data from row 2. As StartRowOfData is not explicitly set is automatically set to 2.

@import parse

This command does all the parsing and analysing of input data.

Example

```
@import parse;
```

The source data file is parsed. As a result result are stored in the location pinpointed by ImportResultDir.

Example output from the @input parse command:



Parsed 5 records. Columns in source: 2 using ',' delimiter

INDEX	NAME	TYPE	NULLABLE	FROM ROW
0	NAME	String(6)	No	2
1	BIRTHDAY	String(16)	No	4

Total bytes: 73 B

The information shows the number of parsed records along with the number of columns found. If the parsed file was a CSV file the used delimiter is printed.

For each column the following information is printed:

- **INDEX:** The index of the column
- **NAME:** If `@import set` parameter `HeaderStartRow` was specified and header information was extracted the extracted column name is printed.
- **TYPE:** The type of data found. The size declaration (E.g. **16**) represents the longest string found.
- **NULLABLE:** If the column is nullable or not.
- **FROM_ROW:** From which row in the source file the data type (e.g. String) was determined. This number serves as a hint to investigate source data when an unexpected type is analyzed.
E.g. The column name **BIRTHDAY** in the source data indicates that this data should be a date. By investigating the source data at row 4 you may find the reason why the column was analyzed as String column.

@import target

This command is responsible of all preparation of the target table prior to import. This includes dropping, truncating, deleting from and creating the table.

When this is executed a check is done if the input data will actually fit the table. This is done by comparing of the analyze result with the specified target and column mapping. Depending on the parameters the check is performed at different occasions. Parameters for this command are:

Parameter	Default	Valid Values
Catalog		The target table Catalog
CleanData		Specifies if data should be cleared before import. Values Drop The table is dropped before import. If this is used either the <code>CreateTableSQL</code> or <code>CreateTableSQLFile</code> must be specified Clear The table is cleared. Either through the use of <code>TRUNCATE</code> or <code>DELETE</code> . Default method is <code>TRUNCATE</code> . Override the default Clear method by specifying the parameter ClearTableMethod . Before the table is cleared the check of input data towards the target table is performed.
ClearTableMethod		Truncate or Delete.
ColumnMapping		Specifies mapping of source columns to target columns. The default is to import the source columns to the target table column by index. First column in source is import in first column in table. To specify another order or to ignore certain columns use <code>ColumnMapping</code> parameter. Syntax: <code>ColumnMapping="<src col>=<tgt col>, <src col=tgt col>, ..."</code> Source column can be identified by index starting with 0 or by its name. Target column can be identified by index starting with 1 or by its name. Example: <code>ColumnMapping="0=2, 1=3"</code> or <code>ColumnMapping="id=no, color=col"</code>
ColumnMappingFile		A reference to a file containing the column mapping.
CreateTableSQL		The SQL needed to create the table to import too. This parameter or the <code>CreateTableSQLFile</code> parameter is required if <code>CleanData="Drop"</code> is specified.
CreateTableSQLFile		A file reference to a file containing the SQL to create the table.
DropTableSQL		The SQL for dropping the table
FailOnDropFailure	false	If true, the Import will fail if the <code>DROP</code> table statement fails.



Parameter	Default	Valid Values
Schema		The target table schema to import to
SkipValidateColumns		A comma separated list of target column names for which validation shall not be done. Example: SkipValidateColumns="Acol,Bcol"
SkipValidateColumnNumbers		A comma separated list of target column numbers for which validation shall not be done. Example: SkipValidateColumnNumbers="1,5"
SkipValidateJdbcTypes		A comma separated list of JDBC type names for which validation shall not be done. Example: SkipValidateJdbcTypes="INTEGER, TINYINT, VARCHAR"
Table		The target table to import to
UseDelimitedIdentifiers	false	true or false If true object identifiers will be delimited.

Some examples

Example 1

```
@import target Table="MyTable" ColumnMapping="0=ID,2=NAME" CleanData="Drop"
CreateTableSQL="CREATE TABLE MyTable (id SMALLINT, name VARCHAR(45))";
```

Target table is the "MyTable" table. The table is dropped and recreated before import. We are mapping the first column of the input data to the target column "ID" and the third column to the target column "NAME".

As the table is dropped we need to supply the DDL/SQL for creation of the table.

Example 2

```
@import target Table="MyTable" ColumnMapping="2=NAME" CleanData="Clear"
```

The table is cleared before the import. The clear method is determined by DbVisualizer. For Databases supporting this Truncate is used.

@import execute

Run the actual import.

Parameter	Default	Valid Values
BatchImport	true	true or false Using batch import will significantly improve the import speed. Note though that batch import may not be supported by all databases or JDBC drivers. In error situations it is also a good idea to switch off batch import.
BatchSize	100	For every 100 (or specified) number of rows being inserted, DbVisualizer will run a commit.
FailOnInsertFailure	false	If true, the Import will fail if an INSERT statement towards the database fails

Examples

```
@import execute BatchImport="false";
```

Run the import. Don't import using batch import

Examples

Selecting data to import and mapping columns

CSV File delimited by exclamation mark "!".

```
Volvo!XC90
BMW!F32 4 Series
Volvo!XC60
Mercedes!C197 SLS AMG
```



Note that the first column of the CSV file is the brand name (Volvo) of the car. The table we are importing to have the columns in opposite order model, brand. I.e. we need to Map the columns.

```
CREATE TABLE carmodel (model VARCHAR(50), brand VARCHAR(50));

@import on;
@import set ImportSource="cars.csv" CsvColumnDelimiter="!" SkipRowsStartingWith="BMW";
@import parse;
@import target Table="carmodel" ColumnMapping="0=brand,1=model";
@import execute;
```

Parameters used

CsvColumnDelimiter="!" specifying that the data is delimited by the character '!'.

SkipRowsStartingWith="BMW" We are not importing BMW cars

ColumnMapping="0=brand,1=model" Column **0** of the CSV file is mapped to the **brand** column of the table. Column **1** is mapped to the **model** column.

The table carmodel content after import:

model	brand
XC90	Volvo
XC60	Volvo
C197 SLS AMG	Mercedes

Overriding analysed type information

When an input file is parsed DbVisualizer analyses the data to determine data types of the input data. The algorithm for this is quite coarse. DbVisualizer does offer a way to override the analysed data type.

CSV data

1	NAME,BIRTHDAY
2	August, "Sat, 21 Jul 1962"
3	Sven, "Fri, 21 Jan 1972"
4	Lotta, "NoData"
5	Bert, "Sat, 21 Jul 1962"

Note that the birthday of "Lotta" is "NoData" which is of course not a valid date. When DbVisualizer parses/analyses the data, it will come to the conclusion that the BIRTHDAY column is a String.

The result of @import parse will contain a table describing information about the data that was parsed.

Parsed 5 records. Columns in source: 2 using ',' delimiter

INDEX	NAME	TYPE	NULLABLE	FROM ROW
0	NAME	String(6)	No	2
1	BIRTHDAY	String(16)	No	4

Total bytes: 73 B

As mentioned earlier you can see that column BIRTHDAY has been interpreted as a String. This was found examining row 4 (FROM ROW column is 4).

In connection with inserting this column in the database DbVisualizer would insert/set this as a string. This would result in total import failure and no rows would be inserted in the database.

This may be addressed by overriding the analysed type for BIRTHDAY (String) and set the type to date.

The SQL



```

1 CREATE TABLE birthdays (name VARCHAR(40), birthday DATE);
2
3 @import on;
4 @import set ImportSource="birthdays.csv" CsvTextQuotedBetween="Double" DateFormat="EEE, d MMM yyyy"
   HeaderStartRow="1";
5 @import parse;
6 @import target Table="birthdays" ColumnMapping="0=name,1(date)=birthday";
7 @import execute;
8 @import off;

```

Parameters

- DateFormat="EEE, d MMM yyyy"
Defining the format to be able to interpret the dates in the CSV file.
- ColumnMapping="0=name,1(date)=birthday"
Note the **1(date)=birthday** where we are mapping the column with index 1 to the target column birthday. The **(date) part specifies that column 1 should be interpreted as a date.**

The result of the import using the script above is that 3 rows are imported (August, Sven and Bert). The row representing Lotta is reported as a failure as indicated below.

```

1 Record affected, Record: 0 originating at row: 4
DataRecordException: Convert error, Column: BIRTHDAY at index: 1
DataTypeConversionException: Value is 'NoData'. Not a valid date format. Valid format: 'EEE, d MMM yyyy'

```

Importing fixed column width input data (TxtColumns parameter)

Text File

```

001  APPLE
002  LEMON
003  ORANGE

```

The SQL Script

```

@import on;
@import set ImportSource="fruitlist.txt" TxtColumns="0,6";
@import parse;
@import target Table="fruitslist" Catalog="test";
@import execute;

```

The parameter **TxtColumns** parameter specifies the column character positions. In this case first column starts at character position 0 and the second column starts at character position 6.

The resulting imported table is

```

id name
-- -----
1  APPLE
2  LEMON
3  ORANGE

```

Note how "LEMON" is imported without preceding blanks. This is because column values are trimmed (TxtTrim parameter default is true).

The TxtColumns parameter

The TxtColumns parameter supports a number of syntaxes as explained in the examples below.

An example when parsing a row "AAA BBB CCC"

TxtColumns parameter	Yields extracted columns
0-2, 4-5	"AAA" "BB"
1-3, 8-9	"AA" "C"

Omitting the end index (as in the SQL script above)



TxtCols parameter	Yields extracted columns
0, 4, 8 (same as 0-3,4-7, 8-end of line)	"AAA" "BBB" "CCC"
1, 8-9 (same as 1-7,8-9)	"AA BBB" "C"

Using the "+" sign

TxtCols parameter	Yields extracted columns
0+3, 4+3, 8 (Same as 0-3,4-7, 8-end of line)	"AAA" "BBB" "CCC"
0+7, 8+1 (Same as 0-7, 8-9)	"AAA BBB" "CC"

Importing Excel data

Excel file

```
A  B
-- --
1  A
2  #DIV/0!
3  C
```

Note how row 2 column B has the value **#DIV/0!**. This value represents a case where a cell is a calculated using formula where the calculation is producing an error.

SQL Script to import

```
CREATE TABLE exceldata (id INT, value VARCHAR(50));

@import on;
@import set ImportSource="excelData.xlsx" ExcelSheetName="mydata" ExcelCellPolicyError="SKIP_ROW";
@import parse;
@import target Table="exceldata";
@import execute;
@import off;
```

Parameters used

ExcelSheetName="mydata"

Specifying that the sheet named mydata is the sheet to import.

ExcelCellPolicyError="SKIP_ROW";

Specifies that if we find a formula that produced an error we should skip the complete row.

Resulting Table

```
id value
-- -----
1  A
3  C
```

Note that row 2 is not imported as we instructed by ExcelCellPolicyError="SKIP_ROW";

Continuing an export that has failed

If any of the input data cannot be imported DbVisualizer will keep track of this. This is done by storing the failed data in a specific errorRecords.drec file in the directory where the import process stores its intermediate results (See ImportResultRoot parameter).

Following is an example were the export fails. It also shows how to import the failed data again. Specifically, the first import fails as Clementine is a name that is too long to fit in the target table column.



```
ID, FRUIT, PRICE
1, Banana, 1.22
2, Clementine, 0.35
3, Orange, 0.55
```

First Import SQL Script

```
CREATE TABLE fruits (id SMALLINT, name VARCHAR(6), price DECIMAL(10,2));

@import on Clean="true" ImportResultDir="/tmp/importContinueFirstImport";
@import set ImportSource="fruits.csv" HeaderStartRow="1";
@import parse;
@import target Table="fruits" SkipValidateJdbcTypes="VARCHAR";
@import execute;
@import off;
```

Note: the table definition for the fruit table defines the column name to be **VARCHAR(6)**. The input data **"Clementine"** will not fit there.

Parameters used

ImportResultDir="/tmp/importContinueFirstImport" We get our results in this directory. Makes it easy to refer in the second import script.

SkipValidateJdbcTypes="VARCHAR" Tells DbVisualizer not to validate VARCHAR columns. This is done for the purpose of this example. If not specified, the import would stop before any data has been imported.

When running this import the Database used in the example (MySQL) will fail when the import tries to insert the data row 3 as Clementine will not fit the column. The Failure printed in the DbVisualizer Log for this looks something like:

```
1 Record affected, Record: id = 0 originating at row: 3
DataRecordException: Error when importing data.
MysqlDataTruncation: Data truncation: Data too long for column 'name' at row 1
```

Note that the source data is pinpointed as **originating at row: 3**.

The Table fruits content after import.

```
id name price
-- -----
1 Banana 1.22
3 Orange 0.55
```

Second import SQL Script

```
ALTER TABLE fruits MODIFY COLUMN name VARCHAR(20);

@import on ImportResultDir="/tmp/importContinueSecond" UseImportFile="/tmp/importContinueFirstImport/
errorRecords.drec" Clean="true";
@import execute;
@import off;
```

The ALTER statement is dealing with the root cause why the import failed. The name column was too small.

Note that when continuing an import, the commands **@import set** and **@import target** is not specified. The settings and target from the old import is used.

Parameters used

ImportResultDir="/tmp/importContinueSecond": Specifying a separate directory for the results

UseImportFile="/tmp/importContinueFirstImport/Results/errorRecords.drec" Pinpointing the file containing the data that contains the data that could not be imported.

The Table fruits content after second import.

```
id name price
-- -----
1 Banana 1.22
3 Orange 0.55
2 Clementine 0.35
```



Testing an import - Dry Run

The client-side import offers a way to run the import script to perform all client side data validation without changing anything in the database. This is done using the **@set dryrun** command.

Note that when running the import, without dry run, the import may fail nevertheless due to checks on the database side. E.g. primary- or unique key constraint checks.

```
@import set ImportSource="fruits.csv";
@import parse;
@set dryrun;
@import target Table="fruits" CleanData="Clear";
@import execute;
@set dryrun off;
@import off;
```

When running the script, no actual clearing of the table will be done as the parameter **CleanData** indicates. Nor does the **@import execute** lead to any rows being inserted in the database.

Since there is a **@set dryrun** command prior to the commands no changes to the database table will be performed.

9.24 Parameterized SQL - Variables and Parameter Markers

A useful feature in the SQL Commander is to use variables or parameter markers in SQL scripts. Variables are used to express that certain parts of the SQL should be replaced with values when the SQL is executed. If you use a script to perform repetitive tasks, such as creating a user and granting permissions, just insert variables for the user name and permissions to grant in the script and DbVisualizer will prompt for the values at execution.

In addition to DbVisualizer's own variable syntax, two parameter marker syntaxes supported natively by some databases/drivers can also be used. This makes it easier to use SQL statements from other tools or code as-is in DbVisualizer, but you need to be aware of the limitations in how they are used compared to DbVisualizer variables.

The following gives an overview of the different formats and how they can be used.



Even if DbVisualizer supports several variable formats it doesn't mean you can always copy/paste the SQLs including the parameter markers to another application and successfully execute it. You need to check the compatibility for the actual connector/driver/framework and even that the database itself supports the used syntax.

The following variable syntaxes are supported by DbVisualizer:

DbVisualizer Variables

**`\${variable} |
value | | type | |
options} \$**

This is the most flexible syntax as it supports setting a name, default value, data type, and other options. Check the [DbVisualizer Variables](#) section for details.

A DbVisualizer variable can be used anywhere in the SQL as the specified value replaces the variable definition as a literal (unless a data type is specified; with a data type, its behavior is exactly the same as for **Named Parameter Markers**).

Example

```
select *
from EMPLOYEE
where FIRST_NAME like '${First Name}|Phil}$'
and AGE > ${Age}|20}$
```

The variable identifiers, **`\${...}\$** can be modified in **Tools->Tool Properties** and in the **General / Variables** category.



Named Parameter Markers

&name
:name
{name}
'name'

These syntaxes are supported natively by a few databases. This format allows only a name for the parameter and no other settings, such as type or default value. The parameter name is the name DbVisualizer shows in the prompt window.

Named parameter values are bound at runtime with the markers in the SQL. Some JDBC drivers/databases requires that the proper data type is set while some are more relaxed. For named (and unnamed) parameter markers, you may choose data type in the prompt window.

Using data type Literal means that the specified value will replace the variable as-is in the SQL statement. I.e the value is not bound at runtime.

Named parameter markers should only be used in contexts supported by the actual database, usually for column values. For example, as opposed to a DbVisualizer variable, a parameter marker cannot be used for a table or column name.

The only difference between **&name**, **:name**, **{name}** and **'name'** is that the latter two, **{name}** and **'name'**, allow white spaces in the name.

Example

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, &FirstName, &LastName, &Address, &Age);

insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, :FirstName, :LastName, :Address, :Age);

insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, {FirstName}, {LastName}, {Address}, {Age});

insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, 'FirstName', 'LastName', 'Address', 'Age');
```

Read more about [named parameter markers](#).

Unnamed Parameter Markers

? The question marker symbol is probably the most supported parameter marker among the supported databases. It is also the most unintuitive marker since the user has to remember the order of question marks and the corresponding values.

Since there is no name associated with it, DbVisualizer shows these as **Parameter 1**, **Parameter 2** and so on in the prompt window.

There is no technical difference between how unnamed and named parameter markers are handled internally in DbVisualizer or when processed by the database. All are bound with a prepared SQL statement.

Example

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, ?, ?, ?, ?)
```

Use named in favor of unnamed parameter markers if there is support in the target database based on the easier reading of named markers. Read more about [unnamed parameter markers](#).



It is not possible to mix DbVisualizer variables and parameter markers, or named and unnamed parameter markers, in the same script. If you do, you will only be prompted for values for one type and the execution will fail.

For more information about the different syntaxes check [Using DbVisualizer Variables](#) and [Using Parameter markers](#).

9.24.1 Using DbVisualizer Variables

DbVisualizer variables are used to build parameterized SQL statements and let DbVisualizer prompt you for the values when the SQL is executed. This is handy if you are executing the same SQL repetitively, just wanting to pass new data in the same SQL statement.

- [Variable Syntax](#)
- [Pre-defined Variables](#)
- [Variables for Java System Properties and OS Environment Variables](#)
- [Using "now" in values for Time, Date, and Timestamp](#)



- [Variable Substitution in SQL statements](#)

i A DbVisualizer variable that **doesn't specify a data type** will always be replaced with the **value as a literal**. This allows use of variables anywhere in an SQL statement. If a **data type is specified**, the prompted value will be bound with the SQL and variables can in this context **only be used where supported** by the target database.

DbVisualizer Variables

`${variable || value || type || options}$`

This is the most flexible syntax as it supports setting a name, default value, data type, and other options. Check the [DbVisualizer Variables](#) section for details.

A DbVisualizer variable can be used anywhere in the SQL as the specified value replaces the variable definition as a literal (unless a data type is specified; with a data type, its behavior is exactly the same as for **Named Parameter Markers**).

Example

```
select *
from EMPLOYEE
where FIRST_NAME like '${First Name || Phil}$'
and AGE > ${Age || 20}$
```

The variable identifiers, `${...}$` can be modified in **Tools->Tool Properties** and in the **General / Variables** category.

Variable Syntax

The variable format supports setting a default value, data type and a few options as in the following example:

```
${FullName || Andersson || String || where pk}$
```

This is the complete syntax for a DbVisualizer variable:

```
${name || value || type || options}$
```

Part	Default	Description
name	Required	Required. This is the name that appear in the prompt window. If multiple variables in a script have the same name, the substitution dialog shows only one and the entered value will be applied to all variables with that name
value	null	The default value for the variable
type	none (= literal)	The type of variable: String, Boolean, Integer, Float, Long, Double, BigDecimal, Date, Time and Timestamp. In addition DbVisualizer defines: BinaryData and TextData (for CLOB). This is used to determine how the data should be passed between DbVisualizer and the database server. If no type is specified, it is treated as a literal



Part	Default	Description
options	none	<p>The options part is used to express certain conditions. Separate these with a whitespace</p> <ul style="list-style-type: none">• pk Indicates that the variable is part of the primary key in the final SQL. Represented with a symbol in the prompt window• where Defines that the variable is part of the WHERE clause. A symbol indicate this condition in the prompt window• noshow This option define that the variable should not appear in the prompt window. A value must be set when using this option, unless it is an output variable (see dir below)• nobind Used in combination with when a type is set and defines that the variable should be replaced as a literal in the SQL rather than being bound as a parameter marker• dir=in out inout The direction for a variable used with the @call command (it is ignored for other uses). A variable assigned the return value for a function must be declared as dir=out, and a variable used for a procedure parameter must use a dir type matching the procedure parameter direction declaration. in is the default• scope=post The scope must be specified as post when using variables representing columns when exporting BLOB/CLOB values to separate files named based on column values.

Pre-defined Variables

A few pre-defined DbVisualizer variables can be used anywhere in the SQL. These are replaced with actual values just before the SQL is sent to the DB server.

i Note that none of the pre-defined variables below will show in the prompt window.

```
`${dbvis-date}`$  
`${dbvis-time}`$  
`${dbvis-timestamp}`$  
`${dbvis-connection}`$  
`${dbvis-database-type}`$
```

By default, date/time variable values are formatted as defined in **Tool Properties->Data Formats**, but you can also specify a custom format for a single use of the variable, e.g.

```
`${dbvis-date|||||format=[yyyymmdd]}`$
```

The following variables can be used only when monitoring a SQL statement that produce a result set and the **Allowed Row Count** for the monitor is > 0. The output format is seconds and milliseconds. Ex: 2.018

```
`${dbvis-exec-time}`$  
`${dbvis-fetch-time}`$
```

The following variable holds the absolute path to the current directory, e.g. set by the **@cd** command:

```
`${dbvis-pwd}`$
```

In an sql script, the name on the result set produced by the next SELECT statement can be set with the **@set resultset name** command (see [Using Client-Side Commands](#)). This result set name is accessible through the variable

```
`${dbvis-resultset-name}`$
```

Variables for Java System Properties and OS Environment Variables

You can use DbVisualizer variables to access the value of a Java system property. Just use a name of the format `java.<property>`, e.g.

```
@echo `${java.user.home}`$
```

To access the value of an operating system environment variable, use a name of the format `env.<envVariable>`, e.g.



```
@echo ${env.USER}$
```

As an example this may be used when exporting files. The export example below shows how to specify the DbVisualizer Bookmarks folder without explicitly giving the hardcoded folder path.

```
@export set filename="${java.dbvis.prefsdir}/Bookmarks/myscript.sql" Format="SQL" AppendFile="false";
```

A list of Java properties can be found in the **Java Properties** tab accessible from the **Help – About.** menu

Using "now" in values for Time, Date, and Timestamp

For variables with the type set to `Time`, `Date`, and `Timestamp`, the value may be set to the literal `now`. The value is then converted to the specified type with the format defined in **Tool Properties** and **Data Formats** category.

Variable	Format	Sample
<code>\${myDate now Date}\$</code>	yyyy-MM-dd	2017-07-17
<code>\${myDate now Time}\$</code>	HH:mm:ss	09:02:50
<code>\${myDate now Timestamp}\$</code>	yyyy-MM-dd HH:mm:ss	2017-07-17 09:03:11

For these types it is also possible to specify the value `now` in the variable prompting window.

Variable Substitution in SQL statements



For variable processing to work in the SQL Commander, make sure the **SQL Commander Options->Parameterized SQL** is checked in the **SQL Commander** main menu.

A simple variable may look like this:

```
${FullName}$
```

A variable is identified by the start and end sequences, `${...}$`. (These can be [re-defined](#) in **Tool Properties**). During execution, the SQL Commander searches for variables and displays the prompt window with the name of each variable and an input (value) field. Enter the value for each variable and then press **Execute**. This will then replace the variable with the value as a literal and finally let the database execute the statement.

Consider the following SQL statement with variables. It is the simplest use of variables since it only contains the variable names. In this case it is also necessary to enclose text values with quotes since the prompt window cannot determine the actual data type for the variables.



```
INSERT
INTO
EMPLOYEES
(
    EMPLOYEE_ID,
    FIRST_NAME,
    LAST_NAME,
    EMAIL,
    PHONE_NUMBER,
    HIRE_DATE,
    JOB_ID,
    SALARY,
    COMMISSION_PCT,
    MANAGER_ID,
    DEPARTMENT_ID
)
VALUES
(
    ${EMPLOYEE_ID}$,
    ${FIRST_NAME}$,
    ${LAST_NAME}$,
    ${EMAIL}$,
    ${PHONE_NUMBER}$,
    ${HIRE_DATE}$,
    ${JOB_ID}$,
    ${SALARY}$,
    ${COMMISSION_PCT}$,
    ${MANAGER_ID}$,
    ${DEPARTMENT_ID}$
)
```

Executing the above SQL will result in the following prompt window:

Key	Name	Value	Type
	EMPLOYEE_ID	(null)	Literal
	FIRST_NAME	(null)	Literal
	LAST_NAME	(null)	Literal
	EMAIL	(null)	Literal
	PHONE_NUMBER	(null)	Literal
	HIRE_DATE	(null)	Literal
	JOB_ID	(null)	Literal
	SALARY	(null)	Literal
	COMMISSION_PCT	(null)	Literal
	MANAGER_ID	(null)	Literal
	DEPARTMENT_ID	(null)	Literal

1: **EMPLOYEE_ID** Pattern: Text
Not NULL
JDBC: N/A, Java: Literal

Show SQL

Continue Cancel

Using variables with no data type defined shows these as **Literal**. This means that the specified value will replace the variable as-is in the SQL statement.



The prompt window has the same look and functionality as the Form Data Editor, i.e. you can sort, filter, insert pre-defined data, copy, paste and edit cells in the multi line editor, plus a lot of other things. In addition the prompt window adds two new commands (leftmost in the toolbar and in the form right-click menu).

Set Default Values	This will set each value to the default value for the variable. If a default value was not specified in the variable, (null) will shown
Set Previously Used Values	Set the value for each variable to the values (matched by name) that was used in the previous run (if there are no values from a previous run, this button is disabled)

The **SQL Preview** area shows the statement with all variables replaced with the values.

Here is an example of a more complex use of variables utilizing default value, data type and options:

```
INSERT
INTO
  EMPLOYEES
  (
    EMPLOYEE_ID,
    FIRST_NAME,
    LAST_NAME,
    EMAIL,
    PHONE_NUMBER,
    HIRE_DATE,
    JOB_ID,
    SALARY,
    COMMISSION_PCT,
    MANAGER_ID,
    DEPARTMENT_ID
  )
VALUES
  (
    ${EMPLOYEE_ID|105|BigDecimal|pk ds=7 dt=NUMERIC}$,
    ${FIRST_NAME|David|String|nullable ds=20 dt=VARCHAR}$,
    ${LAST_NAME|Austin|String|ds=25 dt=VARCHAR}$,
    ${EMAIL|DAUSTIN|String|ds=25 dt=VARCHAR}$,
    ${PHONE_NUMBER|590.423.4569|String|nullable ds=20 dt=VARCHAR}$,
    ${HIRE_DATE|2005-06-25 00:00:00|Timestamp|ds=7 dt=TIMESTAMP}$,
    ${JOB_ID|IT_PROG|String|ds=10 dt=VARCHAR}$,
    ${SALARY|4800|BigDecimal|nullable ds=10 dt=NUMERIC}$,
    ${COMMISSION_PCT|(null)|BigDecimal|nullable ds=4 dt=NUMERIC}$,
    ${MANAGER_ID|103|BigDecimal|nullable ds=7 dt=NUMERIC}$,
    ${DEPARTMENT_ID|60|BigDecimal|nullable ds=5 dt=NUMERIC}$
  )
```

This example use the full capabilities of variables. This example is generated by the **Script to SQL Commander->INSERT COPY INTO TABLE** right click menu choice in the **Data** tab grid. By default it generates variables representing the actual values and the characteristics of the columns.



Key	Name	Value	Type
	EMPLOYEE_ID	105	BigDecimal
	FIRST_NAME	David	String
	LAST_NAME	Austin	String
	EMAIL	DAUSTIN	String
	PHONE_NUMBER	590.423.4569	String
	HIRE_DATE	2005-06-25 00:00:00	Timestamp
	JOB_ID	IT_PROG	String
	SALARY	4800	BigDecimal
	COMMISSION_PCT	(null)	BigDecimal
	MANAGER_ID	103	BigDecimal
	DEPARTMENT_ID	60	BigDecimal

1: **EMPLOYEE_ID** NUMERIC Pattern: Unformatted
Not NULL, Key Column
JDBC: N/A, Java: BigDecimal

Show SQL

Continue Cancel

To highlight that a variable is part of the **WHERE** clause in the final SQL, it is represented with a green symbol in front of the name.

When executing an SQL statement that consist of variables, DbVisualizer replaces each variable with either the value as a literal or as a parameter marker. Using parameter markers to pass data with a statement is more reliable than literals. DbVisualizer will automatically generate a parameter marker if the variable has the data type set and if there is no **nobind** option specified.

The following will be replaced with a parameter marker:

```
`${Name}|rolle|String}`
```

These will be replaced with the value as a literal in the final SQL:

```
`${Name}|rolle}`
```

```
`${Name}|rolle|String|nobind}`
```

Variables in DbVisualizer may be used anywhere in a statement as long as there is no data type specified.

Changing the Delimiter Characters

You can change which identifiers should be used as the prefix, suffix and part delimiter in a variable expression in **Tools->Tool Properties**, in the **General / Variables** category.

9.24.2 Using Parameter Markers

Parameter markers (also referred as **bind/host variables** or **place holders**) are commonly used in database applications where the SQL is composed of static text combined with values represented as markers instead of actual values. These markers are processed during the preparation of the SQL statement and values are then bound with the markers. Each database has its recommendations for how and when to use parameter markers so this is not further discussed here.

- [Named Parameter Markers](#)
- [Unnamed Parameter Markers](#)
- [Get Parameter Types via JDBC](#)
- [Database Support/Driver Support](#)

DbVisualizer supports the most common syntaxes for parameter markers to comply with the supported databases. Parameter markers are categorized as either **named** or **unnamed** markers. The following sections explains their respective syntaxes.



i It is not possible to mix DbVisualizer variables and parameter markers, or named and unnamed parameter markers, in the same script. If you do, you will only be prompted for values for one type and the execution will fail.

Named Parameter Markers

Named Parameter Markers

&name
:name
{name}
'name'

These syntaxes are supported natively by a few databases. This format allows only a name for the parameter and no other settings, such as type or default value. The parameter name is the name DbVisualizer shows in the prompt window.

Named parameter values are bound at runtime with the markers in the SQL. Some JDBC drivers/databases requires that the proper data type is set while some are more relaxed. For named (and unnamed) parameter markers, you may choose data type in the prompt window.

Using data type Literal means that the specified value will replace the variable as-is in the SQL statement. I.e the value is not bound at runtime.

Named parameter markers should only be used in contexts supported by the actual database, usually for column values. For example, as opposed to a DbVisualizer variable, a parameter marker cannot be used for a table or column name.

The only difference between **&name**, **:name**, **{name}** and **'name'** is that the latter two, **{name}** and **'name'**, allow white spaces in the name.

Example

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, &FirstName, &LastName, &Address, &Age);
```

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, :FirstName, :LastName, :Address, :Age);
```

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, {FirstName}, {LastName}, {Address}, {Age});
```

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, 'FirstName', 'LastName', 'Address', 'Age');
```

Read more about [named parameter markers](#).

The following is a sample SQL executed in the SQL Commander:


```
INSERT INTO EMPLOYEES
(EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL, PHONE_NUMBER, HIRE_DATE,
JOB_ID, SALARY, COMMISSION_PCT, MANAGER_ID, DEPARTMENT_ID)
VALUES
(:EMPLOYEE_ID, :FIRST_NAME, :LAST_NAME, :EMAIL, :PHONE_NUMBER,
:HIRE_DATE, :JOB_ID, :SALARY, :COMMISSION_PCT, :MANAGER_ID, :DEPARTMENT_ID);
```

The prompt window will show the markers with their respective names:



Key	Name	Value	Type
	:EMPLOYEE_ID	45	Integer
	:FIRST_NAME	Janne	String
	:LAST_NAME	Shouffer	String
	:EMAIL	janne@guitarr.com	String
	:PHONE_NUMBER		String
	:HIRE_DATE	2012-12-12	Date
	:JOB_ID	PRO	String
	:SALARY	123.45	Integer
	:COMMISSION_PCT	14.4	Integer
	:MANAGER_ID	21	Integer
	:DEPARTMENT_ID	2	Integer

For parameter marker processing to work in the SQL Commander, make sure the **SQL Commander->Parameterized SQL** main menu option is checked.

 To apply the values, close the window and continue with the execution, use key binding **Ctrl+Enter** (**Command+Enter** on macOS).

Unnamed Parameter Markers

Unnamed Parameter Markers

? The question marker symbol is probably the most supported parameter marker among the supported databases. It is also the most unintuitive marker since the user has to remember the order of question marks and the corresponding values.

Since there is no name associated with it, DbVisualizer shows these as **Parameter 1**, **Parameter 2** and so on in the prompt window.

There is no technical difference between how unnamed and named parameter markers are handled internally in DbVisualizer or when processed by the database. All are bound with a prepared SQL statement.

Example

```
insert into EMPLOYEE (ID, FIRST_NAME, LAST_NAME, ADDRESS, AGE)
values (null, ?, ?, ?, ?)
```

Use named in favor of unnamed parameter markers if there is support in the target database based on the easier reading of named markers. Read more about [unnamed parameter markers](#).

This is the same SQL as used in the Named Parameter Marker section but here question marks are used as markers:

```
INSERT INTO EMPLOYEES
(EMPLOYEE_ID, FIRST_NAME, LAST_NAME, EMAIL, PHONE_NUMBER, HIRE_DATE,
JOB_ID, SALARY, COMMISSION_PCT, MANAGER_ID, DEPARTMENT_ID)
VALUES
(?, ?, ?, ?, ?, ?, ?, ?, ?, ?, ?);
```

Since we're using the unnamed marker, **?**, the name of each parameter is displayed as **Parameter 1**, **Parameter 2** and so on:



Enter Data for Parameter Markers

Q

Key	Name	Value	Type
	Parameter1	908	Integer
	Parameter2	(null)	String
	Parameter3	(null)	String
	Parameter4	(null)	String
	Parameter5	(null)	String
	Parameter6	(null)	String
	Parameter7	(null)	String
	Parameter8	(null)	String
	Parameter9	(null)	String
	Parameter10	(null)	String

Show SQL

Continue Cancel

SQL Preview

```
1 INSERT
2 INTO
3   EMPLOYEES
4   (
5     EMPLOYEE_ID,
6     FIRST_NAME,
7     LAST_NAME,
8     EMAIL,
9     PHONE_NUMBER,
10    HIRE_DATE,
11    JOB_ID,
12    SALARY,
13    COMMISSION_PCT,
14    MANAGER_ID,
15    DEPARTMENT_ID
16  )
17  VALUES
18  (
19    ?,
20    ?,
```

Note: The SQL preview show the original SQL without any parameter replacement applied.

Due to the use of unnamed markers it is not very intuitive what parameter correspond to which part in the statement. The **SQL Preview** may be handy to get an idea. The **Type** field is automatically adjusted based on what data is entered for a value. The data type may be manually set by left-click on the type and choose another type from the drop-down.



To apply the values, close the window and continue with the execution, use key binding **Ctrl+Enter** (**Command+Enter** on macOS).

Get Parameter Types via JDBC

The processing of named and unnamed parameter markers is managed by DbVisualizer. By default there is no data type detection of the target columns identified by the markers and DbVisualizer will initially present these as **String** in the prompt window. When changing the value for a parameter in the prompt window, a data analyzer is triggered which will automatically detect the type and update the **Type** field accordingly.

Some drivers (far from all) have the capability to detect the real data type for the referenced columns in the SQL statement. To enable this processing, select the **Get Parameter Types via JDBC** action in the **SQL Commander** menu. DbVisualizer will then show the correct types in the prompt window.



i Having **Get Parameter Types via JDBC** enabled while executing may decrease performance substantially as each SQL statement in the script is then pre-processed with the database before the prompt window is displayed.

Database Support/Driver Support

The support for parameter markers may differ between databases. Please consult the documentation for the database to see what syntax it supports.

In some situations the database and DbVisualizer support for named parameters might be incompatible. An example is when using the same parameter name in multiple places in the SQL. When preparing a statement towards such a database, the database may report that the parameter is only used once. In these cases, DbVisualizer will trust the driver and revert to generating the names visible in the form as Parameter 1, Parameter 2 and so on.

10 Working with Result Sets

You can view result sets in different ways, edit simple result sets, and export or compare them.

10.1 Viewing a Result Set

You can view a result set as a grid, as text or as a chart. Which format to use by default can be specified in the **Tool Properties** dialog, under the **Default Display Mode** section shown in the **SQL Commander > Result Sets** category under the General tab.

Here you can also specify other things like if empty result sets should be shown at all, or which tab should be activated after a successful execution in the **SQL Commander**.

To change the view format for the current result set, use the buttons to the upper right in the grid toolbar.

Below is an example of a Result Set shown in text format.

1	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	JOB_ID
2							
3	100	Steven	King	SKING	515.123.4567	1987-06-17 00:00:00	AD_PRES
4	101	Neena	Kochhar	NKOCHHAR	515.123.4568	1989-09-21 00:00:00	AD_VP
5	102	Lex	De Haan	LDEHAAN	515.123.4569	1993-01-13 00:00:00	AD_VP
6	103	Alexander	Hunold	AHUNOLD	590.423.4567	1990-01-03 00:00:00	IT_PROG
7	104	Bruce	Ernst	BERNST	590.423.4568	1991-05-21 00:00:00	IT_PROG
8	105	David	Austin	DAUSTIN	590.423.4569	1997-06-25 00:00:00	IT_PROG
9	106	Valli	Pataballa	VPATABAL	590.423.4560	1998-02-05 00:00:00	IT_PROG
10	107	Diana	Lorentz	DLORENTZ	590.423.5567	1999-02-07 00:00:00	IT_PROG
11	108	Nancy	Greenberg	NGREENBE	515.124.4569	1994-08-17 00:00:00	FI_MGR
12	109	Daniel	Faviet	DFAVIET	515.124.4169	1994-08-16 00:00:00	FI_ACCOUI
13	110	John	Chen	JCHEN	515.124.4269	1997-09-28 00:00:00	FI_ACCOUI
14	111	Ismael	Sciarra	ISCIARRA	515.124.4369	1997-09-30 00:00:00	FI_ACCOUI
15	112	Jose Manuel	Urman	JMURMAN	515.124.4469	1998-03-07 00:00:00	FI_ACCOUI
16	113	Luise	Baer	LBARR	515.124.4567	1998-12-07 00:00:00	FI_ACCOUI

10.1.1 Viewing as a Grid

When you view the result set as a grid, you have access to the same features as when [viewing table data](#).

10.1.2 Viewing as Text

i **Only in DbVisualizer Pro**


This feature is only available in the DbVisualizer Pro edition.



The text format for a result set presents the data in a tabular style. The column widths are calculated based on the length of each value and the length of the column label.

10.1.3 Merge Result Sets

If you want to combine the text view of a number of result sets into one, select **Merge Result Sets** from the result set tab right-click menu. A dialog lets you select the result sets to merge and also do some configuration:



Auto merging

Using the **Merge Result Sets** drop-down menu in the SQL Commander toolbar, you can enable **Auto Merge after Execution**. You can also select **Merge Result Sets > Configure Merging** from the drop-down menu to adjust various merge options.

10.1.4 Viewing as a Graph

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

To view the result set as a chart, use the rightmost button in the grid toolbar. Please see the [Working with Charts](#) page for how you can arrange the chart.

10.2 Editing a Result Set

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

A result set from a query that fulfills these requirements is editable:

1. The SQL is a SELECT command,
2. Only one table is referenced in the FROM clause,
3. All current columns exist by name (case sensitive) in the identified table.

A result set like this can be edited in the same way as you can [edit table data](#).



i If all of the above requirements are fulfilled but the edit controls are still not shown, please try qualifying the table name with the schema and/or database name.

If you want results to always be read-only, you can enable the **Make Result Sets Read-Only** setting in the Tool Properties dialog, in the **SQL Commander/Result Sets** category under the General tab.

10.3 Exporting a Result Set

You can export a result set as described in [Exporting a Grid](#) or using the `@export client side` command.

10.4 Comparing Result Sets

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

You can compare a result set grid to tables and/or other result set grids.

To compare the grid data to the data of a table or a another result set:

1. Open the **Data** tab for another table or execute an SQL query to open a result set tab,
2. Select **Compare** from the right-click menu in one of the tabs to [compare their grid content](#).


10.5 Pinning Result Sets

Existing Result Set tabs are removed when you execute a script again. If you want to save a Result Set tab between executions, you can "pin" it using the **Pin Tab** right-click menu choice for the tab header, or by simply clicking on the tab icon. There is also a **Pin All** choice if you have multiple tabs you want to pin, and **Unpin All** to make them all be replaced at the next execution.

Whether Result Set tabs should be pinned by default can be controlled in the Tool Properties dialog, in the **SQL Commander/Result Sets** category under the General tab.

10.6 Show Result Sets in a Separate Window

Results Sets and the Log tabs are located just under editor in a SQL Commander tab. Sometimes you may need to get the full screen height available for the editor and detach the result area tabs in its own window. To accomplish this click the symbol at the right-most position in the tab row.



Clicking the symbol while result area tabs are detached will bring them back into the original location.

Note that the symbol to detach and re-attach back can differ slightly depending on Operating system and Look and Feel.

11 Working with Charts

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

Result sets in the SQL Commander and in the Monitor tools can be viewed as charts.

- [Charting a Result Set](#)
 - [Selecting the Category](#)
 - [Selecting the Series](#)
 - [Chart Type](#)
- [Chart Configuration](#)







- Appearance Preferences
- Series Preferences

- Zooming
- Export

The chart support in DbVisualizer presents data from any result set in a configurable chart displayed in a line, bar, area or pie style. It offers much of the charting support you find in MS Excel and other specialized charting tools. Charts may be exported as an image to file, printed and copied to system clipboard for easy sharing with other tools. Charts are configured and viewed in the [SQL Commander](#) and in the [Monitor](#) tool which is really powerful, delivering real time charts of many result sets simultaneously. Charts can be opened by clicking the icon at the the rightmost button in the result tab toolbar (see below).

Here are some sample charts:





11.1 Charting a Result Set

The basic setup of a chart is really easy. Just select one or more columns that should appear as series in the chart and what column to use as the category (X-axis). Further refinement of the chart can be made in the chart preferences window.

The normal output view of a result set in the SQL Commander or Monitor window is in a grid style as shown in the following screenshot. To activate the chart view click the rightmost button in the result tab toolbar:



The screenshot shows the DbVisualizer interface. At the top, the database connection is 'Sakila H2 (dbvis)' and the schema is 'SAKILA'. The SQL query in the editor is:


```
1 select * from SAKILA.SALES_BY_FILM_CATEGORY
```

The results are displayed in a table with the following columns: CATEGORY, TOTAL_SALES, and RENTALS. The data is as follows:

* ID	CATEGORY	TOTAL_SALES	RENTALS
1	Action	4375.85	1112
2	Animation	4656.30	1166
3	Children	3655.55	945
4	Classics	3639.59	939
5	Comedy	4383.58	941
6	Documentary	4217.52	1050
7	Drama	4587.39	1060
8	Family	4226.07	1096
9	Foreign	4270.67	1033
10	Games	4281.33	969
11	Horror	3722.54	846
12	Music	3417.72	830
13	New	4351.62	940
14	Sci-Fi	4756.98	1101
15	Sports	5314.21	1179
16	Travel	3549.64	837


A callout bubble with the text 'Show as Chart' points to the 'Show as Chart' icon in the toolbar.

When switching to the chart view DbVisualizer automatically picks the first date or text column as the category (x-axis) for the chart and the first numeric column as the series (y-axis). In the following example it is the **CATEGORY** and **TOTAL_SALES** columns for this specific result set.



11.1.1 Selecting the Category


Click the category button to pick the column to use for the x-axis. Let the mouse pointer stay on a column name for a second and a tip will show what data type it is.






11.1.2 Selecting the Series

Click the series button to change what series to display in the chart. This drop-down stays on screen while selecting one or more series (the changes are directly propagated in the chart). To close the list either press the **ESC** button or click outside the list. If only one series is selected then its name is listed in the button label. If additional series are selected then the number of selected series are listed in parentheses.




i Tip: Press the ALT key while selecting a series and all currently selected series will be de-selected.

This is the chart after applying category and 2 series:



11.1.3 Chart Type

A chart can be displayed as one of several types. Select what type to use in the toolbar or on the right-click menu (which also offers some other controls):




i Note: For the Pie chart, only one series can be selected.


11.2 Chart Configuration

The chart can be configured to your preferences for titles, colors, legend position, etc. You can also set alternative names for the series in the chart. All appearance settings are automatically re-used when running subsequent queries in the SQL Commander during the same DbVisualizer session. If you save a query as a bookmark script then all appearance settings are saved with the chart. Loading the script at a later time will also load the chart settings.

Open the chart configuration dialog from the toolbar or the right-click menu:



You can also save or load default preferences by clicking the **Settings** button in the lower left corner:



11.2.1 Appearance Preferences

In the Chart Configuration panel, use the controls in the **General** tab to customize the layout and style of the chart.



Chart Configuration [Close]

General | Series

[Icons: Copy, Paste, Info, Refresh, Undo]

- Chart**
 - Title**
 - Chart Type: Line
 - Font: Tahoma, Plain, 11
 - Top Background: 255, 255, 255
 - Bottom Background: 180, 180, 250
- Legend**
 - Show Legend:
 - Position: East
- X Axis**
 - Title**
 - Show Title:
 - Labels Rotation: 45
 - Allow Label Overlap:
 - Show Major Grid Lines:
 - Handle Date/Time as Text:
- Y Axis**
 - Title**
 - Show Title:
 - Show Major Grid Lines:
 - Show Minor Grid Lines:
 - Auto Adjust Start Value:
 - Auto Adjust End Value:
 - Number Format: #,##0. #
- Series**
 - Color Scheme: Tau (20)
 - Show Shadows:
- Line & Area Chart**
 - Line Type: Straight
 - Line Width: 2
 - Show Points:
 - Show Point Labels:
- Bar Chart**
 - Bar Type: Flat
 - Bar Gap: 2
 - Bar Group Gap: 4
- Pie Chart**
 - Pie Type: Flat
 - Label Type: Line Labels

(Name)
(Description)

Settings [Dropdown] [OK] [Apply] [Cancel]




Information about the selected setting in the list is displayed at the bottom of the window.

11.2.2 Series Preferences

The default name of the series is the column name in the result set. In the **Series** tab you can set an alternative label name and also control what series should be visible.

Changes in the Series tab are propagated directly in the chart.




11.3 Zooming

Charts support zooming by selecting a rectangle in the chart area. Selecting another rectangle in that zoomed area will zoom the chart even further, and so on. To unzoom one level, click the Zoom Out button.

i Note: You cannot zoom pie charts.

11.4 Export

Charts can be exported in PNG, GIF or JPG formats.



The default size of the exported image is the same as it appears on the screen. To change the size, either select a pre-defined paper size in the Size list or enter a size in pixels.





12 Exporting a Grid

All grids in DbVisualizer can be exported to file, clipboard or into the SQL Commander using a number of formats.

- [Settings](#)
- [Data page](#)
 - [Generating Test Data](#)
- [Preview](#)
- [Output Destination](#)
- [Settings Menu](#)

The Export wizard gives you full control over the export (there is also an option to [open the grid as a spreadsheet](#) using predefined settings). The commands are available both on the right-click menu and on the toolbar and operate on either selected, visible, or all data:

- **Export Visible:** visible data, observing any sorting, filtering or hidden columns that reduce the contents of the grid
- **Export:** all data loaded into the grid (ignoring filters and sorting)
- **Export Selection:** data in selected cells



12.1 Settings

The first wizard page is the **Settings** page, containing general properties for how the exported data should be formatted.



Export Grid

Output Format

CSV HTML TXT SQL XML XLS JSON Encoding: UTF-8

Data Format

Date: 2020-02-11

Time: 15:44:32

Timestamp: 2020-02-11 15:44:32

Number: 9126183

Decimal Number: 9126183.531815

Grouping Decimal

Boolean Text Value: True False

Binary/BLOB:

CLOB:

Null Value Text

Quote Text Value Duplicate Embedded O'Learys "steaks" -> O'Learys "steaks"

Quote All Values

Options

- Common Options**

Max Rows	200
Total Rows in Grid	200
- Common CSV Options**

Column Delimiter	TAB
Row Delimiter	UNIX/Linux/macOS - LF
Include Column Names	<input checked="" type="checkbox"/>
Use any Label (Alias)	<input checked="" type="checkbox"/>
Remove Newline Characters	<input type="checkbox"/>
Include Original SQL	Don't Include
Row Comment Identifier	

Settings

Select an output format, file encoding (it is also used to set the encoding in the HTML and XML headers, if you select one of those formats), and values for some different data formats (date, time, et.c.).

Note that the text to the right of the selections in the **Data Format** section shows an example of how the currently selected option would look like with real data.

i Only in DbVisualizer Pro

With the DbVisualizer Free edition, only the CSV and HTML formats are supported.



The **Options** section is used to define settings that are specific for the selected output format, for instance the column and row delimiters for the CSV format, or the Excel spreadsheet format.

12.2 Data page

Clicking the **Next** button in the wizards moves you to the **Data** page. Use the columns list to control which columns to export and how to format the data for each columns. The list is exactly the same as the column headers in the original grid, i.e., if a column was manually removed from the grid before launching the Export Wizard, then it will not appear in this list.

Export Grid
✕

Columns

Export	Name	Label (Alias)	Type	Is Text	Value
<input checked="" type="checkbox"/>	EMPLOYEE_ID	EMPLOYEE_ID	BigDecimal	<input type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	FIRST_NAME	FIRST_NAME	String	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	LAST_NAME	LAST_NAME	String	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	EMAIL	EMAIL	String	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	PHONE_NUMBER	PHONE_NUMBER	String	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	HIRE_DATE	HIRE_DATE	Timestamp	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	JOB_ID	JOB_ID	String	<input checked="" type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	SALARY	SALARY	BigDecimal	<input type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	COMMISSION_PCT	COMMISSION_PCT	BigDecimal	<input type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	MANAGER_ID	MANAGER_ID	BigDecimal	<input type="checkbox"/>	\${value}\$
<input checked="" type="checkbox"/>	DEPARTMENT_ID	DEPARTMENT_ID	BigDecimal	<input type="checkbox"/>	\${value}\$

Table Rows

Total Number of Rows in Grid: 107

Number of Rows to Export: 107

Settings ▼

< Back

Next >

Cancel

The **Table Rows** fields show you how many rows are available and let you specify the number of rows to export. This setting along with the **Add Row** button is especially useful when you use the test data generation feature described in the next section.

The columns in this page's grid can be used like this.

Column	Descriptions
Export	Defines whether the column will be exported or not. Uncheck it to ignore the column in the exported output.
Name	The name of the column. This is used if exporting in HTML, XML, XLS, JSON or SQL format. Column headers are optional in the CSV output format.
Label (Alias)	When you export a result set grid for a SELECT statement that uses column aliases, this column holds the alias. If you have also enabled Use any Label (Alias) in the Options section, this value is used in place of the name.
Type	The internal DbVisualizer type for the column. This type is used to determine if the column is a text column (i.e., if the data should be enclosed by quotes or not).
Is Text	Specifies if the column is considered to be a text column (this is determined based on the type) and so if the value should be enclosed in quotes.
Value	The default <code>\${value}\$</code> variable is simply be substituted with the column value in the exported output. You can enter additional static text in the value field. This is also the place where any test data generator variables are defined.



12.2.1 Generating Test Data

The test data generator is useful when you need to add random column data to the exported output.

The **Value** column in the **Data** page grid specifies the data to be in the exported output. By default, it contains the `#{value}` variable, which is simply replaced with the real column value during the export process. You can also add static values before and after the `#{value}` variable, to be exported as entered.

Alternatively, you can use test data generator variables in the **Value** column. The choices are available in the right-click menu when you edit the **Value** column.

Function Name	Function Call	Example
Generate random number	<code>#{var randomnumber(1, 2147483647)}\$</code>	Generates a random number between 1 and 2147483647
Generate random string of random size	<code>#{var randomtext(1, 10)}\$</code>	Generates random text with a length between 1 and 10 characters
Generate random value from a list of values	<code>#{var randomenum(v1, v2, v3, v4, v5)}\$</code>	Picks one of the listed values in random order
Generate sequential number	<code>#{var number(1, 2147483647, 1)}\$</code>	Generates a sequential number starting from 1. The generator re-starts at 1 when 2147483647 is reached. The number is increased with 1 every time a new value is generated.

Here is an example of how to use the test data generators to try out planned changes to the data. Consider this initial data:

*	EMPLOYEE_ID	JOB_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE
1	100	AD_PRES	Steven	King	SKING	515.123.4567	2003-06-17 00:00:00
2	101	AD_VP	Neena	Kochhar	NKOCHHAR	515.123.4568	2005-09-21 00:00:00
3	102	AD_VP	Lex	De Haan	LDEHAAN	515.123.4569	2001-01-13 00:00:00
4	103	IT_PROG	Alexander	Hunold	AHUNOLD	590.423.4567	2006-01-03 00:00:00
5	104	IT_PROG	Bruce	Ernst	BERNST	590.423.4568	2007-05-21 00:00:00
6	105	IT_PROG	David	Austin	DAUSTIN	590.423.4569	2005-06-25 00:00:00
7	106	IT_PROG	Valli	Pataballa	VPATABAL	590.423.4560	2006-02-05 00:00:00
8	107	IT_PROG	Diana	Lorentz	DLORENTZ	590.423.5567	2007-02-07 00:00:00
9	108	FI_MGR	Nancy	Greenberg	NGREENBE	515.124.4569	2002-08-17 00:00:00
10	109	FI_ACCOUNT	Daniel	Faviet	DFAVIET	515.124.4169	2002-08-16 00:00:00
11	110	FI_ACCOUNT	John	Chen	JCHEN	515.124.4269	2005-09-28 00:00:00
12	111	FI_ACCOUNT	Ismael	Sciarra	ISCIARRA	515.124.4369	2005-09-30 00:00:00
13	112	FI_ACCOUNT	Jose Manuel	Urman	JMURMAN	515.124.4469	2006-03-07 00:00:00

After the changes, the **JOB_ID** column should not appear in the output and the new **JOB_CODE** should contain abbreviated job codes. To test this, we simply uncheck the **Export** checkbox for **JOB** entry and set the **Value** for the **JOB_CODE** to use the **Generate random value from a list of values** function. By unchecking the "Export" checkbox for the column **JOB_ID** this column will not be included in the export.



Export Grid

Columns

Export	Name	Label (Alias)	Type	Is Text	Value
<input checked="" type="checkbox"/>	EMPLOYEE_ID	EMPLOYEE_ID	BigDecimal	<input type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	FIRST_NAME	FIRST_NAME	String	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	LAST_NAME	LAST_NAME	String	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	EMAIL	EMAIL	String	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	PHONE_NUMBER	PHONE_NUMBER	String	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	HIRE_DATE	HIRE_DATE	Timestamp	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	JOB_CODE	JOB_CODE	String	<input checked="" type="checkbox"/>	\$(var randomenum(eng, adm, fin))\$
<input type="checkbox"/>	JOB_ID	JOB_ID	String	<input checked="" type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	SALARY	SALARY	BigDecimal	<input type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	COMMISSION_PCT	COMMISSION_PCT	BigDecimal	<input type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	MANAGER_ID	MANAGER_ID	BigDecimal	<input type="checkbox"/>	\$(value)\$
<input checked="" type="checkbox"/>	DEPARTMENT_ID	DEPARTMENT_ID	BigDecimal	<input type="checkbox"/>	\$(value)\$

Table Rows

Total Number of Rows in Grid:

Number of Rows to Export:

Settings < Back Next > Cancel

12.3 Preview

The third wizard page is the **Preview** page, showing the first 100 rows of the data as it will appear when it is finally exported. This is useful to verify the data before performing the export process. If the previewed data is not what you expected, just use the back button to modify the settings.

Previewing the data (or exporting it) in CSV format results in this:

Export Grid

Preview of the first 100 rows (or less)

	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	JOB_CODE	PHONE_NUMBER	HIRE_DATE	SALARY	COMMISSION_PCT	MANAGER_ID	DEPARTMENT_ID
1	100	Steven	King	SKING	fin	515.123.4567	2003-06-17 00:00:00	24000	(null)	(null)	90
2	101	Neena	Kochhar	NKOCHHAR	adm	515.123.4568	2005-09-21 00:00:00	17000	(null)	100	90
3	102	Lex	De Haan	LDEHAAN	fin	515.123.4569	2001-01-13 00:00:00	17000	(null)	100	90
4	103	Alexander	Hunold	AHUNOLD	fin	590.423.4567	2006-01-03 00:00:00	9000	(null)	102	60
5	104	Bruce	Ernst	BERNST	adm	590.423.4568	2007-05-21 00:00:00	6000	(null)	103	60
6	105	David	Austin	DAUSTIN	eng	590.423.4569	2005-06-25 00:00:00	4800	(null)	103	60
7	106	Valli	Pataballa	VPATABAL	adm	590.423.4560	2006-02-05 00:00:00	4800	(null)	103	60
8	107	Diana	Lorentz	DLORENTZ	eng	590.423.5567	2007-02-07 00:00:00	4200	(null)	103	60
9	108	Nancy	Greenberg	NGREENBE	eng	515.124.4569	2002-08-17 00:00:00	12008	(null)	101	100
10	109	Daniel	Faviet	DFAVIET	fin	515.124.4169	2002-08-16 00:00:00	9000	(null)	108	100
11	110	John	Chen	JCHEN	fin	515.124.4269	2005-09-28 00:00:00	8200	(null)	108	100
12	111	Ismael	Sciarra	ISCIARRA	adm	515.124.4369	2005-09-30 00:00:00	7700	(null)	108	100
13	112	Jose Manuel	Urman	JMURMAN	eng	515.124.4469	2006-03-07 00:00:00	7800	(null)	108	100
14	113	Luis	Popp	LPOPP	eng	515.124.4567	2007-12-07 00:00:00	6900	(null)	108	100
15	114	Den	Raphaely	DRAPHEAL	fin	515.127.4561	2002-12-07 00:00:00	11000	(null)	100	30
16	115	Alexander	Khoo	AKHOO	eng	515.127.4562	2003-05-18 00:00:00	3100	(null)	114	30
17	116	Shelli	Baida	SBAIDA	adm	515.127.4563	2005-12-24 00:00:00	2900	(null)	114	30
18	117	Sigal	Tobias	STOBIAS	adm	515.127.4564	2005-07-24 00:00:00	2800	(null)	114	30
19	118	Guy	Himuro	GHIMURO	eng	515.127.4565	2006-11-15 00:00:00	2600	(null)	114	30
20	119	Karen	Colmenares	KCOLMENA	eng	515.127.4566	2007-08-10 00:00:00	2500	(null)	114	30
21	120	Matthew	Weiss	MWEISS	fin	650.123.1234	2004-07-18 00:00:00	8000	(null)	100	50

Settings < Back **Next >** Cancel

12.4 Output Destination

The final wizard page is the **Output Destination** page. The destination field specifies the target destination for the exported data, one of File, SQL Commander or Clipboard.



Click **Export** on this page to export the grid data to the selected destination.

12.5 Settings Menu

If you often use the same settings, you can save them as the default settings for this assistant. If you use a number of common settings, you can save them to individual files that you can load as needed. Use the **Settings** drop-down button to accomplish this:

- **Save as Default Settings**
Saves all format settings as default. These are then loaded automatically when open an Export Schema dialog
- **Use Default Settings**
Use this choice to initialize the settings with default values
- **Remove Default Settings**
Removes the saved defaults and restores the regular defaults
- **Load...**
Use this choice to open the file chooser dialog, in which you can select a settings file
- **Save As...**
Use this choice to save the settings to a file
- **Copy Settings to Clipboard**
Copies the settings to the system clipboard

You can also use settings saved here with the [@export client side command](#).

13 Opening a Grid as Spreadsheet

All grids in DbVisualizer offer options to open the grid data in an external spreadsheet tool using predefined settings (you can also [export the grid](#) to a number of formats with full control). The commands are available both on the right-click menu and on the toolbar and operate on either selected, visible, or all data:

- **Open Visible as Spreadsheet:** visible data, observing any sorting, filtering or hidden columns that reduce the contents of the grid
- **Open as Spreadsheet:** all data loaded into the grid (ignoring filters and sorting)
- **Open Selection as Spreadsheet:** data in selected cells



The screenshot shows a database tool interface with a data grid. The grid has columns for actor information and a timestamp. A context menu is open over the grid, showing options to export the data as a spreadsheet. The menu options are:

- Open Visible as Spreadsheet... (Ctrl+Alt+X)
- Open as Spreadsheet...
- Open Selection as Spreadsheet...

The data grid contains the following information:

Actor ID	First Name	Last Name	Last Update
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
6	BETTE	NICHOLSON	2006-02-15 04:34:33
7	GRACE	MOSTEL	2006-02-15 04:34:33
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
9	JOE	SWANK	2006-02-15 04:34:33
10	CHRISTIAN	GABLE	2006-02-15 04:34:33

The second screenshot shows the same data grid with a different context menu open. The menu options are:

- Select All (Ctrl+A)
- Inverse Selection (Ctrl+Shift+A)
- Select Row(s) (Ctrl+Shift+J)
- Copy Selection (Ctrl+C)
- Copy Selection with Column Header (Ctrl+H)
- Copy Selection As >
- Export >
- Open as Spreadsheet >
- Print >
- Save Selected Cell... (Ctrl+Shift+S)

The 'Open as Spreadsheet' option is expanded, showing the same three options as the first screenshot:

- Open Visible as Spreadsheet... (Ctrl+Alt+X)
- Open as Spreadsheet...
- Open Selection as Spreadsheet...

13.1 Output

The spreadsheet includes the SQL query that created the data, preserves data types and attempts to adjust columns as necessary.



	A	B	C	D
1	ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
2	5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
3	6	BETTE	NICHOLSON	2006-02-15 04:34:33
4	7	GRACE	MOSTEL	2006-02-15 04:34:33
5	8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
6				

Sheet1 | Sheet1-SQL (+)

	A	B	C	D
1	SELECT * FROM "SAKILA"."ACTOR"			
2				
3				
4				
5				
6				

Sheet1 | Sheet1-SQL

14 Comparing Data



Only in DbVisualizer Pro


This feature is only available in the DbVisualizer Pro edition.

With DbVisualizer, you can compare grids and text data, such as scripts or the DDL for two tables or procedures.

- [Selecting the Objects to Compare](#)
- [Comparing Text Data](#)
- [Comparing Grids](#)
- [Comparing Cell Values](#)

14.1 Selecting the Objects to Compare

You can open the **Compare Objects** object chooser via **Tools->Compare...** and select two objects available for comparison.



If you select **Editor**, all **SQL Commander** editors and all **Object View** sub tabs that you have opened that contain text, such as **DDL** , **SQL Editor** , and **Procedure Editor** tabs, are listed. There is also an entry for the **System Clipboard**, holding the last text you copied.

Selecting **Grids** lists all **SQL Commander** Result Set tabs and all **Object View** sub tabs that you have opened that contain a grid, for instance the **Data** and **Columns** tabs for a table, or the **Tables** tab for a schema.


To compare two objects, select one each in the **Left Object** and **Right Object** columns and click **Compare**.

You can also open the object selection dialog from the **Compare...** item in the right-click menu inside a tab that holds an object that can be compared. The object shown in that tab is then preselected as the **Right Object** so you only need to select the **Left Object** in the dialog.

The right-click menu for an **SQL Commander** editor also contains a **Compare to Saved** entry. This bypasses the object selection dialog and opens the **Compare** window directly, showing you how you have changed the script since loading it into the editor.

14.2 Comparing Text Data

To compare text data, either select both text object from the **Tools->Compare** dialog or choose **Compare** from the right-click menu in one of them and select the one to compare to. The text compare window shows you how they differ.





The objects are shown side-by-side, with indications about how they differ in the divider between them. The margin areas outside the left and right objects have markings that also show sections of differences. You can navigate between the differences using the arrow buttons in the toolbar, or by clicking the markings to the left and right.

Comparing two texts is pretty straightforward. You can see what has been changed, inserted and deleted, with row level indications in the divider and details for changed text highlighted in the text panes. A difference may start on one line and span over multiple lines until a match is found again.

If the right object is editable, you can apply the changes needed to remove the differences, one by one or all at once.

Along with the difference indications in the divider there are small icons: arrows and cross marks. Clicking on such an icon updates the modified object to match the original object, by inserting or deleting one or more rows or updating the text or column values.

If you want to apply all changes needed to make the right object match the left object, you can click on the **Sync** button in the toolbar (the second to rightmost button).

You can also edit the right object directly in the **Compare** window.

i No matter how you update the right object, all changes are also applied to the tab where the object was originally opened. To permanently save the changes, you need to use the **Save** button in that tab.

If you want to change sides when comparing objects, you can click the **Flip** button in the toolbar (the rightmost button). One reason for doing this may be that you want to update the object you originally used as the original instead of the modified object.

14.3 Comparing Grids

To compare grids, either select both grid object from the **Tools->Compare** dialog or choose **Compare** from the right-click menu in one of them and select the one to compare to. The **Compare Grids** window shows you how they differ.

Compare Grids

Left Object: 1: actor [200]
Editable: false

Right Object: Sakila DB (H2 embedded): ACTOR*: Data*
Editable: true

ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
6	BETTE	NICHOLSON	2006-02-15 04:34:33
7	GRACE	MOSTEL	2006-02-15 04:34:33
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
9	JOE	SWANK	2006-02-15 04:34:33
10	CHRISTIAN	GABLE	2006-02-15 04:34:33
11	ZERO	CAGE	2006-02-15 04:34:33
12	KARL	BERRY	2006-02-15 04:34:33
13	UMA	WOOD	2006-02-15 04:34:33
14	VIVIEN	BERGEN	2006-02-15 04:34:33

ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	JIM	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
5	BETTE	NICHOLSON	2006-02-15 04:34:33
6	GRACE	MOSTEL	2006-02-15 04:34:33
7	MATTHEW	JOHANSSON	2006-02-15 04:34:33
8	JOE	SWANK	2006-02-15 04:34:33
9	(null)	BETTE	(null)
10	CHRISTIAN	GABLE	2006-02-15 04:34:33
11	ZERO	CAGE	2006-02-15 04:34:33
12	KARL	BERRY	2006-02-15 04:34:33
13	UMA	WOOD	2006-02-15 04:34:33
14	VIVIEN	BERGEN	2006-02-15 04:34:33

3 changes

Legend: Changed (blue), Inserted (green), Deleted (grey), Ignored (red)

Comparing grids is a bit complicated, since each row is a unit in itself, with a unique identifier in the form of a Key. A difference can therefore not span rows. It is also important that both grids are sorted the same way and that the column in one grid is compared to the corresponding column in the other grid, otherwise the result is indeterminably. By default, columns are matched by name, or index if the names differ.

If the default matching is not correct, click the **Column Configuration** button in the toolbar to manually match the columns, and optionally select key columns and ignore some columns.



Column Configuration

Select the **Right Column Name** that matches the **Left Column Name** and mark which column(s) to use as a **Key Column**. You can also mark columns to ignore.

Left Column Name	Right Column Name	Key Column	Ignored Column
actor_id	ACTOR_ID	<input checked="" type="checkbox"/>	<input type="checkbox"/>
first_name	FIRST_NAME	<input type="checkbox"/>	<input type="checkbox"/>
last_name	LAST_NAME	<input type="checkbox"/>	<input type="checkbox"/>
last_update	LAST_UPDATE	<input type="checkbox"/>	<input type="checkbox"/>
photo	<input type="checkbox"/> ACTOR_ID <input type="checkbox"/> FIRST_NAME <input type="checkbox"/> LAST_NAME <input checked="" type="checkbox"/> LAST_UPDATE	<input type="checkbox"/>	<input checked="" type="checkbox"/>

Close

Use the **Right Column Name** drop down lists to select the column matching the **Left Column Name**. If a column does not match another, just leave it blank to exclude it from the comparison.

Use the **Key Column** check boxes to pick the columns that should be used as the key when comparing the grids. If you don't care about the value in some columns, e.g. a column that contains a timestamp that may vary between the grids without being an important difference, you can check the **Ignore Column** check box for that column to exclude it for the comparison.

It gets a bit more complicated if a key column value is changed.

Compare Grids

Left Object: **1: actor [200]**
 Editable: false

Right Object: **Sakila DB (H2 embedded): ACTOR*: Data***
 Editable: true

ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE			ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE		
1	PENELOPE	GUINNESS	2006-02-15 04:34:33	1	1	1	PENELOPE	GUINNESS	2006-02-15 04:34:33		
2	NICK	WAHLBERG	2006-02-15 04:34:33	2	2 x	0	NICK	WAHLBERG	2006-02-15 04:34:33		
3	ED	CHASE	2006-02-15 04:34:33	3	3	3	ED	CHASE	2006-02-15 04:34:33		
4	JENNIFER	DAVIS	2006-02-15 04:34:33	4	4	4	JENNIFER	DAVIS	2006-02-15 04:34:33		
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33	5	5	5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33		
6	BETTE	NICHOLSON	2006-02-15 04:34:33	6	6	6	BETTE	NICHOLSON	2006-02-15 04:34:33		
7	GRACE	MOSTEL	2006-02-15 04:34:33	7	7	7	GRACE	MOSTEL	2006-02-15 04:34:33		
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33	8	8	8	MATTHEW	JOHANSSON	2006-02-15 04:34:33		
9	JOE	SWANK	2006-02-15 04:34:33	9	9	9	JOE	SWANK	2006-02-15 04:34:33		
10	CHRISTIAN	GABLE	2006-02-15 04:34:33	10	10	10	CHRISTIAN	GABLE	2006-02-15 04:34:33		
11	ZERO	CAGE	2006-02-15 04:34:33	11	11	11	ZERO	CAGE	2006-02-15 04:34:33		
12	KARL	BERRY	2006-02-15 04:34:33	12	12	12	KARL	BERRY	2006-02-15 04:34:33		
13	UMA	WOOD	2006-02-15 04:34:33	13	13	13	UMA	WOOD	2006-02-15 04:34:33		
14	VIVIEN	BERGEN	2006-02-15 04:34:33	14	14	14	VIVIEN	BERGEN	2006-02-15 04:34:33		

2 changes

Changed Inserted Deleted Ignored

DbVisualizer considers a changed key value as one inserted row and one deleted row, as shown in the figure above. If the grids do not have any declared key columns, all columns are considered to be regular, non-key columns.

Two grids may also differ in the number of columns they contain. DbVisualizer finds columns that only exist in one of the grids and excludes their values when comparing the grids. If the column names do not match between the two grids, open the **Column Configuration** dialog to manually map the columns.



Compare Grids

There are no differences

Left Object: 1: ACTOR [200]
Editable: false

ACTOR_ID	FIRST_NAME	LAST_NAME
1	PENELOPE	GUINNESS
2	NICK	WAHLBERG
3	ED	CHASE
4	JENNIFER	DAVIS
5	JOHNNY	LOLLOBRIGIDA
6	BETTE	NICHOLSON
7	GRACE	MOSTEL
8	MATTHEW	JOHANSSON
9	JOE	SWANK
10	CHRISTIAN	GABLE
11	ZERO	CAGE
12	KARL	BERRY
13	UMA	WOOD
14	VIVIEN	BERGEN

No change

Right Object: Sakila DB (H2 embedded): ACTOR: Data
Editable: true

ACTOR_ID	FIRST_NAME	LAST_NAME	LAST_UPDATE
1	PENELOPE	GUINNESS	2006-02-15 04:34:33
2	NICK	WAHLBERG	2006-02-15 04:34:33
3	ED	CHASE	2006-02-15 04:34:33
4	JENNIFER	DAVIS	2006-02-15 04:34:33
5	JOHNNY	LOLLOBRIGIDA	2006-02-15 04:34:33
6	BETTE	NICHOLSON	2006-02-15 04:34:33
7	GRACE	MOSTEL	2006-02-15 04:34:33
8	MATTHEW	JOHANSSON	2006-02-15 04:34:33
9	JOE	SWANK	2006-02-15 04:34:33
10	CHRISTIAN	GABLE	2006-02-15 04:34:33
11	ZERO	CAGE	2006-02-15 04:34:33
12	KARL	BERRY	2006-02-15 04:34:33
13	UMA	WOOD	2006-02-15 04:34:33
14	VIVIEN	BERGEN	2006-02-15 04:34:33

Legend: Changed (blue), Inserted (green), Deleted (grey), Ignored (red)

Similarly, DbVisualizer does not consider Binary/BLOB and CLOB columns when comparing, and marks them as ignored. You can manually specify that CLOB columns should be compared in the Column Configuration dialog.

Compare Grids

There are no differences

Left Object: Sakila DB (H2 embedded): STAFF: Data
Editable: false

STAFF_ID	FIRST_NAME	LAST_NAME	ADDRESS_ID	PICTURE	EMAIL
1	Mike	Hillyer	3	BINARY, 36,365 Bytes	Mike.Hi
2	Jon	Stephens	4	(null)	Jon.Ste

No change

Right Object: 1: staff [2]
Editable: true

STAFF_ID	FIRST_NAME	LAST_NAME	ADDRESS_ID	PICTURE	EMAIL
1	Mike	Hillyer	3	BINARY, 36,365 Bytes	Mike.Hi
2	Jon	Stephens	4	(null)	Jon.Ste

Legend: Changed (blue), Inserted (green), Deleted (grey), Ignored (red)

Unable to render include or excerpt-include. Could not retrieve page.

14.4 Comparing Cell Values

In a Data tab or a result set tab, you can also compare the values of two selected cells.

1. Select the two cells to compare,
2. Choose **Compare Two Selected Cells** from the right-click menu.

The values are compared and shown the same way as when comparing text data, with the exception that editing is disabled.

15 Monitoring Data Changes

With the monitor feature, you can track changes in data over time, viewing the results of one or many SQL statements either as grids or graphs. Typically, you configure the monitor to run the statements automatically at certain intervals.

The monitoring feature combined with the [charting](#) capability in DbVisualizer Pro is really powerful, delivering real time charts of many result sets simultaneously. For example, you can use monitoring to spot trends in a production database, surveillance, statistics, database metrics, and so on.

Any SQL statement that produces a result set can be monitored, and when you monitor multiple statements, different statements may use different database connections concurrently.

15.1 Creating a Monitored Query

Monitored SQL statements are managed under the **Monitors** node in the **Scripts** tab in the tree area to the left in the main DbVisualizer window.

- [Monitor table row count](#)
- [Monitor table row count difference](#)



A monitored SQL statement is associated with information about the target database connection and (optionally) the catalog (the JDBC term which translates to a database for some databases, like Sybase, MySQL, SQL Server, etc) and schema. It also has a title, a maximum row count (how many results to keep track of) and a visibility status (whether the monitored statement result should be included in the Monitors windows, discussed below). This information is displayed, and can be edited, in the lower part of the **Scripts** tab, along with information about the file that holds the monitored statement. If you don't want to see these details, you can disable it with the **Show Details** toggle control in the right-click menu for a node.

The screenshot displays the DbVisualizer SQL Editor interface. The main window shows a SQL query in the 'Lab 1: Incidents.sql' script:

```
1 SELECT
2   YEAR(tdate) AS YEAR,
3   MONTH(tdate) AS MONTHNUM,
4   CAST(concat(YEAR(tdate), ' ', date_format(tdate, '%b')) AS CHAR) AS MONT
5   SUM(INCIDENTS) AS 'COUNT'
6 FROM
7   bughouse
8 GROUP BY
9   YEAR,
10  MONTHNUM
11 ORDER BY
12  YEAR ASC,
13  MONTHNUM ASC
```

The left sidebar shows the 'Scripts' tab with a tree view of 'Monitors' containing several SQL files, with 'Incidents.sql' selected. Below the tree is a 'File' panel showing details for 'Incidents.sql':

Name	Incidents.sql
Comment	
Size (bytes)	263
Modified	2016-06-09 14:24:28
Path	C:\Users\hans\,dbvis\Mon...
Encoding	Cp1252

The 'Database Connection' panel shows:

Connection	Lab
Catalog	test
Schema	

The 'Monitor' panel shows:

Title	Incidents/Day
Visible	<input checked="" type="checkbox"/>
Max Row Count	100

The bottom of the interface shows a 'Log' panel with a table header:

Time	Status	Command	Exec	Fetch	Rows	Message	SQL/Command
There are no current log entries							

The status bar at the bottom indicates '0s 0 of 0' and '0/8 0-0'.

The figure above shows the Incidents/Day monitored statement and the SQL that is associated with it.

The following is an example of the result set produced by the statement:



*	YEAR	MONTHNUM	MONTH	COUNT
1	2014	8	2014 Aug	269
2	2014	9	2014 Sep	467
3	2014	10	2014 Oct	244
4	2014	11	2014 Nov	549
5	2014	12	2014 Dec	433
6	2015	1	2015 Jan	443
7	2015	2	2015 Feb	837
8	2015	3	2015 Mar	593
9	2015	4	2015 Apr	511
10	2015	5	2015 May	349
11	2015	6	2015 Jun	437
12	2015	7	2015 Jul	300
13	2015	8	2015 Aug	417
14	2015	9	2015 Sep	581
15	2015	10	2015 Oct	375

The interesting columns in the result are the **Month** and **Count**. The **Year** and **MonthNum** are there just to get the correct ascending order of the result.

You can create and work with monitored statements in the same way as with a Bookmark. The main difference is how they are used and a couple of additional ways monitored statements can be created. For information about how to manually create, manage and share monitored statements, please see the [Managing Frequently Used SQL](#) page. The following sections describe how you can get help creating the bookmarks for a couple of cases that are commonly used for monitoring.

15.1.1 Monitor table row count

It is very common to want to keep track of how the number of rows in a table varies over time. The right-click menu in the grid for a table or result set therefore has a **Create Row Count Data Monitor** operation that creates a monitored statement for you automatically.

It creates a monitor with SQL for returning a single row with the timestamp for when the monitor was executed and the total number of rows in the table at that time. Every time the monitor is executed, a new row is added to the grid, up to a specified maximum number of rows. When the maximum row limit is reached, the oldest row is removed when a new row is added. Example:

PollTime	NumRows
2016-01-23 12:19:10	43123
2016-01-23 12:11:40	43139
2016-01-23 12:21:10	43143
2016-01-23 12:22:40	43184
...	...

The SQL for this monitor uses two variables, **dbvis-date** and **dbvis-time**. These variables are substituted with the current date and time, formatted according to the corresponding Tool Properties settings. The reason for using these variables instead of using SQL functions to retrieve the values is simply that it is almost impossible to get the values in a database-independent way. Another reason is that we want to see the client machine time rather than the database server time. You can, of course, modify the SQL any way you see fit, as long as the **PollTime** and **NumRows** labels are not changed.



```
SELECT '${dbvis-date}$ ${dbvis-time}$' AS PollTime,
       COUNT(*) AS NumRows
FROM ORDERS
```

DbVisualizer keeps the result for previous executions from the Monitor, up to the specified maximum number of rows, so that you can see how the result changes over time. You define the maximum number of rows in the **Max Row Count** field in the details area at the bottom of the Scripts tab. This property is initially set to 100 when you use **Create Row Count Data Monitor** to create the monitor.

The screenshot shows the DbVisualizer interface with the 'Scripts' tab selected. Under 'Monitors', the file 'ORDERS-Row Count.sql' is highlighted. The configuration details for this monitor are as follows:

File	
Name	ORDERS-Row Count.sql
Comment	
Size (bytes)	83
Modified	2016-06-09 15:48:35
Path	C:\Users\hans\.dbvis\Monitors\ORDER...
Encoding	✓ Cp1252
Database Connection	
Connection	CRM Ahoa
Catalog	
Schema	HR
Monitor	
Title	ORDERS: Row Count
Visible	<input checked="" type="checkbox"/>
Max Row Count	100

You can change the value to limit or extend the number of rows that DbVisualizer should keep. Setting it to 0 or a negative number tells DbVisualizer to always clear the grid between executions of monitors.

15.1.2 Monitor table row count difference

In addition to tracking the number of rows in a table over time, you may want to see by how many rows the value changes. You can create a monitor for this purpose with the **Create Row Count Diff Data Monitor** operation, available in the right-click menu for the grid.

In addition to the **Row Count Monitor**, the **Row Count Diff Monitor** reports the difference between the number of rows in the last two executions:

PollTime	NumRows	NumRowsChange
2016-01-23 12:19:10	43123	0
2016-01-23 12:11:40	43139	16



PollTime	NumRows	NumRowsChange
2016-01-23 12:21:10	43143	4
2016-01-23 12:22:40	43184	41
...

The SQL for this monitor adds a third column, named **NumRowsChange**. It utilizes the fact that DbVisualizer automatically creates variables for the columns in a monitor result set, holding the values from the previous execution. The **NumRowsChange** column is set to the value returned by the `count(*)` aggregate function for the current execution minus the value from the previous execution, held by the **NumRows** variable. All columns in a monitor result set can be used like this to reference values from the previous execution of the monitor.

```
SELECT '${dbvis-date}$ ${dbvis-time}$' AS PollTime,
       COUNT(*) AS NumRows,
       COUNT(*) - ${NumRows}||count(*) AS NumRowsChange
from ORDERS
```

15.2 Running a Monitored Query

The Monitor window, launched via the **Tools->Monitor** menu option, is where you active monitors and look at the results. The monitor tabs can be rearranged in the same way as all other tabs, pretty much any way you like. Please see [Getting the Most Out of the GUI](#) for details.

The monitor results can be viewed only as grids in DbVisualizer Free, while DbVisualizer Pro adds the capability to view them as charts or text.

*	YEAR	MONTHNUM	MONTH	COUNT
1	2014	8	2014 Aug	269
2	2014	9	2014 Sep	467
3	2014	10	2014 Oct	244
4	2014	11	2014 Nov	549
5	2014	12	2014 Dec	433
6	2015	1	2015 Jan	443
7	2015	2	2015 Feb	837
8	2015	3	2015 Mar	593
9	2015	4	2015 Apr	511
10	2015	5	2015 May	349
11	2015	6	2015 Jun	437
12	2015	7	2015 Jul	300
13	2015	8	2015 Aug	417

0.000/0.000 sec 34/4 1-13

The Monitor window has a toolbar at the top with an **Auto Reload Interval** field and a **Adjust** box. The **Auto Reload Interval** field is used to control how often, in seconds, to execute the monitors when auto update is running. The specified number of seconds may be increased automatically by DbVisualizer if the total execution time for all monitors is longer than the specified value. Check the **Adjust** box and the Monitor feature will automatically increase the number of seconds so that all monitors will complete before next auto-update.

The rest of the window holds result areas for each monitored statement with the **Visible** attribute enabled. Each individual monitor result tab or window may also have a toolbar with controls that apply just to that result. The screenshot is from DbVisualizer Pro, with **View** buttons in the toolbar for the selected monitor; these buttons are not included in DbVisualizer Free.

When auto reload is running, there is a progress bar shown to the left of the **Auto Reload Interval** field. This progress bar is only shown when auto update is running.



The main toolbar buttons have the following functions:

Toolbar Button	Description
Close	Closes the Monitor window
Reload	Reloads all results (i.e., executes all monitors and updates the result sets)
Locate Current	Locates and select the monitor node in the Scripts tab corresponding to the currently selected result
Clear Current	Clears the currently selected result
Clear All	Clears all results
Show as Tabs	Shows the results as collapsed tabs
Show as Windows	Shows the results as tiled tabs
Show Grids	Shows all results as grids
Show Text	Shows all results as text
Show Chart	Shows all results as graph in the selected chart type
Show/Hide Chart Legends	Toggle this to show/hide chart legends
Show/Hide Monitor Toolbars	Toggle this to show/hide toolbars for each monitor
Start Monitors	Starts auto-update of all monitors, repeatedly executing all statements at the intervals specified by the Auto Reload Interval field
Stop Monitors	Stops the auto-update

In the Tool Properties dialog, you can enable **Show Monitor Window at Startup** and **Start Monitors Automatically**, in the **Monitor** category under the General tab.

16 Accessing Frequently Used Objects

When you work on many different tasks, it is important to easily find and use the data and scripts you need.

DbVisualizer helps you by keeping the tabs you use open between sessions and letting you organize references to objects and scripts.

16.1 Keeping Tabs Open Between Sessions

If you often work with the same objects and a few scripts, you can ensure that the Object View and SQL Commander tabs for these objects remain open between DbVisualizer sessions.

1. Open **Tools->Tool Properties**,
2. Select the **Tabs** category,
3. Enable one or both of **Preserve SQL Commander tabs between Sessions** and **Preserve Object View tabs between Sessions**,
4. Click **Apply** or **OK** to apply the new settings.

This feature is enabled by default for SQL Commander tabs but not for Object View tabs.

The content of the SQL Commander tabs is saved at regular intervals so when you restart DbVisualizer, the content is the same as where you left off.

For Object View tabs, you can also enable **Preserve Object View tabs at Disconnect**. By default, Object View tabs for objects that belong to a connection are closed when it is disconnected.

16.2 Using Favorites




Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.




Navigating the **Databases** tab tree down to the object can be quite time consuming for database objects that you work with often. By adding these objects to the Favorites toolbar, you have one-click access to them instead. In addition to database objects, you can also add **Bookmark** script files to the Favorites toolbar.




When you click on a database object in the Favorites toolbar, the corresponding object is opened in an Object View tab. If you're not connected to the database the object belongs to, a connection is automatically established. Clicking on a Bookmark in the Favorites toolbar opens it in an SQL Commander tab.

You can also easily find the corresponding object in the **Databases** tab or **Scripts** tab tree using the **Select Target Object** right-click menu item.




The easiest way to add an item to the Favorites toolbar is to select the item in the **Databases** tab tree or the **Script** tab tree, drag it with the mouse key depressed and drop it in the Favorites toolbar by releasing the mouse button. If you have created Favorite folders, you can also drop the item on a folder.

You can also use the **Add to Favorite** right-click menu operation for the database object or Bookmark. This opens a dialog where you can add the item, at the top level or in an existing or new Favorite folder.




Use the **Favorites** tab in the navigation area to organize your favorites.



Here you can add folders and drag and drop entries between them. A favorite folder works as a drop-down menu in the Favorites toolbar. Double-click a favorite to open the target script file in the SQL Commander or database object in the Object View.

You can also delete and rename entries here. The right-click menu for an entry also contains entry-type dependent operations, such as executing a Bookmark and open a database object in a separate window.

To sort the favorites, select **Sort...** from the right-click menu for any favorite. The sorting criteria can be defined in the dialog that pops up.





16.3 Using Scripts

A script is a file with one or more SQL statements that you can edit and execute in an SQL Commander tab. You can keep a script as an ordinary file anywhere in the file system and [load it into an SQL Commander tab](#) when needed, but managing it as a [Bookmark](#) under the Scripts tab is more convenient as it also keeps information about which connection you used it with last, among other things.

17 Delimited Identifiers and Qualifiers

Delimited Identifiers must generally be used for database object with names that contain special characters, reserved words or mixed case. Qualifiers are needed when referring to an object in a different schema/catalog than the current one. DbVisualizer uses delimited, qualified identifiers in all SQL it automatically executes in response to user interaction, such as when loading the Data tab for a table, dropping a stored procedure or getting metadata for a DDL statement.

For the features where DbVisualizer generates SQL that you can then execute, you can control if you want to use delimited identifiers and/or qualified object names. In the Properties tab for a connection, or in the Tool Properties dialog for a database type under the Database tab, you find the **Delimited Identifiers** and **Qualifiers** categories.

In the Delimited Identifiers category you can specify which delimiter characters to use, e.g. double-quotes or square brackets, and for which features to use them: **Scripting** (all SQL generating features), **Auto Completion/Query Builder**, **Export**, and **Actions**.

In the Qualifiers category you can specify for which features to use them, and also if column names should be qualified with the table name for the Scripting and the Auto Completion/Query Builder features. For database types that supports fully qualified named (both database and schema qualifiers), you can enable fully qualified names in the References/Navigator Graphs and for the Auto Completion/Query Builder features.

18 Handling Transactions

Database transactions are intended to make sure operations performed simultaneously do not cause data integrity problems.

By default, DbVisualizer commits all changes immediately but you can disable this to have full control over the transactions. You can also set an appropriate transaction isolation level for your connections.

18.1 Changing the Auto Commit Setting

Auto Commit means that each SQL statement successfully executed in an SQL Commander is committed automatically, permanently changing the database. This is the default for a connection, but you can change it at different levels.

- [Changing Auto-Commit for a Database Type](#)
- [Changing Auto-Commit for a Connection](#)
- [Changing Auto-Commit for an SQL Commander tab](#)
- [Changing Auto-Commit for a Statement Block](#)

18.1.1 Changing Auto-Commit for a Database Type

1. Open **Tools->Tool Properties**,
2. Select the **Database** tab,
3. Expand the node for the database type, e.g. **Oracle**,
4. Select the **Transaction** category,
5. Uncheck the **Auto Commit** checkbox.

18.1.2 Changing Auto-Commit for a Connection

1. Double-click the connection node in the **Databases** tab tree to open an **Object View** tab,
2. Select the **Properties** tab,
3. Select the **Transaction** category under the node for the database type, e.g. **Oracle**,
4. Uncheck the **Auto Commit** checkbox.

18.1.3 Changing Auto-Commit for an SQL Commander tab

- Use the **SQL Commander->Transaction->Turn On/Off Auto Commit** toggle item, or,
- Use the corresponding toggle button to the right in the SQL Commander toolbar.



18.1.4 Changing Auto-Commit for a Statement Block

You can use the `@set autocommit` command in a script to enable or disable auto commit for different blocks:

```

@set autocommit off;
INSERT INTO SCOTT.EMP (EMPNO, ENAME, JOB, MGR, HIREDATE) VALUES (61, 'Boo', 2, 1, '2013-06-20');
INSERT INTO SCOTT.EMP (EMPNO, ENAME, JOB, MGR, HIREDATE) VALUES (62, 'Hoo', 2, 1, '2013-07-01');
INSERT INTO SCOTT.EMP (EMPNO, ENAME, JOB, MGR, HIREDATE) VALUES (63, 'Zoo', 2, 1, '2013-07-04');
@set autocommit on;

```

18.2 Setting Transaction Isolation

When you connect to a database that is concurrently modified by other users and processes, the Transaction Isolation Level specifies how changes made by others will affect you and how your changes will affect others.

To set the Transaction Isolation Level for a connection,

1. Double-click the connection node in the **Databases** tree to open an **Object View** tab for it,
2. Select the **Properties** tab,
3. Select the **Transaction** category,
4. Pick an appropriate **Transaction Isolation Level** from the drop-down list.

The levels that are supported depends on the database you are connecting to. Many databases support the levels as defined in the JDBC specification, which are described in the table below. But be aware that there are also many databases that have their own levels and/or terminology.

Level	Transactions	Dirty Reads	Non-Repeatable Reads	Phantom Reads
TRANSACTION_NONE	Not supported	N/A	N/A	N/A
TRANSACTION_READ_COMMITTED	Supported	Prevented	Allowed	Allowed
TRANSACTION_READ_UNCOMMITTED	Supported	Allowed	Allowed	Allowed
TRANSACTION_REPEATABLE_READ	Supported	Prevented	Prevented	Allowed
TRANSACTION_SERIALIZABLE	Supported	Prevented	Prevented	Prevented

A dirty read occurs when transaction A reading a value before transaction B has made permanent, i.e. before it has been committed.

A non-repeatable read occurs when transaction A retrieves a row, transaction B subsequently updates the row, and transaction A later retrieves the same row again. Transaction A retrieves the same row twice but sees different data.

A phantom read occurs when transaction A retrieves a set of rows satisfying a given condition, transaction B subsequently inserts or updates a row such that the row now meets the condition in transaction A, and transaction A later repeats the conditional retrieval. Transaction A now sees an additional row. This row is referred to as a phantom.

Please see the database documentation for the description of transaction isolation values supported by your database.

19 Database Connection Options

The database connection is a central concept in DbVisualizer.

Learn how to configure it to your needs, how to use special features like connecting through an SSH tunnel, using Single-Sign-On, organizing the connections, and much more.


19.1 Setting Up a Connection Manually

To access a database with DbVisualizer, you must first create and setup a Database Connection. The easiest way to set up a connection is to use the [Connection Wizard](#), but you can also do it manually.




19.1.1 Setting Up a Connection Manually

1. Create a new connection from **Database->Create Database Connection** and click **No Wizard** when prompted. An **Object View** tab for the new connection is opened,



2. Enter a name for the connection in the **Name** field, and optionally enter a description of the connection in the **Notes** field,
3. Leave the **Database Type** as **Auto Detect**,
4. Select an installed **JDBC driver** (marked with a green checkmark) from the Driver (JDBC) list (see [Installing a JDBC Driver](#) for how to install a JDBC driver manually),
5. Enter information about the database server in the remaining fields (see below for details),
6. Verify that a network connection can be established to the specified address and port by clicking the **Ping Server** button,
7. If Ping Server shows that the server can be reached, click **Connect** to actually connect to the database server.

 See [Fixing Connection Issues](#) for some tips if you have problems connecting to the database.

Alternatively, you can set the **Settings Format** to **Database URL** (this is the only choice for some custom JDBC drivers). This replaces the fields for information about the database server with a single **Database URL** field, where you can enter the JDBC URL.



The information about the database server that needs to be entered depends on the which JDBC driver you use. For most drivers, you need to specify:

Field	Description
Database Server	The IP address or DNS name for the server where the database runs.
Database Port	The TCP/IP port used by the database.
Database Userid	The database user account name. Enter (null) to not send an account name.
Database Password	The database user account password. Enter (null) to not send a password.

For some database such as Oracle, you may use a [TNS name](#) instead of specifying the server and port. Other drivers may add more fields that are driver specific.

You may also optionally specify [SSH tunneling information](#) and Options, such as:

Option	Description
Auto Commit	Check if you want to enable auto commit in the SQL Commander by default for the connection.
Save Database Password	Check if you want the password to be saved (encrypted) during the session, between sessions, or cleared when you disconnect.
Permission Mode	One of Development , Test or or Production to select which set of Permissions to use.

Additional options are available for some JDBC drivers, such as [Authentication Domain](#) for the SQL Server jTDS driver.

See the [Configuring Connection Properties](#) page for related topics.

19.2 Configuring Connection Properties


- [Tool Properties](#)
- [Connection Properties](#)
 - [Database Profile](#)
 - [Driver Properties](#)
 - [Invoke Java methods in the JDBC driver](#)

In addition to the [basic connection information](#) in the **Connection** tab, there is also a collection of connection properties. Which properties are available depends on the **Database Type** selected for the database connection in the Connection tab. Some database types have more properties than others. Which edition of DbVisualizer you use also affects which connection properties are available.

Properties for a connection can be defined at two different levels: **Tool Properties (Database tab)** and **Connection Properties**.

19.2.1 Tool Properties

The Database tab in **Tool Properties** defines settings for all connections of the specific database type. All supported database types (Oracle, Informix, SQL Server, DB2, MySQL, etc.) are listed, and for each database type there are a number of properties that are applied to any database connection of that type. This means, for instance, that a database connection defined as being a PostgreSQL database type will use the PostgreSQL properties defined in **Tool Properties**.



19.2.2 Connection Properties

The global properties can be overridden for individual connections. The advantage with this inheritance model is that property changes that apply to all connections can be made in one place, instead of having to apply a common setting for every database connection of a specific database type.

The Connection Properties are available in the **Properties** sub tab in the the database connection's **Object View** tab.



The screenshot shows the 'Properties' tab of a database connection configuration window. The left sidebar contains a tree view with the following categories: Connection Properties, Database Profile, Driver Properties, MySQL (selected), Authentication, Delimited Identifiers, Qualifiers, Physical Connection, Transaction, Encoding, SQL Statements, Connection Hooks, Color and Border, SQL Commander, and Query Builder. The main area displays three sections: 'Permission Mode' with radio buttons for Development (selected), Test, and Production; 'Connect when "Connect All"' with a checkbox; and 'JDBC Fetch Size' with a text input field containing '0' and a note '(Driver default is 5,000 rows)'. A 'Global Properties' link is visible in the top right corner of the main area.

The **Properties** tab is organized basically the same way as the **Tool Properties** window. The main difference is that the list contains only the categories that are applicable to this database connection. The **Database Profile** and **Driver Properties** categories are available only in the **Properties** tab and not in **Tool Properties**. The page explains the **Database Profile** and **Driver Properties** categories, while the other categories are described in pages that describe feature the property applies to.

Additional categories may appear in the connection properties depending on the type of database. An example is the category for Explain Plan for the databases where this feature is supported.

At the top right corner, you will also find a link to set the [Global Properties](#) for all connections of this database type.

Database Profile

The [Database Profile](#) category is used to select whether a profile should be automatically detected and loaded by DbVisualizer, or if a specific one should be used for the database connection. The default strategy is to **Auto Detect** a database profile.



Connection Properties Database Info Data Types Search

Connection Properties

- Database Profile
- Driver Properties
 - MySQL
 - Authentication
 - Delimited Identifiers
 - Qualifiers
 - Physical Connection
 - Transaction
 - Encoding
 - SQL Statements
 - Connection Hooks
 - Color and Border
 - SQL Commander
 - Query Builder

Database Profiles

Database profiles in DbVisualizer Pro controls what objects appear in the objects tree, what detailed views are available for each object type and actions used to operate on objects. A database profile is database specific and here you can either decide to let DbVisualizer automatically pick (recommended) the matching profile based on the database type setting or manually choose one. If manually choosing a profile make sure it is compatible with the database you are connecting to. The generic profile works with any database. Note: You must reconnect the database connection after changing profile.

Auto Detect
 Manually Choose
 "Generic" Profile

Profile	Description	Path
db2	Profile for DB2 LUW	D:\Program Files\DbVisualizer BETA\resources\profiles\db2.xml
db2-zos	Profile for DB2 z/OS	D:\Program Files\DbVisualizer BETA\resources\profiles\db2-zos.xml
derby	Profile for Derby	D:\Program Files\DbVisualizer BETA\resources\profiles\derby.xml
exasol	Profile for Exasol	D:\Program Files\DbVisualizer BETA\resources\profiles\exasol.xml
generic	Generic profile for any database	D:\Program Files\DbVisualizer BETA\resources\profiles\generic.xml
h2	Profile for H2	D:\Program Files\DbVisualizer BETA\resources\profiles\h2.xml
informix	Profile for Informix IDS	D:\Program Files\DbVisualizer BETA\resources\profiles\informix.xml
mariadb	Profile for MariaDB	D:\Program Files\DbVisualizer BETA\resources\profiles\mariadb.xml
mimer	Profile for Mimer SQL	D:\Program Files\DbVisualizer BETA\resources\profiles\mimer.xml
mysql	Profile for MySQL	D:\Program Files\DbVisualizer BETA\resources\profiles\mysql.xml
netezza	Profile for IBM Netezza	D:\Program Files\DbVisualizer BETA\resources\profiles\netezza.xml
nuodb	Profile for NuoDB	D:\Program Files\DbVisualizer BETA\resources\profiles\nuodb.xml
oracle	Profile for Oracle	D:\Program Files\DbVisualizer BETA\resources\profiles\oracle.xml
postgresql	Profile for PostgreSQL	D:\Program Files\DbVisualizer BETA\resources\profiles\postgresql.xml
postgresql8	Profile for PostgreSQL 8+	D:\Program Files\DbVisualizer BETA\resources\profiles\postgresql8.xml
redshift	Profile for Amazon Redshift	D:\Program Files\DbVisualizer BETA\resources\profiles\redshift.xml
snowflake	Profile for Snowflake	D:\Program Files\DbVisualizer BETA\resources\profiles\snowflake.xml
sqlite	Profile for SQLite	D:\Program Files\DbVisualizer BETA\resources\profiles\sqlite.xml
sqlserver	Profile for SQL Server	D:\Program Files\DbVisualizer BETA\resources\profiles\sqlserver.xml
sybase-ase	Profile for Sybase ASE	D:\Program Files\DbVisualizer BETA\resources\profiles\sybase-ase.xml
vertica	Profile for Vertica	D:\Program Files\DbVisualizer BETA\resources\profiles\vertica.xml



The way DbVisualizer auto detects a profile is based on the setting of **Database Type** in the **Connection** tab. If the **Database Type** is also set to **Auto Detect**, DbVisualizer first detects the database type based on the JDBC information, and then detects the profile based on the database type.

There is rarely a reason to use another setting than **Auto Detect**, but if you manually choose a database profile, this choice will be saved between invocations of DbVisualizer.

Driver Properties

The **Driver Properties** category is used to fine tune a JDBC driver before the database connection is established. You can use the filter to quickly find a specific property.



Driver Properties

Defines JDBC Driver or JNDI specific properties that can be used to fine tune the database connection. A pre-defined property is reverted to its default value when removing it while user defined properties are removed. The **Edited** flag indicates that the property value has been edited or that the property has been added manually.

fetch

Edited	Parameter	Value
<input checked="" type="checkbox"/>	defaultFetchSize	5000
<input type="checkbox"/>	locatorFetchBufferSize	1048576
<input type="checkbox"/>	useCursorFetch	true

The driver will call `setFetchSize(n)` with this value on all newly-created Statements

The list of parameters, their default values and parameter descriptions are determined by the JDBC driver used for the connection. Not all drivers supports additional driver properties. To change a value, just modify it in the list. The first column in the list indicates whether the property has been modified or not, and so, whether DbVisualizer will pass that parameter and value onto the driver at connect time.

New parameters can be added using the buttons to the right of the list.

Invoke Java methods in the JDBC driver

In addition to driver properties it is also possible to invoke low level Java methods in the JDBC driver classes, [java.sql.Connection](#) and [java.sql.Statement](#). These are edited in the [driver properties](#) list.

You may run single argument methods taking one of **String.class**, **Integer.class**, or **Boolean.class** Java types as argument. The method name should be specified as **Parameter** which must be fully qualified with the all lowercase class name. The argument is specified in the **Value** field in the driver properties list.

Here are a few examples:

Parameter	Value
<code>java.sql.connection.setReadOnly</code>	true
<code>java.sql.statement.setFetchSize</code>	1000

java.sql.connection methods are invoked just after a physical connection with the database has been established. **java.sql.statement** methods are invoked just after a statement has been created and ready for execution.

19.3 Copying an Existing Connection

To copy an existing connection and use as the basis for a new:

1. Select the original connection node in the **Databases** tab tree,
2. Use the **Database->Duplicate Database Connection** to create a copy,

The Object View tab for the copied connection is opened where you can make adjustments.



19.4 Edit Multiple Database Connections

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.


There are situations when you may need to change one or several connection settings for multiple database connections at the same time. Instead of doing this one connection at a time, the connections editor comes in handy.

To open the connections editor by:

- Selecting multiple database connections in the Databases tab, right-click and choose **Edit Database Connection(s)...**
- Selecting multiple database connections in the connections list shown when opening the object view for the **Connections** node. Right-click and choose **Edit Database Connection(s)...**

Note that all database connections that are to be edited must be disconnected.

The screenshot below shows how the **Connections** tab is listing all the connections. The list has been sorted on **Connection Mode** in order to make it easy to select and edit all **Production** databases.



The screenshot displays the DbVisualizer interface with the **Connections** tab active. The main window shows a list of database connections sorted by **Connection Mode**. The list includes connections for Oracle (HR/US), Oracle (HR), Oracle (CRM), Oracle (OE), Oracle (HR), H2, SQL Server, MySQL, and postgres. The **Database Connections Editor** dialog box is open, showing the properties for 4 selected database connections. The dialog has columns for **Property Name**, **Update**, and **Value**. The **Update** column contains checkboxes, and the **Value** column contains the current values for each property. The **Options** section is expanded, showing properties like **Auto Commit**, **Save Database Password**, and **Permission Mode**.

Database Connection	Folder Path	Database Type	Connection Mode	Color	Connect All	Single Physical Connection	Userid	Profile
Oracle (HR/ US)	Oracle Production/Remote	Auto Detect (Oracle)	Production		<input type="checkbox"/>	<input type="checkbox"/>	system	auto
Oracle (HR)	Oracle Production	Auto Detect (Oracle)	Production		<input type="checkbox"/>	<input type="checkbox"/>	system	auto
Oracle (CRM)	Oracle Production	Auto Detect (Oracle)	Production		<input type="checkbox"/>	<input type="checkbox"/>	system	auto
Oracle (OE)	Oracle Production	Auto Detect (Oracle)	Production		<input type="checkbox"/>	<input type="checkbox"/>	system	auto
Oracle (HR)	Test	Auto Detect (Oracle)	Development		<input type="checkbox"/>	<input type="checkbox"/>	system	auto
H2		Auto Detect (H2)	Development		<input type="checkbox"/>	<input type="checkbox"/>		auto
SQL Server		Auto Detect (SQL S...	Development		<input type="checkbox"/>	<input type="checkbox"/>	sa	auto
MySQL					<input type="checkbox"/>	<input type="checkbox"/>	dbvis	auto
postgres					<input type="checkbox"/>	<input type="checkbox"/>	postgres	auto

The connections editor will show only those fields that are commonly available for the database connections being edited.

The window has the following columns:

- **Update:** Indicates if the value is edited. You may manually uncheck this to indicate the setting should not be updated
- **Value:** Enter the new value here. Once the field is being edited its background will change and the Update box is checked.

19.4.1 Changing the database driver

The **Driver (JDBC)** setting is the main setting that controls what properties are available for a database connection. Once Driver (JDBC) has been edited its **Update** checkbox cannot be unchecked.



19.5 Removing a Connection

To remove a connection,

1. Select the connection node in the Database tab tree,
2. Use the **Database->Remove Database Connection(s)** menu choice to remove the connection.


19.6 Organizing Connections in Folders

Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

If you work with many database connections, you can use folder objects to organize and group them in the tree. Folder objects can have child folder objects in an unlimited hierarchy.

Use the **Database->Create Folder** and **Database->Remove Folder** menu choices to create and remove folder objects. You can drag and drop folders and other objects to move them to a new location in the **Databases** tab tree.



By double clicking the Folder node a tab is opened listing all the connections recursively in the folder. This is handy when you need to edit properties for multiple database connection. See the chapter [Edit Multiple Database Connections](#) for details about this.

19.7 Rearranging Connections and Folders

You can sort the nodes under the **Connections** node or a folder node in the Databases tab:

1. Select the Connections node or a folder node,
2. Open the **Sort...** dialog from the right-click menu,
3. Select the sort order and where to place nested folder,
4. Click **OK**.

To move an individual connection node or folder node:

1. Select one or more nodes,
2. Drag the node(s) to the new location,
3. Drop the node.

19.8 Setting Common Authentication Options

DbVisualizer lets you handle authentication in a manner that suits your balance between security and convenience.




19.8.1 Authentication settings in Connection Properties

Userid and password information is generally information that should be handled with great care. By default, DbVisualizer saves both the Database Userid and Database Password (encrypted) for each database connection. The default for **SSH** is to save the SSH Userid but not the SSH Password (or Key Pass-phrase). You can change this behavior to fit your preferences.

You specify how to handle the Database Userid and Password in the **Authentication** category of the **Properties** tab.

The **Require Userid** and **Require Password** properties can be enabled to tell DbVisualizer to automatically prompt for userid and/or password when a connection is to be established if they are not specified for the connection. The following dialog is displayed if requiring both userid and password.



19.8.2 SSH Settings in Tool Properties

The same options are available for the SSH Userid and Password in the **Database Connection/SSH Settings** category in the **General** tab of the **Tool Properties** window.



Tool Properties

General Database

General

- Appearance
 - Fonts
 - Editor Styles
 - Grid Colors
- Key Bindings
- Database Objects Tree
- Tabs
- Master Password
- Database Connection
 - SSH Settings**
 - Database Profile
- Driver Manager
- Permissions
- File
- Data Formats
- Time Zone
- Variables
- Table Data
- Transaction
- Favorites
- Monitor
- Form Viewer
- Grid
- SQL Commander
 - Auto Completion
 - Comments
 - Result Sets
 - SQL Log
 - Statement Delimiters
 - Editor Templates
 - SQL Formatting
- SQL History
- Proxy Setting
- Mail Server Accounts

SSH Keep-Alive Interval

How often an SSH keep-alive message should be sent (in seconds). Set it to 0 to disable SSH keep-alive.

SSH Keep-Alive Interval:

SSH Known Hosts File

The file containing information about hosts that you have verified, see SSH documentation for details.

SSH Config File

Optional file containing SSH configuration, see SSH documentation for details. The file is usually located in <USER_HOME>\.ssh\config. Leave empty for no SSH configuration file.

SSH Authentication

Specify if the SSH password or passphrase for a Connection should be saved (encrypted) between invocations and if userid/password or passphrase is required for SSH servers. (If Require Userid/Password is checked and there is no SSH userid/password or passphrase specified at connect, a dialog will be displayed prompting for it).

Require Userid:

Require Password/Passphrase:

Number of SSH Authentication Tries

Specifies the maximum number of SSH authentication attempts permitted per connection. 0 means that no explicitly setting of the value is done leaving it to the underlying SSH implementation to set an appropriate value. **Note:** Normal authentication procedures may exhaust the retries. Many SSH implementations use 6 as default.

Number of SSH Authentication Tries:

SSH Password/Passphrase

Specify what to do with the SSH password/passphrase. For **Save Between Sessions** there is the option to increase security by specifying a **Master Password** in Tool Properties.

Save Between Sessions

Save During Session

Clear at Disconnect

Defaults OK Apply Cancel

Since a password may need to be handled with great care, you can also specify for how long it should be saved, if at all. If **Clear at Disconnect** is selected, DbVisualizer ensures that the Password field is cleared as soon as the connection is terminated. With **Save During Session**, it is cleared when you shut



down DbVisualizer. To keep the password between sessions, select **Save Between Sessions**. If you use Save Between Sessions, we recommend that you also set a [Master Password](#).

SSH Config File

The configuration value is blank by default thus meaning that Config file parsing is not enabled by default. The default location of the SSH configuration file is in the users .ssh directory (<User home>/.ssh/config).

Note: Even though we do support the parsing of SSH config files all keywords are not supported. E.g. keywords such as **ProxyCommand** is not supported. For a list of supported keywords please see the documentation of [OpenSSHConfig](#). More details on [Configuration Options](#).

The SSH Configuration file support included DbVisualizer has some known issues listed below:

- **Host key word need to start with a capital H**

In the example below the line Host in "Host myhost" need to start with capital H. Having the line specified as "host myhost" will give unpredictable results.

```
Host myhost
  user admin
  port 2222
```

- **Compression support**

SSH Compression is NOT included in DbVisualizer.

Please send us an improvement request, if you need Compression to be included in DbVisualizer by default, and we will consider this for future releases.

19.9 Setting a Master Password

- [Specifying a Master Password](#)
- [Changing a Master Password](#)
- [Resetting the Master Password](#)
- [Connecting with a Master Password specified](#)
- [Manually Requesting the Master Password for New Connections](#)
- [Showing the Encrypted Password in Cleartext](#)
- [Declaring a Master Password Rule](#)

When you use **Save Between Sessions** for database passwords and SSH passwords or pass-phrases, they are by default encrypted using a static key. The same is true for the Proxy password if you have specified one. For better security, you can specify a Master Password that is then used instead of the static key to encrypt all passwords and pass-phrases. This way, only you know the information needed to decrypt the data. The algorithms used for encryption with a Master Password are also more advanced, minimizing the risk that the data can be decrypted by brute force.

Using a Master Password does, however, mean that if you forget it, there is no way to retrieve it and therefore no way to decrypt the saved passwords. It also means that the encrypted passwords cannot be read by a DbVisualizer version earlier than 9.2.



If you forget the Master Password, it cannot be recovered. The only way forward is to reset the Master Password, which also clears all passwords encrypted with it.

Passwords encrypted with a Master Passwords cannot be used in DbVisualizer version earlier than 9.2. If you set a Master Password in 9.2 and then use an earlier version, you will get "invalid password" errors when trying to connect with a saved password. You must enter the database or SSH password again in the earlier version, or go back to using DbVisualizer version 9.2 or later.

19.9.1 Specifying a Master Password

To use a Master Password for encoding of passwords saved between sessions:

1. Open **Tools->Tool Properties** and select the **General/Master Password** category,
2. Enter a password matching the described rules in both the **New Password** and **Confirm New Password** fields,
3. Click **Apply** and then confirm that you want to do this after reading the warning about what it implies.




Master Password _____

When a Master Password is specified, saved database passwords, SSH passwords/pass-phrases and the Proxy password are encrypted using the Master Password as the key instead of a default key for increased security.

The new password must be at least 8 characters long.

New Password:

Confirm New Password:

 **A Master Password is not specified.**

The passwords for all connections with **Save Between Sessions** chosen for the password are now encrypted with the Master Password. The same goes for the SSH passwords/pass-phrases if you have selected to have them saved between sessions, as well as the proxy password, if any.

19.9.2 Changing a Master Password

If you want to change the Master Password:

1. Open **Tools->Tool Properties** and select the **General/Master Password** category,
2. Enter the current password in the **Current Password** field and the new password in both the **New Password** and **Confirm New Password** fields,
3. Click Apply.

Master Password _____


When a Master Password is specified, saved database passwords, SSH passwords/pass-phrases and the Proxy password are encrypted using the Master Password as the key instead of a default key for increased security.

The new password must be at least 8 characters long.

Current Password:

New Password:

Confirm New Password:

 **A Master Password is specified.**

The saved passwords are then decrypted with the current Master Password and re-encrypted with the new.

19.9.3 Resetting the Master Password

If you have forgotten the Master Password, or simply no longer want to use one, you can reset it:

1. Open **Tools->Tool Properties** and select the **General/Master Password** category,
2. Click the **Reset Master Password** button and confirm that you want to do this.



Note that all passwords encoded with the Master Password are then immediately cleared and there is no way to recover them.



19.9.4 Connecting with a Master Password specified

When you have a Master Password specified, you will be prompted to enter it the first time within a DbVisualizer session that you need to connect with a saved password. From then on, you can make other connections with saved passwords without being prompted until you restart DbVisualizer.

19.9.5 Manually Requesting the Master Password for New Connections

You have two options to manually require being prompted for the Master Password again after entering it once within a DbVisualizer session:

1. Select **Database->Require Master Password at Next Connect**,
2. Open **Tools->Tool Properties**, select the **General/Master Password** category and enable **Require Master Password after All Connections Closed**.

19.9.6 Showing the Encrypted Password in Cleartext

When you have specified a Master Password, you can view the saved database password or SSH password/pass-phrase in cleartext.

1. Right-click on the password field label and select **Show Password**,
2. Enter the Master Password when prompted.

19.9.7 Declaring a Master Password Rule

A Master Password must have at least eight characters of any kind by default, but you can declare your own rule using a regular expression in an installation configuration file:

1. Open the *DBVIS-HOME/resources/dbvis-custom.prefs* file,
2. Enter a regular expression as the value of the `dbvis.-MasterPasswordRule` property,
3. Enter a description of the rule for showing the user in Tool Properties as the value of the `dbvis.-MasterPasswordRuleDescr` property.

The regular expression for the default rule is `.{8,}`. It is easy to change the number in this expression to any number you want. There are regular expressions that can describe pretty much any rule you can come up with. For instance, this rule requires at least nine characters, with at least one symbol, one digit, one uppercase character, and one lowercase character:

```
(?=.*{9,})(?=.*?[^\w\s])(?=.*?[0-9])(?=.*?[A-Z]).*[a-z].*
```

If you cannot adopt these examples to your own policy, you can search the Internet for other examples of "regular expressions for password validations".

19.10 Using Connection Keep-Alive

Databases can be configured to terminate sessions that have been idle for some time, and networks often does the same with TCP/IP connection. The **Connection Keep-Alive** feature helps preventing connections to be closed due to time-outs of this kind by periodically executing a simple SELECT statement.

i Network connections may be terminated for other reasons than a time-out in the database or at the network layer, e.g due to a restart of the database or a network element. The Connection Keep-Alive feature does not help in those cases. Also note that connections that are busy, e.g. actively used to run a script, are not "pinged". If a SELECT statement or stored procedure takes a very long time to complete, it is therefore possible that a time-out happens at the network level. In this case, the network configuration must be tuned to handle long running statements without timing out.

To enable Keep-Alive for a connection:

1. Open the **Object View** tab for the connection,
2. Open its **Properties** tab,
3. Select the **Physical Connection** category,
4. Modify or enter a simple SQL statement in the **Validation and Keep-Alive SQL** field, if needed (see note below),
5. Enable **Connection Keep-Alive** and optionally change the **Connection Idle Time**,
6. Click the **Apply** button.



i The SELECT statement used for Connection Keep-Alive can also be specified in the properties pane. For supported databases, it is set to a SELECT statement that has been verified to work for the database type but for connections that use the Generic profile, you must specify a valid SELECT statement in order for this feature to work. For many databases, `SELECT 1` or `SELECT 1 FROM aSmallTable WHERE 1 = 0` should work.

19.11 Security

When DbVisualizer communicates with a database server, all communication (except passwords) is done in plain text; by intercepting the communication, someone can access the transmitted data and even modify it while in transit. To protect your communication you need to encrypt the communication between DbVisualizer and the server.

19.11.1 Using an SSH Tunnel

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

You can use SSH (Secure SHell) to encrypt the network connection between DbVisualizer and a server even for non-SSL-capable clients. A database that sits behind a firewall cannot be accessed directly from a client on the other side of the firewall, but it can often be accessed through an SSH tunnel. The firewall must be configured to accept SSH connections and you also need to have an account on the SSH host for this to work.

If you need to access a database that can only be accessed via an SSH tunnel, you need to specify additional information in the Use SSH Tunnel area of the Connection tab.

i This area is only shown when the **Server Info** settings format is selected, and only for databases identified by at least a **Database Server** and a **Database Port** (i.e. not for embedded databases or when using the TNS Connections Type for an Oracle database, or similar).

Enable SSH tunneling by clicking on the checkbox. When it is enabled, five additional fields are shown.



Database Connection: CRM Ahoa

CRM Ahoa Disconnected

Connection Properties

Connection

Name: CRM Ahoa

Notes:

Database

Settings Format Server Info

Database Type: Auto Detect (Oracle)

Driver (JDBC): Oracle Thin

Connection Type: Service

Database Server: 192.168.1.21

Database Port: 1521

Service: XE

Authentication

Database Userid: hr

Database Password: ●●

Use SSH Tunnel

SSH Host: 192.168.1.100

SSH Port: 22

SSH Userid: hans

SSH Password:

Private Key File:

Options

Connect Disconnect Ping Server

Connection Message

Disconnected.

The **SSH Host** is the name or IP address for the host accepting SSH connections. The SSH Host is typically the same as the Database Server. Enter the port for SSH connections in the **SSH Port** field. The default value is 22.

You may also enter the userid and password for your SSH host account in the **SSH Userid** and **SSH Password** fields, but see [Setting Common Authentication Options](#) for other options. Alternatively, you can enter the path to a private key file (using either the RSA or DSA algorithms) in the **Private Key File** field. The SSH Password field is then replaced by a Key Passphrase field where you can enter the passphrase if the private key is protected with one.

When SSH tunneling is enabled, a tunnel is established when you connect to the database and the connection is then made through the tunnel by constructing a JDBC URL that uses information from both the Connection and Use SSH Tunnel sections.

If you're familiar with using the `ssh` command to set up a tunnel manually, you may be interested in more details. The tunnel corresponds to the tunnel you would set up with the `ssh` command like this:

```
ssh -p <SSHPort> -L<LocalPort>:<DatabaseServer>:<DatabasePort> <SSHUserid>@<SSHHost>
```

where the placeholders correspond to the fields in the Connect and Use SSH Tunnel sections, except for <LocalPort> which is any available port, determined at connect time.




i Note that when using an SSH tunnel, the **Database Server** is evaluated on the SSH host. If the database server is running on the SSH host, you can therefore set **Database Server** to `localhost` in case the database only accepts local connections.

The JDBC URL is constructed using `127.0.0.1` as the Database Server portion and `<LocalPort>` as the Database Port portion, e.g. like this for the Oracle Thin driver when `<LocalPort>` is `50538`:

```
jdbc:oracle:thin@127.0.0.1:50538/XE
```

In other words, the JDBC driver connects to the SSH tunnel's local port, which then forwards all communication to the database server.

The URL that is used for the connection is shown at the top of the **Object View** tab for the database connection when a connection is established, along with a certificate icon if the connection is made through an SSH tunnel.



If you use the SSH Tunnel feature, you may also want to configure a few things in **Tools->Tool Properties**. In the **Database Connection/SSH Settings** category under the General tab, you can specify:

- **SSH Keep-Alive Interval** to minimize the risk that the tunnel is disconnected due to inactivity
- **SSH Known Hosts File** so you don't have to accept connections to known SSH hosts every time you connect
- **SSH Config File** containing optional SSH configuration
- **SSH Authentication** settings
- **Number of SSH Authentication Tries** that limits the number of allowed connection attempts
- **SSH Password/Passphrase** settings

19.11.2 Using SSL

Depending on the database and the JDBC driver, you may be able to use SSL (Secure Socket Layer) to encrypt client/server communications.

In case the JDBC driver supports SSL, you define the SSL settings as [Driver Properties](#) for your connection according to the documentation for the JDBC driver. The exact details depend on the versions of the database and the driver, but using PostgreSQL as an example, the settings can look like this:



Database Connection: Test PostgreSQL Actions

R&D/Test PostgreSQL Disconnected

Connection Properties

Database Profile

Driver Properties

PostgreSQL

- Authentication
- Delimited Identifiers
- Qualifiers
- Physical Connection
- Transaction
- Encoding
- SQL Statements
- Connection Hooks
- Color and Border
- SQL Commander
- Query Builder
- Explain Plan

Driver Properties

Defines JDBC Driver or JNDI specific properties that can be used to fine tune the database connection. A pre-defined property is reverted to its default value when removing it while user defined properties are removed. The **Edited** flag indicates that the property value has been edited or that the property has been added manually.

Edited	Parameter	Value
<input type="checkbox"/>	socketFactoryArg	(null)
<input type="checkbox"/>	socketTimeout	0
<input type="checkbox"/>	ssl	(null)
<input type="checkbox"/>	sslcert	(null)
<input type="checkbox"/>	sslfactory	(null)
<input type="checkbox"/>	sslfactoryarg	(null)
<input type="checkbox"/>	sslhostnameverifier	(null)
<input type="checkbox"/>	sslkey	(null)
<input type="checkbox"/>	sslmode	(null)
<input type="checkbox"/>	sslpassword	(null)
<input type="checkbox"/>	sslpasswordcallback	(null)
<input type="checkbox"/>	sslrootcert	(null)
<input type="checkbox"/>	sspiServiceClass	POSTGRES
<input type="checkbox"/>	stringtype	(null)
<input type="checkbox"/>	targetServerType	any
<input type="checkbox"/>	tcpKeepAlive	false

Allow for changes in client_encoding

Certificates

The most common problem with SSL connections is that the server certificate cannot be validated by the JDBC driver when setting up the connection. A server certificate that is signed by a trusted Certificate Authority (CA) should always work fine, since the Java distribution includes a Trust Store with all the CA public keys. When a self-signed server certificate is used, the Java VM must be told where to find the corresponding public key. If the Java VM cannot validate the certificate, an exception is thrown when trying to connect.

Many forums on the net suggests using the Java keytool to import the certificate into the Java VM's default Trust Store. The drawback with that solution is that it does not survive a Java upgrade; when the Java VM bundled with DbVisualizer is used, upgrading DbVisualizer effectively causes SSL connections to fail. We therefore recommend creating a Trust Store separate from the Java VM (e.g. in /Users/me/MyTrustStore) and import the certificate to that Trust Store. Java VM properties for pointing to the Trust Store can then be added in Tool Properties, in the Java VM Properties area in the General category:

```
-Djavax.net.ssl.trustStore=/Users/me/MyTrustStore  
-Djavax.net.ssl.trustStorePassword=myspassword
```

There is also a Java VM property that can be used to get debugging information from the SSL handshake process.

```
-Djavax.net.debug=all
```



Some drivers have properties corresponding to the Java VM properties that can be used per connection instead of for the whole Java VM.

19.12 Using Oracle TNS Names

All information for connecting to an Oracle database may be stored in a *tnsnames.ora* file, with each database instance defined by a TNS alias. If you want to create a connection in DbVisualizer that uses the information from this file, you must first tell DbVisualizer where it is stored by setting either the `TNS_ADMIN` environment variable to the path of the folder holding the file, or making sure it is located in the `ORACLE_HOME/network/admin` folder and that the `ORACLE_HOME` environment variable is set.

When this configuration is done, you can select **TNS** from the **Connection Type** list for the Oracle connection and then pick the TNS alias from a list of all aliases found in the file.

New Connection Wizard

CRM Ahoa
(Oracle Thin)

Connection

Notes

Database

Settings Format Server Info

Connection Type: TNS

TNS Alias: **ORA 10 10**

Authentication

Database Userid: DWSUN42

Database Password: ORA 10 10

Use SSH Tunnel dwlin165.us.oracle.com

Options

Auto Commit:

Save Database Password: Save Between Sessions

Permission Mode: Development

SYS Role

Ping Server

< Back Finish Cancel

i On macOS, environment variables set in `.bash_profile` or similar are not available to applications started via Spotlight or by double-clicking an app icon. The `launchctl` command can be used to set these environment variables instead, for instance from the `.bash_profile` script. This thread discusses an alternative solutions for Yosemite and El Capitan: <http://stackoverflow.com/questions/25385934/setting-environment-variables-via-launchd-conf-no-longer-works-in-os-x-yosemite>



19.13 Changing an Oracle Password

If your Oracle password has expired, you get a message about this in the Connection Message area for the database connection when you try to connect. For Oracle 12c or later, you can change the password from within DbVisualizer if you use the Oracle Thin JDBC driver (version 12.2 and later):

1. Open the Object View tab for the connection if it is not already open,
2. Check the **Change Password** checkbox in the Authentication area,
3. Enter the new password in the **New Password** field,
4. Click Connect.

The connection is then established and the password is changed. The **Database Password** field is updated with the new password automatically.

You can also change the password as described at any time, even if it hasn't expired.

19.14 Using SQL Server Single-Sign-On or Windows Authentication

With Microsoft SQL Server, you can either let the database server or a Windows domain server handle the authentication. The database server handles it by default using the database user and password you enter for the connection.

To let a Windows domain server handle the authentication instead, you must use the **SQL Server (JTDS)** JDBC driver (bundled with DbVisualizer).


If you run DbVisualizer on a Windows OS client in the same domain as the SQL Server database, leave the **Database Userid** and **Database Password** fields in the **Connection** tab empty. This is also known as Single-Sign On (SSO).

i SSO only works if you installed DbVisualizer using a [Setup installer](#), not if you used an installation archive, because the installer also installs the DLL files needed for SSO.

If you run DbVisualizer on another OS in a network with a Windows domain server, enter the **Authentication Domain** name in the **Options** area in the **Connection** tab. You must also enter the domain user and password in the **Database Userid** and **Database Password** fields. The driver then authenticates with the domain server and then uses those credentials to log in to the database server.

19.15 Using Variables in Connection Fields

Variables can be used in some of the **Connection** tab fields. You can use variables in the **Name**, **Userid** and **Password** (both Database and SSH) fields with the **Server Info** settings format, or in the **Database URL** field when using this settings format. This can be a useful alternative to having a lot of similar database connection objects. Several variables can be defined in a single field, and default values can be set for each variable. The following figure shows an example with variables, described in more detail in the [Using DbVisualizer Variables](#) page.



The following variables appear in the figure:

- \${Name}\$
- \${Database Host}|dbhost2|||choices=[dbhost1,dbhost2,dbhost3]}\$
- \${Port}|1521}\$
- \${SID}|ORCL}\$

All of these variables define a default value after the "|" delimiter, except for the \${Name}\$ variable, which has no default value. The default values appear in the connect dialog when you ask for a connection to be established. The \${Database Host}\$ variable includes the choices option, with a comma separated list of choices that should appear in a drop-down list. The drop-down list is editable, so the user is not locked into the choices from the list.

The following figure shows the connect dialog based on the connection definition shown above.



Enter the appropriate information in the fields and then press the **Connect** button to establish the connection. When the connection is established, DbVisualizer automatically substitutes the variables in the Connection tab with the values entered in the connect dialog. At disconnect from the database, they revert back to the original variable definitions.

19.16 Automatically Connecting at Startup

If you want to automatically connect to a database when you start DbVisualizer there are three ways to achieve this:

The first way will hold for one or more database connections and is:

1. From the **Databases** tree, select the top node and open the **Connections** Object View
2. For each Database Connection that you want to automatically connect, set the **Connect All** check box

The second option will have the same result but for one database connection at the time. Then you do:

1. From the **Databases** tree, select a specific database connection node and open the **Database Connection** Object View
2. Select the **Properties** tab
3. In the left tree, select the database node and set the **Connect when "Connect All"** check box in the right panel

The third option will hold for all database connections of a certain type. Then you do:

1. Open the **Tool Properties** window
2. Under the **Database** tab, select the specific database
3. Set the **Connect when "Connect All"** check box.

Finally after one or more of the alternatives above, the auto connect function must be activated at startup with the following steps:

1. Open **Tools->Tool Properties** and select the **Database Connection** category under the **General** tab,
2. Set the **Run "Connect All" at Startup** check box.

If you enable **Connect when "Connect All"** but do not enable **Run "Connect All" at Startup**, you can instead use the **Database->Connect All** main menu choice to manually connect all connections marked this way.

Note that while the **Database->Connect All** main menu choice, will only connect all database that have **Connect All** selected, the **Database->Disconnect All** main menu choice, will disconnect all database connections.



19.17 Executing SQL at Connect and Disconnect

Connection hooks defines optional SQL commands that are sent to the database at connect and just before disconnect. They are typically used to initialize the database session with custom settings and to clean up various resources at disconnect.

You can enter the SQL you want to execute in the **Properties** tab for the connection, in the **Connection Hooks** category.

You can also set this for all database connection of a certain type. Then you instead do.

1. Open the **Tool Properties** window
2. Under the **Database** tab, select the specific database and the **Connection Hooks** category from the tree
3. Enter the SQL in the shown **Database Connection Hooks** panel.

19.18 Using a Single Shared Physical Connection

By default, DbVisualizer uses multiple physical connections to a database. Each SQL Commander tab is allocated its own connection. Other processes that update the database, such as saving grid edits or importing data to a table, also use their own connections. Finally most read-only operations, such as navigating the database objects tree, use a separate shared connection. This is normally the most efficient way to access the database, but in certain circumstances it is important to instead use one single shared physical connection for all operations. Some examples are:

- Only one session per account is allowed in the target database,
- Locking issues when modifying the same table in the Data tab and in an SQL Commander (when a pending transaction locks the whole table)
- When using one-time passwords, new physical connections cannot be established without prompting for a new password.

For situations like these, you can force DbVisualizer to use a single shared physical connection.

- [Selecting the Single Shared Physical Connection Mode](#)
- [Data Manipulation with a Single Shared Physical Connection](#)
- [Transaction Handling with a Single Shared Physical Connection](#)

19.18.1 Selecting the Single Shared Physical Connection Mode

To use a single shared physical connection:


1. Open the Object View tab for the connection node,
2. Select the **Properties** tab,
3. Select the **Physical Connection** category and enable **Use a Single Shared Physical Connection**.

19.18.2 Data Manipulation with a Single Shared Physical Connection

Executing a script in an SQL Commander tab, using an Action, editing a table in a grid and importing data to a table are all operations that (potentially) modify data in the database. When a single shared physical connection is used, only one such operation may be performed at a time. If you try to start an operation like this while another one is already being processed, a dialog will pop up asking you to try again later.

19.18.3 Transaction Handling with a Single Shared Physical Connection

If you have **Auto-Commit** disabled with Single Shared Physical Connection enabled, commits or rollbacks done in one part of the GUI affect changes done in any other part of the GUI. For instance, if you have executed UPDATE or INSERT statements in an SQL Commander tab and then edit a table in its Data tab and commit those changes, you are also committing the changes made by the UPDATE or INSERT statements. To make this clear, all GUI controls for transaction handling for shared physical connections are shown in a separate Single Physical Connections window.



This window pops up when you connect to a database with Single Shared Physical Connection enabled, or when clicking any of the transaction control buttons in an SQL Commander tab for such a database. You can also click the corresponding button in the DbVisualizer status bar to bring it up. From this window, you can enable or disable Auto-Commit and manually commit or rollback a pending transaction.


You also get prompted to commit, rollback or continue working within the same transaction every time an operation results in data changes. Before potentially making lots of changes, you get prompted to enable Auto-Commit, since making lots of changes (e.g. importing lots of data) may fill up redo logs if running with Auto-Commit disabled.

19.19 JDBC-ODBC Bridge Driver Alternatives

Java has included a JDBC/ODBC Bridge driver as a transitional solution for accessing ODBC data sources, but it has always been considered a very limited driver and the recommendation has always been to use a pure JDBC driver instead. Starting with Java 8, the bridge driver is no longer provided.

For most databases, you can find JDBC drivers from the database vendor or a third party. Try searching the net for the name of your database plus "JDBC driver".

If you cannot find a JDBC driver for a database that can be accessed via ODBC, you find a few alternatives below. Note that we have no relationship with any of the organizations behind these drivers and have not thoroughly tested any of the drivers with DbVisualizer. In other words, please make sure that the driver works for you before committing to one.

 For any technical assistance setting up or using these drivers, please contact respective author.

19.19.1 The UCanAccess Driver for MS Access

This is an Open Source driver specifically for Microsoft Access databases, not for ODBC data sources in general. You can download it here:

<http://ucanaccess.sourceforge.net/site.html>

To use it, you need to download the following JAR files:

UCanAccess-4.0.4-bin.zip (unzip to find JAR file; ucanaccess-4.0.4.jar) from
<https://sourceforge.net/projects/ucanaccess/files/>

jackcess-2.1.11.jar from
<http://sourceforge.net/projects/jackcess/files/>

commons-lang-2.6-bin.zip (unzip to find JAR file) from
http://commons.apache.org/proper/commons-lang/download_lang.cgi



commons-logging-1.1.3-bin.zip (unzip to find JAR file) from
http://commons.apache.org/proper/commons-logging/download_logging.cgi

hsqldb-2.3.1.zip (unzip to find JAR files hsqldb.jar and sqltool.jar) from
<http://sourceforge.net/projects/hsqldb/files/>

apache-log4j-2.1-bin.zip (unzip to find JAR file; you only need log4j-1.2-api-2.1.jar) from
<http://logging.apache.org/log4j/2.x/download.html>

poi-3.11-20141221.zip (unzip to find JAR file) from
<http://poi.apache.org/download.html>

Then start DbVisualizer and open **Tools->Driver Manager** and

1. Create a new Driver and name it UCanAccess,
2. Load all the JAR files in the User Specified tab in the order listed above,
3. Close the Driver Manager,
4. Open the Object View tab for your MS Access connection and set the Driver to UCanAccess,
5. Enter the JDBC URL in this format:
`jdbc:ucanaccess://<absolute_path_to_the_ms_access_file>`
6. Open the Properties tab for the connection and select the **Delimited Identifiers** category,
7. Change the **Begin Identifier** to [and the **End Identifier** to] and click Apply,
8. Switch back to the Connection tab and click Connect.

19.19.2 Easysoft JDBC-ODBC Bridge Driver

This is a commercial JDBC-ODBC Bridge Driver, available here:

http://www.easysoft.com/products/data_access/jdbc_odbc_bridge/

The "Working with ODBC data in DbVisualizer" page at the Easysoft web site explains all details how to use it with DbVisualizer.

20 Finding Database Objects and Data

DbVisualizer provides ways to find all kinds of things, from parts of a script and data in a grid to objects in a connection tree.

20.1 Finding and Replacing Text in the Editor

The **Edit** main menu and the editor right-click menu contain two choices for finding text (**Find** and **Find with Dialog**) and one choice for replacing text (**Replace**).

- **Find** displays a Quick Find field where you can type text to look for, and use the **Up** and **Down** keys (and **F3** and **Shift-F3**, by default) to find the next or previous occurrence. Use the **Escape** key to close the field.
- **Find with Dialog** shows a dialog where you can enter what to look for, either as text, a regular expression or using wildcards. You can also limit the search to the current selection and use other options for a more precise search.
You can use **Find Next** and **Find Previous** to navigate to other matches, by default mapped to the **F3** and **Shift-F3** keys.
 - When using a regular expression or wildcards, the button next to the expression opens a helper menu with common symbols.
- **Replace** shows a dialog identical to **Find with Dialog** but with an additional field for entering the replacement text.
 - When using a regular expression, the button next to the expression opens a helper menu with common symbols.
 - When you use a regular expression with group expressions in the **Find what** field, you can reference the captured text in the **Replace with** field using the **dollar sign** (\$) plus the group number (e.g. \$1 for the first group).

20.1.1 Regular Expression Example:

Text in editor:

```
SELECT
  firstname,
  lastname
FROM
  person;
```

**Find what:**

```
^\s+(\w+)(,?)$
```

Replace with:

```
$1person.$2$3
```

Deselect **Match whole word**, select **Entire scope** and **Use Regular Expression**.

When you click **Find** and choose **All** in the following dialog, you get the following result:

Resulting text:

```
SELECT
  person.firstname,
  person.lastname
FROM
  person;
```

20.2 Finding Data in a Grid

The right-click menu for a grid contains the **Find Data** and **Find Column** choices.

Find Data shows a Quick Find field where you can type text to look for, and use the **Up** and **Down** keys to find the next or previous occurrence. Use the **Escape** key to close the field.

Find Column works the same, except it locates a column with the name you type.

20.3 Locating an Object in an SQL Statement

To open an **Object View** tab for an object named in an SQL statement (e.g. a table in a SELECT statement) in the SQL Commander tab, place the caret in or next to the name and choose **Show Object at Cursor** from the right-click menu.

20.4 Locating an Object in the Databases tab

With a node selected in the Databases tab, typing any character shows a Quick Find field where you can type the name of an object you want to locate. Use the **Escape** key to close the field.

i Note that only the visible, expanded, nodes are searched. To search among all nodes for a connection, see [Searching a Connection](#).

20.5 Searching a Connection

i **Only in DbVisualizer Pro**
This feature is only available in the DbVisualizer Pro edition.

The **Search** tab in the **Object View** tab for a connection is used to search among the objects in the tree by object name. The types of objects that are searchable depends on the database you are connected to. For instance, columns are included in the tree for some databases but not for others.



Type	Name
Table	Schemas/HR/Tables/JOBS
Table	Schemas/HR/Tables/JOB_HISTORY
Column	Schemas/HR/Tables/EMP/Columns/JOB
Column	Schemas/HR/Tables/EMP/Constraints/SYS_C0012505/JOB
Column	Schemas/HR/Tables/EMPLOYEES/Columns/JOB_ID
Column	Schemas/HR/Tables/EMPLOYEES/Constraints/EMP_JOB_FK/JOB_ID
Column	Schemas/HR/Tables/EMPLOYEES/Constraints/EMP_JOB_NN/JOB_ID
Column	Schemas/HR/Tables/EMPLOYEES/Indexes/HR.EMP_JOB_IX/JOB_ID
Column	Schemas/HR/Tables/JOBS/Columns/JOB_ID
Column	Schemas/HR/Tables/JOBS/Columns/JOB_TITLE
Constraint	Schemas/HR/Tables/JOBS/Constraints/JOB_ID_PK
Constraint	Schemas/HR/Tables/JOBS/Constraints/JOB_TITLE_NN
Column	Schemas/HR/Tables/JOBS/Constraints/JOB_ID_PK/JOB_ID
Column	Schemas/HR/Tables/JOBS/Constraints/JOB_TITLE_NN/JOB_TITLE
Column	Schemas/HR/Tables/JOBS/Referenced By Constraints/EMPLOYEES/JOB_ID
Column	Schemas/HR/Tables/JOBS/Referenced By Constraints/JOB_HISTORY/JOB_ID

Search by specifying the name of the object, or name pattern, and press the **Search** button. You can use asterisk (*) as a wildcard in a pattern, or you can use a regular expression pattern if you enable it by checking the **Regular Expression** checkbox. You can also specify where in the tree to start the search, and whether to do a case sensitive search.

You can interrupt a search operation with the **Stop** button in the grid toolbar. Use the **Show Object Path** toolbar toggle button to include or exclude a column for the complete path for each found object in the grid. This path is the same as if navigating to each object manually in the objects tree. Other grid toolbar buttons let you export and print the search result grid.

Shift+Click on a row to switch to the Object View to see detailed information about a specific object. **Shift+Double-click** on a row to see detailed information about a specific object in a separate window.




Note that if you have tree filters or any other property that limits the content of the tree enabled, the search is performed only for those objects that match the filters.

20.6 Synchronizing object tab selection and selection in the tree

By use of this functionality it is possible to set up DbVisualizer to automatically select the database tree node when the corresponding object view tab is selected and vice versa.

This is done through the **Open selected object(s)** dropdown in the toolbar of the Databases tab tree.



The two options controlling this are

- **Autoscroll TO Object View tab** Automatically open the object in an object view tab when the tree node is selected
- **Autoscroll FROM Object View tab** Automatically select the tree node whenever its object view tab is clicked

The default values for **Autoscroll** can be configured in **Tool Properties** -> **General** -> **Database Objects Tree**.

21 Transfer DbVisualizer settings

- [Transfer DbVisualizer settings to new environment](#)
- [Transfer the DbVisualizer Pro license to new machine](#)

21.1 Transfer DbVisualizer settings to new environment

To move your DbVisualizer settings from one machine to another, do as follows:

1. Install DbVisualizer on your new machine.
2. Use **File->Export Settings** in the old machine
3. Transfer the **settings.jar** file to your new machine
4. Open DbVisualizer on your new machine and choose **File->Import Settings** to import the **settings.jar** file
5. Once done, re-start DbVisualizer. (Your settings from your old machine are now migrated)

[Read more about the Export and Import Settings function.](#)

21.2 Transfer the DbVisualizer Pro license to new machine

First make sure you have followed the steps in [Transfer DbVisualizer settings to new environment](#).

1. The location for the license file is listed in [DbVisualizer Pro, license file location](#)
2. Copy the **dbvis.license** file from the old machine to the **Download** folder on your new machine
3. Start DbVisualizer on your new machine and open **Help->License Key**
4. Select the **dbvis.license** file in your **Download** folder
5. Re-start DbVisualizer when prompted
6. Remove the **dbvis.license** file in the old machine


22 Exporting and Importing Settings

Sometimes it may be necessary to migrate all your settings for DbVisualizer and import them in second DbVisualizer installation. This is very handy if you are migrating from one machine to another, or if you want to setup an exact copy on your home computer, or if you would like to share you settings with other users. Another key reason is for backup purposes. Loosing all database connection configurations can be really frustrating.

- [Export Settings](#)
- [Import Settings](#)

22.1 Export Settings


The Export Settings feature is available from the **File->Export Settings** main window menu choice.




The default settings ensures that all settings are exported, but you can selectively exclude certain items. Once you've made the adjustments you want, press OK and the settings will be saved in the specified file. The structure of this JAR file is the same as the content in your DbVisualizer preferences directory.

i The **Relative File Paths** option will transform all path definitions in the exported file to be relative to the DbVisualizer installation directory and your personal settings directory. This is useful if you will import the settings on another machine or share it with other users. Note that the DbVisualizer version importing relative file paths must be 7.1 or later to work properly (importing in earlier versions than 7.1 will not fail but path information will be erroneous for things such as drivers, favorites, etc.)

If [Master Password](#) is enabled for DbVisualizer and passwords are not excluded in the export you must specify an export password. The export password is used to protect the passwords that are exported. This export password is used later when importing the settings.




 You should **not** use your master password as the export password.

22.2 Import Settings

The Import Settings dialog is launched from the **File->Import Settings** main window menu choice.


Import Settings is used to import settings as previously exported with Export Settings. Import examines the content of the specified file and present the choices available.



Use the **Import To** list to set where the imported database connections will appear in the objects tree.

Note how some of the databases and folders are pre-selected. DBVisualizer will automatically pre-select databases and folders depending on differences between the current connection settings and the imported connection settings. In this example, the icon decorations for the pre-selected connections show that the **HR Production** and **HR Test Data** connection already exist but the imported settings are different, and that the **Lab** connection exists only in the imported settings. All the other connections exists with the same settings as in the imported settings.

If the imported data has been exported with an export password you will be prompted to enter it. You can optionally click Cancel to clear the passwords for all the connections.



23 Command Line Interface

i Only in DbVisualizer Pro

This feature is only available in the DbVisualizer Pro edition.

In addition to the DbVisualizer GUI tool, there is also a pure command line interface for running scripts. We recommend that you use this interface for tasks that you schedule via the operating system's scheduling tool, or when you need to include database tasks in a command script for a larger job. It is also the right tool for execution of large scripts, such as a script generated by the DbVisualizer Export Schema feature.

i Don't forget to check all [client-side commands](#) that can also be used in the scripts executed with the command-line interface.

- [Command Line Options](#)
- [Examples](#)
 - [Executing single statements](#)
 - [Executing scripts](#)
 - [Controlling the output](#)
 - [Using variables - prompting for values](#)
 - [Combining OS scripts, the command line interface and DbVisualizer variables](#)
- [Setting up the connection properties on the command line](#)
- [Exit codes from dbviscmd](#)
- [Generating a Command From SQL Commander](#)

On Windows and Linux/Unix, you find this command as a BAT file (*dbviscmd.bat*) or a shell script (*dbviscmd.sh*) in the DbVisualizer installation directory. For macOS, the shell script is located in */Application/DbVisualizer-<Version>.app/Contents/Resources/app*.

23.1 Command Line Options

The command line interface supports the following options:



```
Usage: dbviscmd (-connection <name> | -url <URL> |
  -url <URL> -drivername <name> |
  -url <URL> -driverclass <name> -driverpath <p1:p2...> )
  [-userid <userid>] [-password <password>]
  [-masterpw <password>]
  (-sql <statements> |
  -sqlfile <filename> [-encoding <encoding>] )
  [-catalog <catalog>] [-schema <schema>]
  [-maxrows <max>] [-maxchars <max>]
  [-stoponerror] [-stoponsqlwarning] [-stoponnorows]
  [-stripcomments (true | false)]
  [-processvariables]
  [-emptypromptvalue <string>]
  [-listconnections]
  [-output (all | none | log | result)] [-outputfile <filename>]
  [-debug [-debugfile <filename>]]
  [-errordir <directory>]
  [-prefsdir <directory>]
  [-help] [-version]
```

Options:

-connection <name>	Database connection name (created with the GUI)
-url <URL>	Database URL
-drivername <name>	Database driver name (created with the GUI)
-driverclass <name>	Full name of the JDBC Driver class name
-driverpath <p1:p2...>	Paths to the jar files constituting the JDBC driver. Each path separated by a ":"
-userid <userid>	Userid to connect as.
-password <password>	Password for userid.
-masterpw <password>	Master Password for encrypted database passwords
-sql <statements>	One or more delimited SQL statements
-sqlfile <filename>	SQL script file to execute
-encoding <encoding>	Encoding for the SQL script file
-catalog <catalog>	Catalog to use for unqualified identifiers
-schema <schema>	Schema to use for unqualified identifiers
-maxrows <max>	Maximum number of rows to display for a result set
-maxchars <max>	Maximum number of characters to display for a column
-stoponerror	Stop execution when getting an error
-stoponsqlwarning	Stop execution when getting an SQL warning
-stoponnorows	Stop execution when empty result set or no affected rows
-stripcomments < true/false >	Strip comments before sending to database. Default is the setting made in the GUI
-output <out>	"all" (default), output both log msgs and result sets "none", suppress both log messages and result sets "log", output only log messages "result", output only result sets
-outputfile <filename>	Script execution output file. Default is stdout
-processvariables	Process variables
-emptypromptvalue <string>	String to use when entering an empty value when prompted for variable(s)
-listconnections	Lists all database connections
-debug	Write debug messages
-debugfile <filename>	File for debug messages. Default is stderr
-errordir <directory>	Use an alternate location for error logs
-prefsdir <directory>	Use an alternate user preferences directory
-help	Display this help
-version	Show version info

There are two options to specify which database to connect to:

- Using a connection already defined by the DbVisualizer tool. This is done by using the `-connection` parameter. If you have forgot the connection name, use the `-listconnections` option to get a list of all existing names.
- Specifying the connection properties by using the parameter `-url`. The `-url` parameter specifies the JDBC URL for the database to connect to. For information about the JDBC url see [Setting Up a Connection Manually](#). There are also some examples below showing how to specify connection properties using the `-url` parameter



23.2 Examples

23.2.1 Executing single statements

You can use the command line interface to execute a single SQL statement:

```
> dbviscmd.bat -connection "Oracle" -sql "select * from hr.countries"
14:34:48 START Executing Command Line, Database Connection: Oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
14:34:48 INFO Physical database connection acquired for: Oracle
COUNTRY_ID COUNTRY_NAME REGION_ID
-----
AR Argentina 2
AU Australia 3
BE Belgium 1
BR Brazil 2
CA Canada 2
CH Switzerland 1
CN China 3
DE Germany 1
DK Denmark 1
EG Egypt 4
FR France 1
HK HongKong 3
IL Israel 4
IN India 3
IT Italy 1
JP Japan 3
KW Kuwait 4
MX Mexico 2
NG Nigeria 4
NL Netherlands 1
SG Singapore 3
UK United Kingdom 1
US United States of America 2
ZM Zambia 4
ZW Zimbabwe 4
14:34:48 SUCCESS [SELECT - 25 rows, 0.007 secs] Result set fetched
select * from hr.countries;
14:34:48 END Execution 1 statement(s) executed, 25 row(s) affected, exec/fetch time: 0.007/0.005 secs [1
successful, 0 errors]
```

If you like to execute just a few statements, you can pass in a list of statements:



```
> dbviscmd.bat -connection "Oracle" -sql "select * from hr.countries; select * from hr.regions"
14:42:21 START Executing Command Line, Database Connection: Oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
14:42:21 INFO Physical database connection acquired for: Oracle
COUNTRY_ID COUNTRY_NAME REGION_ID
-----
AR Argentina 2
AU Australia 3
BE Belgium 1
BR Brazil 2
CA Canada 2
CH Switzerland 1
CN China 3
DE Germany 1
DK Denmark 1
EG Egypt 4
FR France 1
HK HongKong 3
IL Israel 4
IN India 3
IT Italy 1
JP Japan 3
KW Kuwait 4
MX Mexico 2
NG Nigeria 4
NL Netherlands 1
SG Singapore 3
UK United Kingdom 1
US United States of America 2
ZM Zambia 4
ZW Zimbabwe 4
14:42:21 SUCCESS [SELECT - 25 rows, 0.004 secs] Result set fetched
select * from hr.countries;
REGION_ID REGION_NAME
-----
5 Australia
6 South America
1 Europe
2 Americas
3 Asia
4 Middle East and Africa
14:42:21 SUCCESS [SELECT - 6 rows, 0.003 secs] Result set fetched
select * from hr.regions;
14:42:21 END Execution 2 statement(s) executed, 31 row(s) affected, exec/fetch time: 0.007/0.002 secs [2
successful, 0 errors]
```

23.2.2 Executing scripts

If you frequently want to execute a number of statements, it's best to put them into a script file. Here's how to execute a script that contains the two statements from the example above:



```
> dbviscmd.bat -connection "Oracle" -sqlfile "myscript.sql"

14:45:11 START Executing Command Line, Database Connection: Oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
14:45:11 INFO Physical database connection acquired for: Oracle
COUNTRY_ID COUNTRY_NAME REGION_ID
-----
AR Argentina 2
AU Australia 3
BE Belgium 1
BR Brazil 2
CA Canada 2
CH Switzerland 1
CN China 3
DE Germany 1
DK Denmark 1
EG Egypt 4
FR France 1
HK HongKong 3
IL Israel 4
IN India 3
IT Italy 1
JP Japan 3
KW Kuwait 4
MX Mexico 2
NG Nigeria 4
NL Netherlands 1
SG Singapore 3
UK United Kingdom 1
US United States of America 2
ZM Zambia 4
ZW Zimbabwe 4
14:45:11 SUCCESS [SELECT - 25 rows, 0.004 secs] Result set fetched
select * from hr.countries;
REGION_ID REGION_NAME
-----
5 Australia
6 South America
1 Europe
2 Americas
3 Asia
4 Middle East and Africa
14:45:11 SUCCESS [SELECT - 6 rows, 0.003 secs] Result set fetched
select * from hr.regions;
14:45:11 END Execution 2 statement(s) executed, 31 row(s) affected, exec/fetch time: 0.007/0.002 secs [2
successful, 0 errors]
```

23.2.3 Controlling the output

You can use options to control how much output to generate. If you only want to see the results, use the `-output` option with the result keyword:



```
> dbviscmd.bat -connection "Oracle" -sqlfile "myscript.sql" -output result
COUNTRY_ID  COUNTRY_NAME      REGION_ID
-----
AR          Argentina         2
AU          Australia         3
BE          Belgium           1
BR          Brazil            2
CA          Canada            2
CH          Switzerland       1
CN          China             3
DE          Germany           1
DK          Denmark           1
EG          Egypt            4
FR          France            1
HK          HongKong          3
IL          Israel            4
IN          India             3
IT          Italy             1
JP          Japan             3
KW          Kuwait           4
MX          Mexico           2
NG          Nigeria          4
NL          Netherlands       1
SG          Singapore         3
UK          United Kingdom    1
US          United States of  2
           America
ZM          Zambia            4
ZW          Zimbabwe          4
REGION_ID   REGION_NAME
-----
1           Europe
2           Americas
3           Asia
4           Middle East and Africa
```

For other scripts, for instance a script containing INSERT statements, you may only want to see the log messages:

```
> dbviscmd.bat -connection "Oracle" -sqlfile "myscript.sql" -output log
14:25:29 START Executing Command Line, Database Connection: Oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
14:25:30 INFO Physical database connection acquired for: Oracle
14:25:30 SUCCESS [SELECT - 25 rows, 0.012 secs] Result set fetched
select * from hr.countries;
14:25:30 SUCCESS [SELECT - 4 rows, 0.009 secs] Result set fetched
select * from hr.regions;
14:25:30 END Execution 2 statement(s) executed, 29 row(s) affected, exec/fetch time: 0.021/0.004 secs [2
successful, 0 errors]
```

23.2.4 Using variables - prompting for values

The DbVisualizer command line execution supports the DbVisualizer Variables as described in [Using DbVisualizer Variables](#). To enable this you will need to use the option `-processvariables`.



```
> dbviscmd.bat -connection "Oracle" -sql "SELECT FIRST_NAME FROM HR.EMPLOYEES where FIRST_NAME LIKE ${Name}||A%||String||};" -processvariables
dbviscmd: Valid inputs: Enter '_B_' for empty, '(null)' for null
dbviscmd: Variable 'Name' (Literal) [A%]: B%
11:25:26 START Executing Command Line for: 'Oracle' [Oracle], Schema: SYSTEM
11:25:26 INFO Physical database connection acquired for: Oracle
FIRST_NAME
-----
Bruce
Britney
11:25:26 SUCCESS [SELECT - 2 rows, 0.047 secs] Result set fetched
SELECT FIRST_NAME, LAST_NAME, PHONE_NUMBER FROM HR.EMPLOYEES where EMPLOYEES.FIRST_NAME LIKE B%;
11:25:26 END Execution 1 statement(s) executed, 2 row(s) affected, exec/fetch time: 0.047/0.000 secs [1
successful, 0 errors]
```

23.2.5 Combining OS scripts, the command line interface and DbVisualizer variables

For more complex tasks, you can call the command line interface from a shell script, for instance a Bourne shell script on Unix or a BAT file on Windows. You can also use DbVisualizer variables to pass information between the shell script and the SQL script. In this example, we have a simple SQL script (*cmdtest.sql*) that contains a SELECT statement with a variable in place for the table name:

cmdtest.sql

```
select * from ${table};
```

A text file (*tables.txt*) contains the table names we want to execute the SQL script with:

tables.txt

```
hr.countries
hr.regions
```

In a command shell (Bourne or Bash), we can then execute the script using the table names from the text file:



```
for name in `cat tables.txt`;
do ./dbviscmd.sh -connection "oracle" -sql "@run cmdtest.sql \${table}||\${name}||||nobind}\$";
done

15:01:19 START Executing Command Line, Database Connection: oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
15:01:20 INFO Physical database connection acquired for: oracle
15:01:20 RUNNING [@run ...ntries||||nobind}$ - - secs]
@run cmdtest.sql \${table}||hr.countries||||nobind}$;
COUNTRY_ID COUNTRY_NAME REGION_ID
-----
AR Argentina 2
AU Australia 3
BE Belgium 1
BR Brazil 2
CA Canada 2
CH Switzerland 1
CN China 3
DE Germany 1
DK Denmark 1
EG Egypt 4
FR France 1
HK HongKong 3
IL Israel 4
IN India 3
IT Italy 1
JP Japan 3
KW Kuwait 4
MX Mexico 2
NG Nigeria 4
NL Netherlands 1
SG Singapore 3
UK United Kingdom 1
US United States of America 2
ZM Zambia 4
ZW Zimbabwe 4
15:01:20 SUCCESS [SELECT - 25 rows, 0.016 secs] Result set fetched
select * from hr.countries;
15:01:20 SUCCESS [@run ...ntries||||nobind}$ - 0.016 secs] Script processed
@run cmdtest.sql \${table}||hr.countries||||nobind}$;
15:01:20 END Execution 1 statement(s) executed, 25 row(s) affected, exec/fetch time: 0.016/0.012 secs [1
successful, 0 errors]
java -cp /Users/ulf/work/github/dbvis/trunk/pureit/apps/dbvis/classes:/Users/ulf/work/github/dbvis/trunk/pureit/
apps/dbvis/resources:/Users/ulf/work/github/dbvis/trunk/pureit/apps/dbvis/external/* -Xmx512M -Djava.awt.headless=tr
ue -Ddbvis.home=/Users/ulf/work/github/dbvis/trunk/pureit/apps/dbvis com.onseven.dbvis.DbVisualizerCmd -masterpw
stairway -connection oracle -sql @run cmdtest.sql \${table}||hr.regions||||nobind}$;
15:01:23 START Executing Command Line, Database Connection: oracle Database Type: ORACLE Catalog: null Schema:
SYSTEM
15:01:23 INFO Physical database connection acquired for: oracle
15:01:23 RUNNING [@run ...egions||||nobind}$ - - secs]
@run cmdtest.sql \${table}||hr.regions||||nobind}$;
REGION_ID REGION_NAME
-----
5 Australia
6 South America
1 Europe
2 Americas
3 Asia
4 Middle East and Africa
15:01:23 SUCCESS [SELECT - 6 rows, 0.001 secs] Result set fetched
select * from hr.regions;
15:01:23 SUCCESS [@run ...egions||||nobind}$ - 0.001 secs] Script processed
@run cmdtest.sql \${table}||hr.regions||||nobind}$;
15:01:23 END Execution 1 statement(s) executed, 6 row(s) affected, exec/fetch time: 0.001/0.000 secs [1
successful, 0 errors]
```

The command line interface is called with the `-sql` option, specifying the [client-side command](#) `@run`. A [DbVisualizer variable](#) is passed to the `@run` command with the value taken from the shell variable. This DbVisualizer variable value is then available to the script executed by the `@run` command.



Note that you may need to escape certain characters that the shell would otherwise interpret, like the dollar signs that are part of the DbVisualizer variable delimiters.

23.3 Setting up the connection properties on the command line

As an alternative to using a connection already set-up through the DbVisualizer tool you may use the `-url` parameter. In combination with the parameters `-drivername`, `-driverclass`, and `-driverpath` these parameters enables you connect without prior specification using the DbVisualizer tool.

Following are some examples.

Executing SQL towards a MySQL instance running on localhost port 3306. The parameter `"-drivername MYSQL"` specifies that we are using a JDBC driver specified in the DbVisualizer tool named MySQL. For listing of the existing drivers use the **Tools->Driver Manager** in the DbVisualizer tool. Read more in [Installing a JDBC Driver](#).

Using -url and -drivername parameters

```
./dbviscmd.sh -url jdbc:mysql://localhost:3306/  
-drivername MYSQL  
-sql "select * from sakila.actor"  
-userid root
```

An alternative to use the `-drivername` you may use the parameters `-driverclass` and `-driverpath` to specify the JDBC driver.

Using -driverclass and -driverpath parameters

```
./dbviscmd.sh -url jdbc:oracle:thin:@localhost:1521/ORCL  
-driverclass oracle.jdbc.OracleDriver  
-driverpath "ojdbc6.jar:ora18n.jar:xdb.jar:xmlparserv2.jar"  
-sql "select * from HR.COUNTRIES"  
-userid system  
-password oracle
```

The above example connects to an Oracle instance on localhost and port 1521. Note that the separator character `!` between the different jar files is platform dependant. On Windows-based desktop platforms, the value of this field is the semicolon `;`.

23.4 Exit codes from dbviscmd

These are the exit codes when running dbviscmd

Code	Meaning
0	OK
1	Other error
2	Connect error
3	Script execution resulted in an error. Execution stopped
4	Script execution resulted in errors
5	Script execution failed unexpectedly

23.5 Generating a Command From SQL Commander

From time to time, you may want to use some SQL that you have tested in the GUI and run it in the command-line interface. You can generate the string with all parameters and paste that string on the command line or a script. Use menu option **SQL Commander -> Generate Command for dbviscmd** to open a dialog where you can specify the options. Some options are selected and some are disabled depending on the editor contents.

If you generate a command from an anonymous script (a script that has not been saved to file) with more than one line, you will be prompted to save the file or to generate a temporary file. If you generate the command from a file that is modified, you will be prompted to save the file before generating the command.

Besides the [Command Line Options](#), there are a few settings in the dialog:

- You can use a predefined (named) or an anonymous connection; this will enable and disable connection options accordingly.



- You can choose whether or not to **Include SQL Commander Options**; this is a convenient way to enable or disable all corresponding options. You can still enable or disable individual options as desired.
- You can choose whether or not to **Include Output Options**; this is a convenient way to enable or disable all corresponding options. You can still enable or disable individual options as desired.

Generate Command for dbviscmd [3: HR-selectSalaryLevel.sql] ✕

Generate a command line string for use with the command-line interface, **dbviscmd** (see [DbVisualizer Users Guide](#) for details). Select relevant options and **copy** to system clipboard when done.

Use Predefined Connection Use Anonymous Connection
 Include SQL Commander Options Include Output Options

Options

Include	Option	Value	Description
<input checked="" type="checkbox"/>	-connection <name>	Oracle Box	Database connection name (created with the GUI)
<input type="checkbox"/>	-url <URL>	jdbcoracle:thin:@192.168.1.187:1521/ORCL	Database URL
<input type="checkbox"/>	-drivername <name>	Oracle Thin	Database driver name (created with the GUI)
<input type="checkbox"/>	-driverclass <name>	oracle.jdbc.OracleDriver	Full name of the JDBC Driver class name
<input type="checkbox"/>	-driverpath <p1;p2;...>	D:\Program Files\DbVisualizer\jdbc\oracle\jdbc6.jar;D:\Program Files\DbVisualizer\jdbc\oracle\ora11g.jar;D:\Program Files\DbVisualizer\jdbc\oracle\xdb.jar;D:\Program Files\DbVisualizer\jdbc\oracle\mparserv2.jar	Paths to the jar files constituting the JDBC driver. Each path separated by a ";"
<input type="checkbox"/>	-userid <userid>	system	Userid to connect as
<input type="checkbox"/>	-password <password>	#UNDEFINED#	Password for userid
<input type="checkbox"/>	-masterpw <password>	<password>	Master Password for encrypted database passwords
<input type="checkbox"/>	-sql <statements>	N/A (multi-line statement)	One or more delimited SQL statements
<input checked="" type="checkbox"/>	-sqlfile <filename>	C:\Users\p2r\,dbvis\Bookmarks\HR-selectSalaryLevel.sql	SQL script file to execute
<input checked="" type="checkbox"/>	-encoding <encoding>	UTF-8	Encoding for the SQL script file
<input type="checkbox"/>	-catalog <catalog>	<catalog>	Catalog to use for unqualified identifiers
<input type="checkbox"/>	-schema <schema>	HR	Schema to use for unqualified identifiers
<input type="checkbox"/>	-maxrows <max>	1000	Maximum number of rows to display for a result set
<input type="checkbox"/>	-maxchars <max>	-1	Maximum number of characters to display for a column
<input type="checkbox"/>	-stoponerror		Stop execution when getting an error
<input type="checkbox"/>	-stoponsqlwarning		Stop execution when getting an SQL warning
<input type="checkbox"/>	-stoponnorows		Stop execution when empty result set or no affected rows
<input type="checkbox"/>	-stripcomments <true/false>	false	Strip comments before sending to database. Default is the setting made in the GUI
<input type="checkbox"/>	-processvariables		Process variables
<input type="checkbox"/>	-emptypromptvalue <string>	<string>	String to use when entering an empty value when prompted for variable(s)
<input type="checkbox"/>	-output <out>	<out>	"all" (default), output both log msgs and result sets "none", suppress both log messages and result sets "log", output only log messages "result", output only result sets
<input type="checkbox"/>	-outputfile <filename>	<filename>	Script execution output file. Default is stdout
<input type="checkbox"/>	-debug		Write debug messages
<input type="checkbox"/>	-debugfile <filename>	<filename>	File for debug messages. Default is stderr
<input type="checkbox"/>	-errordir <directory>	<directory>	Use an alternate location for error logs

Preview

Wrap Lines

```
D:\code\git.root\DbVis\intellij\pureit\apps\dbvis\bin\dbviscmd
-connection "Oracle Box"
-sqlfile "C:\Users\p2r\,dbvis\Bookmarks\HR-selectSalaryLevel.sql"
-encoding "UTF-8"
```



24 Database Profiles



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

A Database Profile is the foundation for database specific support in DbVisualizer. Technically the database profile is a single XML file specifying what object types, actions and viewers/editors should be available in the DbVisualizer user interface for a specific database.

24.1 Understanding Database Profiles



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

A database profile is, somewhat simplified, a definition of the kind of information that is presented in the database objects tree and in the various object views for a specific database engine. In addition, the profile defines the actions for the object types defined in the profile. DbVisualizer loads the matching database profile when you connect to a database. If no matching profile is found, or if you are running DbVisualizer Free, DbVisualizer uses a **Generic** profile with just the general database information and actions included.


DbVisualizer Pro currently offer database specific support (database profiles) for the following databases (click links for details):

- [DB2 LUW](#)
- [Exasol](#)
- [H2](#)
- [Informix](#)
- [JavaDB/Derby](#)
- [MariaDB](#)
- [Mimer SQL](#)
- [MySQL](#)
- [Netezza](#)
- [NuoDB](#)
- [Oracle](#)
- [PostgreSQL](#)
- [Redshift](#)
- [Snowflake](#)
- [SQL Server](#)
- [SQLite](#)
- [Sybase ASE](#)
- [Vertica](#)

The specialized database profiles define different object types, so the database objects tree may look different depending on which database you are connected to. The structure and organization of a database profile is also something that may impact the layout of the objects tree, even though the provided ones are similar in their structure. There are two root nodes in the majority of the provided profiles:

- **Schema Objects**
- **DBA objects**


Schema objects are, for example, **tables**, **views**, **triggers**, and **functions**, while DBA objects most often are objects that require administration privileges in the database in order to access them. The convention in DbVisualizer is to put all DBA objects under the **DBA Views** tree node. If you connect to a database using an account with insufficient privileges to access a DBA object, you may see error messages if you try to select nodes under the DBA Views node. The following is an example of the DBA sub tree for Oracle:



For databases that have no specific profile, DbVisualizer uses the **Generic** profile. DbVisualizer supports a wide range of databases. The nature of the databases and what they support differ from vendor to vendor, so the appearance and structure of the tree below the database connection objects for different databases differ as well. The generic database profile (the only profile available in DbVisualizer Free) displays objects based on what JDBC offers in terms of database information (aka metadata information). DbVisualizer asks the JDBC driver for all schemas, databases, tables and procedures, and then builds the tree based on what the driver returns.

The advantage of using JDBC to get database metadata is that it is a standard way to access the information, independent of the database engine type; the JDBC driver layer hides the proprietary details about where and how the information is really stored. The drawback with using JDBC is that JDBC doesn't offer access to all metadata a database may hold. While the information presented by the generic profile, with its reliance on JDBC, is sufficient for many tasks, a database specific profile offers far more details as well as more features. If you use DbVisualizer Free with one of the databases supported by database specific profiles, you may want to upgrade to the DbVisualizer Pro edition.

The generic database profile when used for an Oracle connection look as follows:



The appearance of the generic database profile may include schema objects and/or catalog objects depending on whether the database supports these objects. The Procedures object always appear in the tree, regardless of if the database connection supports procedures or not. There is no DBA Views node in the generic profile.

24.1.1 Affected DbVisualizer features

Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

One of the most important and central features in DbVisualizer is the **database objects tree**, used to navigate databases, and the **object view**, showing details about specific objects. The general problem exploring any database is that they are all different with respect to the information describing what's in the database (also called system tables or database meta data). This basically means that it's rather complex to implement a multi-database support product, such as DbVisualizer, since each database must be handled specifically. All databases also support different object types, apart from the most common ones, such as table, view, index, etc.

The database profile framework is used to simplify the process of defining what information DbVisualizer will display and operate on for a specific database. Technically, a database profile is an **XML** file with all of the logic, structure and actions mapped to the visual components in DbVisualizer. Another great benefit of separating the database specific logic from the implementation of DbVisualizer is that anyone with some degree of domain knowledge can create a database profile. All that is needed is a text editor (preferably with XML support) and some ideas of what should be the final result.

A great source for inspiration (except for related sections in the users guide) is all the existing database profiles that comes with DbVisualizer. All database profiles that comes with DbVisualizer are stored in the `DBVIS-HOME/resources/profiles` directory (exact path is OS dependent).



The following figure illustrates which features in DbVisualizer are controlled by the database profile.

The screenshot shows the DbVisualizer Pro interface. On the left, the 'Database Objects Tree' is visible, showing a hierarchy of objects under the 'CRM Ahoa' database. The 'EMPLOYEES' table is selected, and its data is displayed in a grid view on the right. The grid view shows columns for 'EMPLOYEE_ID', 'FIRST_NAME', 'LAST_NAME', 'EMAIL', and 'PHONE_NUMBER'. The data is presented in a table format with 20 rows.

EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER
1001	Steven	King	SKINGA	515.123.4567
100	Steven	King	SKING	515.123.4567
101	Neena	Kochhar	NKOCHHAR	515.123.4568
102	Lex	De Haan	LDEHAAN	515.123.4569
103	Alexander	Hunold	AHUNOLD	590.423.4567
104	Bruce	Ernst	BERNST	590.423.4568
105	David	Austin	DAUSTIN	590.423.4569
106	Valli	Pataballa	VPATABAL	590.423.4560
107	Diana	Lorentz	DLORENTZ	590.423.5567
108	Nancy	Greenberg	NGREENBE	515.124.4569
109	Daniel	Faviet	DFAVIET	515.124.4169
110	John	Chen	JCHEN	515.124.4269
111	Ismael	Sciarra	ISCIARRA	515.124.4369
112	Jose Manuel	Urman	JMURMAN	515.124.4469
113	Luis	Popp	LPOPP	515.124.4567
114	Den	Raphaely	DRAPHEAL	515.127.4561
115	Alexander	Khoo	AKHOO	515.127.4562
116	Shelli	Baida	SBAIDA	515.127.4563
117	Sigal	Tobias	STOBIAS	515.127.4564
118	Guy	Himuro	GHIMURO	515.127.4565

The red box at the left shows the **database objects tree**. This tree is used to navigate the objects in the database. Selecting an object in the tree shows the **object view (blue box)** for the selected object type. An object view may have several **data views (green)**, showing object information. DbVisualizer shows these as labeled tabs. The green box in the screenshot shows the content of the data view labeled Columns. The type of viewer that is presenting the data in the screenshot is the grid viewer. Read more about all data viewers in the [Viewers](#) section.

Common to both the database objects tree and the object view are the SQL **commands** that are used to fetch the information from the database. The associated SQL is executed by DbVisualizer whenever a node in the tree is expanded (to expose any child objects) or when a node is selected (to fill the object data views).

Right-clicking the mouse on an object in the tree or clicking the **Actions** button in the object view shows a menu with all valid **actions** for the selected object. These are also defined per database profile and object type. Read more about the capabilities of actions in the definition of [user actions](#) section.

The mapping from the visual components in the user interface described earlier and the element definitions in the XML file is, briefly, as follows:

- The database objects tree (green box) is described by the [ObjectsTreeViewDef](#) root element,
- The object views (green and blue boxes) are described by the [ObjectsViewDef](#) root element,
The commands used to execute the SQL to get the information for ObjectsTreeDef, ObjectsViewDef and ObjectsActionDef definitions are defined by the [Commands](#) root element,
- All Actions for an object are defined by the [ObjectsActionDef](#) root element.



24.1.2 How a Database Profile is loaded

i Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

DbVisualizer automatically detect what database profile to use based on the **Database Type** setting for a database connection. A database profile can also be manually specified in the connection properties.

A database profile is located using the search paths defined in **Connection Properties** tab and the **Database Profile** category. The standard directories in the search path are:

1. `PREFSDIR\ext\profile`
2. `DBVIS-HOME\resources\profiles`

PREFSDIR is the `.dbvis` directory located in the users home directory and it keeps all user settings for DbVisualizer. The list of paths may be reorganized and directories can be added. Profile files are searched in the specified order.

If the actual database profile is found in the search path it is loaded and any parent profile(s) it extends are also loaded and finally merged.

If there is no matching profile or if using the **DbVisualizer Free** edition then the **generic** profile is automatically used. This is very basic profile and shows only rudimentary information about the objects in the database and should support most databases with a JDBC driver.

A database profile other than the generic is built for a specific database. Manually selecting for example a database profile for Oracle while connecting to DB2 will result in all sorts of errors.

24.2 Creating a Database Profile

i Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

At a first glance creating and developing a database profile in XML may seem difficult. However, all definitions forming the functionality for a specific database are expressed in a single file and the XML elements are well formed. The general recommendation is to use one of the existing database profiles as base (copy/paste) and then step-by-step modify it for the actual database. You may use an external text editor (preferably with XML support) or the SQL editor in DbVisualizer to edit the file. Once new changes has been made, save the file, reconnect the database connection in DbVisualizer to test the layout and functionality changes.

Creating a new database profile should only be made for databases with no database profile available. If you are looking into changing one of the existing database profiles by adding or modifying existing functionality, it should be extended.

i For information where custom database profiles should be saved check the [How a Database Profile is loaded](#) is section.

For more information how to **create a new database profile** or **extending an existing database profile** check the [Extending a Database Profile](#) section.

24.3 Extending a Database Profile

i Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

- [Extending Commands](#)
- [Extending Database Objects Tree](#)
- [Extending Actions](#)
- [Extending Object Views](#)
- [Remove an Element](#)
- [Complete sample Database Profile](#)



All database profiles must extend the **generic** database profile. The generic profile handles the very basic object types in a relational database such as **Tables**, **Columns**, **Indexes** and **Procedures**. Its implementation is based entirely on what the **JDBC** driver provide in terms of database meta data. Due to the tight connection between the generic profile and the JDBC driver, the generic profile can be used to access almost any database with a JDBC driver.

The selection on what database profile should be used is determined with the **Database Type** setting for the database connection. Some of the database types that can be picked have a dedicated database profile with extended support while others have not. For databases with no database profile available, the generic one is used. It is also possible to manually choose the generic profile in the **Connection Properties / Database Profiles** settings.

The most important area in the database profile as seen from the DbVisualizer user interface is the section describing the **database objects tree**. This is the browser or navigator showing database objects. This is also the place that connects **actions** used to operate on database objects and **views** (not database views) used to display detailed information.

This section of the users guide is mainly focused on extending an existing database profile (not the generic profile) rather than creating a completely new profile (which should extend the generic database profile).

i Extending a database profile is not only about adding functionality to an existing profile but also the process of changing and removing existing definitions in any of the profiles that are extended.

24.3.1 Extending Commands

Extending the **Commands** and **InitCommands** elements is simple as every command should be uniquely identified. To add a **Command** just insert the new command.

```
<Commands extends="true">
  <Command id="sample.getLoginSchema">
    <SQL>
      <![CDATA[
select '${schema}' as schema from dual
      ]]>
    </SQL>
  </Command>
</Commands>
```

To override the definition of an existing command in the parent profile, just make sure the **id** of the new command match the id of the parent profile command. It will then be replaced.

24.3.2 Extending Database Objects Tree


Extending or modifying the database objects tree (ObjectsTreeDef) require some attention since the modifications must match the exact object paths as defined in the parent profile. The object path is determined by the **GroupNode** and **DataNode** structure in the ObjectsTreeDef with the addition of the **type** attribute. The following is an example of the object path to the **Columns** sub node for a **Table** node:

```
GroupNode[@type='Schemas']/DataNode[@type='Schema']/GroupNode[@type='Tables']/DataNode[@type='Table']/
GroupNode[@type='Columns']
```


(The [analyze database profile](#) utility will report object paths in the above **xpath** format).

i The hierarchy of GroupNode and DataNode is important when extending the database objects tree since the exact same hierarchy must be implemented in the extended profile. This also involve any conditional elements such as If/Else/Elseif that are used in the parent profile.

Consider the following example showing the objects tree (for Oracle) with the **Schemas** node being expanded to show all schemas in the database:



Instead of showing all schema objects in the database we want to adjust so that only the default schema is displayed at the top level (below the Oracle database connection node). The default schema node should in addition only show **table** objects rather than all 20 (or so) object types being displayed in the standard Oracle database profile.



The previous screenshot shows the new **My Schema: HR** node at the top while the **Schemas** node has been renamed **All Schemas**. To accomplish the above a custom database profile has been created in the `$(dbvis.prefsdir)/ext/profiles/sample-ext-oracle.xml` file with the following content required for the **ObjectsTreeDef** definition:



```
<!--Commands used in this profile-->
<Commands extends="true">
  <Command id="sample.getLoginSchema">
    <SQL>
      <![CDATA[
select '${schema}' as schema from dual
      ]]>
    </SQL>
  </Command>
</Commands>

<ObjectsTreeDef extends="true">
  <!--The following "Schema" definition shows the login schema directly below-->
  <!--the Database Connection for faster access. It is limited to only show-->
  <!--tables (by setting the "Table" DataNode to isLeaf="true")-->
  <DataNode type="Schema" label="My Schema: ${sample.getLoginSchema.SCHEMA}" order-before="0">
    <SetVar name="schema" value="${sample.getLoginSchema.SCHEMA}"/>
    <Command idref="sample.getLoginSchema">
      <Input name="schema" value="#db.loginSchema"/>
    </Command>

    <DataNode type="Table" label="${oracle.getTables.TABLE_NAME}" isLeaf="true">
      <SetVar name="objectname" value="${oracle.getTables.TABLE_NAME}"/>
      <SetVar name="rowcount" value="true"/>
      <SetVar name="acceptInQB" value="true"/>
      <Command idref="oracle.getTables">
        <Input name="owner" value="${schema}"/>
        <Input name="temporary" value="N"/>
        <ProcessDataSet action="sortcolumn" index="getTables.TABLE_NAME"/>
        <Filter index="getTables.TABLE_NAME" label="Table"/>
      </Command>

      <!--These are needed for the viewers defined in the parent profile-->
      <!--associated with the "Table" type-->
      <SetVar name="tableName" value="{objectname}"/>
      <SetVar name="parentName" value="{objectname}"/>
      <SetVar name="triggersCondition" value="and table_name = '{tableName}'"/>

    </DataNode>
  </DataNode>

  <!--Renaming the standard Schemas node to "All Schemas"-->
  <GroupNode type="Schemas" label="All Schemas"/>
</ObjectsTreeDef>
```

In the **Commands** section there is a new **Command** that run a dummy SQL SELECT only to create a result set containing a single row/column with the value of the **`\${schema}`** variable. The value for the **`\${schema}`** variable is provided in the Command element for **DataNode type="Schema"** using the **`\${db.loginSchema}`** variable value as input. This variable is maintained by DbVisualizer and contain the login schema as specified in the connection setup. For Oracle this is the **userid**.

```
<Command idref="sample.getLoginSchema">
  <Input name="schema" value="#db.loginSchema"/>
</Command>
```

The command above is used to present the default schema as in the following **DataNode** declaration.

```
<DataNode type="Schema" label="My Schema: ${sample.getLoginSchema.SCHEMA}" order-before="0">
  <SetVar name="schema" value="${sample.getLoginSchema.SCHEMA}"/>
  <Command idref="sample.getLoginSchema">
    <Input name="schema" value="#db.loginSchema"/>
  </Command>

  <DataNode type="Table">
    ...
  </DataNode>
</DataNode>
```



The label for this Schema type is `label="My Schema: ${sample.getLoginSchema.SCHEMA}"`. The `${sample.getLoginSchema.SCHEMA}` variable name consists of two parts, the name of the command: `sample.getLoginSchema` and the column name: `SCHEMA` in the result set the produced by the command.

As a sub node to the **My Schema** node there is the **DataNode type="Table"** definition for the Table object type. The complete declaration for the Table element and its sub elements has been copied from the parent profile:

```
<DataNode type="Table" label="${oracle.getTables.TABLE_NAME}" isLeaf="true">
  <SetVar name="objectname" value="${oracle.getTables.TABLE_NAME}"/>
  <SetVar name="rowcount" value="true"/>
  <SetVar name="acceptInQB" value="true"/>
  <Command idref="oracle.getTables">
    <Input name="owner" value="${schema}"/>
    <Input name="temporary" value="N"/>
    <ProcessDataSet action="sortcolumn" index="TABLE_NAME"/>
    <Filter index="TABLE_NAME" label="Table"/>
  </Command>

  <!--These are needed for the viewers defined in the parent profile-->
  <!--associated with the "Table" type-->
  <SetVar name="theTableName" value="${objectname}"/>
  <SetVar name="theParentName" value="${objectname}"/>
  <SetVar name="triggersCondition" value="and table_name = '${theTableName}'"/>
</DataNode>
```

The **Table** objects in the extended profile should not show any sub nodes such as columns or triggers and these declarations are then removed in the copied **DataNode** for the Table object. The `isLeaf="true"` attribute specifies that there will be no child nodes.

The new **All Schemas** node in the extended profile is supposed to have the exact same content and definition as in the parent profile when it was called **Schemas**. The following definition will just rename the label of the existing node.

```
<GroupNode type="Schemas" label="All Schemas"/>
```

This example show adding a new **Role** node under all **DBA / Users / User** objects.

In the parent Oracle profile there are no child nodes below **User**. To handle this all nodes from **DBA** down to **User** must be specified (aka the object type path). The only requirement is that the type attribute is specified and that it match the type in the parent profile. In addition, this example specify the **label** attribute for some of the nodes just to show that **overridden attributes** will replace any parent equivalent node attributes.



Only attributes for **GroupNode** and **DataNode** can be overridden. If you need to override for example a **SetVar** in a **DataNode** then all of the attributes in the **DataNode** and all its sub elements must be specified.

```
<GroupNode type="DBA" label="Database Administration">
  <GroupNode type="Users">
    <!--The "User" type don't allow child nodes in the parent profile.-->
    <!--Setting isLeaf="false" is needed to override this and allow the-->
    <!--new "Role" child node-->
    <DataNode type="User" isLeaf="false">
      <!--Here comes the new child "Role" DataNode-->
      <DataNode type="Role" isLeaf="true" label="${oracle.getGranteeRoles.GRANTED_ROLE} - ext">
        <SetVar name="objectname" value="${oracle.getGranteeRoles.GRANTED_ROLE}"/>
        <Command idref="oracle.getGranteeRoles">
          <Input name="grantee" value="${objectname}"/>
        </Command>
      </DataNode>
    </DataNode>
  </GroupNode>
</GroupNode>
```

The following are specified only to redefine the position of the **Locks** and **Sessions** nodes. One of **order-before** and **order-after** attributes are used to either identify a type for which the node should be positioned before or after, or an index. The index is the fixed position or 0 which means first or a somewhat high number means last. The following will move the **Sessions** first among the **DBA** child nodes.

```
<GroupNode type="Sessions" order-before="0"/>
<!--The following will move the "Locks" node before "Sessions"-->
<GroupNode type="Locks" order-before="Sessions"/>
```



24.3.3 Extending Actions

Extending `ActionGroup` and `Action` elements follow the same rules as for extending `ObjectsTreeDef` section. The following example show removing the `oracle-schema-stringsearch` action for the `Schema` object type in the parent profile. A new **ActionGroup: Extended Schema Actions** is added with a single new **Action: sample-schema-sample-action**.

```
<ObjectsActionDef extends="true">
  <ActionGroup type="Schema">
    <!--Remove action from parent profile for "Schema"-->
    <Action id="oracle-schema-stringsearch" action="drop"/>
    <!--Adds an "Extended Schema Actions" sub menu in the "Schema" actions menu-->
    <ActionGroup type="sample-schema-test" label="Extended Schema Actions">
      <!--Sample action that does nothing-->
      <Action id="sample-schema-sample-action" label="Sample Action"
        reload="true" resetcatalogs="true" icon="remove">
        <Input label="Text Field" name="textField" style="text" editable="true"/>
        <Command>
          <SQL><![CDATA[Sample Action "${textField}]]></SQL>
        </Command>
        <Confirm>
          Really run Sample Action "${textField}"?
        </Confirm>
        <Result>
          Sample Action "${textField}" processed!
        </Result>
      </Action>
    </ActionGroup>
  </ActionGroup>
</ObjectsActionDef>
```

24.3.4 Extending Object Views

Extending `<ObjectView>` and `<DataView>` elements follow the same rules as previously explained.

```
<ObjectsViewDef extends="true">
  <!--Schema is dropped in the Oracle profile. Redefine it here and show the-->
  <!--dictionary views. That data is really not associated with the single schema-->
  <!--defined in this profile but is a way to have it quickly accessed from-->
  <!--a single node.-->
  <ObjectView type="Schema">
    <DataView id="sample-schema-dict" label="Dictionary"
      icon="sample-schema-dict" viewer="grid">
      <Command idref="sample.getDict"/>
      <Message>
        <![CDATA[
<html>
Simple viewer showing all dictionary tables with description. Easily accessed
by opening the Schema viewer since that is empty anyway in the
parent <b>oracle</b> profile.
</html>
]]>
      </Message>
    </DataView>
  </ObjectView>
</ObjectsViewDef>
```

24.3.5 Remove an Element

Removing an object in the parent profile is easy, just add the `action="drop"` attribute to any of `GroupNode`, `DataNode`, `ObjectView`, `DataView`, `ActionGroup` and `Action` elements. If there are any sub elements for the object being dropped, these are also removed.



24.3.6 Complete sample Database Profile

This document describe the different parts of a extended sample database profile for an Oracle database. Here follow the complete sample database profile. If you would like to test it with your Oracle database, then just copy and paste it to your `$HOME\.dbvis\ext\profiles` folder as `sample-oracle.xml`. In DbVisualizer open **Connection Properties** for your Oracle connection and click **Database Profiles** category. In the list of profiles choose **sample-oracle**, click **Apply** and then connect.



```
<?xml version="1.0" encoding="UTF-8" ?>
<!DOCTYPE DatabaseProfile SYSTEM "dbvis-defs.dtd">

<!--
  Copyright (c) DbVis Software AB. All Rights Reserved.
-->

<DatabaseProfile
  desc="Sample profile extending the Oracle profile"
  extends="oracle"
  minver="9.5">

  <!--Commands used in this profile-->
  <Commands extends="true">
    <Command id="sample.getLoginSchema">
      <SQL>
        <![CDATA[
select '${schema}' as schema from dual
        ]]>
      </SQL>
    </Command>

    <Command id="sample.getDict">
      <SQL>
        <![CDATA[
select * from dict order by table_name
        ]]>
      </SQL>
    </Command>
  </Commands>

  <ObjectsActionDef extends="true">
    <ActionGroup type="Schema">
      <!--Remove action from parent profile for "Schema"-->
      <Action id="oracle-schema-stringsearch" action="drop"/>

      <!--Adds an "Extended Schema Actions" sub menu in the "Schema" actions menu-->
      <ActionGroup type="sample-schema-test" label="Extended Schema Actions">
        <!--Sample action that does nothing-->
        <Action id="sample-schema-sample-action" label="Sample Action" reload="true"
          resetcatalogs="true" icon="remove">
          <Input label="Text Field" name="textField" style="text" editable="true"/>
          <Command>
            <SQL><![CDATA[Sample Action "${textField}"]]></SQL>
          </Command>
          <Confirm>
            Really run Sample Action "${textField}"?
          </Confirm>
          <Result>
            Sample Action "${textField}" processed!
          </Result>
        </Action>
      </ActionGroup>
    </ActionGroup>
  </ObjectsActionDef>

  <ObjectsTreeDef extends="true">
    <!--The following "Schema" definition shows the login schema directly below-->
    <!--the Database Connection for faster access. It is limited to only show-->
    <!--tables (by setting the "Table" DataNode to isLeaf="true")-->
    <DataNode type="Schema" label="My Schema: ${sample.getLoginSchema.SCHEMA}" order-before="0">
      <SetVar name="schema" value="${sample.getLoginSchema.SCHEMA}"/>
      <Command idref="sample.getLoginSchema">
        <Input name="schema" value="${#db.loginSchema}"/>
      </Command>

      <DataNode type="Table" label="${oracle.getTables.TABLE_NAME}" isLeaf="true">
```



```
<SetVar name="objectname" value="{oracle.getTables.TABLE_NAME}"/>
<SetVar name="rowcount" value="true"/>
<SetVar name="acceptInQB" value="true"/>
<Command idref="oracle.getTables">
  <Input name="owner" value="{schema}"/>
  <Input name="temporary" value="N"/>
  <ProcessDataSet action="sortcolumn" index="TABLE_NAME"/>
  <Filter index="TABLE_NAME" label="Table"/>
</Command>

<!--These are needed for the viewers defined in the parent profile-->
<!--associated with the "Table" type-->
<SetVar name="theTableName" value="{objectname}"/>
<SetVar name="theParentName" value="{objectname}"/>
<SetVar name="triggersCondition" value="and table_name = '{theTableName}'"/>

</DataNode>
</DataNode>

<!--Renaming the standard Schemas node to "All Schemas"-->
<GroupNode type="Schemas" label="All Schemas"/>

<!--The main purpose with the following is to add a "Role" child DataNode -->
<!--for each "User". In the parent Oracle profile there are no child-->
<!--nodes below "User". To handle this all nodes from "DBA" down to "User"-->
<!--must be specified. The only requirement is that the type attribute is-->
<!--specified and that it match the type in the parent profile.-->

<!--In addition, this example specify the label attribute for some of the-->
<!--nodes just to show that overridden attributes will replace any parent-->
<!--equivalent node attributes.-->
<GroupNode type="DBA" label="Database Administration">
  <GroupNode type="Users">
    <!--The "User" type don't allow child nodes in the parent profile.-->
    <!--Setting isLeaf="false" is needed to override this and allow the-->
    <!--new "Role" child node-->
    <DataNode type="User" isLeaf="false">
      <!--Here comes the new child "Role" DataNode-->
      <DataNode type="Role" label="{oracle.getGranteeRoles.GRANTED_ROLE} - ext" isLeaf="true">
        <SetVar name="objectname" value="{oracle.getGranteeRoles.GRANTED_ROLE}"/>
        <Command idref="oracle.getGranteeRoles">
          <Input name="grantee" value="{objectname}"/>
        </Command>
      </DataNode>
    </DataNode>
  </GroupNode>
</GroupNode>

<!--The following are specified only to re-define the position of the-->
<!--"Locks" and "Sessions" nodes. One of "order-before" and "order-after" -->
<!--attributes are used to either identify a type for which the node should-->
<!--be positioned before or after, or an index. The index is the fixed position-->
<!--or 0 which means first or a somewhat high number means last.-->

<!--The following will move the "Sessions" first among the "DBA"-->
<!--child nodes-->
<GroupNode type="Sessions" order-before="0"/>

<!--The following will move the "Locks" node before "Sessions"-->
<GroupNode type="Locks" order-before="Sessions"/>
</GroupNode>
</ObjectsTreeDef>

<ObjectsViewDef extends="true">
  <!--Schema is dropped in parent profile. Re-define it here and show the-->
  <!--dictionary views. That data is really not associated with the single schema-->
  <!--defined in this profile but is a way to have it quickly accessed from-->
  <!--a single node.-->
```



```
<ObjectView type="Schema">
  <DataView id="sample-schema-dict" label="Dictionary" icon="sample-schema-dict" viewer="grid">
    <Command idref="sample.getDict"/>
    <Message>
      <![CDATA[
<html>
Simple viewer showing all dictionary tables with description. Easily accessed
by opening the Schema viewer since that is empty anyway in the
parent <b>oracle</b> profile.
</html>
      ]]>
    </Message>
  </DataView>
</ObjectView>
</ObjectsViewDef>
</DatabaseProfile>
```

24.4 Top level XML Elements



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The top level XML elements in a database profile is as follows:

- [InitCommands](#) (optional)
Defines SQLs that are executed before the profile is being loaded,
- [Commands](#)
Defines the SQLs for the ObjectsTreeDef, ObjectsViewDef and ObjectsActionDef,
- [ObjectsActionDef](#) (optional)
Defines actions for object types,
- [ObjectsTreeDef](#)
Defines the structure and what objects should be visible in the objects tree,
- [ObjectsViewDef](#)
Defines the object views for a specific object type.

All database connections loads a database profile from an XML file and if there is no matching database profile, the **generic** profile is used. This profile use standard JDBC metadata requests to obtain information about the (some) objects in the database. The generic profile is located in `DBVIS-
HOME\resources\profiles\generic.xml`.

24.4.1 XML template

The following show an overview of a database profile with the top level XML elements.



```

1 <?xml version="1.0" encoding="UTF-8"?>
2 <!DOCTYPE DatabaseProfile SYSTEM "dbvis-defs.dtd">
3
4 <DatabaseProfile desc="Profile for Sybase ASE"
5     version="$Revision: 20369 $"
6     date="$Date: 2016-05-24 17:29:25 +0200 (Tue, 24 May 2016) $"
7     minver="9.5"
8     extends="generic">
9
10 <InitCommands extends="true">
11     ...
12 </InitCommands>
13
14 <Commands extends="true">
15     ...
16 </Commands>
17
18 <ObjectsActionDef extends="true">
19     ...
20 </ObjectsActionDef>
21
22 <ObjectsTreeDef extends="false">
23     ...
24 </ObjectsTreeDef>
25
26 <ObjectsViewDef extends="true">
27     ...
28 </ObjectsViewDef>
29
30 </DatabaseProfile>

```

The DOCTYPE identifier at row 2 defines the DTD that is used to validate the XML.

The root element for the database profile framework is the [DatabaseProfile](#) element setting various attributes. Continue to the next sections for information about XML elements forming a database profile.

24.4.2 XML element - DatabaseProfile

Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The DatabaseProfile is the root element in the XML file. It is required and have the following attributes:

```

<DatabaseProfile desc="Profile for Sybase ASE"
    minver="9.5"
    extends="generic">
    ...
</DatabaseProfile>

```

Attribute	Description
desc	The description of the profile
minver	The minimum version of DbVisualizer that is required for the profile to work
abstract	Used in a sub profile to indicate that the profile should not be selectable in DbVisualizer. An example is the mysql-base which can only be selected using the extended profiles for MySQL and MariaDB. The default is false
extends	The parent profile that is extended. In most situations at least generic should be specified

Most attributes except **extends** are informative and are displayed in the **Database Profile** list when selecting the connection properties for a database connection:



Database Connection: Sybase ASE Actions ▾

Sybase ASE Disconnected

Connection **Properties**

- ✓ Connection Properties
- Database Profile
- Driver Properties
- [-] Sybase ASE
 - Authentication
 - Delimited Identifiers
 - Qualifiers
 - Connection Keep-Alive
 - Physical Connection
 - Transaction
 - Encoding
 - SQL Statements
 - Connection Hooks
 - Color and Border
 - SQL Commander
 - Query Builder

Database Profiles

Database profiles in DbVisualizer Pro controls what objects appear in the objects tree, what detailed views are available for each object type and actions used to operate on objects. A database profile is database specific and here you can either decide to let DbVisualizer automatically pick (recommended) the matching profile based on the **database type** setting or manually choose one. If manually choosing a profile make sure it is compatible with the database you are connecting to. The **generic** profile works with any database. **Note:** You must reconnect the database connection after changing profile.

Auto Detect
 Manually Choose
 "Generic" Profile

Profile	Description	Date
db2-zos	Profile for DB2 z/OS	2016-06-03
db2	Profile for DB2 LUW	2016-06-03
derby	Profile for Apache Derby/3...	2016-05-24
generic	Generic profile for any dat...	2016-05-18
h2	Profile for H2	2016-04-25
informix	Profile for Informix IDS	2016-05-24
mimer	Profile for Mimer SQL	2016-06-03
mysql	Profile for MySQL	2016-06-03
neoview	Profile for HP Neoview	2016-01-14

Defaults Apply

24.4.3 XML element - InitCommands

i Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The **InitCommands** element define initialization **commands** that are executed just before the rest of the database profile is loaded. These commands are typically used to determine characteristics of the target database and database session. The result of these commands are stored in **variables** that can be used in **conditions** that are evaluated when the rest of the profile is loaded. A common use case is to find out the authorization level of the current user as defined in the database. If the user have limited privileges then some object types, views and actions should be disabled.

Multiple commands may be defined in the InitCommands element and these are executed in order.

The main purpose with the following sample and the commands is to first determine the database version by querying a system table. Based on the database version a condition controls which of two queries will be executed to find out another property from the database. The result of the executed query is stored in a the **METACAT** variable.



```
<InitCommands extends="true">
  <Command id="neoview.getDbVersion" method="runBeforeConditionsEval">
    <SQL>
      <![CDATA[
SELECT SUBSTRING(SYSTEM_VERSION FROM 10)
FROM (GET VERSION OF SYSTEM) V(SYSTEM_VERSION)
      ]]>
    </SQL>
    <Output id="DBVERSION" index="1"/>
  </Command>

  <Command id="neoview.getMaster">
    <If test="#DBVERSION gte 2400">
      <SQL>
        <![CDATA[
SELECT MIN(SYSTEM_CATALOGS) AS MASTER_CAT
FROM (GET SYSTEM CATALOGS) V(SYSTEM_CATALOGS)
WHERE SYSTEM_CATALOGS LIKE _IS088591'NONSTOP_SQLMX_%'
        ]]>
      </SQL>
    </If>
    <Else>
      <SQL>
        <![CDATA[
SELECT 'NONSTOP_SQLMX_#{@dp.METACAT}'
FROM (VALUES(1)) AS T1
        ]]>
      </SQL>
    </Else>
    <Output id="METACAT" index="1"/>
  </Command>
</InitCommands>
```

The **extends="true"** attribute specifies that the list of commands will extend the list of commands defined in the profile being [extended](#).

Initialization commands are processed in two stages:

1. First stage is to execute all commands having the attribute **method="runBeforeConditionsEval"** set. As the attribute reveal, these commands are execute before any conditions are evaluated,
2. The second and last stage will execute all commands **with no** method="runBeforeConditionsEval" set. This time any conditions are evaluated.

The reason for these stages is that the processing of initialization commands may also rely on conditions.

Here is an example how the new **METACAT** variable is used in the rest of the database profile:

```
<Command id="neoview.getCatalogs">
  <SQL>
    <![CDATA[
SELECT
  TRIM(CAT_NAME) AS CATALOG_NAME
FROM
  ${METACAT}.SYSTEM_SCHEMA.CATSYS C
WHERE
  CAT_NAME NOT LIKE _IS088591'NONSTOP_SQLMX_%'
  AND CAT_NAME NOT IN (_IS088591'NSMWEB', _IS088591'NVSCRIPT', _IS088591'METRIC',
    _IS088591'MATRIX', _IS088591'GENUSCAT', _IS088591'MANAGEABILITY')
ORDER BY
  CATALOG_NAME
FOR READ UNCOMMITTED ACCESS
    ]]>
  </SQL>
</Command>
```

Here is another example for Oracle getting the **instance_type** property from the **v\$parameter** table and put the value in the **INSTANCE_TYPE** variable.



```
<InitCommands extends="true">
  <Command id="oracle.initGetInstanceType" method="runBeforeConditionsEval">
    <SQL>
      <![CDATA[
select value from v$parameter where name = 'instance_type';
      ]]>
    </SQL>
    <Output id="INSTANCE_TYPE" index="1"/>
  </Command>
</InitCommands>
```

Below show that only if **INSTANCE_TYPE** have the value **RDBMS** schema objects should be displayed in the database objects tree:

```
<ObjectsTreeDef extends="false">
  <If test="#INSTANCE_TYPE eq 'RDBMS'">
    <GroupNode type="Schemas" label="Schemas">
      ...
    </GroupNode>
  </If>

  <GroupNode type="Properties" label="Session Properties" isLeaf="true"/>
  <GroupNode type="DBA" label="DBA Views">
    ...
  </GroupNode>
</ObjectsTreeDef>
```

One more example showing the use of **<OnError>** and **<Message>** element **<InitCommands>**. Based on the database major version it runs one of two SQLs. If any **924** error (table not found) is raised the message will be logged in the DbVisualizer log. The `type="info"` defines that the log entry should be logged without further notification. Leaving the type out or setting it to `type="warning"` will also raise the error balloon in the DbVisualizer tool. Use this only when really necessary.

```
<InitCommands extends="true">
  <Command id="oracle.initInstanceNumber">
    <If test="#util.isDatabaseVersionLT(9)">
      <SQL><![CDATA[select -1 from dual;]]></SQL>
      <Output name="OWN_INSTANCE_NUMBER" index="1"/>
    </If>
    <Else>
      <SQL><![CDATA[select instance_number from v$instance;]]></SQL>
      <Output name="OWN_INSTANCE_NUMBER" index="1"/>
    </Else>
    <OnError>
      <If test="#result.getErrorCode() eq 942" context="runtime">
        <Message type="info">
          <![CDATA[
Could not to retrieve own INST_ID (probably due to missing privileges) which is needed to browse DBA->Sessions, etc.
DbVisualizer will work fine but related features will be disabled
          ]]>
        </Message>
      </If>
    </OnError>
  </Command>
</InitCommands>
```

Click these links for more information about the [command](#) element and [conditions](#).

24.4.4 XML element - Commands



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The **Commands** element is a simple grouping element for **Command** elements.

- [XML element - Command](#)



- [Result Set](#)
- [XML element - Input](#)
- [XML element - Output](#)
- [Filter](#)
- [ProcessDataSet](#)
- [ProcessSQLWarning](#)

```
<Commands extends="true">
  <Command id="profileName.xxx">
    ...
  </Command>
</Commands>
```

The **extends="true"** attribute specifies that the list of commands will extend the list of commands defined in the profile being [extended](#).

XML element - Command

The main purpose with the **Command** element is to run a single **SQL statement** or a **script** of SQL statements. In most cases, the script should return a result set with 0 or multiple rows with the exception for [actions](#) which not necessarily need to return a result set, e.g., a "drop" action). The following show the command element, its attributes with default values, and valid sub elements.

```
<Command id="sybase-ase.getLogins"
  method="dynamic"
  exectype="script"
  processmarkers="true"
  autocommit="true"
  whensuccess="commit"
  wherror="rollback">
  <SQL>
    ...
  </SQL>
  <Input>
    ...
  </Input>
  <Output>
    ...
  </Output>
  <Filter>
    ...
  </Filter>
  <ProcessDataSet>
    ...
  </ProcessDataSet>
  <ProcessSQLWarning>
    ...
  </ProcessSQLWarning>
</Command>
```

Attribute	Description
id	The command element is identified with a unique id attribute. This id is referred in ObjectsTreeDef , ObjectsViewDef and ObjectsActionDef definitions using the idref attribute. The id naming convention for command elements is to prefix with the name of the profile and a dot. Example oracle.xxx , sqlserver.xxx , and so on.



Attribute	Description
method	<ul style="list-style-type: none"> • dynamic this is the default value and define that the SQL is a dynamic SQL statement as opposed to setting it to JDBC which defines that the SQL is really a JDBC meta data call rather than SQL, • jdbc See description for dynamic, • runBeforeConditionsEval this value is only considered if the command is define in the InitCommands section.
exectype	<ul style="list-style-type: none"> • script • asis • explain <p>The default behavior is that the SQL may contains multiple SQL statements each delimited by a semi colon (;). Set this attribute to false to disable multiple SQL statements.</p>
autocommit	<ul style="list-style-type: none"> • true • false
whensuccess	<ul style="list-style-type: none"> • commit • rollback • ask
whenevererror	<ul style="list-style-type: none"> • commit • rollback • ask • ignore

The following command queries login information in Sybase ASE.

```
<Command id="sybase-ase.getLogins">
  <SQL>
    <![CDATA[
SELECT name "Name", suid "SUID", dbname "Default Database", fullname "Full Name",
language "Default Language", totcpu "CPU Time", totio "I/O Time", pwdate "Password Set"
FROM master.dbo.syslogins ORDER BY 1
]]>
  </SQL>
</Command>
```

The id for this command is **sybase-ase.getLogins**. The reason for prefixing the id with the name of the profile is that profiles can be extended and id's need to be unique.



This SQL example show a command with a **SELECT** statement using **column aliases**. If no aliases are specified the column names should be used to refer the data.

Result Set

This is the result set for the previous query:


Name	SUID	Default Database	Full Name	Default Language	CPU Time	I/O Time	Password Set
jstask	3	master	(null)	(null)	0	10	2009-12-22 09:53:50
probe	2	subsystemdb	(null)	(null)	0	0	2009-12-22 08:37:35
sa	1	master	(null)	(null)	182	168723	2009-12-22 08:36:54

How DbVisualizer handle the result set depends on whether the command is executed as a request in the database objects tree (ObjectsTreeDef) or in the object view (ObjectsViewDef). If executed in the database objects tree, each row in the result set will be represented by a node in the tree. If executed in the object view, it is the viewer component that decide how the result will be displayed.

Another important difference between the database objects tree and the object view is that the tree is a hierarchical structure of objects while the object view presents information about a specific object. An object that is inserted in the database objects tree is a 1..1 mapping to a row from the result set. The end user will see these objects (nodes) by some descriptive label, as defined in the ObjectsTreeDef. All data for the row from the original result set is stored with the object in the tree and may be used in the **label, variables, conditions**, etc. This is not the case in the ObjectsViewDef.



The following example put some light on this. Consider the previous result set and that it is used to create objects in the database objects tree. The end user will see the following in DbVisualizer. (The label for each row is the name column in the result set.):



Each of the **jstask**, **probe** and **sa** nodes have all their respective data from the result set associated with the nodes. The data is referenced as **commandId.columnName**, i.e., **sybase-ase.getLogins.Name**, **sybase-ase.getLogins.Default Database**, etc. All associated data for the **sa** node in the example is listed next:

```
sybase-ase.getLogins.Name = sa
sybase-ase.getLogins.suid = 1
sybase-ase.getLogins.Default Database = master
sybase-ase.getLogins.Full Name = (null)
sybase-ase.getLogins.Default Language = (null)
sybase-ase.getLogins.CPU Time = 182
sybase-ase.getLogins.I/O Time = 168716
sybase-ase.getLogins.Password Set = 2009-12-22 08:36:54.576
```

The **DataNode** element definition presenting **jstask**, **probe** and **sa** nodes in the previous screenshot use the associated data for the **label** as follows:

```
<DataNode type="Login" label="{sybasease.getLogins.Name}" isLeaf="true">
  <SetVar name="objectname" value="{sybasease.getLogins.Name}"/>
  <Command idref="sybasease.getLogins">
    <Output id="sybasease.getLogins.Name" index="1"/>
    <Output id="sybasease.getLogins.suid" index="2"/>
  </Command>
</DataNode>
```

XML element - Input



The **Input** sub element for a **Command** is only used when a command is being referred with the **idref** attribute in any of **ObjectsActionDef**, **ObjectsTreeDef** or **ObjectsViewDef**. It has no effect specifying it for a **Command** in the **Commands** section.

There are two types of commands, with and without dynamic input. The difference is that dynamic commands accepts input data that is typically used to form the **WHERE** clause in **SELECT** SQLs. The previous example illustrates a static **SELECT** statement (without dynamic data).

To allow for dynamic input, just add variables at the positions (can be anywhere) in the **SQL** statement that should be replaced with dynamic values. The following is an extension of the previous example that allows for dynamic input.



```
<Command id="sybase-ase.getLogins">
  <SQL>
    <![CDATA[
SELECT name "Name", suid "SUID", dbname "Default Database", fullname "Full Name",
language "Default Language", totcpu "CPU Time", totio "I/O Time", pwdate "Password Set"
FROM master.dbo.syslogins WHERE name = '${name}' and suid = '${suid}' ORDER BY 1
]]>
  </SQL>
</Command>
```

This example add two input variables: **`\${name}`** and **`\${suid}`**. Values for these variables should then be supplied wherever the command is referred for execution via the Input element.

The following is an example from the ObjectsTreeDef that specify the **Input** sub elements to **map values** to the variables defined in the SQL.

```
<GroupNode type="Logins" label="Logins">
  <DataNode type="Login" label="${sybase-ase.getLogins.Name} isLeaf="true">
    <SetVar name="objectname" value="${sybase-ase.getLogins.Name}">
      <Command idref="sybase-ase.getLogins">
        <Input name="name" value="sa">
          <Input name="suid" value="${sybase-ase.getProcesses.suid}">
        </Command>
      </DataNode>
    </GroupNode>
```

(Note that the Command element refer the command via the **idref** attribute which is then matched with the corresponding **id** for the Command).

The **`\${name}`** variable in the SQL will be replaced with string **sa**.

The value for the **`\${suid}`** variable will in this case get the value of another variable, **sybase-ase.getProcesses.suid**. So where is this variable defined? As explained in the [Result Set](#) section, all the data for a row in the result set is associated with the corresponding node in the database objects tree. In addition, it is possible to use all the data kept by the node and even its parent nodes (as presented in the objects tree) in the input to commands. So to evaluate the **`\${sybase-ase.getProcesses.suid}`** variable, DbVisualizer first look for the variable in the current node. If it doesn't exist, it continues to look through the parent nodes until it reaches the root, which is the **Connections** node in the objects tree. If the variable is not found, it will be set to the string representation for null, which is (**null**) by default. Whenever a matching variable is found, DbVisualizer use its value and stops searching.

XML element - Output

As mentioned earlier, a specific column value in a result set row is referenced by the name of the column and then prefixed by the command id. Sometimes this is not desirable and the **Output** definition can be used to change this behavior. The following identifies a column in the result set by its **index number**, starting from 1, and then force its name to be set.

```
<Output index="1" name="sybase-ase.getLogins.Name"/>
<Output index="2" name="sybase-ase.getLogins.suid"/>
```

(The index attribute accepts either the name of the column or index number in the result set starting from the first column at index 1).

Filter

The Filter element assists the Database Objects Tree filtering what fields are available for the user to filter on. The label attribute for DataNode is always available for filtering. Declaring a specific Filter is useful if for example using the label1 attribute to show additional information about an object and it should be possible to filter its label.

Here is an example of the Column sub-node to Table objects showing a filter definition:

```
<GroupNode type="Columns" label="Columns">
  <DataNode type="Column" label="${getColumnDefinitions.COLUMN_NAME}"
    label1="${getColumnDefinitions.TYPE_NAME}" isLeaf="true"
    icon="#dataMap.get('getColumnDefinitions.IS_PRIMARY_KEY') eq true ? 'PrimaryKey' : 'Column'">
    <SetVar name="objectname" value="${getColumnDefinitions.COLUMN_NAME}"/>
    <Command idref="getColumnDefinitions">
      <Input name="schema" value="{schema}"/>
      <Input name="objectname" value="{theTableName}"/>
      <Input name="tableType" value="Table"/>
      <Filter index="TYPE_NAME" label="Type"/>
    </Command>
  </DataNode>
</GroupNode>
```




Above is filter is defined for the **TYPE_NAME** column in the result set. The label for it as it will appear in the filtering pane in DbVisualizer is **Type**.



The **Show Default Database/Schema** pre-defined filter in DbVisualizer requires a Filter for the **DataNode type="schema"** command. The label for this filter must be **Name**:

```
<DataNode type="Schema" label="${oracle.getSchemas.TABLE_SCHEM}">
  <SetVar name="schema" value="${oracle.getSchemas.TABLE_SCHEM}"/>
  <Command idref="oracle.getSchemas">
    <Filter index="TABLE_SCHEM" label="Name"/>
  </Command>
  ...
```

ProcessDataSet

The ProcessDataSet element is used to process the result set generated by a command. This process is performed just after the result set has been retrieved and before any **Output** elements are handled. Examples:

```
<ProcessDataSet action="addcolumn" index="Added Column" value="Add column with value 'Static string ${dbvis-jdbcURL}'"/>
<ProcessDataSet action="addrow" index="first" value="${#db.loginDatabase}"/>
<ProcessDataSet action="convertnullvalues" index="1" value=""/>
<ProcessDataSet action="convertsqlwarningtodataset"/>
<ProcessDataSet action="distinct" index="Country"/>
<ProcessDataSet action="dropcolumn" index="AUTO_INCREMENT"/>
<ProcessDataSet action="dropidenticalcolumns" name="datname"/>
<ProcessDataSet action="movecolumn" index="datname" value="first"/>
<ProcessDataSet action="printdataset"/>
<ProcessDataSet action="removeisnullrows" index="VALUE"/>
<ProcessDataSet action="removerowsifequalto" index="DATA_LENGTH" value="16384"/>
<ProcessDataSet action="renamecolumn" index="2" name="NewName"/>
<ProcessDataSet action="sortcolumn" index="LAST_NAME, FIRST_NAME"/>
<ProcessDataSet action="trimcolumn" index="PAD_COLUMN"/>
<ProcessDataSet action="truncatedataset" value="keeplast 5"/>
```

Explanation of the actions. The index attribute for actions that process columns, the start index is 1, while actions processing rows start with index 0.

action	Description
addcolumn	Adds a new column to all rows with the value specified in the value attribute. The value may contain variables using the \${...} notation
addrow	Adds a new row in the result set at the specified position which can be "first", "last" or a specific row index starting at 0. The value attribute is a TAB separated list of column values. The first element will go into column 0 in the result set, the second in column 1, and so on. Variables may be used in the value.
convertnullvalues	Converts any null values in the specified column to the literal specified in the value attribute.
convertsqlwarningtodataset	Converts any SQL Warnings generated by the command to a result set
distinct	This action is used to remove all duplicates identified by the specified column index. What rows are removed may be different from time to time since matching is done on a single column value
dropcolumn	Drops the specified column
dropidenticalcolumns	Drops identically named columns (keeps first)
movecolumn	Moves the column specified by the index attribute by index or name to the position specified by the value attribute. The latter can be expressed as "first", "last" or a specific column index.
printdataset	Prints the result set to the debug log which is useful during profile development. Debug DbVisualizer must be enabled in the Tool->Debug Window.
removeisnullrows	Removes the row if the value in the specified result set column is null



action	Description
removerowsifequalto	Removes the row if the data in the specified column is equal to the specified value
renamecolumn	Renames the result set column identified by the index
sortcolumn	Enter one or several column names (or indexes) separated with command (',') which are used to sort the result set
trimcolumn	Trims the data in the specified column index by removing all leading and trailing whitespaces
truncatedataset	Truncates, i.e. removes a number of rows, from the start or the end of the result set: <ul style="list-style-type: none">• keepfirst <n>• keeplast <n>• removefirst <n>• removelast <n> truncatedataset is useful in for example <DataNode ... viewer="graph"> uses.

ProcessSQLWarning

The ProcessSQLWarning element will look for any SQLWarning raised during execution of the command and convert it to a result set.

```
<InitCommands extends="true">
  <Command id="netezza.supportsMultipleSchemas">
    <SQL>
      <![CDATA[
show enable_schema_dbo_check
      ]]>
    </SQL>
    <ProcessSQLWarning action="convertsqlwarningtodataset"/>
    <Output index="1" name="SUPPORTS_MULTIPLE_SCHEMAS"/>
  </Command>
</InitCommands>
```

Note: The SQLWarning support is quite brute as it will remove any other data sets produced by the command, and insert the SQLWarning alone as the only data set having a single 0,0 cell with the complete warning string.

The <If> condition based on the output from the previous InitCommand is:

```
<If test="#SUPPORTS_MULTIPLE_SCHEMAS.matches('^.*ENABLE_SCHEMA_DBO_CHECK is [12]$')">
  ...
</If>
```

24.4.5 XML element - ObjectsTreeDef



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The **ObjectsTreeDef** element section controls how the database objects tree should be presented and which commands should be executed to form its content (nodes).

- [XML element - GroupNode](#)
- [XML element - DataNode](#)
 - [XML element - Command](#)
 - [XML element - Filter](#)
 - [XML element - SetVar](#)



```
<ObjectsTreeDef extends="false">
  <GroupNode type="xxx" label="xxx">
    <DataNode type="yyy" label="yyy">
      ...
    </DataNode>
  </GroupNode>
</ObjectsTreeDef>
```

Setting the **extends** attribute to **"true"** attribute specifies that the ObjectsTreeDef will extend the ObjectsTreeDef definition in the profile being *extended*.

The mapping between the graphical representation in DbVisualizer and its ObjectsTreeDef XML is as quite straight forward:



Representation in DbVisualizer	XML specification
	<pre data-bbox="555 353 1476 1339"><ObjectsTreeDef extends="false"> <GroupNode type="Databases"> <DataNode type="Catalog"> <GroupNode type="Schemas"> <DataNode type="Schema"> <GroupNode type="Tables"> <DataNode type="Table"/> </GroupNode> <GroupNode type="SystemTables"> <DataNode type="SystemTable"/> </GroupNode> <GroupNode type="Views"> <DataNode type="View"/> </GroupNode> <GroupNode type="Indexes"> <DataNode type="Index"/> </GroupNode> <GroupNode type="Triggers"> <DataNode type="Trigger"/> </GroupNode> <GroupNode type="Procedures"> <DataNode type="Procedure"/> </GroupNode> <GroupNode type="Functions"> <DataNode type="Function"/> </GroupNode> </DataNode> </GroupNode> <GroupNode type="Users"> <DataNode type="User"/> </GroupNode> <GroupNode type="Groups"> <DataNode type="Group"/> </GroupNode> <GroupNode type="Types"/> </DataNode> </GroupNode> <GroupNode type="DBA"> <GroupNode type="ServerInfo"/> <GroupNode type="Logins"> <DataNode type="Login"/> </GroupNode> <GroupNode type="Devices"> <DataNode type="Device"/> </GroupNode> <GroupNode type="RemoteServers"/> <GroupNode type="Processes"/> <GroupNode type="ServerRoles"> <DataNode type="ServerRole"/> </GroupNode> <GroupNode type="Transactions"/> <GroupNode type="Locks"/> </GroupNode> </ObjectsTreeDef></pre>

The screenshot in the above example shows all **nodes** representing the **GroupNode** definitions in the ObjectsTreeDef. One exception is the **Logins** object, which has been expanded (**jstask**, **probe** and **sa** child objects) to illustrate how **DataNode** objects look like. The ObjectsTreeDef in the example has been simplified to show only the **type** attribute. (The label of the nodes as they appear in the screenshot is not listed in the example XML). The difference between a GroupNode and a DataNode is that GroupNode represents a static object in the tree while DataNode is dynamically created based on result sets produced by running a SQL statement. See GroupNode as a container holding other GroupNodes and DataNodes.

The database objects tree in DbVisualizer is the core visual component and it is the place where the user opens object details and launches actions. To connect **object actions** and **object views** with a node in the objects tree, the **type** attribute is used. The type should be a descriptive word for a node such



as **Table**, **Schemas**, **MaterializedQueryTable**, and so on. The type also map to a predefined **icon**. Check the [database profile utilities](#) for information how to show all bundled icons and their type mappings.

There is no limitation on the number of levels in the objects tree expressed by nesting GroupNode and DataNode elements. A good rule is as always to keep it intuitive, simple and clean.

XML element - GroupNode

The GroupNode element represents a static object in the tree. A GroupNode do not have any associated SQL and appear only once where they are defined. A GroupNode is primarily used for structural and grouping purposes. The GroupNode element have the following attributes.

```
<GroupNode type="SystemTables" label="System Tables" isLeaf="false">
  ...
</GroupNode>
```

The **isLeaf** attribute is optional (default is **false**) and controls whether the GroupNode may have any child objects or not. It can always be set to false, the effect in the visual database objects tree is then that an expand handle always will be visible next to the icon, even if the node don't have any child nodes.



If **isLeaf** is set to true and there are child Group and/or Data -nodes, these will not appear. The result may cause some frustration during the design of the database profile.

The complete set of attributes for the DataNode element:

Attribute	Value	Description
type		The type of node
label		The visual label for the node
label1		Optional label which shows additional information about the object
isLeaf	true/false	Specifies if the node cannot have child objects
icon		Icons are typically mapped using the type attribute with an icon name in the icon.prefs file(s). The icon attribute for a GroupNode can be set to specify an alternative icon. Conditions can be used to identify alternate icons (see below)
drop-label-not-equal		Do not add the node if the label is not equal to this value or variable
drop-on-condition		Read more in drop-on-condition attribute
order-before		Specifies the order of this GroupNode among a collection of nodes having the same parent node. It can either be an index starting at 0 (first) or a node type. Ex. order-before="Views" will order this GroupNode before nodes defined by the type="Views" attribute
order-after		Specifies the order of this GroupNode among a collection of nodes having the same parent node. It can either be an index starting at 0 (first) or a node type. Ex. order-after="0" will order this GroupNode after the first node definition

XML element - DataNode

The DataNode element feeds the tree with nodes produced by a **Command**. The example in the [Command](#) section querying for all logins in Sybase ASE look as follow in the ObjectsTreeDef:

```
<GroupNode type="Logins" label="Logins">
  <DataNode type="Login" label="{sybase-ase.getLogins.Name}" isLeaf="true">
    <Command idref="sybase-ase.getLogins"/>
  </DataNode>
</GroupNode>
```


First, there is a **GroupNode** element with the purpose to group all child objects in a Logins node. The **DataNode** in this example have the same attributes as the GroupNode, the type is however singular **Login** instead of plural **Logins** (as it is for the GroupNode). This difference is important when the user decide to open one of the nodes, since the object view will show the matching views based on the object type. For Logins a list of all logins is displayed while opening a Login, details for that specific login is displayed.

The DataNode definition can be seen as a template, as the associated command fetches rows of data from the database and DbVisualizer uses the DataNode definition to create one node per row in the result set.



The **label** attribute for the data node introduce the use a variable. The real value for the label will, in this example, be the value in the **Name** column produced by the **sybase-ase.getLogins** command (variable names are automatically prefixed with the command id that produced them).

The **Command** element uses the **idref** attribute to identify the command that should be executed. The command in this case produce a [result set](#) with 3 rows and 8 columns. The result will be two nodes for each row, with the label of the **Name** column in the result set.



The label1 attribute can be set to any other valid variable, a combination of several variables or even static text:

```
label1="{sybase-ase.getLogins.Default Database}"
```

The example above results in the following labels:

```
jstask master
probe subsystemdb
sa master
```

The complete set of attributes for the DataNode element:

Attribute	Value	Description
type		The type of node
label		The visual label for the node
label1		Optional label which shows additional information about the object
icon		Icons are typically mapped using the type attribute with an icon name in the icon.prefs file(s). The icon attribute for a DataNode can be set to specify an alternative icon. A condition can be specified which is used to choose an icon based on evaluating other variables for the node. Ex: icon="#dataMap.get('getColumnDefinitions.IS_PRIMARY_KEY') eq true ? 'PrimaryKey' : 'Column'"



Attribute	Value	Description
tip		An optional description that is displayed when hovering the node. This is useful to describe why a different icon is displayed for the node using the icon attribute. Ex: <code>tip="#dataMap.get('getColumnDefinitions.IS_PRIMARY_KEY') eq true ? 'This is a primary key column' : ''</code>
actiontype		Object type used for object actions
isLeaf	true/false	Specifies if the node cannot have child objects
drop-label-not-equal		Do not add the node if the label is not equal to this value or variable
stop-label-not-equal		The node will be a leaf if the label doesn't match the specified value or variable value
warnstate		A condition expression returning either true or false. For true, show a warning overlay icon for the node. Ex: <code>errorState="!#dataMap.get('oracle.getTriggers.STATUS'). equals('ENABLED')"</code>
errorstate		A condition expression returning either true or false. For true, show an error overlay icon for the node. Ex: <code>errorState="!#dataMap.get('oracle.getObjectsByType.STATUS'). equals('VALID')"</code>
is-empty-output	continue/stop	If result set is empty, use this to control whether child GroupNode/DataNodes should be added anyway
drop-on-condition		Read more in drop-on-condition attribute
order-before		Specifies the order of this DataNode among a collection of nodes having the same parent node. It can either be an index starting at 0 (first) or a node type. Ex. order-before="View" will order this node before nodes defined by the type="View" attribute
order-after		Specifies the order of this DataNode among a collection of nodes having the same parent node. It can either be an index starting at 0 (first) or a node type. Ex. order-after="0" will order this DataNode after the first node definition

The Command definition in the example above is simple, since it doesn't use any variables in the SQL. Continue reading the next section for details about passing input data to commands.

XML element - Command

The SQL used to generate the data used by the DataNodes are defined in the **Command** element.

A command is referenced by the **idref** attribute and that **id** must already be defined in the [Commands](#) section of the profile. For most DataNode definitions input must be supplied with the command and this is done by adding **Input** elements as children to the Command.

```
<DataNode type="Login" label="{sybase-ase.getLogins.Name}" isLeaf="true">
  <Command idref="sybase-ase.getLogins">
    <Input name="name" value="sa">
    <Input name="suid" value="{sybase-ase.getProcesses.suid}">
  </Command>
</DataNode>
```

The **value** for a variable specified in an **Input** element is evaluated using the syntax outlined in the [result set](#) section.



For detailed information about the capabilities with the Command element, check the [Command](#) section.

XML element - Filter

The Filter element is specific for Command elements that appear in the DataNode element. A filter define which data for a DataNode that can be searched in filter. This filter functionality is commonly referred as the [Database Objects Tree Filtering](#) in DbVisualizer. The filtering setup appears below the database objects tree, and the following example shows that filtering may be specified for these object types:

- Catalog
- Table
- System Table
- View
- User
- Group



- Trigger
- Procedure

For each of the filter definitions, one or several columns can be included in the filtering criteria.

Filters for **Catalog** objects (filter set: **default**)

<input checked="" type="checkbox"/>	Field	Condition	Value
<input checked="" type="checkbox"/>	Label	begins with	m

```
<DataNode type="View" label="\${sybase-ase.getViews.Name}" isLeaf="true">
  <Command idref="sybase-ase.getViews">
    <Filter index="TABLE_NAME" label="View Table"/>
  </Command>
</DataNode>
```

The above filter definition specifies a filter for the Catalog (database) object type. The **index** attribute should specify a **column name** or **index** in the result set while the **label** attribute is the name how it appears in the object type drop-down list.

XML element - SetVar

The SetVar element is used in the ObjectsTreeDef for GroupNode and DataNode elements. Some object types have special meaning in DbVisualizer. Two examples are the **Catalog** and **Schema** object types. For DataNode objects, you must use SetVar elements to identify them with the name attribute set to **catalog** or **schema**, respectively.



```
<DataNode type="Catalog" label="{getCatalogs.TABLE_CAT}">
  <SetVar name="catalog" value="{getCatalogs.TABLE_CAT}">
</DataNode>
```

All DataNodes except Catalog and Schema must use SetVar to set the **objectname** variable:

```
<DataNode type="View" label="{sybase-ase.getViews.Name}" isLeaf="true">
  <SetVar name="objectname" value="{sybase-ase.getViews.Name}">
  <SetVar name="rowcount" value="true">
</DataNode>
```

The **objectname** variable is used to identify the object represented by the data node, so that it can be uniformly referenced in [object views](#) and [object actions](#). Its value should be the identifier for the object as it is identified in the database, for example a table name or view name.

The **rowcount** variable is optional (default is false) and controls whether the object supports showing row count information when [Show/Hide Table Row Count](#) right-click menu choice is enabled for the database connection.

Another optional variable (not shown in the example above) is named **acceptInQB** (default is false). If set to true, nodes of this type can be used in the [Query Builder](#). It should only be set to true for object types representing tabular data that can be queried with an SQL SELECT statement, such as tables, views, materialized views, etc.

Variables defined with SetVar are by default invisible in for example the [node form viewer](#). If you want to override this behavior then add the **action** attribute and set its value to **show**. If you want to drop a variable completely from the node simply set the **action** attribute to **drop**.

Using SetVar for GroupNode's is used to set static values (since GroupNode's doesn't execute a Command). This may be used to pass a static value for later use in an Action or DataView. See [vertica.xml](#) which illustrates using SetVar for GroupNode's.

24.4.6 XML element - ObjectsViewDef



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

The ObjectsViewDef element define all views for the object types in the objects tree. These views are displayed in the [Object View](#) area for the selected object. Which views should appear when selecting a node in the tree is based on the object type for the tree node and the corresponding object [view](#) definition.

- [XML element - ObjectView](#)
- [XML element - DataView](#)
 - Viewers
 - [Viewer - chart](#)
 - [Viewer - ddl](#)
 - [Viewer - form](#)
 - [Viewer - grid](#)
 - [Drill-down view](#)
 - [Adding custom menu items in the grid](#)
 - [Setting initial max column width](#)
 - [Viewer - message](#)
 - [Viewer - navigator](#)
 - [Viewer - node-form](#)
 - [Hiding columns](#)
 - [Viewer - procedure-editor](#)
 - [Viewer - table-data](#)
 - [Disable data editing](#)
 - [Viewer - table-refs](#)
 - [Viewer - tables-refs](#)
 - [Viewer - table-rowcount](#)
 - [Viewer - text](#)
 - [Specify what column to browse](#)
 - [Enable SQL formatting of the data](#)
 - [Adding newline to each row](#)
 - [XML element - Command](#)
 - [XML element - Input](#)



- XML element - Message


```
<ObjectsViewDef extends="true">
  <ObjectView type="xxx">
    <DataView id="yyy" label="yyy">
      ...
    </DataView>
  </ObjectView>
</ObjectsViewDef>
```

The **extends="true"** attribute specifies that this definition will extend the ObjectsViewDef definition in the database profile being **extended**.



All database profiles should extend **generic** profile as the very top level profile.

When an object is opened in the database tree (**sa** in the screenshot below) a corresponding object view tab is created (right in the sample). Each of the DataView elements in the ObjectView will appear as sub tabs in the object view tab. The selected object and its information is passed to each of the data views for processing and presentation. The following example show the Object View in DbVisualizer and its ObjectView element definition.

Representation in DbVisualizer	XML definition
	<pre><ObjectView type="Logins"> <DataView type="Logins" label="Logins" viewer="grid"> <Command idref="sybase-ase.getLogins"/> </DataView> </ObjectView> <ObjectView type="Login"> <DataView type="Info" label="Info" viewer="node-form"/> <DataView type="Databases" label="Databases" viewer="grid"> <Command idref="sybase-ase.getLoginDatabases"/> </DataView> <DataView type="Roles" label="Roles" viewer="grid"> <Command idref="sybase-ase.getLoginRoles"/> </DataView> </ObjectView></pre>

The screenshot and the database tree show both the **Logins** node and its child nodes, **jstask**, **probe** and **sa**. These nodes are instances of the object types **Logins** (labeled Logins in the screenshot) and **Login** (the three sub nodes: **jstask**, **sa** and **probe**).

The ObjectView XML definitions above shows the data views for these two types, **Logins** and **Login**. Opening the node labeled **Logins** in the tree will show the object view for the **<ObjectView type="Logins">** definition while opening the node labeled **jstask**, **probe** or **sa** will show the object view for the **<ObjectView type="Login">**.

The example shows **sa** being selected. Its DataView definitions displayed as tabs in the object view are (by label):

- Info
- Databases
- Roles

XML element - ObjectView

The ObjectView element is associated with an object type and groups all DataView elements that appear when the object type is selected in the database objects tree. Here follows the ObjectView definition for the Login object type.


```
<ObjectView type="Login">
  ...
</ObjectView>
```

The **type** attribute value is used when a node is clicked in the database objects tree to map with the corresponding ObjectView definition. The following lists the attributes for ObjectView:




Attribute	Description
type	The type of the ObjectView as declared in the GroupNode and DataNode elements in the ObjectsTreeDef section
layout	<p>The layout attribute is used to tile the contained DataViews so that they are all visible at once in the object view. The default (collapse) shows all DataViews as tabs in a single tab group while tile shows them all side-by-side</p> <ul style="list-style-type: none"> • tilevertical <n> • tilehorizontal <n> • collapse (default) <p>The number <n> specifies how many DataViews should be present in the first group (vertical or horizontal) of DataViews.</p>
drop-on-condition	Read more in drop-on-condition attribute

The **layout** attribute is useful to tile DataViews side-by-side, either vertically or horizontally. Leaving it out will **collapse** the DataView tabs in a single tab group:



<p>layout="tilevertical"</p> <p>Tiles all tabs vertically in a single column</p>	<p>layout="tilevertical 2"</p> <p>Tiles the tabs vertically with two tabs in the first column and the rest in the second column</p>
---	--





layout="tilehorizontal"

Tiles all tabs horizontally in a single row



layout="tilehorizontal 2"

Tiles the tabs horizontally with two tabs in the first row and the rest in the second row 2



The previous tile examples all use the viewer="chart" for the DataView's. Please note that any supported viewer may be tiled.




XML element - DataView

The DataView element is comparable with the [DataNode](#) element in the ObjectsTreeDef. It defines what SQL (command) should be executed, labeling, viewer type (presentation form) and other characteristics. The following is the DataView definitions for the **Login** object type. (The ObjectView element is part of the sample just for clarification).

```
<ObjectView type="Login">
  <DataView type="sybasease-login-info" icon="Info" label="Info" viewer="node-form"/>
  <DataView type="sybasease-login-databases" icon="Databases" label="Databases" viewer="grid">
    <Command idref="sybase-ase.getLoginDatabases"/>
  </DataView>
  <DataView type="sybasease-login-roles" icon="Roles" label="Roles" viewer="grid">
    <Command idref="sybase-ase.getLoginRoles"/>
  </DataView>
</ObjectView>
```

All three DataView elements have a **viewer** attribute identifying how the data in the view should be presented, e.g., as a grid or a form. See the next sections for a list of viewers. The following lists all attributes for DataView:

Attribute	Description
id	Every DataView element must have a unique id which is not only unique in the current profile but also with all id's in extended profiles <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> To make sure the id is unique use the following recommended format: profileName-objectViewType-viewerLabel. Ex: sybasease-login-databases (The id should not contain any empty space or special characters other than dash ("-")).</div>
label	The label for the viewer as it will appear in the tab
icon	The icon as defined in the icons.prefs file(s)
viewer	One of: <ul style="list-style-type: none">• chart• ddl• form• grid• message• navigator• node-form• procedure-editor• table-data• table-refs• tables-refs• table-rowcount• text See the viewers section in this document for more information
drop-label-not-equal	Drop the viewer if its label is not equal to the value of this attribute
class	Used to specify a custom Java class used as the viewer
classargs	Used to pass arguments to a custom viewer
drop-on-condition	Read more in drop-on-condition attribute
doclink	Relative HTML link to the related chapter in the users guide.
order-before	Specifies the order of this DataView among a collection of viewers having the same parent ObjectView. It can either be an index starting at 0 (first) or a node type. Ex. order-before="sybasease-login-databases" will order this DataView before viewers defined by the id="sybasease-login-databases" attribute



Attribute	Description
order-after	Specifies the order of this DataView among a collection of viewers having the same parent ObjectView. It can either be an index starting at 0 (first) or a node type. Ex. order-after="sybasease-login-databases" will order this DataView after viewers defined by the id="sybasease-login-databases" attribute

Viewers

The viewer attribute for a DataView define how the data for the viewer should be presented. The following sections walk through the supported viewers:

- **chart**
- **ddl**
- **form**
- **grid**
- **message**
- **navigator**
- **node-form**
- **procedure-editor**
- **table-data**
- **table-refs**
- **tables-refs**
- **table-rowcount**
- **text**

The following sample illustrates the viewer attribute.

```
<ObjectView type="Login">
  <DataView type="Info" label="Info" viewer="node-form"/>
</ObjectView>
```

DataView definitions may be nested and the viewers are then presented with the nested DataView in the lower part of the screen.

Viewer - chart

The chart viewer presents a result set as a **chart**. This is typically useful for displaying monitoring metrics, statistics, and any result set from a query from the database. Using it with the **layout** attribute for the **ObjectView** element allows creating dashboards with charts and other viewers.

Here is a simple example defining the **DataView** using the chart viewer:

```
<DataView id="exasol-monitoringlastday-cpu" icon="Monitoring"
  label="CPU / Load" viewer="chart">
  <Command idref="exasol.getMonitorLastDay"/>

  <Input name="displayMode" value="chart"/>
  <Input name="toolbarVisible" value="false"/>

  <Input name="chart.category_column" value="Measure time"/>

  <Input name="chart.serie.0.name" value="Load"/>
  <Input name="chart.serie.0.visible" value="true"/>
  <Input name="chart.serie.1.name" value="CPU in %"/>
  <Input name="chart.serie.1.visible" value="true"/>

  <Input name="chartTitle" value="CPU/Load last hour"/>
  <Input name="xaxisHandleTimeAsText" value="false"/>
  <Input name="xaxisTitle" value="Time"/>
  <Input name="yaxisTitle" value=""/>
</DataView>
```

Here is the **Command** used in the previous example:




```


<Command id="exasol.getMonitorLastDay">
  <SQL>
  <![CDATA[
SELECT
  MEASURE_TIME 'Measure time',
  LOAD 'Load',
  CPU 'CPU in %',
  TEMP_DB_RAM 'Temp DB RAM [MiB]',
  HDD_READ 'HDD Read [MiB/sec]',
  HDD_WRITE 'HDD Write [MiB/sec]',
  NET 'Network [MiB/sec]',
  SWAP 'Swap [MiB/sec]'
FROM
  EXA_STATISTICS.EXA_MONITOR_LAST_DAY
WHERE MEASURE_TIME >= add_minutes(CURRENT_TIMESTAMP,-60)
ORDER BY 1
  ]]>
  </SQL>
</Command>

```

And here is how it looks having the **Measure Time** column in the result set as the category (along the X axis) and the **Load**, and **CPU in %** as series.



CPU/Load last hour



All the options available to configure a chart in the DbVisualizer GUI are available as parameters using this syntax:

```

<Input name="displayMode" value="chart"/>

```

These are the parameters controlling what series should be available in the chart.

i For **chart.serie.<n>...** parameters below, the **<n>** should be replaced with sequential integers starting with 0 and are increased with 1 for every serie.



Parameter	Description	Values
chart.category_column	Identifies the column in the original result set that should represent the category column. These are the labels that should be displayed along the X axis.	
chart.serie.<n>.name	Defines the column in the result set that should appear as a serie. If you are using aliases to rename columns, use the alias name here.	
chart.serie.<n>.visible	Defines whether the serie should be initially visible or not. It will still be selectable in the chart series drop-down.	Valid values: true (default) or false
chart.serie.<n>.label	If the name of the column in the result set defined by chart.serie.<n>.name needs to be changed, this parameter can be used to set an alternative name.	

The following parameters controls the appearance and content of the chart:

Parameter	Description	Values
displayMode	Defines how the result set should be presented when displayed. The mode can be changed by the user using the toolbar or right-click menu.	chart, grid or text
toolbarVisible	Specifies if the toolbar should be visible.	true (default) or false
statusBarVisible	Specifies if the status bar in the grid or text mode should be visible.	true (default) or false
Chart		
chartTitle	The chart title displayed in big text at the top	
chartType	The type of chart	<ul style="list-style-type: none"> • result-set-chartviewer-line-chart-command (default) • result-set-chartviewer-point-chart-command • result-set-chartviewer-area-chart-command • result-set-chartviewer-stacked-area-chart-command • result-set-chartviewer-bar-chart-command • result-set-chartviewer-stacked-bar-chart-command • result-set-chartviewer-pie-chart-command
chartFont	The font for all text in the chart	Syntax: <FontFamily>-<Style>-<Size> Example: Lucida Grande-plain-13 Default: same
chartTopBackground	The top background color. This is used as start color for a gradient background	Example: #ffffff Default is based on current look anf feel.
chartBottomBackground	The bottom background color. This is the end color for a gradient background	Example: #ccffcc Default is based on current look anf feel.
Legend		
legendVisible	Check this to show legend box with labels for all series in the chart	true (default) or false
legendLocation	The position of the legend box	North, West, South or East (default)
X Axis		
xaxisTitle	The X axis title displayed below the X axis	
xaxisTitleVisible	Check this to display the X axis title	true (default) or false



xaxisRotation	The rotation of the X axis labels	Horizontal, 45 (default) or Vertical
xaxisLabelOverlap	Check this to allow X axis labels to overlap each other	true or false (default)
xaxisMajorGridLines	Check this to display X axis major grid lines	true or false (default)
xaxisHandleTimeAsText	Check to handle date	true (default) or false
Y Axis		
yaxisTitle	The Y axis title displayed to the left of the Y axis	
yaxisTitleVisible	Check this to display Y axis title	true (default) or false
yaxisMajorGridLines	Check this to display of Y axis major grid lines	true (default) or false
yaxisMinorGridLines	Check this to display of Y axis minor grid lines	true or false (default)
yaxisAutoStartValue	Check to adjust the Y-axis start value based on the data	true (default) or false
yaxisStartValue	The start value for the Y-axis	0.0
yaxisAutoEndValue	Check to adjust the Y-axis end value based on the data	true (default) or false
yaxisEndValue	The end value for the Y-axis	0.0
yaxisNumberFormat	The number format for value labels	#,##0.# Format documentation .
Series		
chartColorScheme	Choose color scheme for the chart series	These are the available color schemes. Make sure the name is specified as presented below. <ul style="list-style-type: none"> • Qualitative Set1 (9) • Qualitative Set3 (10) • Diverging Spectral (10) • HTML Color Names (140) • New Tau (10) • Tau (20) (default) • Tau Color Blind (10) • Divirgent Color Scale (13)
chartShadow	Check this to display a shadow border for series	true (default) or false
Line & Area Chart		
chartLineType	Render straight or smooth lines for line charts	Straight (default) or Smooth
chartLineWidth	The line width in pixels	2
chartShowPoints	Check this to display points for each value	true (default) or false
chartShowPointLabels	Check this to display point labels	true or false (default)
Bar Chart		
chartBarType	Render bars as raised or flat	Flat (default), Raised , Cylinder or 3D
chartBarGap	The gap in pixels between bars	2
chartBarGroupGap	The gap in pixels between groups of bars	4
Pie Chart		
chartPieType	Render pie as raised	Flat (default), Raised or 3D
chartPieLabelType	Use this setting to specify how slice labels will be displayed	Line Labels (default), Simple Labels or No Labels

As a reference to the chart configuration in the DbVisualizer GUI, here are the same parameters (and order of appearance) as the list of parameters explained above:



Chart Configuration X

General | Series

Chart

Title	HDD / Network / SWAP last hour
Chart Type	Line
Font	Tahoma, Plain, 11
Top Background	<input type="text" value="255, 255, 255"/>
Bottom Background	<input type="text" value="180, 180, 250"/>

Legend

Show Legend	<input checked="" type="checkbox"/>
Position	East

X Axis

Title	Time
Show Title	<input checked="" type="checkbox"/>
Labels Rotation	45
Allow Label Overlap	<input type="checkbox"/>
Show Major Grid Lines	<input type="checkbox"/>
Handle Date/Time as Text	<input type="checkbox"/>

Y Axis

Title	MiB
Show Title	<input checked="" type="checkbox"/>
Show Major Grid Lines	<input checked="" type="checkbox"/>
Show Minor Grid Lines	<input type="checkbox"/>
Auto Adjust Start Value	<input checked="" type="checkbox"/>
Auto Adjust End Value	<input checked="" type="checkbox"/>
Number Format	#,##0.##

Series

Color Scheme	Tau (20)
Show Shadows	<input checked="" type="checkbox"/>

Line & Area Chart

Line Type	Straight
Line Width	2
Show Points	<input checked="" type="checkbox"/>
Show Point Labels	<input type="checkbox"/>

Bar Chart

Bar Type	Flat
Bar Gap	2
Bar Group Gap	4

Pie Chart

Pie Type	Flat
Label Type	Line Labels

(Name)
(Description)

Settings OK Apply Cancel



Viewer - ddl

The **ddl** viewer is special as it requires support in the DbVisualizer codebase to work properly. When supported it will show the DDL based on the actual object's **catalog**, **schema**, and **objectname** variables.

```
<DataView id="oracle-table-ddl" icon="Source" label="DDL" viewer="ddl">
  <Input name="formatSQL" value="true"/>
  <Input name="objectType" value="Table"/>
</DataView>
```

The **formatSQL** parameter specifies if the generated DDL should be formatted (false by default). The **objectType** parameter is used by some DDL generators to distinguish what object type is being processed.

Viewer - form

The **form** viewer displays row(s) from a result set in a form. If several rows are in the result, they are presented in a list. Selecting one row from the list presents all columns and data for that row in a form.

Here is a sample of the XML for the form viewer:

```
<DataView id="oracle-table-info" icon="Info" label="Info" viewer="form" order-before="0">
  <Command idref="oracle.getTable">
    <Input name="owner" value="${schema}"/>
    <Input name="table" value="${objectname}"/>
  </Command>
</DataView>
```

And here is a screenshot of the Info tab based on the previous definition.

Name	Value
OWNER	HR
TABLE_NAME	EMPLOYEES
TABLESPACE_NAME	EXAMPLE
CLUSTER_NAME	(null)
IOT_NAME	(null)
STATUS	VALID
PCT_FREE	10
PCT_USED	(null)
INI_TRANS	1
MAX_TRANS	255
INITIAL_EXTENT	65536
NEXT_EXTENT	1048576
MIN_EXTENTS	1
MAX_EXTENTS	2147483645
PCT_INCREASE	(null)
FREELISTS	(null)
FREELIST_GROUPS	(null)
LOGGING	NO
BACKED_UP	N
NUM_ROWS	107
BLOCKS	5
EMPTY_BLOCKS	0
AVG_SPACE	0



Viewer - grid

The **grid** viewer presents a result set in a grid with standard grid features such as search, copy, fit columns, export and so on. The result set is presented exactly as it is produced by the associated **Command** and any optional **Output** processing.

Here is a sample of the XML for the grid viewer:

```
<DataView type="oracle-columns-columns" icon="Columns" label="Columns" viewer="grid">
  <Command idref="oracle.getColumns">
    <Input name="owner" value="{schema}"/>
    <Input name="table" value="{objectname}"/>
  </Command>
</DataView>
```

And here is a screenshot of the standard grid viewer created from the above definition.

OWNER	TABLE_NAME	COLUMN_NAME	DATA_TYPE	DATA_LENGTH	DATA_SCALE	NULLABLE	DATA
HR	EMPLOYEES	EMPLOYEE_ID	NUMBER	22	0	N	(null)
HR	EMPLOYEES	FIRST_NAME	VARCHAR2	20	(null)	Y	(null)
HR	EMPLOYEES	LAST_NAME	VARCHAR2	25	(null)	N	(null)
HR	EMPLOYEES	EMAIL	VARCHAR2	25	(null)	N	(null)
HR	EMPLOYEES	PHONE_NUMBER	VARCHAR2	20	(null)	Y	(null)
HR	EMPLOYEES	HIRE_DATE	DATE	7	(null)	N	(null)
HR	EMPLOYEES	JOB_ID	VARCHAR2	10	(null)	N	(null)
HR	EMPLOYEES	SALARY	NUMBER	22	2	Y	(null)
HR	EMPLOYEES	COMMISSION_PCT	NUMBER	22	2	Y	(null)
HR	EMPLOYEES	MANAGER_ID	NUMBER	22	0	Y	(null)
HR	EMPLOYEES	DEPARTMENT_ID	NUMBER	22	0	Y	(null)

0.219/0.015 sec | 11/36 | 1-11

Drill-down view

The nesting capability for grid viewers is really powerful, as it can be used to create a **drill-down** view of the data. Consider the scenario with a grid viewer showing all Trigger objects. Wouldn't it be nice to offer the user the capability to display the trigger source when selecting a row in the list? This is easily accomplished with the following definition:

```
<DataView id="oracle-table-triggers" icon="Trigger" label="Triggers" viewer="grid">
  <Command idref="oracle.getTriggers">
    <Input name="owner" value="{schema}"/>
    <Input name="condition" value="{triggersCondition}"/>
  </Command>
  <DataView id="oracle-table-triggers-source" icon="Source" label="Source" viewer="text">
    <Input name="dataColumn" value="text"/>
    <Input name="formatsSQL" value="true"/>
    <Command idref="oracle.getTriggerSource">
      <Input name="owner" value="{OWNER}"/>
      <Input name="name" value="{TRIGGER_NAME}"/>
    </Command>
  </DataView>
  <DataView id="oracle-table-triggers-info" icon="Info" label="Info" viewer="node-form"/>
</DataView>
```

- The first DataView element define the top grid viewer labeled **Triggers** and the command to get the result set for it
- The next DataView is the **nested text viewer** labeled **Source**, specifying various input parameter for the viewer along with the command to get the source for the trigger. The difference here is that the input parameters for this command reference column names in the top grid. Since this viewer is nested, it will automatically be notified whenever an entry in the top grid is selected
- The third DataView labeled **Info** is presented as a tab next to the **Source** viewer, and presents additional information about the selected trigger

The following screenshot illustrates the above sample:



0.156/0.078 sec 2/13 1-2

OWNER	TRIGGER_NAME	TRIGGER_TYPE	TRIGGERING_EVENT	TABLE_OWNER	BASE
HR	SECURE_EMPLOYEES	BEFORE STATEMENT	INSERT OR UPDATE OR DELETE	HR	TABLE
HR	UPDATE_JOB_HISTORY	AFTER EACH ROW	UPDATE	HR	TABLE

Source Info

```
1 TRIGGER secure_employees
2 BEFORE INSERT OR UPDATE OR DELETE ON employees
3 BEGIN
4 secure_dml;
5 END secure_employees;
```

0.281/0.000 sec 5/2

A drill-down type of setup can also be done with a chart as drill-down viewer showing data in the chart based on the selection in the top grid:

Films

title	rental_rate	special_features	rating
ARIZONA BANG	2.99	Trailers,Deleted Scenes	PG
ARK RIDGEMONT	0.99	Trailers,Commentaries,Deleted Scenes,Behind the Scenes	NC-17
ARMAGEDDON LOST	0.99	Trailers	G
ARMY FLINTSTONES	0.99	Trailers,Commentaries	R
ARSENIC INDEPENDENCE	0.99	Trailers,Deleted Scenes,Behind the Scenes	PG
ARTIST COLDBLOODED	2.99	Trailers,Behind the Scenes	NC-17
ATLANTIS CAUSE	2.99	Behind the Scenes	G

Format: <Select a Cell> 0.000/0.015 sec 1000/4 37-43

Customers

Customer	Rental Rate
WADE	6.99
SIMPSON	1.99
JOHNSTON	8.99
WOOD	5.99
CARROLL	9.99
GARZA	1.99
THOMAS	7.99
RICE	3.99
OLIVER	10.99
SCOTT	9.99
MARTINO	5.99
GEARY	8.99
WRIGHT	5.99
MASON	10.99
MORRELL	1.99
COY	7.99



Adding custom menu items in the grid

The grid right-click menu contain a lot of standard actions. Custom commands can be defined in the DataView element and these will appear last in the menu.

```
<Input name="menuItem" value="Open in New Tab...">
  <Input name="action" value="open-object-in-new-tab-command ${schema}||OWNER}${object}||TABLE_NAME"/>
</Input>
<Input name="menuItem" value="Open in Floating Tab...">
  <Input name="action" value="open-object-in-floating-tab-command ${schema}||OWNER}${object}||TABLE_NAME"/>
</Input>
<Input name="menuItem" value="Script: SELECT ALL">
  <Input name="command" value="select * from ${schema}||OWNER}${object}||TABLE_NAME"/>
</Input>
<Input name="menuItem" value="Script: DROP TABLE">
  <Input name="command" value="drop table ${schema}||OWNER}${object}||TABLE_NAME"/>
</Input>
```

The **<Input name="menuItem">** element define a menu item entry that should appear in the grid right-click menu. The **value** for the menuItem is the **label** for the item as it will appear in the menu while the child **Input** element with **name="command"** is the **SQL command** that should be produced for all selected rows when the menu item is selected. Invoking a custom menu item will **not execute** the produced SQL directly but rather **copy the statements to a SQL Editor**. In the SQL Editor you will then need to manually execute the script and track the result.

The **name="action"** attribute declare that the value is a pre-defined action. Valid actions are:

- open-object-in-new-tab-command
- open-object-in-floating-tab-command

Any variables in the SQL statement should identify column names in the result set. The user may select any cells in the grid and choose a custom menu item. It is only the actual rows that are picked from the selection as the columns are predefined by the menuItem declaration.

The variables specified in these examples starts with **\${schema=...}** and **\${object=...}**. These define that the first variable represents a schema variable while the second defines an object. This is needed for DbVisualizer to determine whether delimited identifiers should be used and if identifiers should be qualified, as defined in the connection properties for the database.

Here is a sample:



The screenshot shows a table with the following columns: OWNER, TABLE_NAME, TABLESPACE_NAME, CLUSTER_NAME, IOT_NAME, and STATUS. The table contains 20 rows of data. A context menu is open over the row where TABLE_NAME is 'BLOBTEST'. The menu items include: Select All (Ctrl+A), Inverse Selection (Ctrl+Shift+A), Select Row(s) (Ctrl+Shift+J), Copy Selection (Ctrl+C), Copy Selection with Column Header (Ctrl+H), Copy Selection as Formatted Text (Ctrl+Alt+H), Copy Selection as Comma list, Copy Selection as IN clause, Export... (Ctrl+Alt+E), Export Selection..., Print..., Print Selection..., Print Preview..., Save Selected Cell... (Ctrl+Shift+S), Reload (Ctrl+R), Compare..., Find Data... (Ctrl+F), Find Column... (Ctrl+Alt+F), Browse Row in Window..., Browse Cell in Window..., Describe Data..., Aggregation Data for Selection... (Ctrl+Shift+C), Open in New Tab... (Ctrl+Alt+L), Open in Floating Tab... (Ctrl+Shift+L), Script: SELECT ALL, and Script: DROP TABLE. The 'Script: DROP TABLE' option is highlighted by the mouse cursor.

OWNER	TABLE_NAME	TABLESPACE_NAME	CLUSTER_NAME	IOT_NAME	STATUS
HR	A1B	EXAMPLE	(null)	(null)	VALID
HR	A_B	EXAMPLE	(null)	(null)	VALID
HR	BLOBTEST	EXAMPLE	(null)	(null)	VALID
HR	CARS				
HR	CARSNEGATIVE				
HR	CLOBTEST				
HR	COUNTRIES				
HR	DBV				
HR	DEPARTMENTS				
HR	EMPLOYEES				
HR	INSERTTEST				
HR	ITEM_PRICING				
HR	JOB_HISTORY				
HR	JOBS				
HR	LOCATIONS				
HR	NEWTABLE				
HR	PURCHASEORDER				
HR	RAWTABLE				
HR	REGIONS				
HR	SQLDEV				
HR	XMLTYPE_TEST				

Setting initial max column width

Some result sets may contain wide columns. The following parameter sets an initial maximum width for all columns in the grid.

```
<Input name="columnWidth" value="" />
```

Viewer - message

The message viewer is really simple as it just shows a message in the DataView.



```
<DataView id="mimer-auto-properties" icon="properties" label="Mimer SQL Auto" viewer="message">
  <Message>
    <![CDATA[
<html>
Mimer SQL Auto database server type has no capabilities to list the contents of the database schema.<br/><br/>
Please enter the precompiled statement names in the command window to perform operations
towards the database.
</html>
]]>
  </Message>
</DataView>
```

It may also be useful to define viewers based on [conditions](#) such as in this example:

```
<If test="#ROLE_IS_SECURITY_ADMIN eq 1">
  <DataView id="snowflake-users-users" icon="Users" label="Users" viewer="grid">
    <Command idref="snowflake.getUsers">
      <Input name="catalog" value="{catalog}"/>
    </Command>
  </DataView>
</If>
<Else>
  <DataView id="snowflake-users-users" icon="Users" label="Users" viewer="message">
    <Message>
      <![CDATA[
<html>
Insufficient privileges. SECURITYADMIN Role is required to view Users.
</html>
]]>
    </Message>
  </DataView>
</Else>
```

Viewer - navigator

The **navigator** viewer defines the [Navigator](#) tab for table objects in the DbVisualizer UI.

```
<DataView id="generic-table-navigator" icon="Navigator" label="Navigator" viewer="navigator"/>
```

Viewer - node-form

The **node-form** viewer presents all data associated with the selected DataNode (variables). Here is a sample of the XML for the node-form viewer:



Name	Value
OWNER	HR
TABLE_NAME	EMPLOYEES
CONSTRAINT_NAME	EMP_DEPT_FK
CONSTRAINT_TYPE	Foreign Key
DDL_TYPE	REF_CONSTRAINT
SEARCH_CONDITION	(null)
R_OWNER	HR
R_CONSTRAINT_NAME	DEPT_ID_PK
DELETE_RULE	NO ACTION
STATUS	ENABLED
DEFERRABLE	NOT DEFERRABLE
DEFERRED	IMMEDIATE
VALIDATED	VALIDATED
GENERATED	USER NAME
BAD	(null)
RELY	(null)
LAST_CHANGE	2013-06-28 11:30:40
INDEX_OWNER	(null)
INDEX_NAME	(null)
INVALID	(null)
VIEW_RELATED	(null)

Hiding columns

There may be data associated with the object that you don't want to present in the node form. The **hidecolumn** input parameter control what data for the object that should be invisible and you may repeat this option as many times you like to handle multiple variables that shouldn't be displayed.

```
<Input name="hidecolumn" value="oracle.getKeys.TABLE_OWNER"/>
```

Viewer - procedure-editor

The **procedure-editor** is special as it requires support in the DbVisualizer codebase to work properly. When supported it will open the [procedure editor](#) for the selected code object such as procedure, function, package, package body, etc.

```
<DataView id="mimer-function-functioneditor" classargs="FUNCTION" icon="SourceEditor" label="Function Editor" viewer="procedure-editor"/>
```

Viewer - table-data

The **table-data** viewer shows the data for a table in a grid with various features such as filtering and editing (if licensed) functionality. This viewer is referred as **Data** tab in the DbVisualizer UI.

i Information presented in the grid is obtained automatically by the viewer via a standard **SELECT * FROM table** statement, i.e., the object type having this viewer defined must be able to support getting a result set via this SQL statement.

It is important that the **Database Type** in the connection setup is properly set to match the database being accessed. The reason is that the identifiers (schema, database, table) are delimited automatically. Delimiters are database specific and if having the wrong database type set it may result in an error getting the result.



Here is a sample of the XML for the table-data viewer:

```
<DataView id="oracle-view-data" icon="Data" label="Data" viewer="table-data"/>
  <Input name="disableEdit" value="false"/>
</DataView>
```

And here is a screenshot of the **Data** tab based on the previous definition.

*	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE
1	1001	Steven	King	SKINGA	515.123.4567	2003-01-0
2	100	Steven	King	SKING	515.123.4567	2003-06-1
3	101	Neena	Kochhar	NKOCHHAR	515.123.4568	2005-09-2
4	102	Lex	De Haan	LDEHAAN	515.123.4569	2001-01-1
5	103	Alexander	Hunold	AHUNOLD	590.423.4567	2006-01-0
6	104	Bruce	Ernst	BERNST	590.423.4568	2007-05-2
7	105	David	Austin	DAUSTIN	590.423.4569	2005-06-2
8	106	Valli	Pataballa	VPATABAL	590.423.4560	2006-02-0
9	106	Valli	Pataballa	VPATABAL	590.423.4560	2006-02-0
10	106	Valli	Pataballa	VPATABAL	590.423.4560	2006-02-0
11	107	Diana	Lorentz	DLORENTZ	590.423.5567	2007-02-0
12	108	Nancy	Greenberg	NGREENBE	515.124.4569	2002-08-1
13	109	Daniel	Faviet	DFAVIET	515.124.4169	2002-08-1
14	110	John	Chen	JCHEN	515.124.4269	2005-09-2
15	111	Ismael	Sciarra	ISCIARRA	515.124.4369	2005-09-3
16	112	Jose Manuel	Urman	JMURMAN	515.124.4469	2006-03-0
17	113	Luis	Popp	LPOPP	515.124.4567	2007-12-0
18	114	Den	Raphaely	DRAPHEAL	515.127.4561	2002-12-0
19	115	Alexander	Khoo	AKHOO	515.127.4562	2003-05-1

Disable data editing

The default strategy for the table-data viewer is to automatically check whether the data can be edited or not. If editing is allowed a few related buttons will appear in the toolbar. However, sometimes you may want to disable editing completely for the **table-data** viewer. Do this with the following input element:

```
<Input name="editDisabled" value="true"/>
```


Viewer - table-refs

The **table-refs** viewer shows the [references graph](#) for the [current object](#) (this must be an object supporting referential integrity constraints, such as a Table),

Here is a sample of the XML for the table-refs viewer:

```
<DataView id="generic-table-references" icon="References" label="References" viewer="table-refs"/>
```

And here is a screenshot of the References tab based on the previous definition.




Viewer - tables-refs

The **tables-refs** viewer shows the [references graph](#) for **several tables** in the result set (the result set must contain objects supporting referential integrity constraints, such as a Table). Here is a sample of the XML for the tables-refs viewer:

```
<DataView id="oracle-tables-references" icon="References" label="References" viewer="tables-refs">
  <Command idref="oracle.getTables">
    <Input name="owner" value="{schema}"/>
    <ProcessDataSet action="renamecolumn" index="OWNER" name="TABLE_SCHEM"/>
    <ProcessDataSet action="renamecolumn" index="TABLE_NAME" name="TABLE_NAME"/>
  </Command>
</DataView>
```

And here is a screenshot of the References tab based on the previous definition.



Viewer - table-rowcount

The table-rowcount viewer shows the row count for a (table) object.

i The row count is obtained automatically by the viewer via a traditional **SELECT COUNT(*) FROM table** statement, i.e., the object type having this viewer defined must be able to support getting a result set via this SQL statement.

It is that the **Database Type** in the connection setup is properly set to match the database being accessed. The reason is that the identifiers (schema, database, table) are delimited automatically. Delimiters are database specific and if having the wrong database type set it may result in an error getting the result.

Here is a sample of the XML for the table-rowcount viewer:



```
<DataView id="generic-table-rowcount" icon="RowCount" label="Row Count" viewer="table-rowcount"/>
```

Viewer - text

The **text** viewer presents data from **one column** in a result set in a text browser (read only). This viewer is typically used to present large chunks of data, such as source code, SQL statements, etc. If the result set contain several rows, the text viewer reads the data in the column for each row and present the combined data.

Here is a sample of the XML for the text viewer:

```
<DataView id="oracle-table-triggers-source" icon="Source" label="Source" viewer="text">
  <Input name="dataColumn" value="text"/>
  <Input name="formatSQL" value="true"/>
  <Input name="newline" value=""/>
  <Command idref="oracle.getTriggerSource">
    <Input name="owner" value="{OWNER}"/>
    <Input name="name" value="{TRIGGER_NAME}"/>
  </Command>
</DataView>
```

And here is a screenshot of the Source tab based on the previous definition.

```
1
2 CREATE TABLE "HR"."EMPLOYEES"
3 (
4   "EMPLOYEE_ID" NUMBER(6,0),
5   "FIRST_NAME" VARCHAR2(20),
6   "LAST_NAME" VARCHAR2(25) CONSTRAINT "EMP_LAST_NAME_NN" NOT NULL
7   "EMAIL" VARCHAR2(25) CONSTRAINT "EMP_EMAIL_NN" NOT NULL ENABLE,
8   "PHONE_NUMBER" VARCHAR2(20),
9   "HIRE_DATE" DATE CONSTRAINT "EMP_HIRE_DATE_NN" NOT NULL ENABLE,
10  "JOB_ID" VARCHAR2(10) CONSTRAINT "EMP_JOB_NN" NOT NULL ENABLE,
11  "SALARY" NUMBER(8,2),
12  "COMMISSION_PCT" NUMBER(2,2),
13  "MANAGER_ID" NUMBER(6,0),
14  "DEPARTMENT_ID" NUMBER(4,0),
15  CONSTRAINT "EMP_SALARY_MIN" CHECK (salary > 0) ENABLE,
16  CONSTRAINT "EMP_EMAIL_UK" UNIQUE ("EMAIL")
17 USING INDEX PCTFREE 10 INITRANS 2 MAXTRANS 255 COMPUTE STATISTICS NOL
18 STORAGE(INITIAL 65536 NEXT 1048576 MINEXTENTS 1 MAXEXTENTS 2147483645
19 PCTINCREASE 0 FREELISTS 1 FREELIST GROUPS 1
20 BUFFER_POOL DEFAULT FLASH_CACHE DEFAULT CELL_FLASH_CACHE DEFAULT)
21 TABLESPACE "EXAMPLE" ENABLE,
22  CONSTRAINT "EMP_EMP_ID_PK" PRIMARY KEY ("EMPLOYEE_ID")
23 USING INDEX PCTFREE 10 INITRANS 2 MAXTRANS 255 COMPUTE STATISTICS NOL
24 STORAGE(INITIAL 65536 NEXT 1048576 MINEXTENTS 1 MAXEXTENTS 2147483645
25 PCTINCREASE 0 FREELISTS 1 FREELIST GROUPS 1
26 BUFFER_POOL DEFAULT FLASH_CACHE DEFAULT CELL_FLASH_CACHE DEFAULT)
27 TABLESPACE "EXAMPLE" ENABLE,
28  CONSTRAINT "EMP_DEPT_FK" FOREIGN KEY ("DEPARTMENT_ID")
```

Specify what column to browse

By default, the text viewer uses the data in first column. This behavior can be controlled by using the dataColumn input parameter. Simply specify the name of the column in the result set or its index (starting at 1 from the left).

```
<Input name="dataColumn" value=""/>
```

Enable SQL formatting of the data



The text viewer have the **SQL Formatting** function, which when invoked formats the SQL buffer in the viewer. The **formatSQL** input parameter is used to control whether formatting should be made automatically when the data first displayed. If formatSQL is not specified, no initial formatting is made.

```
<Input name="formatSQL" value=""/>
```

Adding newline to each row

For a result set containing multiple rows and all rows should be displayed in a text viewer, the **newline** parameter define the character(s) that should separate the rows in the viewer. A **\n** somewhere in the value will be converted to a platform dependent newline sequence in the viewer. By default there is no newline sequence between multiple rows.

```
<Input name="newline" value="\n"/>
<Input name="newline" value="as-sql"/>
```

The **as-sql** value will append an SQL statement delimiter and a platform specific newline sequence at the end of every row.

XML element - Command

Check the [commands](#) section for more information.

XML element - Input

The **Input** element is supported for some of the viewers. Check the viewer sections for more information.

XML element - Message

The **Message** element is very simple as it just define a message that should appear at the top of the viewer. The text in the message may contain HTML tags such as **** (bold), **<i>** (italic), **
** (line break), etc.

Here is a sample of the XML for using the message element in a grid viewer:

```
<ObjectView type="RecycleBin">
  <DataView id="oracle-recyclebin-recyclebin" icon="RecycleBin" label="Recycle Bin" viewer="grid">
    <Command idref="oracle.getRecycleBin">
      <Input name="schema" value="{schema}"/>
      <Input name="login_schema" value="{dbvis-defaultCatalogOrSchema}"/>
    </Command>
    <Message>
      <![CDATA[
<html>
These are the tables currently in the recycle bin for this schema. Right click on a bin
table in objects tree to restore or permanently purge it.<br>
<b>Note: The recycle bin is always empty if not looking at the bin for your
login schema (default).</b>
</html>
]]>
    </Message>
  </DataView>
</ObjectView>
```

And here is a screenshot of the **Recycle Bin tab** based on the previous definition.



24.4.7 XML element - ObjectsActionDef

i Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

- Introduction
- Variables
- XML element - ActionGroup
- XML element - Action
 - XML element - Input
 - Style - check (true/false, on/off, selected/unselected)
 - Style - check-list (large number non exclusive choices)
 - Style - grid (configurable multi row/columns input)
 - Style - label
 - Style - list (large number of exclusive choices)
 - Style - note
 - Style - number
 - Style - password
 - Style - radio (limited number of choices)
 - Style - separator (visual divider between input controls)
 - Style - text (single line)
 - Style - text-editor (multi line)
 - Style - wrapped-text-editor (multi line)
 - XML element - SetVar
 - XML element - Confirm
 - XML element - Result
 - XML element - Command
 - XML element - Message
 - Action showing just a message

Introduction

Objects actions (ObjectsActionDef) define what operations are available for the object types defined in the **ObjectsTreeDef**. Object actions are powerful, as they offer an extensive number of features to define actions for almost any type of object operation.

In DbVisualizer, the object actions menu is accessed via the right-click menu in the objects tree or via the **Actions** button in the object view:



Table: EMPLOYEES Actions ▾

CRM Ahoa/All Schemas/HR/Tables/EMPLOYEEES

Info Columns **Data** Row Count Primary Key Row Id References

	EMPLOYEE_ID	FIRST_NAME	LAST_NAME	EMAIL	PHONE_NUMBER	HIRE_DATE	
1	1001	Steven	King	SKINGA	515.123.4567	2003-0	
2	100	Steven	King	SKING	515.123.4567	2003-0	
3	101	Neena	Kochhar	NKOCHHAR	515.123.4568	2005-0	
4	102	Lex	De Haan	LDEHAAN	515.123.4569	2001-0	
5	103	Alexander	Hunold	AHUNOLD	590.423.4567	2006-0	
6	104	Bruce	Ernst	BERNST	590.423.4568	2007-0	
7	105	David	Austin	DAUSTIN	590.423.4569	2005-0	
8	106	Valli	Pataballa	VPATABAL	590.423.4560	2006-0	
9	107	Diana	Lorentz	DLORENTZ	590.423.5567	2007-0	
10	108	Nancy	Greenberg	NGREENBE	515.124.4569	2002-0	
11	109	Daniel	Faviet	DFAVIET	515.124.4169	2002-0	
12	110	John	Chen	JCHEN	515.124.4269	2005-09-28 00:00:00	FI_ACCOUNT
13	111	Ismael	Sciarra	ISCIARRA	515.124.4369	2005-09-30 00:00:00	FI_ACCOUNT
14	112	Jose Manuel	Urman	JMURMAN	515.124.4469	2006-03-07 00:00:00	FI_ACCOUNT
15	113	Luis	Popp	LPOPP	515.124.4567	2007-12-07 00:00:00	FI_ACCOUNT
16	114	Den	Raphaely	DRAPHEAL	515.127.4561	2002-12-07 00:00:00	PU_MAN
17	115	Alexander	Khoo	AKHOO	515.127.4562	2003-05-18 00:00:00	PU_CLERK
18	116	Shelli	Baida	SBAIDA	515.127.4563	2005-12-24 00:00:00	PU CLERK

Max Rows: 100000 Max Chars: -1 Pattern: Text 0.266/0.015 sec 108/11 1-18

All of the operations for the current **Table** object in the figure above are expressed in the ObjectsActionDef section in the database profile. The implementation for these actions are either declared entirely in XML via standard definitions, or via custom definitions. (The Java API for action handlers is not yet documented). The following screenshot shows the dialog appearing when executing an action via a standard XML definition:



Create Trigger

Create Trigger in Database Connection: CRM Ahoa

Table Schema: HR

Table Name: EMPLOYEES

Trigger Schema: HR

Trigger Name:

Trigger Time: BEFORE AFTER INSTEAD OF

Trigger Event: DELETE INSERT UPDATE

Trigger Type: STATEMENT ROW

Source

```
1 --
2 -- Insert your own trigger code here
3 --
4  DBMS_OUTPUT.PUT_LINE('Sample output');
```

Show SQL

Execute Cancel

The first field in the dialog, **Database Connection**, is always present and shows the alias of the database connection the current object is associated with. At the bottom, there is a **Show SQL** control that, when checked, displays the final SQL for the action. The bottom right buttons are used to run the action (the label of the button may be **Execute** or **Script** based on the action mode), or to **Cancel** the action completely.

Variables

Variables are used to reference data for the object for which the action was launched, and the data for all its parent objects in the objects tree. Variables are also used to reference input data specified by the user in the actions dialog. Variables are typically used in the **Command**, **Confirm**, **Result** and **SetVariable** elements.

Variables are specified in the following format:

\${variableName}

The following is an example for a **Rename Table** action. It first shows the name of the database connection (which is always present) with information about the table being renamed. The last two input fields should be entered by the user and identify the new name of the table. The **New Database** component is a list from which the user should select the name of the new database. The new table name should be entered in the **New Table Name** field.

If the **Show SQL** control is checked, you will see any edits in the dialog being reflected immediately in the final **SQL Preview**.



Rename Table

Rename Table in Database Connection: MySQL

Database: confluence

Table: AO_187CCC_SIDE BAR_LINK

New Database: confluence

New Table Name: DRAJVER

Show SQL

Execute Cancel

SQL Preview

```
1 rename table `confluence`.`AO_187CCC_SIDE BAR_LINK` to `confluence`.`DRAJVER`
```

The complete action definition for the previous **Rename Table** action is as follows:

```
<Action id="mysql-table-rename" label="Rename Table" reload="true" icon="rename">
  <Input label="Database" style="text" editable="false">
    <Default>${catalog}</Default>
  </Input>

  <Input label="Table" style="text" editable="false">
    <Default>${objectname}</Default>
  </Input>

  <Input label="New Database" name="newCatalog" style="list">
    <Values>
      <Command><SQL><![CDATA[show databases]]></SQL></Command>
    </Values>
    <Default>${catalog}</Default>
  </Input>

  <Input label="New Table Name" name="newTable" style="text"/>

  <Command>
    <SQL>
      <![CDATA[
rename table `${catalog}`.`${objectname}` to `${newCatalog}`.`${newTable}`
]]>
    </SQL>
  </Command>

  <Confirm>
    <![CDATA[
Confirm rename of ${catalog}.${objectname} to ${newCatalog}.${newTable}?
]]>
  </Confirm>

  <Result>
    <![CDATA[
Table ${catalog}.${objectname} renamed to ${newCatalog}.${newTable}!
]]>
  </Result>
</Action>
```

First, there is the **Action** element with some attributes specifying the label of the action, icon and whether the objects tree (and the current object view) should be reloaded after the action has been executed.

The next block of elements are **Input** fields defining the data for the action. As you can see in the example, there is a **\${catalog}** variable in



the **Default** element for the Database input and an **`\${objectname}`** variable in the **Default** element for the Table input. The values for these variables are fetched from the current object in the objects tree (**GroupNode** or **DataNode**). Variables are evaluated by first checking if the variable is in the scope of the action dialog (i.e., another input field), then if the variable is defined for the object for which the action was launched, and then if it is defined for any of the parent objects until the root object in the tree (**Connections** node) is reached. If a variable is not found, its value is set to **(null)**.

In the XML sample, the value of the **`\${catalog}`** variable is the name of the database in which the table object is stored. The **`\${objectname}`** is the current name of the table (these variables are described in the **ObjectsTreeDef** section).

The **New Database** input field is a list component showing a list of databases based on the result set of the specified **SQL** command. The **Default** setting for the database will be the database in which the table is currently stored based on the **`\${catalog}`** variable.

The **New Table Name** input field is a simple text field in which the user may enter any text (the new table name).

Both the **New Database** and **New Table Name** fields are editable and should be specified by the user. This data is then available via the variables specified in the name attribute, i.e., **newCatalog** and **newTable**.

The **Command** element declares the **SQL** statement that should be executed by the action. In this example, the SQL combines static text with variables.

XML element - ActionGroup

The **ActionGroup** element is a container and groups a collection of **ActionGroup**, **Action** and **Separator** elements. It is used to define what actions should be present for a particular object type. It also define in what order the actions should appear in the menu and where any separators should be located. ActionGroup elements can be nested and these will be displayed as sub menus in DbVisualizer.

```
<ActionGroup type="Table">
  <Action id="xxx">
    ...
  </Action>
</ActionGroup>
```

The attributes for an ActionGroup are:

Attribute	Value	Description
type		This defines what object type the ActionGroup is mapped to. This attribute is required and valid only for top level ActionGroup elements (not nested ActionGroup elements). An example is the Table object type, the corresponding <ActionGroup type="Table"> will only be displayed when the current object is a Table
label		This attribute is required for nested ActionGroup elements and is the label displayed in the sub menu. (This attribute have no effect on top level ActionGroup elements)
drop-on-condition		Read more in drop-on-condition attribute
order-before		Specifies the order of this ActionGroup among a collection of ActionGroup elements located at the same level. It can either be an index starting at 0 (first) or a node type. Ex. order-before="Views" will order this ActionGroup before ActionGroup elements defined by the type="Views" attribute
order-after		Specifies the order of this ActionGroup among a collection of ActionGroup elements located at the same level. It can either be an index starting at 0 (first) or a node type. Ex. order-after="Views" will order this ActionGroup after ActionGroup elements defined by the type="Views" attribute

XML element - Action

The **Action** element defines the characteristics of the action. The following show the complete definition of the **Drop Table** action in Oracle.



```
<Action id="oracle-table-drop" label="Drop Table" reload="true" icon="remove">
  <Input label="Schema" style="text" editable="false">
    <Default>${schema}</Default>
  </Input>
  <Input label="Table" style="text" editable="false">
    <Default>${objectname}</Default>
  </Input>
  <Input label="Drop Referential Integrity Constraints" name="cascade" style="check"
    tip="Enable this to drop all referential integrity constraints
    that refer to primary and unique keys in the dropped table">
    <Values>cascade constraints</Values>
  </Input>
  <If test="#util.isDatabaseVersionGTE(10)">
    <Input label="Purge Space" name="purge" style="check"
      tip="Enable this if you want to drop the table and
      release the space associated with it in a single step">
      <Values>purge</Values>
    </Input>
  </If>
  <Else>
    <SetVar name="purge" value=""/>
  </Else>
  <Command>
    <SQL>
      <![CDATA[drop table "${schema}.${objectname}" ${cascade} ${purge}]]>
    </SQL>
  </Command>
  <Confirm>
    Really drop table ${schema}.${objectname}?
  </Confirm>
  <Result>
    Table ${schema}.${objectname} has been dropped!
  </Result>
</Action>
```

The available attributes for the **Action** element:

Attribute	Value (bold = default)	Description
id		Every Action element must have a unique id which is not only unique in the current profile but also with all id's in extended profiles. <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> The recommended format is profileName-actionGroupType-action. Ex: oracle-table-drop </div>
icon		The name of the icon that should be displayed next to the label in the actions menu
label		The label for the action as it should be displayed in the list of actions and in the actions dialog
reload	true/false	Specifies if the parent node (in the objects tree) should be reloaded after successful execution. This is recommended for actions that change the visual appearance of the object, such as remove, add or name change
mode	<ul style="list-style-type: none"> • script show the action dialog, process user input and send the final SQL to the SQL Commander without executing the command • script-immediate will not show the action dialog but instead pass the final SQL directly to the SQL Commander without executing the command 	Specifies how the action will be prepared and displayed



Attribute	Value (bold = default)	Description
resultaction	<ul style="list-style-type: none"> mergeasscript mergeastext 	<ul style="list-style-type: none"> mergeastext will merge multiple result sets to a single result tab mergeasscript will merge multiple result sets to a single result tab, each row will be terminated with a semi-colon (";") Default is that result sets are displayed in individual tabs
resulttarget	<ul style="list-style-type: none"> editor 	Only applicable if the resultaction attribute is specified. With the value editor the merged results will be opened in a new SQL Commander tab
hideif		There may be situations when an action should be dropped due to a condition. The hideif attribute is used to express a condition which is evaluated when the list of actions is created. Example: hideif="#dataMap.get('actionlevel') neq 'toplevel'"
resetcatalogs	true/false	Setting this attribute to true will reset any cached databases for the actual database connection. Useful when for example the action create, rename or delete a database
resetschemas	true/false	Setting this attribute to true will reset any cached schemas for the actual database connection. Useful when for example the action create, rename or delete a schema
supportsmultipleobjects	true/false	An action support processing multiple objects if the style attribute for all input elements is one of: <ul style="list-style-type: none"> check check-list list radio separator node label read-only text The supportsmultipleobjects="true" attribute is used to disable multi object processing even if the previous criteria is satisfied
class		Used to specify a custom Java class used as the action
classargs		Used to pass arguments to a custom action
doclink		Relative HTML link to the related chapter in the users guide
drop-on-condition		Read more in drop-on-condition attribute
order-before		Specifies the order of this Action among a collection of Action elements located at the same level. It can either be an index starting at 0 (first) or a node type. Ex. order-before="View" will order this Action before Action elements defined by the type="View" attribute
order-after		Specifies the order of this Action among a collection of Action elements located at the same level. It can either be an index starting at 0 (first) or a node type. Ex. order-after="View" will order this Action after Action elements defined by the type="View" attribute

XML element - Input

An Input element specifies the characteristics of a field component in the actions dialog. The **label** attribute is recommended and is presented to the left of input field. If a label is not specified, the input field will occupy the complete width of the action dialog. All input fields are editable by default. The **name** attribute is required for editable fields and should specify the name of the variable in which the user input is stored.



Attribute	Value (bold = default)	Description
label		The label for the input component
name		For editable input this should be the name of the variable holding the value specified by the user
tip		Message displayed when hovering over the component
editable	true /false	Enables or disables editing of the component
linebreak	true/ false	If set to true, no line break will be made after the input component. This is useful when for example having multiple <Input style="check"> elements in a single row
style	list, radio, text , check, check-list, password, number, text-editor, wrapped-text-editor, grid, separator, label, note	The style of the input element. See following sections for more details
hideif		There may be situations when an Input element should be dropped due to a condition. The hideif attribute is used to express a condition which is evaluated when the action is initialized. Example: hideif="#dataMap.get('actionlevel') neq 'toplevel'"
runsetDefaultwhenvaluechanged		The runsetDefaultwhenvaluechanged attribute defines what other inputs default command should be triggered when the value for the input is changed

This is a minimal definition of an input field. It will show a **read-only text** field control labeled Size.

```
<Input label="Size" editable="false"/>
```

If the input field is changed to be **editable**, the **name** attribute must be used to specify the identifier for the **variable name**.

```
<Input label=Size" editable="true" name="theSize"/>
```

Any input element may contain the **tip** attribute. It is used to briefly document the purpose of the input field and is displayed as a tooltip when the user hover the mouse pointer over it.

```
<Input label=Size" editable="true" name="theSize" tip="Please enter the size of the new xxx"/>
```

The **hideif** attribute is useful to limit what input fields should appear for an action. The condition specified in the **hideif** attribute have the same syntax as described in the **<SetVar>** section. Example:

```
<Input label="Unit" hideif="#dataMap.get('actionlevel') neq 'toplevel'">
```

Input fields can be aligned on a single row with the **linebreak** attribute. The default behavior is that every input field is displayed on a single row. Use the **linebreak="false"** attribute to define that the next input field will be arranged on the same line. To re-start the automatic line breaking feature you must use the **linebreak="true"** attribute.

```
<Input name="size" label="Size" style="number" linebreak="false">
  <Default>10</Default>
</Input>
<Input name="unit" label="Unit" style="list" linebreak="true">
  <Labels>KB|MB</Labels>
  <Values>K|M</Values>
  <Default>M</Default>
</Input>
```

The previous example show the use of the **linebreak** attribute. The **Size** number field and the **Unit** list will appear in the same row.

Specifying the **default value** as a result from an SQL statement is a trivial task:



```
<Input label=Size" editable="true" name="theSize">
  <Default>
    <Command>
      <SQL>
select size from systables where tablename = '${objectname}'
      </SQL>
    </Command>
  </Default>
</Input>
```

The **Default** definition above will execute a **SQL** statement, it will automatically pick the value in the first row's first column and present it as the default value for the input component. SQL may be specified in the **Default** element for all styles while SQL in **Values** and the **Labels** elements are **valid only for list, radio, and check** styles. In some rare situations it may not be possible to express a SQL statement that will return a single column that should be displayed for Values, Labels and Default. An example is when data is collected via a stored procedure. To solve this problem specify the **column** attribute. Its value must be a **column name** or **column index** in the result set.

column index (**column="2"** attribute):

```
<Input label=Size" editable="true" name="theSize">
  <Default column="2">
    <Command idref="getSize">
      <Input name="objectname" value="${objectname}"/>
    </Command>
  </Default>
</Input>
```

or by **column name** (**column="THE_SIZE"** attribute):

```
<Input label=Size" editable="true" name="theSize">
  <Default column="THE_SIZE">
    <Command idref="getSize">
      <Input name="objectname" value="${objectname}"/>
    </Command>
  </Default>
</Input>
```

An alternative to embedding the SQL in the element body, as in one of the previous examples, is to refer to a **command** via the standard **idref** attribute:

```
<Input label=Size" editable="true" name="theSize">
  <Default>
    <Command idref="getSize">
      <Input name="objectname" value="${objectname}"/>
    </Command>
  </Default>
</Input>
```

Instead of having duplicated SQLs in multiple actions, consider using **<Command idref="xxx">** elements instead.



Referring commands in actions via the **idref** attribute is recommended when the same SQL is used in several actions. Use **Input** elements for the **Command** to pass parameters to the command.

The following sections presents the **supported styles** that can be used in the **Input** element.

Style - check (true/false, on/off, selected/unselected)

The **check** style is suitable for **yes/no, true/false, here/there** types of input. Its checked state indicates that the **Value** for the input will be set in the final variable. If the check box is unchecked, the variable value is blank.

```
<Input label="Cascade Constraints" name="cascade" style="check">
  <Values>compact</Values>
</Input>
```

- This will create a check component with the label **Cascade Constraints**
- Checking the check box will set the value of the variable identified by name (cascade) to the value of **Value**, which is **compact**
- If the check box is unchecked, the variable value will be blank



Style - check-list (large number non exclusive choices)

The **check-list** style is much like the **list** style except that each choice have a check box in front allowing multiple values to be selected

```
<Input label="Weekdays" name="weekdays" style="check-list">
  <Arg name="output" value="jschours[{$value}] = true"/>
  <Arg name="newline" value=", "/>
  <Labels>Monday|Tuesday|Wednesday|Thursday|Friday|Saturday|Sunday</Labels>
  <Values>00|11|22|33|44|55|66</Values>
  <Default>22|44</Default>
</Input>
```

To produce a desirable output from the check-list it is possible to define how each choice should be generated in the final result. The **output** argument and its **value** attribute is used to define how each value should be generated. In the example each choice will be formatted as: **jschours[22] = true**. The **newline** argument defines any delimiter between each choice. If the user selects both Monday and Friday in the action window the following will be generated:

```
jschours[00] = true, jschours[44] = true
```

Style - grid (configurable multi row/columns input)

The **grid** input style is presented as a grid with user controls to **add**, **remove** and **move** rows. The columns that should appear in the grid are defined by using any of the primitive styles: **text**, **number**, **password**, **check**, **list** and **radio**. The grid style is useful for data that allows the user to define multiple entries. Examples are, defining columns that should appear in a table index, setup data files for a tablespace or databank.

This example show a grid style definition that will ask the user for parameters that will be part of a create procedure action.

```
<Input name="parameters" style="grid">
  <Arg name="output" value="{$direction} {$name} {$type}{$_default}"/>
  <Arg name="newline" value=", "/>

  <Input name="name" label="Name" style="text">
    <Default>parm</Default>
  </Input>
  <Input name="direction" label="Direction" style="list">
    <Values>IN|INOUT|OUT</Values>
    <Default>IN</Default>
  </Input>
  <Input name="type" label="Type" style="text">
    <Default>nvarchar(20)</Default>
  </Input>
</Input>
```

Here is the result:



Create Procedure
✕

⚙️ Create Procedure in Database Connection: Mimer - mimer_store

Schema:

Procedure:

Specific Name:

Deterministic: NOT DETERMINISTIC DETERMINISTIC

Access Option: ▾

Parameters

Name	Direction	Type	
P1	IN	nvarchar(20)	+
	IN		↑
	INOUT		↕
	OUT		↓

Source

```

1 --
2 -- Insert your own procedure code here
3 --
4 declare var1 integer;
5 set var1 = 10;
```

Show SQL

The sub elements for the grid style is different from the other input styles as it accepts nested **Input** elements. These input styles define what columns should appear in the grid and the first input style will appear to the leftmost and the last in the rightmost column.

This example doesn't specify the label attribute as we want the grid to extend the full width of the actions dialog. The grid style use the **Arg** elements to customize the appearance and function of the field. The following arguments are handled by the grid style:

- **output**
Defines the output format for each row in the grid. The value may contain variables and static text. To create conditional output check the **SetVar** element below
- **newline**
Defines the static text that should separate every row in the grid. A "\n" somewhere in the value will be converted to a newline sequence in the final output
- **rowprefix**
Specifies any prefix for every row in the grid
- **rowsuffix**
Specifies any suffix for every row in the grid

The resulting parameter list is created automatically by the control and is available in the variable name specified in the example to be parameters.

The **SetVar** element in the context of a grid style is used to process the data that will appear as defined by the **<Arg name="output">** element. It is used to process the data for every row in the grid. Let's say that the output must contain the word " default " if the value in a column named **Default** is entered. **SetVar** is used to handle this:

```

<SetVar name="_default" value='#default.equals("") ? "" : " default " + #default' />
```

The **#default** input value is here evaluated and if it is not empty the " default " text s prefixed to the value of the #default value. The result is stored in the **_default** variable which is also refered in the output argument above.

Style - label

The **label** style is useful when the standard left aligned label should not be displayed. The following example will show seven check boxes each labeled individually and all displayed in the same row.



```
<Input style="label" linebreak="false"/>
<Input label="Mon" name="mon" style="check">
  <Values>mon</Values>
</Input>
<Input label="Tue" name="tue" style="check">
  <Values>tue</Values>
</Input>
<Input label="Wed" name="wed" style="check">
  <Values>wed</Values>
</Input>
<Input label="Thu" name="thu" style="check">
  <Values>thu</Values>
</Input>
<Input label="Fri" name="fri" style="check">
  <Values>fri</Values>
</Input>
<Input label="Sat" name="sat" style="check">
  <Values>sat</Values>
</Input>
<Input label="Sun" name="sun" style="check">
  <Values>sun</Values>
</Input>
```

Style - list (large number of exclusive choices)

The **list** style displays a list of choices in a drop-down component. Only one choice can be selected. The list can be editable, meaning that the field showing the selection may be editable by the user. Here is a sample XML for the list style.

```
<Input label="Select index type" name="type" style="list">
  <Values>Pizza|Pasta|Burger</Values>
  <Default>Pasta</Default>
</Input>
```

The **Values** element should, for static entries, list all choices separated by a **vertical bar (|)** character. A Default value can either list the name of the default choice or the index number (first choice starts at 0). In the example above, setting Default to **{2}** would set Burger to the default selection.

It is also possible to use the **Labels** element. If present, this should list all choices as they will appear in the actions dialog. Consider the following example and the labels shown to the user, while **Values** in this case should list the choices that will go into the final SQL via the variable.

```
<Input label="Select index type" name="type" style="list">
  <Values>Pizza|Pasta|Burger</Values>
  <Labels>Pizza the French style|Pasta Bolognese|Texas Burger</Labels>
  <Default>Pasta</Default>
</Input>
```

If the users selects **Texas Burger** then the value for variable type will be **Burger**.

The following show how to use SQL to feed the list of values:

```
<Input label="New Database" name="newCatalog" style="list">
  <Values>
    <Command>
      <SQL>
        <![CDATA[
show databases
]]>
      </SQL>
    </Command>
  </Values>
  <Default>${catalog}</Default>
</Input>
```

Here a **Command** element is specified as a sub element to **Values**. The result of the **show databases** SQL will be presented in the list component.

To make the list editable, specify the attribute **editable="true"**.



Style - note

The **note** style is just a simple label that can be put after for example input fields. Often used in combination with the **linebreak** attribute.

```
<Input label="Sleep Between Each Statement" name="sleep" style="number" linebreak="false">
  <Default>1000</Default>
</Input>
<Input label="millis" style="note" linebreak="true"/>
```

Style - number

A **number** style is the same as text except that it only accept number values.

```
<Input label="Size" name="size" style="number" editable="true"/>
```

Style - password

A **password** field is the same as text except that it masks the value as ***.

```
<Input label="Password" name="pw" style="password" editable="true"/>
```

Style - radio (limited number of choices)

The **radio** style display a list of choices organized as button components. The only difference between the radio and list styles are:

- All choices for a radio style are displayed on the screen (better overview of choices but suitable only for a limited number of choices)
- The **<Arg name="direction" value="vertical"/>** element can be specified for radio style to present the radio choices vertically (default is horizontally)

See the **list** style for complete capabilities of the radio style.

Style - separator (visual divider between input controls)

The **separator** style is not really an input element but is used to visually divide input components in the in the action dialog. If the **label** attribute is specified, it will be presented to the left of the separator line. If no label is specified, only the separator is displayed.

```
<Input label="Parameters" style="separator"/>
```

The separator is a useful substitute for the standard label presented to the left of every input field. Here is a sample:



Create Function

Create Function in Database Connection: Mimer - mimer_store

Schema: mimer_store

Function: MyFunc

Specific Name:

Return Data Type: nvarchar(20)

Deterministic: NOT DETERMINISTIC DETERMINISTIC

Access Option: READS SQL DATA

Parameters

Name	Type
P1	nvarchar(20)
P1	nvarchar(20)
P1	BOOLEAN

Source

```
1 --
2 -- Insert your own function code here
3 --
4 declare var nvarchar(20);
5 set var = n'abc';
6 return var;
```

Show SQL

Execute Cancel

The figure shows the use of separators and two fields that extend to the full width of the action dialog. The separators for **Parameters** and **Source** are here used as alternatives to labels for the fields below them.

Style - note

The **note** style is especially useful when a description or text should be anchored directly after another input.

```
<Input label="Sleep Between Each Statement" name="sleep" style="number" linebreak="false">
  <Default>1000</Default>
</Input>
<Input label="millis" style="note" linebreak="true"/>
```

The previous sample looks like this:

Sleep Between Each Statement: millis

Style - text (single line)

The **text** style is used to present single-line data in a text field.

```
<Input label="Enter your userid" name="userid" style="text">
  <Default>agneta</Default>
</Input>
```



- The optional **Default** element is used to define a default value for the field. Variables, static text and Command elements can be used to define the default value.
- A text input is editable by default. To make it read only specify **editable="false"**

Style - text-editor (multi line)

A **text-editor** field is the same as the text style except that it presents a multi-line field.

```
<Input label="Description" name="desc" style="text-editor" editable="true">
  <Arg name="height" value="30"/>
</Input>
```

The **Arg** element defines the height (in DLU) for the text-editor. The default height is 80 DLU's.

Style - wrapped-text-editor (multi line)

This is exactly the same as text-editor except that the wrapped-text-editor wraps long lines.

XML element - SetVar

The **SetVar** element is used to do conditional processing and create new variables based on the content of other variables or static text.

Consider an SQL statement for creating new users in the database:

```
create user 'user' identified by 'password'
```

In this case it is quite easy to map the user field to an **Input** element for the action since it is a required field. The question arise for password which is optional. The **identified by** clause should only be part of the final SQL if the password is entered by the user. The solution for this scenario is to use the **SetVar** element. Here is the complete action definition:

```
<Action id="mydb-user-create" label="Create User" reload="true" icon="add">
  <Input label="Userid" name="userid" style="text"/>
  <Input label="Password" name="password" style="password"/>

  <SetVar name="_password" value='#password.equals("") ? "" : " identified by \"" + #password + "\"'/>

  <Command>
    <SQL>
      <![CDATA[
create user ${userid} ${_password}
      ]]>
    </SQL>
  </Command>
</Action>
```

The SetVar element accepts three attributes:

Attribute	Description
name	The name of the new variable
value	Should contain the expression that will be evaluated. The expression is based on the OGNL toolkit. This is an expression library that mimics most of what is being supported by Java. Variables are referenced as #variableName
action	This attribute is optional and can have any of the following values: <ul style="list-style-type: none"> • show - default and indicates that the variable (and its value will appear in node-form viewers) • hide - the variable will not display in node-form viewers • drop - the SetVar element is not evaluated when actions is being processed • runwheninit - runs the SetVar only during initialization of the action (before window is displayed)

The expression in the example above checks whether the password variable is empty. If it is empty, a blank value is being assigned to the **_password** variable. If it is not empty, the value for **_password** will be set to **identified by theEnteredPassword**.

The SQL in the Command element now refer the new **\$_password** variable instead of the original **#{password}**.



i It is recommended that variables produced via SetVar elements are prefixed with an underline (_) to highlight where they come from.

i A SetVar having "password" in its name attribute will be displayed as "****" in the SQL Preview pane.

XML element - Confirm

The **Confirm** element is displayed to the user when a request to Execute the action is made. If there are only read-only input fields in the action, this message is displayed in the body of the action dialog. Otherwise the message is displayed in a confirmation dialog.

```
<Confirm>Really drop table ${table}?</Confirm>
```

i Note that the message text can be composed of HTML tags such as , <i>,
, etc.

XML element - Result

The **Result** element is optional and if specified, it is shown in a dialog after successful execution.

i Result elements are currently not displayed in DbVisualizer. It is however recommended that you specify these as they will most likely appear in some way or another in a future version. If you want to test the appearance of Result elements then open the DBVIS-HOME/resources/dbvis-custom.xml file in a text editor and make sure dbvis.showactionresult is set to true.

```
<Result>Table ${table} has been dropped!</Result>
```

- The Result message will be displayed in a dialog after successful execution.
- If the execution fails, a generic error dialog is displayed and the Result is not displayed.

XML element - Command

The **Command** element specifies the SQL code that is executed by the action.

```
<Command>
<SQL>
  <![CDATA[
drop table ${table} mode ${mode} including constraints ${includeconstraints}
  ]]>
</SQL>
</Command>
```

For more information about the Command element check the [XML element - Commands](#) section.

XML element - Message

The **Message** element can be used to specify a highlight message that will appear at the top of the action window.

```
<Message>
  <![CDATA[<html>
This action will be <b>deprecated</b> in a future version as it use database calls that has been declared by the
database vendor as <b>extremely bad performing</b>.</html>
  ]]>
</Message>
```

You may use simple HTML tags in the message content.

Action showing just a message

There may be situations when an action should show a message in a simple dialog with just an OK button. One scenario when this is useful is when a condition is evaluated for an action requiring certain DB privileges to run it. If proper authorization is missing a message should be displayed.



This is accomplished by having a single **Confirm** element for the **Action** element. The following illustrates an example:

```
<If test="#SUPERUSER">
  <Action id="vertica-table-analyze-workload" label="Analyze Workload For Table" resultaction="show">
    <Input label="Schema" style="text" editable="false">
      <Default>${schema}</Default>
    </Input>
    <Input label="Table" style="text" editable="false">
      <Default>${objectname}</Default>
    </Input>
    <Command>
      <SQL>
        <![CDATA[SELECT analyze_workload('${schema}.${objectname}')]></SQL>
      </Command>
    <Confirm>
      Really Analyze Workload on ${schema}.${objectname}?
    </Confirm>
  </Action>
</If>
<Else>
  <Action id="vertica-table-analyze-workload-INFO" label="Analyze Workload For Table">
    <Confirm>
      <![CDATA[
        This feature requires the <b>super user</b> authorization.
      ]]>
    </Confirm>
  </Action>
</Else>
```

24.5 Icons



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

24.5.1 Introduction

Icons related to functionality defined in a database profile are displayed in the database objects tree, actions and object viewers. Icons are declared by mapping a logical name with the file name for the icon. For database profiles provided with DbVisualizer, the **type="xxx"** attribute for **GroupNode** and **DataNode** elements map the **xxx** with a matching icon file name. Icons are normally of minor interest until you decide to build your own database profile or extend an existing one.

The following show the use of the **icon** attribute for a **DataNode** element. A condition control what icon to use based on the value of **getCatalogs.TABLE_CAT**.

```
<DataNode type="Catalog" label="${getCatalogs.TABLE_CAT}"
  icon="#dataMap.get('getCatalogs.TABLE_CAT').equals('sales') ? 'salesIcon' :
  (#dataMap.get('getCatalogs.TABLE_CAT').equals('support') ? 'supportIcon' : null)">
</DataNode>
```

The following sections explain how icons are handled and what choices you have to add your own icons.

24.5.2 icons.prefs file

Icons are defined in a simple text file with each row in the format: **name=iconFileName**. In DbVisualizer there is a *icons.prefs* file provided with the installation and it maps all icons used not only in database profiles but for all features. Here is a sample of the *icons.prefs* file.



PhysicalStandby=	server_certificate
Plan=	FIX_execute_explain
PrimaryKey=	key
Privileges=	key
Procedure=	gears
Procedures=	gears
Process=	cpu
Processes=	cpu
Program=	hat_green
Programs=	hat_green
Properties=	control_panel
PublicDatabaseLinks=	FIX_public_link
PublicDatabaseLink=	FIX_public_link

The first name is the logical name used in the database profile. For all object types such as **Table**, **Column**, **View**, **Source** and so on these names are defined in the *icons.prefs* file. For non object types icons are named with the name the icon represents such as **cut**, **copy**, **paste**, **open** and so on. The value for each logical name is the file name without the extension .png.



The object type may refer grouping objects (**GroupNode**) such as **Tables**, **Views**, **Procedures** and specific a objects (**DataNode**) such as **Table**, **View**, **Procedure**. The general recommendation is to name the object type for a GroupNode in a plural form and in singular form for DataNode objects. The icon representing for example **Tables** and **Table** is in most cases the same, still there must be two definitions in the *icons.prefs* file.

24.5.3 Icons Search Path

The database profile search path defined in **Tool Properties / General / Database Connection / Database Profile** not only define what directories are searched for profiles but also icons. These are the default folders searched:

```
${dbvis.prefsdir}/ext/profiles  
${dbvis.home}/resources/profiles
```

`${dbvis.prefsdir}` is replaced with the setting directory for DbVisualizer on the platform being used. On Windows this is **C:\Users\<user>\.dbvis** while `${dbvis.home}` is the installation directory for DbVisualizer. If there is an *icons.prefs* file available in the scanned directories the actual icon files must be available in the **images/16x16** and **images/24x24** sub directories such as `${dbvis.prefsdir}/ext/profiles/images/16x16`. The 16x16 directory should contain a 16 by 16 sized icon and the 24x24 a 24 by 24 sized icon.

This is an example of the `${dbvis.prefsdir}/ext/profiles/icons.prefs` file:

```
sample-schema-dict=dict
```

The actual icon represented by the **dict** file name is located in:

```
${dbvis.prefsdir}/ext/profiles/images/16x16/dict.png  
${dbvis.prefsdir}/ext/profiles/images/24x24/dict.png
```

24.6 Conditional Processing



Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

- [Introduction](#)
- [Conditional processing when database connection is established](#)
- [Conditional processing during command execution](#)
- [drop-on-condition attribute](#)

24.6.1 Introduction

Conditional processing simply means that a profile can adjust its content based on certain conditions. A few examples:

- Which version of the database is being accessed



- The format of the database URL
- The client environment i.e Java version, vendor, etc.
- User properties
- Database connection properties

Conditional processing is especially useful when adapting the profile for different versions of the database (and/or JDBC driver). Another use is to replace generic error messages with more user friendly messages.

If you have some programming skills conditions are expressed using **If**, **Elseif** and **Else** statements.

There are two phases when conditions are processed:

1. **Conditional processing when database connection is established**
If, **Elseif** and **Else** elements can be specified almost everywhere in the profile
2. **Conditional processing during command execution**
The **OnError** element is used to define a message that will appear in DbVisualizer if a command fails. Conditions are used to control what message should appear

DbVisualizer uses the **type** attribute to determine which **If** elements should be executed in which of the two phases. If this attribute is set to the value **runtime**, it will be processed in the second phase. If it is not specified, it will be processed in the first phase.

24.6.2 Conditional processing when database connection is established

These are the call signatures for the utilities used when processing conditions:

```
boolean #util.isNull(String string)
boolean #util.isNullOrWhitespace(String string)
boolean #util.isDatabaseVersionLT(Integer major)
boolean #util.isDatabaseVersionLT(Integer major, Integer minor)
boolean #util.isDatabaseVersionLTE(Integer major)
boolean #util.isDatabaseVersionLTE(Integer major, Integer minor)
boolean #util.isDatabaseVersionEQ(Integer major)
boolean #util.isDatabaseVersionEQ(Integer major, Integer minor)
boolean #util.isDatabaseVersionGTE(Integer major)
boolean #util.isDatabaseVersionGTE(Integer major, Integer minor)
boolean #util.isDatabaseVersionGT(Integer major)
boolean #util.isDatabaseVersionGT(Integer major, Integer minor)
boolean #util.isDatabaseType(String type)
boolean #util.isNotDatabaseType(String type)
```

The following example shows the use of conditions that are processed during connect of the database connection.

```
<Command id="sybase-ase.getLogins">
  <If test="#util.isDatabaseVersionLTE(5)">
    <SQL>
      <![CDATA[
select name from master.dbo.syslogins
      ]]>
    </SQL>
  </If>
  <ElseIf test="#util.isDatabaseVersionEQ(9)">
    <SQL>
      <![CDATA[
select name, suid from master.dbo.syslogins
      ]]>
    </SQL>
  </ElseIf>
  <Else>
    <SQL>
      <![CDATA[
select name, suid, dbname from master.dbo.syslogins
      ]]>
    </SQL>
  </Else>
</Command>
```

The above means that if the major version of the database being accessed is less than or equal to 5, the first SQL is used. If the major version is equal to 9, the second SQL is used, and the last SQL is used for all other versions. The test attribute may contain conditions that are ANDed or ORed. Conditions can contain multiple evaluations, combined using parenthesis. The If, Elseif and Else elements may be placed anywhere in the XML file.



Here is another example that controls whether certain nodes will appear in the database objects tree or not.

```
<!-- Getting Table Engines was added in MySQL 4.1 -->
<If test="#util.isDatabaseVersionGTE(4, 1)">
  <GroupNode type="TableEngines" label="Table Engines" isLeaf="true"/>

  <!-- "Errors" was added in MySQL 5 -->
  <If test="#util.isDatabaseVersionGTE(5)">
    <GroupNode type="Errors" label="Errors" isLeaf="true"/>
  </If>
</If>
<Commands>
  <OnError>
    <!-- The ORA-942 error means "the table or view doesn't exist" -->
    <!-- It is caught here since these errors typically indicates -->
    <!-- that the user don't have privileges to access the SYS and/or -->
    <!-- V$ tables. -->
    <If test="#result.getErrorCode() eq 942" context="runtime">
      <Message>
        <![CDATA[
You don't have the required privileges to view this object.
        ]]>
      </Message>
    </If>
    <ElseIf test="#result.getErrorCode() eq 17008" context="runtime">
      <Message>
        <![CDATA[
Your connection with the database server has been interrupted!
Please <a href="connect" action="connect">reconnect</a> to re-establish the connection.
        ]]>
      </Message>
    </ElseIf>
  </OnError>
  ...
</Commands>
```

As you can see, this example contains **nested** uses of **If**.

24.6.3 Conditional processing during command execution

Using conditional processing to evaluate any errors from a Command may be useful to rephrase error messages to be more user friendly.

```
<Commands>
  <OnError>
    <!-- The ORA-942 error means "the table or view doesn't exist" -->
    <!-- It is caught here since these errors typically indicates -->
    <!-- that the user don't have privileges to access the SYS and/or -->
    <!-- V$ tables. -->
    <If test="#result.getErrorCode() eq 942" context="runtime">
      <Message>
        <![CDATA[
You don't have the required privileges to view this object.
        ]]>
      </Message>
    </If>
    <ElseIf test="#result.getErrorCode() eq 17008" context="runtime">
      <Message>
        <![CDATA[
Your connection with the database server has been interrupted!
Please <a href="connect" action="connect">reconnect</a> to re-establish the connection.
        ]]>
      </Message>
    </ElseIf>
  </OnError>
  ...
</Commands>
```



The **OnError** element can be used in **Commands** and **Command** elements. If used in **Commands** element, its conditions are processed for all its commands. If it's part of a specific Command, it is processed only for that command.

24.6.4 drop-on-condition attribute

The drop-on-condition attribute is processed during profile load and may have the constant value **"always"** or a boolean statement that is evaluated. This attribute is valid for the following XML elements:

- Action
- ActionGroup
- GroupNode
- DataNode
- ObjectView
- DataView

This will drop the element if the database version is less than 4.1:

```
<GroupNode type="TableEngines" label="Storage Engines"
  drop-on-condition="#util.isDatabaseVersionLT(4,1)">
```

This will drop the element unconditionally which is useful in a sub profile needing to for example drop a parent DataView defined in the same ObjectView:

```
<DataView id="generic-catalog-tables" drop-on-condition="always"/>
```

24.7 Database Profile Utilities

Only in DbVisualizer Pro

This document and the Database Profile Framework in general is appropriate only when using the licensed DbVisualizer Pro edition.

In the **Database Profiles** list in **Connection Properties** there is a right-click menu with various commands to process the database profile and list of profiles. These

commands are useful while developing a database profile. Read the following sections for more details about each command.

- [Analyze Database Profile](#)
- [Show All Type and Icon Attributes](#)
- [Show Available Icons](#)
- [Export Merged Profile](#)
- [Configure Search Path](#)
- [Reload Database Profiles List](#)

24.7.1 Analyze Database Profile

This command verify the loaded database profile and perform various consistency checks and may report:

Check
GroupNode and DataNode elements with no matching ObjectView (by "type" attribute)
ObjectView elements with no matching GroupNode or DataNode (by "type" attribute)
ActionGroup elements with no matching GroupNode or DataNode (by "type" attribute)
DataView elements located in the same ObjectView having same "label" attribute
No matching icon for these elements (by the "type" or "icon" attributes)

24.7.2 Show All Type and Icon Attributes

This command examine the loaded profile and report all used icons (logical name) as referenced by the object type and specific icon attributes. The following is an example doing running this command with the MySQL profile loaded.



These are all "type" and "icon" references in the profile:

```
add
catalog
catalogs
charset
collation
column
columns
data
databases
dba
edit
errors
event
events
export
function
functions
import
index
indexes
info
login
navigator
primarykey
privileges
procedure
procedures
process
processes
references
remove
rename
role
rowcount
rowid
schema
schemas
scriptobject
slavestatus
source
sourceeditor
stateerror
status
table
tableengine
tableengines
tableprivileges
tables
trigger
triggers
users
variables
view
views
warning
warnings
```

24.7.3 Show Available Icons

This will show a window with all available icons, their name, icon file name and an indicator if the icon is used in the loaded database profile.



Key	Filename ix3	Used in Profile "mysql"
calctree	object_cube	
calculator	calculator	
cascadeframes	windows	
caselower	navigate_close	
caseupper	navigate_open	
catalog	data	Yes
catalogdatabase	data	
catalogs	data	Yes
cellclear	table_selection_cell badges/delete[SE]	
celledit	table_selection_cell badges/edit[SE]	
cellinsert	table_selection_range badges/gearwheel...	
changename	note_pinned badges/edit[SE]	
charset	font	Yes
chartarea	chart_area	
chartbar	chart_column	
chartline	chart_line	
chartpie	chart_pie	
chartpie2	chart_pie	
chartpoint	chart_dot	
chartpreferences	tools	

0.000/0.000 sec 814/3 55-74

24.7.4 Export Merged Profile

This will export the currently loaded profile. If the profile has been merged using the [extend](#) attribute the exported profile file is the complete and processed profile.

24.7.5 Configure Search Path

This will open **Tool Properties / General / Database Connection / Database Profile** pane used to configure the search path for database profile loading.

24.7.6 Reload Database Profiles List

This will reload the list of database profiles in case a new profile has been added (or renamed) since last launch of DbVisualizer.



24.8 Database Profile changes in 11.0

This document collects changes in the database profile framework in DbVisualizer 11.0.

- [Common attribute changes](#)
- [New attributes for the ProcessDataSet sub element for Command](#)
- [New attributes for the ObjectView element](#)
- [New "chart" viewer for DataView elements](#)

24.8.1 Common attribute changes

- The **action="drop"** attribute replaced with **drop-on-condition="..."**
 - Read more in [drop-on-condition](#) attribute

24.8.2 New attributes for the ProcessDataSet sub element for Command

The ProcessDataSet definition defines if and how a DataSet generated by a Command should be processed after retrieved from the database.

The following new actions for ProcessDataSet are new in 11.0:

- **addrow**
- **convertnullvalues**
- **convertsqlwarningtodataset**
- **movecolumn**
- **truncatedataset**

Read more in [XML element - Commands](#)

24.8.3 New attributes for the ObjectView element

The DataView element now supports this new attribute:

- **layout="tilehorizontal/tilevertical/collapse"**

Read more in: [XML element - ObjectsViewDef](#)

24.8.4 New "chart" viewer for DataView elements

The DataView element now supports the new **chart** viewer.

- **viewer="chart"**

Read more in: [XML element - ObjectsViewDef](#)

24.9 Database Profile changes in 9.5

This document collects changes in the database profile framework in DbVisualizer 9.5.

- [New/changed attributes for Command](#)
- [Action element improvements](#)
 - [New runsetdefaultwhenvaluechanged attribute](#)
 - [Check list style](#)
 - [Check style](#)
 - [Action layout](#)
- [Changes for DataNode and GroupNode](#)
- [New utility class](#)
- [Changed icons definition](#)

24.9.1 New/changed attributes for Command

These are the changes in the attributes for the Command element.

- **exectype="script/asis/explain"** (replaces **parsestql="true/false"**)



- **script** will execute each individual statement in a multi statement script, **asis** will execute all of the SQL as one statement and **explain** will try generate an explain plan for the single statement
- processmarkers="true/withdriver"
 - Defines whether markers such as :name, ? should be processed either internally by DbVisualizer or by letting the driver (if it supports it) do the parsing
- autocommit="true/false"
 - Specifies if the command should be auto committed after execution
- whensuccess="commit/rollback/ask"
 - If autocommit="false" then this attribute defines what to do after successful execution
- whenerror="commit/rollback/ask/ignore"
 - If autocommit="false" then this attribute defines what to do after failed execution

24.9.2 Action element improvements

- Moved processmarkers="true|false" to **Command processmarkers="true|withdriver"**
- Removed **execute** value for the **mode** attribute (since it is default)
- Removed **resulttype="resultset|dbmsoutput"** and replaced by using the **@set server output** client side command in script when needed
- Replaced **resultaction="ask|show|showtext|script"** with **resultaction="mergeastext/mergeasscript"**
- Added **resulttarget="editor"**

Notes:

- If none of **resultaction** and **resulttarget** is present and there are results generated, the results are presented as tabs (same as SQL Commander). The result set tab option to **Merge All Result Sets** tabs is available
- If **resultaction** is present all result sets will be merged into a single result tab
- If **resulttarget** is present it will copy the merged results to a new SQL Commander tab

New runsetdefaultwhenvaluechanged attribute

The **runsetdefaultwhenvaluechanged** attribute defines what other inputs should be triggered when the value for the input is changed. Whenever this happens the other inputs Default commands are executed. This is useful if there are for example two list inputs. Changing the selected entry in the first list will then notify the second input so that its Default command is re-executed using the new value as condition.

```
<Action id="postgresql-settings-alter" label="Alter Setting" reload="true" icon="edit">
  <Input name="setting" label="Setting" runsetdefaultwhenvaluechanged="value,desc" style="list">
    <Values>
      <Command><SQL><![CDATA[select name from pg_settings]]></SQL></Command>
    </Values>
  </Input>
  <Input name="value" label="Value" style="text">
    <Default>
      <Command><SQL><![CDATA[select setting from pg_settings where name = '${setting}']]></SQL></Command>
    </Default>
  </Input>
  <Input name="desc" label="Description" style="text" editable="false">
    <Default>
      <Command><SQL><![CDATA[select short_desc from pg_settings where name = '${setting}']]></SQL></Command>
    </Default>
  </Input>
  <Command>
    <SQL><![CDATA[alter system set ${setting} = ${value}]]></SQL>
  </Command>
  <Confirm>
    Really alter setting ${setting}?
  </Confirm>
</Action>
```

Check list style

The new check-list input shows a list with options allowing multiple selections.



```
<Input label="Weekdays" name="weekdays" style="check-list">
  <Arg name="output" value="jschours[${value}] = true"/>
  <Arg name="newline" value=" " />
  <Labels>Monday|Tuesday|Wednesday|Thursday|Friday|Saturday|Sunday</Labels>
  <Values>00|11|22|33|44|55|66</Values>
  <Default>22|44</Default>
</Input>
```

The `<Arg name="output" value="jschours[${value}] = true"/>` defines that for each selected value in the list (ex Monday, Thursday, Friday), the output in the **weekdays** variable will be:

```
jschours[11] = true, jschours[33] = true, jschours[44] = true
```

The **newline** argument defines the string used to separate the output entries.

Check style

Check inputs now supports a second values argument:

```
<Input label="Check with true/false value" name="enabled" style="check">
  <Values>On|Off</Values>
  <Default>Off</Default>
</Input>
```

The first, "On" is set if the checkbox is checked. "Off" is set if the checkbox is unchecked. If the second argument is not specified an empty string is set if the checkbox is unchecked.

Action layout

- Improved support for having input fields on the same row
- Previously when using **linebreak="false"** any label on that row was not displayed. Now if there is a label it is shown
- New: **type="label"** input attribute. Used to create just a label. Useful when **linebreak="false"** by having a general label for the row and then each component can have their individual label. Ex: "Days: Mon: X Tue: X"
- **New: type="note"** input attribute. Is the exact same as "label" but can be used to specify some informative text that is not suffixed with a colon

24.9.3 Changes for DataNode and GroupNode

- In addition to the label attribute the new label1 is now available. In the objects tree it will show optional information about the object. This is displayed in italic gray text.
- The **sort** attribute has been replaced with the **ProcessDataSet action="sortcolumn"**

24.9.4 New utility class

The new #util class can be used in profiles to primarily perform conditional checks such as what target database version is used. This is useful to adjust what parts of the database profile should be visible to the user. These are the methods available:

```
boolean #util.isNull(String string)
boolean #util.isNullOrWhitespace(String string)
boolean #util.isDatabaseVersionLT(Integer major)
boolean #util.isDatabaseVersionLT(Integer major, Integer minor)
boolean #util.isDatabaseVersionLTE(Integer major)
boolean #util.isDatabaseVersionLTE(Integer major, Integer minor)
boolean #util.isDatabaseVersionEQ(Integer major)
boolean #util.isDatabaseVersionEQ(Integer major, Integer minor)
boolean #util.isDatabaseVersionGTE(Integer major)
boolean #util.isDatabaseVersionGTE(Integer major, Integer minor)
boolean #util.isDatabaseVersionGT(Integer major)
boolean #util.isDatabaseVersionGT(Integer major, Integer minor)
boolean #util.isDatabaseType(String type)
boolean #util.isNotDatabaseType(String type)
boolean #util.replaceAll(String source, String search, String replacement )
```




24.9.5 Changed icons definition

Many icons are composed of a full size (16x16, 24x24) base icon and a badge icon (half the size) representing things like, new, delete, error, clock, and so on. The badge icon is typically anchored south east on the base icon.

Prior to DbVisualizer 9.5 there were no separate badge icons as these were integrated with the base icon resulting in many duplicated base icons only with different badge symbols.

In DbVisualizer 9.5 a new icon library was introduced and now base icons are separate from the badge icons. Any badge icons that should be attached are defined in the `icons.prefs` file and the final icon is dynamically created.

25 Troubleshooting

Even though we make our very best to ensure the quality of DbVisualizer, you may run into problems of different kinds. The runtime environment for DbVisualizer is rather complicated when it comes to tracking the source of a problem, since it's not only DbVisualizer that may cause the problem but also the JDBC driver, or even the database engine.

There are a few things that you can try before reporting a problem, depending on the nature of the problem:

1. Make sure you are using the latest version of [Java](#) available for your platform (Java 8 or later),
2. Make sure you are using a [version](#) of the JDBC driver that we've tested DbVisualizer with, or a later, production quality version,
3. Read the DbVisualizer [FAQ](#),
4. Check the online [Forums](#),
5. Read the DbVisualizer [Users Guide](#),
6. ... the last resort is to post a question via the [problem report form](#) or send an email to support@dbvis.com. (Note that we generally love detailed reports as well as screenshots when possible)

25.1 Debugging DbVisualizer

The **Tools->Debug Window** is useful to see what is going on in DbVisualizer and the JDBC driver(s). The checkboxes at the top of the **Debug** tab controls what parts of DbVisualizer should be debugged. The **Debug JDBC Drivers** option will enable debug of the current JDBC driver. Note that the amount of output is determined by the JDBC driver.

```
2016-06-07 14:12:12.610 FINE 721 [ExecutorRunner-pool-3-thread-1 - H.?] JDBC connection established: HR Production [oracle.jdbc.driver.T4CConnection@1f59a7f]
2016-06-07 14:12:12.610 FINE 721 [ExecutorRunner-pool-3-thread-1 - F.?] HR Production (DefaultEditor40)
2016-06-07 14:12:12.610 FINE 721 [ExecutorRunner-pool-3-thread-1 - F.?] Connection state(s) for HR Production (DefaultEditor40): CONNECTED
2016-06-07 14:12:12.610 FINE 721 [ExecutorRunner-pool-3-thread-1 - J.?] Executing...
2016-06-07 14:12:12.610 FINE 721 [pool-4-thread-1 - C.?] DefaultEditor40: T4CConnection.createStatement()
2016-06-07 14:12:12.610 FINE 721 [pool-4-thread-1 - B.?] DefaultEditor40: OracleStatementWrapper.execute("SELECT
EMP.FIRST_NAME,
EMP.LAST_NAME,
EMP.EMAIL,
DEP.DEPARTMENT_NAME,
CASE
WHEN SALARY > 100000
THEN 'HIGH'
WHEN SALARY BETWEEN 50000 AND 99000
THEN 'MEDIUM'
ELSE 'LOW'
END AS SALARY_LEVEL
FROM
EMPLOYEES EMP
INNER JOIN
DEPARTMENTS DEP
ON
(
EMP.DEPARTMENT_ID = DEP.DEPARTMENT_ID)")
2016-06-07 14:12:12.626 FINE 721 [ExecutorRunner-pool-3-thread-1 - L.?] Fetched Rows: 106 Columns: 5 Exec: 0.000 Fetch: 0.016 sec
2016-06-07 14:12:12.626 FINE 721 [ExecutorRunner-pool-3-thread-1 - L.?] Edit DataSet is not enabled: More than one table is referenced in the FROM clause
2016-06-07 14:12:13.207 FINE 721 [ExecutorRunner-pool-3-thread-1 - L.?] Executing 'select sys_context( 'userenv', 'current_schema' ) from dual' for: HR Production
2016-06-07 14:12:13.207 FINE 721 [pool-4-thread-1 - C.?] DefaultEditor40: T4CConnection.createStatement()
2016-06-07 14:12:13.207 FINE 721 [pool-4-thread-1 - B.?] DefaultEditor40: OracleStatementWrapper.executeQuery("select sys_context( 'userenv', 'current_schema' ) from dual")
```

The log window shows the end of the log files produced by DbVisualizer. The **Debug Log** tab shows the debug log file and the **Error Log** tab the error log file. DbVisualizer writes its log files to a log directory which may be opened using the **Open Log Directory** link at the top right. DbVisualizer maintains the content of the log directory in a way that limits the size of its content. The content of the log tabs is also automatically truncated to preserve memory.

The toolbar contains the following buttons:



- **Save** saves the content of the visible log tab to file
- **Copy** copies any selection to the clipboard
- **Clear** clears the content of the log tab
- **Start** starts monitoring of the corresponding log file. This button is of course disabled if monitoring is already started
- **Stop** stops the monitoring of the log files (if started)

The button labeled **Contact Support** serves as a shortcut to open the window for [Reporting Issues](#) where you may optionally attach the content of the DbVisualizer log files to a support ticket.

25.2 Fixing Connection Issues

There may be many reasons for why you cannot connect to a database, but some of the most common are:

- Incorrect values for the **Database Server** or **Database Port** fields in the **Object View** tab for the connection,
- TCP/IP access is not enabled in the database server,
- A firewall between the client and the database server blocks connections to the database port,
- A syntax error in a manually entered JDBC URL,
- The user account is not authorized to connect from the client where you run DbVisualizer,
- Native libraries for a JDBC driver are not found.

The first three problems usually results in a somewhat cryptic message about I/O errors or a time-out. You can use the **Ping Server** button to make sure that the a TCP/IP network connection can be established to the specified server and port. If this test fails, please ask your system or database administrator for help.

JDBC syntax errors typically result in one of two error messages:

- "The selected Driver cannot handle the specified Database URL. The most common reason for this error is that the database URL contains a syntax error preventing the driver from accepting it. The error also occurs when trying to connect to a database with the wrong driver. Correct this and try again."
- "java.sql.SQLException: Io exception: Invalid number format for port number Io exception: Invalid number format for port number"

In both cases, we recommend using the **Server Info** settings format instead of the **Database URL** format for the connection, and let DbVisualizer build a valid JDBC URL for you. If you must enter a JDBC URL manually, make sure that you replace possible placeholders enclosed with "<" and ">" in a template you have copied, such as <1521>, and look for other syntax errors. Also verify that the [JDBC driver is installed](#) correctly.


Authorization problems are usually described by more straight forward messages. Ask you database administrator to help you get it resolved.

If you get a message about native libraries not being found, e.g. "no ocijdbc11 in java.library.path" or similar, it is because you have not installed these in a location where DbVisualizer can read them. Unless you have a very good reason for using a JDBC driver that requires native code, we recommend that you use a pure Java JDBC driver (a Type 4 driver) instead, like the "Oracle Thin" driver for Oracle.

If none of this helps, please contact us using the [Help->Contact Support](#) form. Most of the information we can gather about the problem is typically already filled in, but please add any additional details that may help us figure out what is wrong.


25.3 Handling Dropped Connections

All tasks that may potentially take a bit of time to perform or that may not finish at all because a database connection has dropped are executed in the background so that you can still do other things. You can see that background tasks are running by looking at an indicator icon in the status bar.



If there are tasks running, the indicator icon is animated, showing a spinning pattern.

You can see exactly which tasks are running by clicking on the icon. This opens the **Task Manager** window.



You can abort a long running task by clicking the **Stop** button next to the progress bar.

If the task did not complete because the connection dropped, you also need to reconnect to the database. If this happens frequently, you can enable [Connection Keep-Alive](#) to send a dummy SELECT statements to the database occasionally to prevent time-outs.

25.4 Handling Memory Constraints

DbVisualizer has a fixed amount of memory available, and things may go bad if you load so much data that you're getting close to this limit. The most common effect is that the GUI becomes very unresponsive or freezes completely.

To minimize the risk of this happening, DbVisualizer keeps track of the memory usage when you load tables or files and similar tasks that consume memory. If you're getting so close to the limit that problems are likely to begin to show, all memory consuming background tasks are suspended and the High Memory Usage window pops up.



High Memory Usage Detected

You are running out of memory.

Please **close tabs** and **stop tasks** listed below until you have freed up enough memory to continue. You may also need to click the garbage bin icon to the left of the **memory usage** bar to force release of memory.

To see how you can avoid this problem in the future, please open **Help->Online Resources** and choose the FAQ page. It explains how you can increase the memory available to DbVisualizer.

Current Tabs

Tab Name	Memory Usage	Action
HR Production FRUITDATA	75,20 MB	Close (X)
1: FRUITDATA [60000]	45,12 MB	Close (X)
HR Production EMPLOYEES	0,14 MB	Close (X)
HR Production SYSTEM_PRIVILEGE_MAP	0,04 MB	Close (X)

Current Tasks

'1: miscData.sql' executing

Executing: SELECT ID, COMB, FRUIT, COLOR, STR1, STR2, STR3 FROM FRUITDATA

Memory Usage

341M of 341M

Buttons: Continue (Warning), Shutdown DbVisualizer, Create Heap Dump

All open tabs are listed along with an estimate for how much memory each tab uses. All background tasks are also shown. You need to resolve the high memory usage problem before you can continue working with DbVisualizer. Click on the red cross next to tabs that use lots of memory to close them and stop tasks that consume memory.

When you have released enough memory to get below the critical level, the icon in the Continue button changes to a green checkmark. Click it to close the window and continue to work.

If you often see this window, first consider using features that minimizes the memory usage, such as using the @run command to [execute your script](#) and the @export command to [write query results to a file](#). As a last resort, you can increase the amount of memory DbVisualizer can use. Please see the [FAQ page](#) on our web site for how to do so.

In rare cases, closing tabs and stopping tasks do not release enough memory to continue, possibly due to memory leaks in the DbVisualizer code. If this happens, you can click the **Create Heap Dump** button. The heap dump file is named *heap.bin* and stored in the preferences folder, typically the *.dbvis* folder in your home folder. It may help us find memory leaks and fix them, so please send it to us with a description of what you were doing when you ran into this problem. The file can be huge, so please compress it (e.g. using the zip command) before mailing it to us.

If you cannot release enough memory to continue, you can use the **Shutdown DbVisualizer** button to shut down and start fresh.

25.5 Reporting Issues

25.5.1 Contacting support

There following are the alternatives getting help with issues or support requests:


- Using Help->Contact Support in the DbVisualizer application (Recommended)
- Using the web form at <https://www.dbvis.com/company/contact/>
- Using the forums and knowledge base at <http://support.dbvis.com>




Using Help-Contact Support

This is the recommend way to report an issue or support requests as it gathers information about your settings and connections that help us provide you with better analysis of any problems without having to get back to you and ask for additional information.

Please describe as detailed as possible the actions leading to the issue.

 Post a Support request ✕

 Specify your support request. Please consider **attaching screenshots** as these are really valuable for the developers.

Application Properties

Product: DbVisualizer Pro 110 [Build #3069]
OS: Windows 10
OS Version: 10.0
OS Arch: x86
Java Version: 1.8.0_241
Java VM: Java HotSpot(TM) Client VM

Enter details about your support request

Getting failure when running delete on X

1. Selecting object X in the tree
2. Running the action drop X

The above results in an exception.

Attach Logs Attach File...

Your Contact Information

Last Name Email Address Remember

Post on Web Site


25.5.2 Encountering Errors

DbVisualizer sometimes detects errors that need the attention from the user. This can be done in two ways

- The pop up of an Error dialog
- The pop up of a "Red balloon" in the status bar of DbVisualizer


The Error Dialog

If you encounter an error that causes an error alert dialog to pop up, please click the **Report Problem** button to open the contact form with the details of the error filled in.



The Red Balloon - log errors

DbVisualizer constantly monitor the log entries it writes to it's log files. If log entries representing errors are detected, a "Red balloon" pops up in the DbVisualizer status bar as indicated below.



Clicking the red button will bring up the [debug window](#).

25.6 Using special characters in passwords

Passwords entered for connections etc. can optionally be saved between sessions by DbVisualizer. Passwords containing special characters such as ♥ can not be saved when the default encoding for passwords is used. More specifically DbVisualizer only supports characters in the 8859-1 character set with the default encoding; other characters are corrupted when saved.

To be able to save passwords containing any characters, you need to enter a Master Password. Please see the section [Setting a Master Password](#) for more information.

26 Reference Material

Here you find details about areas that are not covered elsewhere.

26.1 GUI Command Line Arguments

As an alternative to start DbVisualizer via the menu items and icons created by the installer, you can also start DbVisualizer from a shell (terminal) on all operating systems using the following scripts:



```
# DbVisualizer GUI on Windows:
DBVIS-HOME\dbvisgui.bat

# DbVisualizer GUI on Linux/UNIX:
DBVIS-HOME/dbvisgui.sh

# DbVisualizer GUI on macOS:
DbVisualizer.app/Contents/java/app/dbvisgui.sh
```

The scripts supports a number of command line arguments. These are also listed in the **Help->About** menu choice, under the **Command Line** tab, in DbVisualizer.

```
Usage: dbvisgui [-connection <name>] [-userid <userid>] [-password <password>]
               [-encoding <encoding>]
               [-prefsdir <directory>]
               [-windowtitle <title>]
               [-help] [-version]
               [<filename>]
```

General Options:

-connection <name>	Database connection name (created with the GUI)
-userid <userid>	Userid to connect as
-password <password>	Password for userid
-encoding <encoding>	Encoding for the SQL script file
-prefsdir <directory>	Use an alternate user preferences directory
-windowtitle <title>	Additional window title
-help	Display this help
-version	Show version info
<filename>	SQL script file to load into editor



Please note that these scripts use the first Java version that is found in the PATH. The result may be that a non supported Java version is used.

26.2 Installation Structure

The installer and launcher for DbVisualizer is based on the install4j™ product (<http://www.install4j.com>). The structure of the installation directory (referred as DBVIS-HOME throughout the Users Guide) contains the following. (The exact content may differ between platforms):

```
.install4j/
doc/
editor/
jdbc/
lib/
resources/
wrapper/
dbvis.vmoptions
dbvis.exe
README.txt
uninstall.exe
```

The *dbvis.exe* file is used to start DbVisualizer. The remaining files and directories are only of interest if you need to do nonstandard customization. For information on how to increase the memory for the Java process that runs DbVisualizer, and also on how to modify the Java version being used, please read the online [FAQ](#) for the latest information.

26.3 Installing a JDBC Driver

DbVisualizer bundles JDBC drivers for most common databases, so typically you do not need to install a JDBC driver.

- [What is a JDBC Driver?](#)
- [Get the JDBC driver file\(s\)](#)
- [Driver Manager](#)
 - [JDBC Driver Finder](#)
 - [Loading and Configuring Drivers Manually](#)
 - [Setup a JDBC driver](#)
 - [JDBC drivers that requires several JAR or ZIP files](#)



- [Errors \(why are some paths red?\)](#)
- [Several versions of the same driver](#)

This page describes the way JDBC drivers are managed in DbVisualizer. If a JDBC driver for your database is bundled with DbVisualizer, see [Driver Info](#) on the [Supported Databases](#) page, you typically do not need to read this chapter.

If, however, any of these things apply to you, keep on reading:

- want to learn how the Driver Manager in DbVisualizer works,
- need to have several versions of the same JDBC driver loaded simultaneously,
- need to add a Driver that does not exist in the list of default drivers.

26.3.1 What is a JDBC Driver?

DbVisualizer is a generic tool for administration and exploration of databases. DbVisualizer does not deal directly with how to communicate with each database type. That job is done by a JDBC driver, which is a set of Java classes. All JDBC drivers conform to the JDBC specification and its standardized Java programming interfaces. This is what DbVisualizer relies on. A JDBC driver implements all details for how to communicate with a specific database and database version, and there are drivers available from the database vendors themselves as well as from third parties. To establish a connection to a database, DbVisualizer loads the driver and then gets connected to the database through the driver.

It is also possible to obtain a database connection using the Java Naming and Directory Interface (JNDI). This technique is widely used in enterprise infrastructures, such as application server systems. It does not replace JDBC drivers but rather adds an alternative way to get a handle to an already established database connection. To enable database "lookup's" using JNDI, an Initial Context implementation must be loaded into the DbVisualizer Driver Manager. This context is then used to lookup a database connection.

The following sections describe the steps for installing a JDBC Driver, and also how to configure DbVisualizer to use JNDI to obtain a database connection.

26.3.2 Get the JDBC driver file(s)

DbVisualizer comes bundled with all commonly used JDBC drivers that have licenses that allow for distribution with a third party product. Currently, drivers for DB2, H2, JavaDB/Derby, Mimer SQL, MySQL, NuoDB, Oracle, PostgreSQL, SQLite, Vertica as well the JTDS driver for SQL Server and Sybase, are included with DbVisualizer. If you only need to connect to databases of these types, you can skip the rest of this chapter and jump straight to the [Creating a Connection](#) page, because by default, DbVisualizer configures all these drivers automatically the first time you start DbVisualizer.

If you need to connect to a database that is not supported by a bundled JDBC driver, you must get a JDBC driver that works with your database type and version. The following web page contains an up-to-date listing of the database/driver combinations we have tested:

<http://www.dbvis.com/doc/database-drivers/>

To find a JDBC driver for your database, go to the database vendor's website or search for the name of the database plus the word JDBC.

Download the driver to an appropriate directory. Make sure to read the installation instructions provided with the driver. Some drivers are delivered in ZIP or JAR format but need to be unpacked to make the driver files visible to the Driver Manager. The [Databases and JDBC Drivers](#) web page describes where you can download some drivers and also what additional steps may be needed to install and load the driver in DbVisualizer.

i Drivers are categorized into 4 types. We're not going to explain the differences here, just give you the hint that the "type 4," aka "thin," drivers are the easiest to maintain, since they are pure Java drivers and do not depend on any external DLL's or dynamic libraries. Even though DbVisualizer works with any type of driver, we recommend that you get a type 4 driver if there is one for your database.


When you have downloaded the JDBC driver into a local folder (and unpacked it, if needed), you can go ahead and create a database connection with the Connection Wizard, as described in the [Creating a Connection](#) page. You will then be asked to load the driver files when the wizard needs them. Alternatively, you can move (or copy) the JDBC driver files to the DBVIS_HOME/jdbc folder, where they will be picked up and loaded automatically by the [JDBC Driver Finder](#) the next time you start DbVisualizer.

26.3.3 Driver Manager

The **Driver Manager** in DbVisualizer is used to define the drivers that will be used to communicate with the databases. You can manually locate the JDBC driver files and configure the driver, or you can use the JDBC Driver Finder to do most of the work for you, either on demand or automatically.

JDBC Driver Finder

The **JDBC Driver Finder** is a very powerful part of the Driver Manager that automates most of the driver management work. Given the folders where JDBC drivers are located, it loads and configures new drivers (if any) every time you start DbVisualizer. You can configure the JDBC Driver Finder in **Tools->Tools Properties**, in the **Driver Manager** category under the **General** tab.



Use the following properties to specify the finder behavior:

Property	Description
Run JDBC Driver Finder at Startup	If enabled, the finder will run automatically every time you start DbVisualizer. If it finds any new driver files, it will automatically load and configure them.
Replace Driver Files	If enabled, the driver files are replaced for the matching driver even if the driver already has proper driver files.
Display When New Files	If enabled, the finder window pops-up if it finds any new files when you start DbVisualizer. Otherwise the finder runs invisibly in the background.
Display on Error	If enabled, the finder window pops up if it encounters any errors loading and configuring new drivers. Otherwise it is silent about errors and you have to launch the Tools->Driver Manager to see which drivers are not loaded successfully. Enabling this property is only meaningful if you have disabled Display When New Files .



You can also specify the folders the JDBC Driver Finder will search. By default, it will search folders named jdbc in the DbVisualizer installation directory (`${dbvis.home}`) and the DbVisualizer preferences folder (`${dbvis.prefdir}`). These folder paths are shown under the list of **Driver Finder Paths**.

Finally, you can specify regular expression patterns for filenames that the finder should ignore. This can be useful if you need to store other files besides driver files in the designated folders.

If you let the JDBC Driver Finder load all drivers for you, all you need to do to install a new driver is to put the driver files in one of the folders specified for the finder in Tool Properties and then restart DbVisualizer.




The Driver Finder is always activated when upgrading from an older DbVisualizer version.

Loading and Configuring Drivers Manually

You can also load and configure JDBC drivers manually using the Driver Manager. If you use JNDI to provide access to the database, you must use this option, since the JDBC Driver Finder does not handle JNDI. Start the Driver Manager dialog using the **Tools->Driver Manager** menu choice.

The left part of the driver manager dialog contains a list of driver names with a symbol indicating whether the driver has been configured or not. The right part displays the driver configuration for the selected driver in terms of the following:

- **Name**
A driver name in the scope of DbVisualizer is a logical name for either a JDBC driver or an Initial Context in JNDI. This is the name shown in the Connectiontab when selecting which driver to use for a Database Connection
- **URL Format**
The URL format specifies the pattern for the JDBC URL or a JNDI Lookup name. Its purpose is to assist the user in the Connection tab when entering URL information or a lookup name. See [Using Variables in Connection Fields](#) for more about how you can make it really easy to create Database Connections for this driver later on.
- **Driver Class**
Defines the main class for the JDBC driver, used for connecting to the database.
- **Driver Version**
Shows the version for a loaded driver.
- **Web Site**
Link to the DbVisualizer web site, where you can get up-to-date information about how to download the drivers for many databases.
- **Driver JAR Files**
Defines all paths to search for JDBC drivers or Initial Contexts when connecting to the database.



Initially, the driver list contains a collection of default drivers. They are not fully configured, as the paths to search for the classes need to be identified. You can edit the list, i.e., create, copy, remove and rename drivers. A driver is ready to use once a driver class has been identified, which is indicated with a green check icon in the list. Drivers that are not ready for use are shown without an icon, or with a red cross icon if an error has been detected (such as a missing file).

Setup a JDBC driver

The recommended way to setup a predefined driver without bundled driver files is to pick a matching driver name from the list and then simply load the JAR, ZIP or directory that keeps the driver class(es). For instances, if you are going to load the JDBC driver for **DB2 (DataDirect)**, select the corresponding driver entry in the list. You can also create a new driver or copy an existing one.


If you want to use other driver files for a bundled driver, it is best to create a new driver entry. For instance, to use an older Oracle driver, you may copy the default Oracle entry and name the new driver entry Oracle Old, and replace the bundled files with the old files for that entry. If you just replace the bundled file for the existing entry, they may be reset when you upgrade to a new DbVisualizer version.

Check the following online web page with the most current information about the tested databases and drivers:

<http://www.dbvis.com/doc/database-drivers/>

- It lists which databases and drivers we have tested
- Download links to JDBC drivers
- Information about which files to load in the driver manager for each JDBC driver
- Information about which Driver Class to choose

When you have selected the driver to configure, you need to load the driver files. Click the **Load** button to the right of the **User Specified** paths tree to show the file chooser and load the driver JAR, ZIP or individual files.



A JDBC Driver implementation typically consists of several Java classes. If they are packaged in a JAR or a ZIP file, you don't have to worry about the details; just select and load the JAR or ZIP file. For instance, in the example above, use the `ojdbc6.jar` file.

If the driver classes are not packaged, it is important to select and load the root folder for the JDBC Driver. Java classes are typically organized using a package name structure. Example:

```
oracle.jdbc.driver.OracleDriver
```

Each package part in the name above (separated by ".") is represented by a folder in the file system. The root folder for the driver is the folder named by the first part, i.e., the `oracle` directory in this example. The class files are stored in the `oracle/jdbc/driver` sub folder. When the driver classes are located in a folder structure like this, you must select and load the root folder, so that the Driver Manager gets the complete package structure.


When a connection is established in the Connection tab, DbVisualizer searches the selected drivers files tree. The files are searched from the top of the tree, i.e., if there are several identical classes, the topmost class will be used. Loading several paths containing different versions of the same driver in one driver definition is not recommended, even though it works (if you do this, you must move the driver you are going to use to the top of the tree). The preferred method for handling multiple versions of a driver is to create several driver definitions.

When you load files in the Driver JAR Files list, DbVisualizer analyzes each file to find the classes that represent main driver classes. Each such class is listed under the path where it was found in the Driver JAR Files list, and it is also added to the **Driver Class** list in the Driver Settings area above. If there is more than one class in the list, make sure you select the correct Driver Class from the list. Consult the driver documentation (or the [Databases and JDBC Drivers](#) page) for information about which class to select.

JDBC drivers that requires several JAR or ZIP files

Some drivers depend on several ZIP or JAR files, or directories. One example is if you want XML support for an Oracle database. In addition to the standard JAR file for the driver, you then also need to load two additional JAR files. These are not JDBC driver files but adds functionality the driver needs to fully support XML.

Simply select all JARs at once and press **Open** in the file chooser dialog. The Driver Manager will then automatically analyze each of the loaded files and present any JDBC driver classes or JNDI initial context classes it finds.



Errors (why are some paths red?)

A path in red color indicates that the path is invalid. This may happen if the path has been removed or moved after it was loaded into the driver manager. Simply remove the erroneous path and locate the correct one.

Several versions of the same driver

The Driver Manager supports loading and using several versions of the same driver concurrently. We recommend that you create a unique driver definition per version of the driver and name the driver definitions properly, e.g., **Oracle 9.2.0.1**, **Oracle 10.2.1.0.1**, etc.

26.4 Setting Up a JNDI Connection

Initial Context classes are needed to get a handle to a database connection that is registered with a JNDI lookup service. In DbVisualizer, these context classes are similar to JDBC driver classes in that an Initial Context implementation for a specific environment is required.



Remember that the appropriate JDBC driver classes must be loaded into the Driver Manager even if the database connection is obtained using JNDI.

To load Initial Context classes into the Driver Manager, simply follow the steps outlined for [installing a custom JDBC driver](#). The difference is that you will load paths containing Initial Context classes instead of JDBC drivers. When you load a path, DbVisualizer locates all Initial Context classes in the path and lists them in the User Specified paths list.

When you create a database connection using a JNDI Lookup driver, the **Properties sub** tab in the connection's Object View tab will then, in this case, contain the same set of driver properties.

The list of options for JNDI lookup is determined by the constants in the `javax.naming.Context` class. To change a value, just modify the value of the parameter. The first column in the list indicates whether the property has been modified or not, and so, whether DbVisualizer will pass that parameter and value onto the driver at connect time.



New parameters can be added using the buttons to the right of the list. Be aware that additional parameters do not necessarily mean that the InitialContext class will do anything with them.


26.5 Special Properties

DbVisualizer utilizes a few special properties that you can use to modify characteristics of the application. These properties are available in the *DBVIS-HOME/resources/dbvis-custom.prefs* file.

Property	Description
dbvis.-AutoSaveRunInterval=30	The number of seconds between auto-saving open SQL editors.
dbvis.disabledataedit=false	Specifies if table data editing should be completely disabled, i.e. the form and inline editors. Note: This has an effect only when used with a licensed edition.
dbvis.driver.ignore.dir=lib:resources:.install4j	Specify directories from DBVIS-HOME that should not be listed in the Driver Manager "System Classpath" list. Directories are separated with ":". Accepted values: one or several directory names starting from DBVIS-HOME.
dbvis.grid.encode=false	Specifies if encoding of data in result set grids will be performed or not. If set to true then make sure the <code>dbvis.grid.fromEncode</code> and/or <code>dbvis.grid.toEncode</code> are also set.
dbvis.grid.fromEncode=ISO8859_1	Encoding used when translating text data that is fetched from the database
dbvis.grid.toEncode=GBK	Encoding used when translating data that will appear in the result set grid
dbvis.removepartialresultsets=false	Defines whether the result set(s) should be removed when interrupting an ongoing execution in the SQL Commander.
dbvis.savedatacolumns=false	Column layout changes such as reordering and/or visibility are saved for all grids in the Objects Views *except* for the "Data" grid. This property can be used to also include the layout in the "Data" grid. Note: This will result in DbVisualizer saving the layout for each table that is displayed in the Data grid = huge XML file...
dbvis.showactionresult=false	This defines whether the result for all actions should be displayed or only failures (default).
dbvis.sqlwarning.maxrows=5000	Defines the number of SQL Warning rows that should be processed before truncating.
dbvis.usegetobject=false	Specifies if the generic <code>ResultSet.getObject()</code> method in JDBC will be used in favor of the data type specific get methods or not. Default is false.
dbvis.usestandardgridfit=false	Enable this property and DbVisualizer will use an accurate but slow method to automatically resize grid columns. "Accurate" since it does a real calculation of the columns width. If leaving this property disabled then column widths are determined much faster but depending on what grid font is used some columns may be truncated with "...". This property has an effect only if Tool Properties->Grid->Auto Resize Column Widths is enabled
dbvis.-ConnectionTestTimeout=20	The timeout in seconds for the "Ping Server" feature.
dbvis.<database>.IgnoreMaxRowsForNonSELECT=true	Ignore the Max Rows setting for statements other than SELECT. MS SQL Server applies Max Rows also to DELETE, INSERT and UPDATE (upto and including SQL Server 2008).
dbvis.<database>.-RemoveNewLineChars=false	Backward compatibility setting used to specify that the SQL command will be trimmed of all whitespaces, tabs and newlines just before it is executed by the DB server.
locale=en,us	Use this to specify an alternate Locale
dbvis.-FileForceSync=true	By default, all XML settings files are synced with the underlying storage device at the time when these are saved. Use this property to disable the syncing and instead rely on OS syncs. Note: relying on OS syncs and performing an uncontrolled shutdown of Windows may corrupt files.
dbvis.-MasterPasswordRule={8,}	By default, a Master Password must be at least 8 characters. This is the definition of the default implementation. Please see the <i>dbvis-custom.prefs</i> file for some additional examples.



Property	Description
dbvis.-MasterPasswordRuleDescr=\ The new password must be at least 8 characters long	Use this to specify a description of the master password rule.

 You rarely need to modify these properties, as the default values are sufficient for most usage. Also note that these properties may change in future versions of DbVisualizer. Some are also experimental and may be removed or instead introduced in the DbVisualizer GUI.